



ADDENDUM #1
2100 North/Fruitland Drive Storm Drain Project


The following changes are hereby made to the Contract Documents for the above referenced Project:

- On the plans, a note has been added at Sta. 0+30.08 to include the information needed for the 12" RCP stub pipe into the existing field. (See attached)
- Line Item #13 called for 12" Drain Pipe. We need both RCP, PVC and ADS. Line Item #13 was updated to 12" RCP. Line Items #26 and #27 were added to include the 12" ADS and 12" C900 PVC respectively. (See attached)

This Addendum is hereby attached to and made part of the Bidding Documents and each Bidder shall acknowledge receipt of this Addendum on the Bid Form.

Project Engineer:

Shane Taggart, P.E.
Jones & Associates
6080 Fashion Point Drive
South Ogden, UT 84405
www.jonescivil.com



**BID SCHEDULE
NORTH OGDEN CITY
2100 NORTH AND FRUITLAND DRIVE STORM DRAIN PROJECT**

CONTRACTOR: _____

BASE BID

Item #	M&P Reference*	Bid Item Description	Estimated Quantity	Unit	Unit Price**	Bid Price
1	MP001	Mobilization	1	ls	\$	\$
2	MP003	SWPPP	1	ls	\$	\$
3	MP005	Traffic Control	1	ls	\$	\$
4	MP006	Exploratory Pothole	10	ea	\$	\$
5	MP007	Construction Staking/Survey	1	ls	\$	\$
6	MP500	Clear and Grub Site	5,500	sf	\$	\$
7	MP600	Saw Cut Asphalt	700	lf	\$	\$
8	MP602	Remove Asphalt	2,800	sf	\$	\$
9	MP603	Remove Concrete Waterway	200	sf	\$	\$
10	MP200	Remove Exist Storm Drain Pipe	280	lf	\$	\$
11	MP203	Abandon Exist Manhole	1	ea	\$	\$
12	MP204	Abandon Exist Storm Drain Pipe	200	lf	\$	\$
13	MP205	New Storm 12" RCP Drain Pipe	10	lf	\$	\$
14	MP205	New Storm 15" RCP Drain Pipe	50	lf	\$	\$
15	MP205	New Storm 30" RCP Drain Pipe	950	lf	\$	\$
16	MP208	New Storm Drain Manhole	7	ea	\$	\$
17	MP209	New Combo Box	1	ea	\$	\$
18	MP213	Connect 12" ADS Pipe to New MH (STA 3+62.93)	1	ea	\$	\$
19	MP213	Connect Exist 15" Pipe to New MH (STA 6+75.45 & 8+06.24)	2	ea	\$	\$
20	MP214	Connect New SD to Exist Structure	2	ea	\$	\$
21	MP318	Fire Hydrant Service Loop	1	ea	\$	\$
22	MP411	Irrigation Water Line Loop	1	ea	\$	\$
23	MP504	Import Fill	250	ton	\$	\$
24	MP612	Asphalt Patch (3" HMA, 8" UTBC)	2,800	sf	\$	\$
25	MP635	New Concrete Waterway	200	sf	\$	\$
26	MP205	New Storm 12" ADS	20	lf	\$	\$
27	MP205	New 12" C900 PVC	10	lf	\$	\$

Total Base Bid (Items# 1-27): \$ _____

***To go directly to Measurement and Payment click here.**

****Unit Price shall contain no more than 2 decimal points (e.g., \$0.00)**

