



SCOPE OF WORK

SSLC ANIMAL SHELTER KENNELS

PROJECT BACKGROUND

The existing kennels at the shelter are showing signs of severe deterioration. This project is to provide materials for installation of new kennels to provide city staff and housed animals with a better working and living environment. Provide all materials, connections and hardware for kennels as per the Project Description and the attached floor plan.

PROJECT DESCRIPTION

1. Submit documentation for all products to be used (walls, doors, panels, covers, hardware) for review at time of bid.
2. 16 kennels positioned back to back at 8 locations as shown on the attached plan.
3. 4 single kennels as shown on the attached plan.
4. 3 double deck kennels as shown on the attached plan.
5. Material for kennels:
 - Side panels to be constructed of plastic, HDPE, FRP, PVC or other non-metallic solid panel for lower 4' of panel.
 - Top of side panels to be 2' of stainless steel mesh
 - Top of kennels to be stainless steel mesh
 - Back to back kennels to have transfer door between kennels and constructed of same non-metallic material as side panels.
 - Transfer door to be guillotine type door
 - Fronts of kennels and doors to be glass.
 - Door to swing both ways
 - Hardware for single hand use
 - Side panels, covers, and doors to be constructed with stainless steel members. Attachments and construction shall be as per vendors specifications.
6. Kennels to have raised resting beds.
7. Kennels to be installed on existing concrete floor.
 - Provide all materials, wall and floor connectors and full instructions for installation.
8. Installation to be done by owner.

SCHEDULE

Provide information on current lead times with submission of quote.

BIDDING REQUIREMENTS

1. All bidding requirements and deadline are stated in the Request for Bids. Late submittals are not accepted.