

October 7, 2024

ADDENDUM NO. 3 (DOCUMENT 00 91 13)
2024 - 2025 Sidewalk Replacement Projects

Attached are copies of Addendum no. 3.

In case of any conflicts between the drawings, specifications, and the attached Addendum, the Addendum shall govern.

Addendum 3 replaces the entire Bid Schedule and Measurement and Payment

This Addendum is hereby attached to and made part of the Contract Documents and each Bidder shall acknowledge receipt of this Addendum in this Bid.

The Addendum consists of 6 pages.

Sincerely,



Eric Casperson, PE
City Engineer

Attachments

cc: Rian Santoro
Bowen Koenig

DOCUMENT 00 91 13
ADDENDUM No. 3

PART 1 GENERAL

1.1 DOCUMENT INCLUDES

- A. Updated Bid Schedule and Measurement and Payment

1.2 CONSTRUCTION CONTRACT

- A. 2024 – 2025 Sidewalk Replacement Project

PART 2 CHANGES

2.1 CHANGES TO PRIOR ADDENDA

- A. None

2.2 CHANGES TO BIDDING REQUIREMENTS

- A. None

2.3 CHANGES TO AGREEMENT AND OTHER CONTRACT FORMS

- A. Replace Entire Bid Schedule and Measurement and Payment

2.4 CHANGES TO CONDITIONS OF THE CONTRACT

- A. None

2.5 CHANGES TO SPECIFICATIONS

- A. None

2.6 CHANGE TO DRAWINGS

- A. None

END OF ADDENDUM NO. 3

BIDDING SCHEDULE

NORTH OGDEN CITY CORPORATION 2024 - 2025 SIDEWALK REPLACEMENT PROJECTS

Item	Description	Quantity	Unit	Unit Price	Total Amount
------	-------------	----------	------	------------	--------------

Work shall be performed at locations shown on the table following the Bidding Schedule. No priorities have been set at this time. They may be set at a future date and some locations may be deleted, depending on budget.

1	Remove and replace 4" thick concrete sidewalk with 4" thick road base under.	3,300	SF	_____	_____
---	--	-------	----	-------	-------

	Total Bid (item 1)			\$	
--	---------------------------	--	--	----	--

2	Remove and replace 30" concrete curb & gutter with 8" thick road base under.	845	LF	_____	_____
---	--	-----	----	-------	-------

	Total Bid (item 2)			\$	
--	---------------------------	--	--	----	--

3	Furnish & install 6" thick concrete and truncated dome panel for ADA ramps.	18	EA	_____	_____
---	---	----	----	-------	-------

	Total Bid (item 3)			\$	
--	---------------------------	--	--	----	--

4	Remove and Replace Concrete Waterway Transition Structure	30	SF	_____	_____
---	---	----	----	-------	-------

	Total Bid (item 4)			\$	
--	---------------------------	--	--	----	--

PROJECT LOCATIONS TABLE

Approximate Address/Location:			Notes
4" Thick Sidewalk	Sections	Approx. Total SF	
163 W 3100 N	1	16	
3331 N 900 E	4	64	
3587 N Lakeview Dr	6	96	
1029 E 2800 N	4	64	
Bates Elementary	30	480	
1974 N 550 E	2	32	
2025 N 556 E	7	112	

2675 N 700 E	2	32	
459 E 1800 N	5	80	
353 E 3475 N	10	160	
829 E 3300 N	10	160	
733 E 1700 N	8	128	
1185 E 2800 N	2	32	
458 E 1900 N	5	80	
450 E 1886 N	3	48	
466 E 1900 N	4	64	
577 E 2300 N	2	32	
476 E 3525 N	4	64	
1843 N 725 E	6	96	
3661 N 650 E	4	64	
3550 N 800 E	4	64	
2750 N 1000 E	2	32	
2675 N 725 E	3	48	
2675 N 719 E	4	64	
638 E 1700 N	7	112	
648 E 1700 N	5	80	
1133 E 2925 N	5	80	
1149 E 2925 N	5	80	
1168 E 2925 N	3	48	
3100 N 800 E	18	288	
514 E 3600 N	4	64	
2162 N 800 E	2	32	
2545 N 1550 E	4	64	
2813 N 1050 E	9	144	
370 E 3350 N	12	192	
Total	206	3296	

30" Curb & Gutter	Lineal Ft	Notes
3274 N 1000 E	30	
3200 N 990 E (on 1000 E)	20	
1491 E 2525 N	10	
1475 E 2525 N	10	
1414 E 2925 N	20	
3566 N 475 E	20	
2833 N 1375 E	20	
694 E 2900 N	30	
343 E 3625 N	10	
1205 E 2550 N	20	
3560 N 475 E	20	

3358 N 700 E	25	
1510 N 873 E	10	
733 E 1700 N	20	
3591 N 500 E	20	
499 E 3550 N	20	
450 E 1900 N	90	ADA Ramp
500 E 1900 N	90	ADA Ramp
600 E 1900 N	30	ADA Ramp
550 E 1950 N	30	ADA Ramp
450 E 2650 N	30	ADA Ramp
575 E 2900 N	30	ADA Ramp
575 E 3050 N	30	ADA Ramp
750 E 3100 N	30	ADA Ramp
900 E 3100 N	30	ADA Ramp
2675 N 700 E	30	ADA Ramp
3100 N 175 W	60	ADA Ramp
1843 N 725 E	30	ADA Ramp
2700 N 1050 E	30	ADA Ramp
Total	845	

ADA Ramp	Quantity	Notes
450 E 1900 N	3	
500 E 1900 N	3	
600 E 1900 N	1	
550 E 1950 N	1	
450 E 2650 N	1	
575 E 2900 N	1	
575 E 3050 N	1	
750 E 3100 N	1	
900 E 3100 N	1	
2675 N 700 E	1	Replace Existing
3100 N 175 W	2	
1843 N 725 E	1	Replace Existing
2700 N 1050 E	1	
Total	18	

Concrete Waterway Transition Structure	Quantity (SF)	Notes
694 E 2900 N	30	
Total	30	

It is understood that the quantities stated are approximate only and are for the purpose of comparing bids and fixing the amount of bonds, and the payments will only be made on the basis of the above unit prices in the actual quantities, as determined by the Owner's Engineer in the completed work.

The undersigned have checked carefully all of the above figures and understand that the Owner will not be responsible for any errors or omissions on the part of the undersigned in making up this bid.

In submitting this bid, it is understood that the right is reserved by the Owner to reject any and all bids and award any and all schedules together or separately in the interest of the Owner.

It is agreed that the bid may not be withdrawn over a period of thirty (30) days from the opening thereof.

It is understood that the Owner cannot enter into a contract for the physical performance of services within the state with a contractor unless the contractor registers and participates in the Status Verification System to verify the work eligibility status of the contractor's new employees that are employed in the state. Accordingly, by signing below, the Contractor certifies that he or she is a participant in the Status Verification System.

Similarly, each contractor or subcontractor working under the Contractor shall certify to the main contractor by affidavit that the contractor or subcontractor has verified through the Status Verification System the employment status of each new employee of the respective contractor or subcontractor.

Respectfully submitted:

_____ Contractor		_____ Contractor's License #	
By: _____		_____ Title	
_____ Business Address	_____ City	_____ State	_____ Zip Code

SECTION 3.2

MEASUREMENT AND PAYMENT

- 3.2.01 GENERAL:** Measurement and calculation of quantities for payment will be specified in this section. Unit price bid shall be full compensation for furnishing all labor, materials, tools and equipment, and doing all work shown on the Drawings or stipulated in the Specifications.
- 3.2.02 REMOVE AND REPLACE 4" THICK CONCRETE FLATWORK (Bid item 1):** Measurement and payment for this item shall be on a per square foot basis as measured in the field following construction. All sections of sidewalk needing replacement will be marked by City personnel prior to commencement of work. Payment shall be full compensation to complete the item including mobilization, saw cut, removal of existing flatwork, loading, hauling and disposal of the concrete flatwork in a lawful manner, coordination with the home owner, excavation and root removal, installation of the concrete flat work, including all labor, materials, equipment, traffic control including pedestrian traffic, grade controls, preparation and compaction of subgrade, furnish and placing road base material under flatwork (4" thick UTBC as per City Standard), grading, forming, control joints and expansion joints as needed, finishing concrete, curing, form stripping, protection of concrete until it has properly cured, restoration or relocation of miscellaneous surface improvements damaged during construction (including sprinkler systems, mailboxes, signs, backfill, topsoil, sod repair, misc. landscaping improvements), and cleanup following construction.
- 3.2.03 REMOVE & REPLACE 30" CONCRETE CURB AND GUTTER (Bid item 2):** Measurement and payment for this item shall be on a per lineal foot basis as measured along the top back of curb in the field following construction. Payment shall be at the unit price bid amount and be full compensation to complete the work associated with removal of and construction of curb and gutter in the locations shown on the drawings. The work includes but not limited to the following: mobilization, all labor, materials, traffic control including pedestrian traffic, equipment, saw cut of asphalt and curb and gutter, removal and disposal of asphalt pavement adjacent to new curb and gutter, removal of existing curb & gutter, loading, hauling and disposal of the curb & gutter in a lawful manner, coordination with the home owner, excavation and root removal, installation of the 30" concrete curb & gutter, grade controls, furnish and placing 4" thick road base material under the new curb & gutter (4" thick UTBC as per City Standard), forming, furnishing concrete, constructing drop back for driveway approaches and ADA ramps if needed, installation of new asphalt patch and freshening of road base at a minimum of 2 feet wide by the length of new curb and gutter, expansion joints, contraction joints, construction joints, finishing and curing concrete, protection of concrete until it has properly cured, restoration or relocation of miscellaneous surface improvements damaged during construction (including sprinkler systems, mailboxes, signs, backfill, topsoil, sod repair, misc. landscaping improvements), and cleanup following construction. Engineer or owners representative must be allowed to inspect curb string line or forms before casting of curb and gutter.
- 3.2.04 FURNISH & INSTALL 6" THICK CONCRETE AND TRUNCATED DOME PANEL FOR ADA RAMPS (Bid Item 3):** Measurement and payment for this item shall be on a per square foot basis as measured in the field following construction. All ADA ramps needing replacement or installation will be marked by City personnel prior to commencement of work. Payment shall be full compensation to complete the item including mobilization, saw cut, removal of existing flatwork, loading, hauling and disposal of the concrete flatwork in a lawful manner, coordination with the home owner, excavation and root removal, installation of the concrete flat work, including all labor, materials, equipment, traffic control including pedestrian traffic, grade controls, preparation and compaction of subgrade, furnish and placing road base material under flatwork (6" thick UTBC as per City Standard), grading, forming, control joints and expansion joints as needed, finishing concrete, curing, form stripping, protection of concrete until it has properly

cured, restoration or relocation of miscellaneous surface improvements damaged during construction (including sprinkler systems, mailboxes, signs, backfill, topsoil, sod repair, misc. landscaping improvements), and cleanup following construction.

3.2.05 REMOVE AND REPLACE CONCRETE WATERWAY TRANSITION STRUCTURE (Bid item 4):

Measurement and payment for this item shall be on a per square foot basis as measured in the field following construction. Includes removal and proper disposal of concrete waterway transition structure, including reinforcing steel and replacement of waterway transition structure including steel reinforcement. Limits of transition structure needing replacement will be marked by City personnel prior to commencement of work. Payment shall be full compensation to complete the item including mobilization, saw cut, removal of existing structure, loading, hauling and disposal of the concrete structure in a lawful manner, coordination with the home owner, excavation and root removal, installation of the concrete transition structure, installation of asphalt patch in areas to make transition function, including all labor, materials, equipment, traffic control including pedestrian traffic, grade controls, preparation and compaction of subgrade, furnish and placing road base material under structure, grading, forming, control joints and expansion joints as needed, finishing concrete, curing, form stripping, protection of concrete until it has properly cured, restoration or relocation of miscellaneous surface improvements damaged during construction (including sprinkler systems, mailboxes, signs, backfill, topsoil, sod repair, misc. landscaping improvements), and cleanup following construction.

3.2.06. QUANTITY LIMITS: The Owner reserves the right to adjust and direct the actual quantities of work performed on the project in order to maintain budget control. All unit price bid amounts shall not be subject to negotiated modifications unless the actual quantities constructed or directed to be constructed, amount to 50% above or below the quantity shown on the original bidding schedule.