



**Wednesday, June 25, 2025
Development Review Committee**

DEVELOPMENT REVIEW COMMITTEE AGENDA

PUBLIC NOTICE is hereby given that the Development Review Committee of Spanish Fork, Utah, will hold a regular meeting at the City Council Chambers at Library Hall, 80 South Main Street, Second Floor, Spanish Fork, Utah, commencing at 10:00 a.m. This meeting is not available to attend virtually.

1. Final Plat

A. ZIONS LANDING 2.0. This proposal involves the approval of a Final Plat for six single-family residential lots located at 1495 East 400 North.

2. Site Plan

A. PACIFIC HORIZON CREDIT UNION. This proposal involves the development of a commercial bank located at 1175 South Main Street.

3. Concept Review

A. WEST MEADOWS CONCEPT REVIEW.

4. Adjourn



Zions Landing 2.0
Final Plat
1495 East 400 North
2.09 acres
R-1-9 with the Complete
Neighborhood Overlay District
General Plan Designation
Medium Density Residential



PROPOSAL

This proposal involves the approval of a Final Plat for six single-family residential lots to be located at 1495 East 400 North. The project is utilizing the Complete Neighborhood Overlay District in order to allow for a twin-home on lots 1A and 1B.

The applicant has provided revised building plans and elevations for the twin-home lots.

Some of the key issues to consider are: landscaping and subdivision improvements.

STAFF RECOMMENDATION

That the proposed Final Plat for the Zions Landing 2.0 Subdivision be approved based on the following findings and subject to the following conditions:

Findings

1. That the proposal conforms to the City's General Plan Land Use Map and Zoning Map,
2. That the submitted plans are consistent with the approved Preliminary Plat.




Conditions





1. That the Applicant meets the City's Development and Construction standards, Zoning requirements and other applicable City Ordinances.
2. That all remaining red-lines be addressed before a preconstruction meeting is held.



EXHIBITS

1. Area Maps
2. Subdivision Plat
3. Landscaping
4. Building Elevations

EXHIBIT 1







SOIL CUT SHOULD BE BENCHMARKED AS NEEDED TO PROTECT WORKERS AND TO COMPLY WITH OSHA REQUIREMENTS.

RETAINING WALLS ARE VULNERABLE TO EROSION AND HYDROSTATIC STABILIZATION OF THE SOIL BEHIND THE WALL PRIOR TO THE PLACEMENT OF LANDSCAPING/FINISHING ELEMENTS (E.G. LANDSCAPING, HARDSCAPE, CURB & GUTTER, PAVEMENT, ETC.) TO MINIMIZE THE RISK OF DAMAGE TO THE WALL DURING ADDITIONAL CONSTRUCTION. THE FOLLOWING PRECAUTIONS SHOULD BE TAKEN FROM THE WALL EXCESS WATER DURING HEAVY PRECIPITATION EVENTS, IF NOT DRAINED PROPERLY, CAN CAUSE WASHOUTS AT THE BASE OF THE WALL. PRECAUTIONS SHOULD BE TAKEN DURING WALL CONSTRUCTION, AND AFTER, UNTIL THE FINAL SITE DRAINAGE, LANDSCAPING AND/OR PAVING ARE COMPLETE.


3. THE DESIGN OF AN APPROPRIATE SAFETY FENCE/BARRICADE SHOULD BE CONSIDERED BY THE OWNER ABOVE THE RETAINING WALL. THE DESIGN OF THE FENCE/BARRICADE IS SPECIFICALLY EXCLUDED FROM THE ENGINEERING OF THIS WALL. THE PLACEMENT OF THE FENCE SHOULD BE DETERMINED BY THE OWNER AND THE FENCE SHOULD BE CONSIDERED BY THE OWNER.

IF A FENCE SYSTEM WILL BE A CHAIN LINK, WROUGHT IRON FENCE OR RAILING, FOLLOW BLOCK MANUFACTURERS' RECOMMENDATIONS (SEE VENDOR BLOCK CONSTRUCTION MANUAL AND EARTHLOCK DETAILS SHEET).

IF A FENCE SYSTEM WILL BE A PRIVACY FENCE (E.G. VINYL, WOOD, PRECAST, ETC.) SHOULD BE CONTACTED TO PROVIDE CONSTRUCTION RECOMMENDATIONS FOR THE FENCE POST LOCATION.

VERTI-BLOCK SCHEDULE (BLOCK SIZE FOR EACH COURSE FOR VARIOUS WALL HEIGHTS, WITH COURSE 1 BEING THE BOTTOM COURSE)					
COURSE	WALL HEIGHT (FEET)				
	2'	3'	4'	5'	6'
3	-	-	-	1"TOP	TOP
2	-	1"TOP	TOP	36"	36"
1	TOP	36"	36"	48"	48"

- TOP = TOP BLOCK
- 1' TOP = 1-FOOT TALL TOP BLOCK
- 36" = 36-INCH BLOCK
- 48" = 48-INCH BLOCK



TYPICAL SECTION VIEW
APPROXIMATE GRAPHICAL SCALE: 1 INCH = 2 FEET (11X17 ONLY)



REV	REVISION DESCRIPTION	DATE	BY	CHK



12429 SOUTH 300 EAST
DRAPER, UTAH 84020
(801) 748-4044

VERTI-BLOCK RETAINING WALL
ZIONS LANDING SUBDIVISION
1540 EAST 400 NORTH
SPANISH FORK, UTAH
TYPICAL SECTION VIEW

DESIGNED BY: PQL	5-19-2025	PLOT SCALE 1=1 DWG SCALE 1"=2'	
DRAWN BY: PQL	5-19-2025		
CHECKED BY: BMJ	5-19-2025		
APPROVED BY: BMJ	5-19-2025		
IGTS PROJECT NO: 04554.003		SHEET NO: 4	REV: N/A



1 INTRODUCTION

- 1 FOLLOW THE GUIDANCE OBTAINED IN THE VERT-BLOCK CONSTRUCTION MANUAL FOR THE RETAINING WALL RETAINING WALLS MORE SPECIFICALLY SUPERSEDED BY MORE STRINGENT SPECIFICATIONS OR MATERIAL PROPERTIES PROVIDED HEREIN OR ON THE DRAWINGS.
- 1.1 IN THE EVENT THERE IS ANY CONFLICT OR AMBIGUITY BETWEEN THE FOLLOWING SPECIFICATIONS AND THE REFERENCED GUIDANCE, BEING ADHERED IMMEDIATELY TO THE ATTENTION OF IER, INC. FOR WRITTEN CLARIFICATION.
- 1.2 DESIGN AND CONSTRUCTION INFORMATION IS BASED ON INFORMATION OBTAINED FROM CIVIL PLANS (ATLAS ENGINEERING), PROJECT GEOTECHNICAL REPORT (OER), DISCUSSIONS WITH THE CLIENT AND THE ENGINEERING ANALYSIS PERFORMED AS PART OF THE SCOPE OF WORK FOR THIS PROJECT BY IER, INC.
- 1.3 LOCATE ALL EXISTING UTILITIES PRIOR TO RETAINING WALL CONSTRUCTION.
- 1.4 IMPLEMENT THE FOLLOWING MEASURES TO REDUCE THE POTENTIAL FOR HYDROSTATIC PRESSURES TO BUILD UP BEHIND THE RETAINING WALL.
- 1.4.1 ESTABLISH VEGETATION OR EROSION CONTROL MEASURES ABOVE AND BELOW THE RETAINING WALL IMMEDIATELY FOLLOWING CONSTRUCTION.
- 1.4.2 PLACE A 4-INCH (MINIMUM) PERFORATED DRAIN PIPE AT BOTTOM OF GRAVEL INFILL.
- 1.5 CONDITIONS SUCH AS LEAKY OR BROKEN IRRIGATION LINES AND/OR UNCONTROLLED RUNOFF FROM IMPROPER SITE GRADING (E.G., ALLOWING WATER PONDING BEHIND THE RETAINING WALL) CAN LEAD TO SLOPE OR WALL MOVEMENT.
- 1.5.1 HYDROSTATIC CONDITIONS WERE NOT CONSIDERED IN THE ANALYSES AND MUST BE AVOIDED.
- 1.5.2 RETAINING WALLS ARE VULNERABLE TO EROSION AND HYDROSTATIC PRESSURES IMMEDIATELY AFTER INSTALLATION OF THE RETAINING WALL BLOCKS, BUT PRIOR TO THE PLACEMENT OF THE LANDSCAPING OR FINISHING ELEMENTS AT THE SITE (E.G., 8 INCHES OF LOW-MEASUREABLE SOLIDSCAPE, VEGETATION OR SLOPES, ETC.) AS THESE ARE CRITICAL COMPONENTS TO THE OVERALL STABILITY OF THE RETAINING WALL. THE RETAINING WALL IS NOT CONSIDERED COMPLETELY INSTALLED UNTIL THE LANDSCAPING/FINISHING ELEMENTS ARE COMPLETED. WE RECOMMEND THAT THESE ELEMENTS BE INSTALLED IMMEDIATELY FOLLOWING THE INSTALLATION OF THE BLOCKS.
- 1.5.3 THE OWNER SHALL BE AWARE OF THE RISK IF THESE OR OTHER CONDITIONS OCCUR THAT COULD SATURATE OR SECE THE SOIL BEHIND THE WALL, OR IF THE FINISHING/LANDSCAPING ELEMENTS ARE NOT INSTALLED IMMEDIATELY FOLLOWING THE INSTALLATION OF THE RETAINING WALL BLOCKS.
- 1.6 COMPLY WITH ALL ASPECTS OF OSHA 1926 SUBPART P AND B, SLOPING AND BENCHING FOR ALL EXCAVATED SLOPES.
- 2 VERT-BLOCK RETAINING WALL MATERIALS
- 2.1 RETAINED BACKFILL CONSISTING OF NATIVE GRANULAR SOILS OR IMPORT MATERIALS COMPLYING WITH THE FOLLOWING CRITERIA:
- 2.1.1 GRANULAR MATERIALS CONTAINING LESS THAN 25% FINES AND A MAXIMUM NOMINAL PARTICLE SIZE OF 4 INCHES
- 2.1.2 PH GREATER THAN 3 BUT LESS THAN 5 AND PI OF 6% OR LESS
- 2.1.3 MAXIMUM TREE PROXIMITY OR OTHER DELICIOUS MATERIALS
- 2.1.4 MINIMUM EFFECTIVE FRICTION ANGLE OF 32 DEGREES
- 2.1.5 ANY STRUCTURAL FILL USED BELOW OR BEHIND THE RETAINING WALL SHALL BE TESTED FOR COMPLIANCE WITH THE SPECIFICATIONS ABOVE.
- 2.2 LEVELING PAD
- 2.2.1 6-INCHES (MINIMUM) OF CLEAN 1-INCH MINUS CRUSHED STONE OR CRUSHED GRAVEL.
- 2.3 USE NEW BLOCK MATERIALS MEETING THE MINIMUM REQUIREMENTS OF VERT-BLOCK RETAINING WALL SYSTEMS (VERT-CRETE, LLC).
- 2.4 FACED FILL AND DRAINAGE FACED FILL.
- 2.4.1 CLEAN CRUSHED STONE OR CRUSHED GRAVEL THAT COMPLIES WITH THE FOLLOWING CRITERIA:
- | SEVE SIZE | % PASSING |
|-----------|-----------|
| 2" | 100 |
| 1" | 75-100 |
| 3/4" | 0-15 |
| NO 4 | 0-10 |
| NO 200 | 0-5 |
- 2.5 4-INCH (MINIMUM) PERFORATED PIPS (NO SOCK IS REQUIRED).
- 3 VERT-BLOCK RETAINING WALL INSTALLATION
- 3.1 FIELD VERIFY PROPOSED FINISHED GRADE AT BOTTOM OF WALL TO PROVIDE THE MINIMUM WALL EMBEDEDMENT AS SHOWN ON THE SECTION DRAWING.
- 3.2 GRADE AND COMPACT FOUNDATION SUB-GRADE SOILS FOR THE FULL LENGTH OF THE LEVELING PAD AND UP TO THE SOIL CUT PRIOR TO PLACEMENT OF THE LEVELING PAD AND ANY BACKFILL.
- 3.2.1 REMOVE ANY FOUNDATION SOILS FOUND TO BE UNSUITABLE OR UNSTABLE AND REPLACED WITH APPROVED FILL.
- 3.3 SET THE LEVELING PAD LEVEL, SIDE-TO-SIDE AND FRONT-TO-BACK.
- 3.3.1 INSTALL LEVELING PAD TO A MINIMUM OF 6 INCHES THICK AND EXTEND Laterally A MINIMUM OF 6 INCHES BEYOND THE ENDS OF THE BLOCKS BOTH FRONT AND BACK AS SHOWN ON THE DRAWINGS.
- 3.4 SET THE FIRST ROW OF VERT-BLOCK UNITS AND CHECK FOR LEVEL AND ALIGNMENT.
- 3.4.1 INSTALL WALL ELEMENTS IN ACCORDANCE WITH VERT-BLOCK GUIDELINES.

4. POUR DRAINAGE INFTLL GRAVEL INTO THE HOLLOW CORE OF EACH VERT-BLOCK AND BETWEEN AND WITHIN THE BLOCKS AS EACH ROW OF BLOCKS IS INSTALLED. BEFORE ADDITIONAL COURSES OF BLOCKS ARE ADDED, THE CONTRACTOR MUST ENSURE THAT ALL VOIDS ARE FILLED AND NO AIR POCKETS ARE DETECTED.
- 3.51 SET DRAINAGE PIPS AT THE BASE OF THE GRAVEL INFTLL ZONE WHICH SHALL SLOPE TO DAYLIGHT AND DISCHARGE AT THE LOW END OF THE RETAINING WALL.
- 3.6 REMOVE AND SWEEP OFF ALL EXCESS AGGREGATE AND OTHER MATERIALS FROM THE TOP OF THE BLOCKS BEFORE CONTINUING TO THE NEXT COURSE.
- 3.7 PLACE WALL BACKFILL MATERIAL IN 12 INCH MAXIMUM LOOSE LIFTS AND COMPACT TO A MINIMUM OF 95 PERCENT OF ASTM D1557 (MODIFIED PROCTOR). THEREAFTER LIFTS MAY BE NECESSARY TO ACHIEVE REQUIRED COMPACTION.
- 3.71 PERFORM DENSITY TESTING OF THE BACKFILL SOILS AT 50-FOOT INTERVALS ON EVERY LIFT.
- 3.72 USE ONLY SMALL, WALK-BEHIND-TYPE COMPACTION EQUIPMENT WITHIN 3 FEET OF THE BACK OF THE RETAINING WALL BACKFILL.
- 3.73 IF ANY LOCATIONS EXIST WHERE THE RETAINING WALL WILL NOT BE PLACED UPON NATIVE SOILS, COMPACT THE FILL TO A MINIMUM OF 95 PERCENT OF THE MAXIMUM DRY DENSITY PER ASTM D1557 (MODIFIED PROCTOR).
- 3.8 INSTALL EACH SUBSEQUENT COURSE TO BOND ON TOP OF THE BASE ROW. POSITION BLOCKS TO BE OFFSET FROM SEAMS OF BLOCKS ON LOWER COURSE. BLOCKS SHALL BE PLACED AT A 1/4 INCH SETBACK AND RECESSED AROUND THE ALIGNMENT HOOK.
- 3.81 CHECK EACH BLOCK COURSE FOR PROPER ALIGNMENT AND LEVEL.
- 3.82 CONTINUE TO BUILD EACH COURSE OF WALL TO THE OUTLINE OF UNIT AS DESCRIBED IN NOTES 3.5 THROUGH 3.7.
- 3.9 PROVIDE A FINAL GRADE ABOVE AND BELOW THE RETAINING WALL THAT WILL ALLOW FOR POSITIVE DRAINAGE AND PREVENT PONDING.
- 3.10 PROTECT FINAL COMPLETED RETAINING WALL FROM ADDITIONAL SITE CONSTRUCTION.
- 3.101 DO NOT OPERATE LARGE EQUIPMENT OR STORE MATERIALS ABOVE THE WALL THAT EXCEED THE DESIGN SURCHARGE LOADS AS SPECIFIED ON THE DESIGN CRITERIA SHEET.
- CONSTRUCTION OBSERVATION
- 4.1 TO RULED, ANY APPLICABLE CITY, COUNTY AND/OR STATE AGENCY REQUIREMENTS, AND TO PROTECT THE CONTRACTOR AND DESIGN ENGINEER, I/OES, INC MUST PERFORM PERIODIC CONSTRUCTION OBSERVATIONS TO PROVIDE A FINAL CONSTRUCTION OBSERVATION LETTER.
- 4.1.1 IF I/OES, INC DOES NOT OBSERVE THE RETAINING WALLS DURING CONSTRUCTION, A FINAL LETTER REGARDING COMPLIANCE OF THE WALL, CONSTRUCTION WITH THE DESIGN CRITERIA AND RECOMMENDATIONS CANNOT BE PROVIDED. IF I/OES, INC DOES NOT PERFORM THE PERIODIC CONSTRUCTION OBSERVATIONS OUTLINED BELOW, THE CONTRACTOR/OWNER ASSUMES ALL RESPONSIBILITY FOR THE RETAINING WALLS.
- 4.2 WALL OBSERVATIONS SCHEDULE
- 4.2.1 OBSERVE THE EXCAVATION OF THE LEVELING PAD FOUNDATION SOILS
- 4.2.1.1 ASSESS THE SUITABILITY OF THE FOUNDATIONS SOILS.
- 4.2.2 OBSERVE THE INSTALLATION OF THE RETAINING WALL BLOCK AT VARIOUS STAGES OF CONSTRUCTION.
- 4.2.2.1 ASSESS MINIMUM EMBEDMENT REQUIREMENTS.
- 4.2.2.2 ASSESS DEPTH OF GRAVEL DRAINAGE ZONE AND TYPE, LOCATION AND DIAMETER OF DRAINAGE PIPE.
- 4.2.2.3 ASSESS BLOCK PLACEMENT AND POSITIONING FOR COMPLIANCE WITH THE REQUIREMENTS IN THE SECTIONS ABOVE.
- 4.2.3 OBSERVE THE INSTALLATION OF THE BACKFILL MATERIAL.
- 4.2.3.1 VERIFY THAT THE BACKFILL MATERIAL MEET THE REQUIREMENTS SET FORTH IN THE SECTIONS ABOVE.
- 4.2.3.1.1 ASSESS LOOSE LIFT THICKNESS, FILL PLACEMENT AND COMPACTION.
- 4.2.3.1.2 ASSESS COMPACTED BACKFILL MATERIAL FOR COMPLIANCE WITH REQUIREMENTS SET FORTH IN THE SECTIONS ABOVE.
- 4.2.4 OBSERVE THE COMPLETED RETAINING WALL SYSTEM.
- 4.2.4.1 OBSERVE THE FINISHED RETAINING WALL, HEAD AND BATTER.
- 4.2.4.2 OBSERVE THAT BACKFILLS AND TOE/LOOSE GRADING CONDITIONS DO NOT EXCEED DESIGN GEOMETRY TOLERANCES.
- 4.2.4.3 ASSESS SUITABILITY OF EROSION CONTROL MEASURES INSTALLED ABOVE THE RETAINING WALL.


REV	REVISION DESCRIPTION	DATE	BY	CHECK




12429 SOUTH 300 EAST
DRAPER, UTAH 84020
(801) 748-4044

VERTI-BLOCK RETAINING WALL
ZIONS LANDING SUBDIVISION
1540 EAST 400 NORTH
SPANISH FORK, UTAH
CONSTRUCTION SPECIFICATIONS A

DESIGNED BY: PQL	5-19-2025	PLOT SCALE
DRAWN BY: PQL	5-19-2025	1=1
CHECKED BY: BMJ	5-19-2025	DWG SCALE
APPROVED BY: BMJ	5-19-2025	NTS
IGES PROJECT NO:	SHEET NO:	REV
04654.003	5	N/A





DETAILS PROVIDED BY VERTI-Crete RETAINING WALL SYSTEMS, INC.

										12429 SOUTH 900 EAST 190-2475, UTAH 84020 (801) 748-4044					VERTI-BLOCK RETAINING WALL ZIONS LANDING SUBDIVISION 150-2475, UTAH 84020 SPANISH FORK, UTAH					DESIGNED BY: POOL 5-10-2023 DRAWN BY: POOL 5-10-2023 CHECKED BY: BMD 5-10-2023 APPROVED BY: BMD 5-10-2023 IGES PROJECT NO: 046514003					PLOT SCALE 1"=1' DWG. SCALE NTS 6"=1'-0"									
REV	REVISION DESCRIPTION	DATE	BY	CHK																														
																				VERTI-BLOCK DETAILS														

RETAINING WALL GEOMETRY AND LOADING CONDITIONS			
LENGTH (FEET)	MAXIMUM HEIGHT (FEET)	BACKSLOPE CONDITIONS	SURCHARGE LOADING
90	6	RELATIVELY FLAT	250 PSF (ROADWAY)

SOIL CONDITIONS USED IN DESIGN (ASSUMED)			
EARTH MATERIALS	FRICTION ANGLE	COHESION	UNIT WEIGHT
RETAINED SOIL	32°	0 PSF	120 PCF
FOUNDATION SOIL	32°	50 PSF	120 PCF

- SOURCES & NOTES:**
- IGES, GEOTECHNICAL INVESTIGATION, ZIONS LANDING SUBDIVISION, 1495 EAST 400 NORTH, SPANISH FORK, UTAH, IGES PROJECT NO. 04651-001, DATED MAY 10, 2024.
 - COHESION USED ONLY IN GLOBAL STABILITY ANALYSES.

GENERAL NOTES:

- THE ENGINEERING PRESENTED IN THIS DESIGN PACKAGE IS BASED ON SPECIFIC PRODUCTS (E.G., VERTI-BLOCKS, FILL MATERIAL, ETC.). ANY SUBSTITUTION OF THE SPECIFIED PRODUCTS WILL INVALIDATE THIS ENGINEERING. ANY CHANGES IN WALL LOCATION, ELEVATIONS OF LEVELING PAD, GRADES AT THE TOE OR TOP OF THE WALL, AND SOIL PARAMETERS AT THE SITE WILL ALSO INVALIDATE THE ENGINEERING. FIELD ADJUSTMENTS/CHANGES MAY BE NEEDED TO MEET ACTUAL CONDITIONS ONCE CONSTRUCTION COMMENCES. IGES SHOULD BE CONSULTED WHERE FIELD CHANGES ARE REQUIRED.
- THESE DOCUMENTS ARE INSTRUMENTS OF SERVICE AND SHALL REMAIN THE INTELLECTUAL PROPERTY OF IGES, INC. THE DESIGN PACKAGE HAS BEEN FURNISHED FOR THIS SPECIFIC PROJECT ONLY. ANY PARTY ACCEPTING THIS DOCUMENT DOES SO IN CONFIDENCE AND AGREES THAT NO USE OR RE-USE OF THESE DOCUMENTS (WHOLE OR IN PART) SHALL BE PERMITTED UNLESS EXPRESSLY AUTHORIZED IN WRITING BY IGES, INC.
- RETAINING WALLS ARE VULNERABLE TO FROSTION AND HYDROSTATIC PRESSURES IMMEDIATELY AFTER INSTALLATION BEFORE THE PLACEMENT OF LANDSCAPING/FINISHING ELEMENTS AT THE SITE (E.G., LANDSCAPING, HARDSCAPE, CURB & GUTTER, PAVEMENT, ETC.). TO MINIMIZE THE RISK OF DAMAGE TO THE WALL DURING ADDITIONAL SITE WORK, ALL SURFACE DRAINAGE SHOULD BE DIRECTED AWAY FROM THE WALL. EXCESS WATER DURING HEAVY RAIN EVENTS, IF NOT DRAINED PROPERLY, CAN CAUSE WASHOUTS AT WALL ENDS AND "BLOWOUTS" OF INTERIOR SECTIONS. THESE PRECAUTIONS SHOULD BE TAKEN DURING AND AFTER WALL CONSTRUCTION UNTIL THE FINAL SITE DRAINAGE, LANDSCAPING AND PAVING ARE COMPLETE.

ENGINEERING ANALYSIS USED IN DESIGN	
ANALYSIS	DESIGN REFERENCES/SOFTWARE
EXTERNAL STABILITY (VERTI-BLOCK)	VERTI-BLOCK RETAINING WALLS, 2023 VERTICrete WALL DESIGNER SOFTWARE, VERSION 6.0.2160.045, BUILD DATE JUNE 9, 2023, AUTHOR ROBERT RACE
GLOBAL STABILITY	SLIDE 2: ROCSCIENCE, INC., 1998-2025, VERSION 9.008, BUILD DATE MARCH 3, 2025.

SEISMIC PARAMETERS USED IN DESIGN					
SEISMIC CRITERIA	MCE _g PGA	SITE CLASS	F _{PGA}	PGA _{td}	HORIZONTAL COEFFICIENT (k _h)
ASCE 7-16	0.661g	D	1.2	0.793g	0.087 _k (EXTERNAL) 0.397 _k (GLOBAL)

SOURCES & NOTES:

- SEISMIC PARAMETERS DEVELOPED FOLLOWING THE CRITERIA OUTLINED IN ASCE 7-16. THE ASCE 7 HAZARD TOOL WAS USED TO DETERMINE THE MAPPED MCE_g PEAK GROUND ACCELERATION (MCE_g PGA) FOR THE SITE. BASED ON THE GEOTECHNICAL INVESTIGATION (IGES, 2024), THE SITE SOIL CLASS IS REPRESENTED BY A SITE CLASS D - STIFF SOIL. THE MCE_g PEAK GROUND ACCELERATION WAS ADJUSTED FOR SITE CLASS EFFECTS (PGA_{td}).
- HORIZONTAL SEISMIC COEFFICIENT (k_h)
 - EXTERNAL SEISMIC COEFFICIENT (k_{h,ext})
 - THE EXTERNAL COEFFICIENT WAS DETERMINED USING THE METHODOLOGY OUTLINED IN BRAY ET AL. (2010) [SEE ALSO AASHTO LRFD BRIDGE DESIGN MANUAL IN CHAPTER 11 APPENDIX THE 1% DAMPED RESPONSE SPECTRUM NSHM CONTINUOUS U.S. 2023 MODEL (2% IN 40 YEARS) WAS UTILIZED FOR THE CALCULATIONS (SEE OUTPUT GIVEN IN SECTION 4) FOUND AT <https://earthquake.mgs.gov/ishmp/hazard/dynamic>]. LACKING ANY CRITICAL STRUCTURES OF FACILITIES WITHIN THE INFLUENCE ZONE OF THE WALLS, AN ALLOWABLE DISPLACEMENT OF 15 CENTIMETERS (~6 INCHES) WAS CONSIDERED ACCEPTABLE FOR THE WALLS ON THIS PROJECT.
 - IN ACCORDANCE WITH RECOMMENDATIONS CONTAINED IN BRAY ET AL. (2010), THE ESTIMATED DISPLACEMENT FOR THE MAXIMUM SECTION OF THE RETAINING WALLS WAS EVALUATED. TWO METHODS WERE UTILIZED TO ESTIMATE THE SEISMIC DISPLACEMENT: THE NEWMARK DISPLACEMENT METHOD (ANDERSON ET AL., 2008), AND THE SIMPLIFIED PROCEDURE (BRAY AND TRAVASAROU, 2007). BASED ON THESE ANALYSES, THE ANTICIPATED MEAN DISPLACEMENT FOR THE MAXIMUM SECTION OF THE RETAINING WALL WILL BE APPROXIMATELY LESS THAN 1 INCH, WHICH IS WITHIN THE TOLERABLE LIMITS FOR THIS WALL TYPE.
 - GLOBAL SEISMIC COEFFICIENT (k_{h,global})
 - ONE-HALF OF THE PGA_{td} WAS USED TO MODEL THE HORIZONTAL SEISMIC ACCELERATION FOR GLOBAL STABILITY ANALYSES (k_h = 0.397g).
- REFERENCES:
 - ANDERSON, D.G., MARTIN, G.R., LAM, L., WANG, J.N., 2008. SEISMIC ANALYSIS AND DESIGN OF RETAINING WALLS, BURIED STRUCTURES, SLOPES, AND EMBANKMENTS, NATIONAL COOPERATIVE HIGHWAY RESEARCH PROGRAM (NCHRP) REPORT 611.
 - BRAY, J.D., TRAVASAROU, T., 2007. SIMPLIFIED PROCEDURE FOR ESTIMATES EARTHQUAKE INDUCED DEVIATORIC SLOPE DISPLACEMENTS, JOURNAL OF GEOTECHNICAL & GEOENVIRONMENTAL ENGINEERING, ASCE, V. 133(4), PP. 381-392, APRIL 2007.
 - BRAY, J.D., TRAVASAROU, T., AND ZUPAN, J., 2010. SEISMIC DISPLACEMENT DESIGN OF EARTH RETAINING STRUCTURES, ASCE EARTH RETENTION CONFERENCE 3, BELLEVUE, WA. AMERICAN SOCIETY OF CIVIL ENGINEERS, RESTON, VA, PP. 638-655.
 - IGES, GEOTECHNICAL INVESTIGATION, ZIONS LANDING SUBDIVISION, 1495 EAST 400 NORTH, SPANISH FORK, UTAH, IGES PROJECT NO. 04651-001, DATED MAY 10, 2024.

REV	REVISION DESCRIPTION	DATE	BY	CHK										



IGES
EST. 1982

12429 SOUTH 300 EAST
ZIONS LANDING SUBDIVISION
1540 EAST 400 NORTH
SPANISH FORK, UTAH
(801) 745-4044

VERT-BLOCK RETAINING WALL
ZIONS LANDING SUBDIVISION
1540 EAST 400 NORTH
SPANISH FORK, UTAH

DESIGNED BY: POL 5-19-2023
DRAWN BY: POL 10-15-2023
CHECKED BY: BMD 1-19-2024
APPROVED BY: BMD 10-20-2023

DESIGN CRITERIA
0.65x1.00

PLOT SCALE
1"=1'-0"



DWG SCALE
1"=1'-0"

REVISIONS
7

BRADLEY M. JOHNSON
06/21/2025
REGISTERED PROFESSIONAL ENGINEER
No. 26777
STATE OF UTAH

SHEET NO: 7
TOTAL SHEETS: 7



EXHIBIT 3



Page 15

EXHIBIT 4







Pacific Horizon Credit Union
Site Plan
1175 South Main Street
1 acre
C-2 Zone
Mixed Use General Plan Designation



PROPOSAL

The Applicant applied for Site Plan approval to construct a building for a financial institution on the subject property. Financial Institutions are listed as a permitted use in the C-2 Zone. The site will have access from Main Street and South Lane with the proposed building located towards the west site of the property.

An eight-foot-tall precast concrete wall is shown on the civil drawings along the north property line adjacent to existing residential properties, with a note that the wall height will drop to three feet tall to allow clear vision along South Lane. The municipal code requires a six-foot-tall wall adjacent to a residential zone, but the City Council can approve a wall up to eight feet tall (§15.4.16.150). Fencing adjacent to the residential property on the south side will be installed depending on the development timing of that property. Staff is currently reviewing a site plan for an office building on that adjacent property.

Some of the key issues to consider are: development timing, utilities, easements, road dedication, fencing.

STAFF RECOMMENDATION

That the proposed Pacific Horizon Site Plan be approved based on the following finding and subject to the following conditions:

Finding

1. That the proposal conforms to the City's General Plan Designation and Zoning Map,




Conditions


1. That the Applicant meets the City's development and construction standards and other applicable City ordinances.
2. That any remaining redlines are addressed prior to a building permit being issued.
3. That the City Council approves an eight-foot-tall wall prior to a building permit being issued

EXHIBITS

1. Area Maps
2. Site Plan
3. Landscape Plan
4. Building Elevations

EXHIBIT 1










EXHIBIT 4




D1 BUILDING ELEVATION - SOUTH A

AX1: -B - F.B.



C1 BUILDING ELEVATION - SOUTH B

AX1: -B - F.B.



A1 BUILDING ELEVATION - EAST

AX2: -B - F.B.

KEYNOTES

- 108 ARCHITECTURAL CLOFFY
- 52 ALUMINUM FRAMED STOREFRONT SYSTEM
- 521 ALUMINUM CLIMATE WALL SYSTEM
- 525 INTERLOCKING ALUMINUM CLIMATE WALL SYSTEM

EXTERIOR MATERIAL LEGEND


- COMMERCIAL NORMAN BRICK
- SHAPED WOOD PANELING, NO BASIS OF DESIGN
- FASTENING, UNIFORM, LONGWOOD OR SIMILAR
- 2" ALUMINUM PANEL SYSTEM, LONGWOOD OR SIMILAR
- INTERLOCKING ALUMINUM CLIMATE WALL SYSTEM
- SPANDREL GLASS

KEYNOTES

- 52 ALUMINUM FRAMED STOREFRONT SYSTEM
- 522 ALUMINUM FRAMED STOREFRONT SYSTEM
- 521 ALUMINUM CLIMATE WALL SYSTEM


EXTERIOR MATERIAL LEGEND

- COMMERCIAL NORMAN BRICK
- SHAPED WOOD PANELING, NO BASIS OF DESIGN
- FASTENING, UNIFORM, LONGWOOD OR SIMILAR
- 2" ALUMINUM PANEL SYSTEM, LONGWOOD OR SIMILAR
- INTERLOCKING ALUMINUM CLIMATE WALL SYSTEM
- SPANDREL GLASS




C1 BUILDING ELEVATION - NORTH A

AX2: -B - F.B.



A1 BUILDING ELEVATION - NORTH B

AX2: -B - F.B.



A3 BUILDING ELEVATION - WEST

AX2: -B - F.B.

