

ADDENDUM No.2 Sheet 1 of 2

July 17 2025, the following changes and additional information shall be incorporated into the Contract Documents and Specifications for the **Washington City 2025 Canal Trails** project. These modifications shall supersede any existing specifications as detailed herein.

Clarification

Clarification #1

The following clarifications on the gate size and type are as follows. All Gates will be changed to a 6-Bar Tube Metal Gate. With hinges and latches as required. The gate will be mounted to the wood post fence. The color for the gates will be Grey or Black.



Washington Dam Rd to Silver Falls

Bid Item 25: *Wood Post Fence Gates*. These gates are going to be changed to the following:

- 5' man gate STA 12+15: Change to **4' tube metal gate**
- 10' access gate STA 12+25: Change to **8' tube metal gate**
- 15' access gate STA 13+10: Change to **16' (2) 8' gates) tube metal gate**

Silver Falls to Lost Ridge Dr.

Bid Item 44: *Wood Post Fence Gates*. These gates are going to be changed to the following:

- 20' access gate STA 49+15: Change to **16' (2) 8' gates) tube metal gate**
- 20' access gate STA 50+60: Change to **16' (2) 8' gates) tube metal gate**

Clarification #2

The chacane are a size of **7'-2"**. Also, the chacane maybe fabricated locally but must meet the same size and dimensions, color as detailed out in the specifications.

All bidders shall acknowledge receipt and acceptance of this Addendum by submitting this signed Addendum with the bid package. Bid forms received without this Addendum will be considered informal.

ALLIANCE CONSULTING

CONTRACTOR

Signature: _____

Signature: _____

Title: Project Manger

Title: _____

Date: 7-17-2025

Date: _____