

Voyage Academy

Board of Directors
12.30.2025

BOARD PACKET

TABLE OF CONTENTS.....2

AGENDA.....3

DRAFT MEETING MINUTES 10.09.....4

KINDER PLAYGROUND PRICING.....8



VOYAGE ACADEMY BOARD OF DIRECTORS MEETING AGENDA

Date: December 30, 2025

Time: Public Session from 12:30pm-1:00pm

Location: 1891 N. 1500 W., Clinton, UT 84015 or virtually at [Microsoft Teams Link](#)

MISSION STATEMENT

Voyage Academy is dedicated to cultivating student growth through Expeditionary Learning. Our mission is to promote responsibility, integrity, and the development of essential life skills, guiding students toward becoming respectful, compassionate, and motivated lifelong learners.

ATTENDEES

Courtnie Moore, Danielle Pedersen, Janae Howell, Valerie Hulsey, Dennis Henry, Blaire Barker, Kami Coleman, Nicole Jones, Roger Simpson

AGENDA

OPENING BUSINESS

The meeting will formally commence with the call to order and roll call.

PUBLIC COMMENT

Please limit comments to 3 minutes

CONSENT AGENDA

Approval of October 9, 2025, Board Meeting Minutes

DISCUSSION AND ACTION ITEMS

Approval of Kindergarten Playground Equipment, Ground Cover and Installation purchase price of up to \$62,000.

CALENDARING

The next Board Meeting is scheduled for January 15, 2026.

ADJOURNMENT

The meeting will adjourn upon completion of all agenda items.

*In compliance with the Americans with Disabilities Act, individuals needing special accommodations (including auxiliary communicative aids and services) during this meeting should notify Voyage Academy at 801-776-4900 at least 3 working days prior to the meeting.

Voyage Academy Board of Directors Meeting



Date: October 9, 2025

Location: 1891 North 1500 West Clinton, UT 84015

In Attendance: Courtnie Moore, Danielle Pedersen, Janae Howell, Dennis Henry, Blaire Barker

Others in Attendance: Kami Coleman, Roger Simpson, Hannah Jones

Excused: Valerie Hulsey, Dan Ripple

"The mission of Voyage Academy is that through Expeditionary Learning, children will explore Life Skills and gain personal responsibility. As they strive for excellence in the molding of their future, they will become honest, compassionate, and respectful seekers of learning."

MINUTES

CALL TO ORDER

Courtnie Moore called the meeting to order at 6:03 PM.

PUBLIC COMMENT

There were no comments.

REPORTS

- **Director Report**
Kami Coleman announced upcoming events at the school. The school carnival raised \$4,800. Over 200 vaccines were given at the school event "Boo to the Flu". More than 350 students and family members attended the walk to school event. Currently enrollment is 529 students. There is math enrichment after school starting soon. Amy Mills will be shadowed by lunch managers from Ogden Preparatory Academy and Davinci Academy. The maturation program will remain the same and will be distributed to parents on Friday, March 27th. Choir has begun. Kami concluded the director's report with a "getting to know you" activity with board members.
- **Committee Reports**
Roger Simpson reported that the completed audit report should be ready within the next couple of weeks. The bonds are scheduled to be priced out on November 4th. As construction progresses, the school's balance will fluctuate based on monthly draws and billing activity. Dennis Henry noted that a recent safety meeting had several new attendees. Parking lot construction plans are still being finalized. The school conducted a successful evacuation drill with support from Clinton City police officers. Expansion may create new safety and security challenges during the construction period. Kami Coleman shared that the team will begin budgeting for marketing efforts to attract new students. Planned campaigns will include promotions at Fat Cats, local movie theaters, signage, flyers, and posters. Stout Construction will also place signage to highlight the school's expansion. Fall treat bags were distributed to staff and board members in appreciation. Courtnie Moore and Kami Coleman presented a construction and expansion calendar, noting that it will need to be developed earlier than usual this year. Some days may need to be blocked out. Site work is scheduled to begin on October 27th. Courtnie informed the board that Dan Ripple will be stepping down. The board will need to recruit two new members for next year and an additional replacement

for Dan. Interviews will take place this year to onboard new members for next year's term. Dennis Henry requested clarification on his board role, as he will no longer have a student enrolled next year.

David Robertson joined the meeting at 6:43 PM.

VOTING ITEMS AND DISCUSSION ITEMS

- **Authorizing Resolution**

David Robertson spoke to the board about the authorizing resolution. The board had no questions or concerns about the resolution.

Janae Howell made a motion to approve the Authorizing Resolution. Dennis Henry seconded. The motion passed unanimously. The votes were as follows: Courtnie Moore, Aye; Danielle Pedersen, Dennis Henry, Aye; Blair Barker, Aye; Janae Howell, Aye.

- **Stout Construction Contract**

Roger Simpson discussed the Stout Construction Contract which is a lump sum contract. The rate they are receiving is in line with what they expected. There was no further discussion.

Dennis Henry made a motion to approve the Stout Construction Contract. Danielle Pedersen seconded. The motion passed unanimously. The votes were as follows: Courtnie Moore, Aye; Danielle Pedersen, Aye; Janae Howell, Aye; Dennis Henry, Aye; Blaire Barker, Aye.

David Robertson left the meeting at 7:16 PM.

- **Amended Bullying, Cyber-Bullying, Hazing, Abusive Conduct, and Retaliation Policy**
- **New Hotline Complaint Policy** The board discussed the amended policy and new policy. Board members were informed of a training that goes along with the new hotline Complaint Policy. There was no further discussion.

Danielle Pedersen made a motion to approve the Amended Bullying, Cyber-Bullying, Hazing, Abusive Conduct and Retaliation Policy and the Hotline Complaint Policy. Blaire Barker seconded. The motion passed unanimously. The votes were as follows: Courtnie Moore, Aye; Danielle Pedersen, Aye; Dennis Henry, Aye; Blaire Barker, Aye; Janae Howell, Aye.

CALENDARING

The next board meeting is scheduled for January 15, 2026. There will be an additional board meeting in November taking place electronically.

CONSENT ITEMS

- **August 21, 2025, Board Meeting Minutes**
Dennis Henry made a motion to approve the August 21, 2025, Board Meeting Minutes. Blaire Barker seconded. The motion passed unanimously. The votes were as follows: Courtnie

In compliance with the Americans with Disabilities Act, persons needing accommodations for this meeting should call 801-444-9378 to make appropriate arrangements. One or more board members may participate electronically or telephonically pursuant to UCA 52-4-207.

Moore, Aye; Danielle Pedersen, Aye; Dennis Henry, Aye; Blaire Barker, Aye; Janae Howell, Aye.

CLOSED SESSION- to discuss the character, professional competence, or physical or mental health of an individual pursuant to Utah Code 52-4-205(1)(a).

At 7:21 PM Dennis Henry made a motion to enter a closed session to discuss the character, professional competence, or physical or mental health of an individual pursuant to Utah Code 52-4-205(1)(a). Janelle Howell seconded. The motion passed unanimously. The votes were as follows: Courtnie Moore, Aye; Danielle Pedersen, Aye; Dennis Henry, Aye; Blaire Barker, Aye; Janae Howell, Aye.

At 7:33 PM Danielle Pedersen made a motion to leave the closed session. Janae Howell seconded. The motion passed unanimously. The votes were as follows: Courtnie Moore, Aye; Danielle Pedersen, Aye; Dennis Henry, Aye; Blaire Barker, Aye; Janae Howell, Aye.

ADJOURN

At 7:34 PM Danielle Pedersen made a motion to adjourn the meeting. Janae Howell seconded. The motion passed unanimously. The votes were as follows: Courtnie Moore, Aye; Danielle Pedersen, Aye; Dennis Henry, Aye; Blaire Barker, Aye; Janae Howell, Aye.

Voyage Academy
Board of Directors Closed Session
Meeting Date: 10.9.2025
Location: 1891 North 1500 West Clinton, UT 84015




CLOSED SESSION SWORN STATEMENT:

At a duly noticed public meeting held on the date listed above, the board of directors for Voyage Academy entered into a closed session for the sole purpose of discussing the character, professional competence, or physical or mental health of an individual in accordance with Utah Code Ann. 52-4-2(1)(a).

I declare under criminal penalty under the law of Utah that the foregoing is true and correct.

Signed on the 9th day of October 2025, at Clinton, Utah.

Courtne Moore, Board Chair



Signature



Play Structures



Voyage Academy Kinder Playground

Option 1





Play Power LT Farmington, Inc

Company Description & Qualifications

General Information:

Manufacturing Firm: Play Power LT Farmington, Inc.

Corporation Address: 878 E Highway 60

Monett, Missouri 65708

Phone: (800) 325-8828

Accts Payable Submit to: Play Power LT Farmington, Inc

PO Box 734155

Dallas, TX 75373-4155

Business: Play Power LT Farmington, Inc.
(Under current name since June 2004)

Previously know as: Little Tikes Commercial, Inc.

Iron Mountain Forge, now PlayPower LT started operations in 1979.

46 Years in Business!

President: Bryan Yeazel

Regional Sales Manager: Greg Sippel

Purchasing Associations: SourceWell (formerly NJPA), NASPO
Utah State Contract MA2568

Principal Agent: Michael Feidler - Primary Park and Play, LLC

Area: Utah and Southern Idaho

Phone: (801) 855-6213

Email: mike@primaryparkandplay.com

Qualifications:

PlayPower LT Farmington, Inc. is a division of Play Power, Inc. a publicly held company. Primary Park and Play, LLC is the sole distributor of Play Power LT Farmington, Inc (formerly know as Little Tikes Commercial, Inc.) in Utah and Southern Idaho.

Playground equipment and fall surfacing IPEMA Certified



PlayPower LT Farmington, Inc.
878 E. US Hwy 60
Monett, MO 65708
1-800-325-8828

QUOTE: OE25019810
CUSTOMER: VO09212
PROJECT: 25016372
DESIGN NAME: Voyage Kinder Opt 1

Bill To:
AMY MILLS
VOYAGE ACADEMY
1891 N 1500 W
CLINTON, UT 84015
801-668-0737 Ext. (phone)

Project Name & Location:
Voyage Academy
Attn: Voyage Academy Kinder
Playground

Prepared by:
PRIMARY PARK AND PLAY, LLC
Mike Feidler
MICHAEL TODD FEIDLER
SARATOGA SPRINGS, UT 84045

Ship To Address:
Amy Mills
Voyage Academy
1891 North 1500 West
Clinton, UT 84015, USA
(801) 668-0737 (phone)

End User:
Amy Mills
Voyage Academy
1891 North 1500 West
Clinton, UT 84015, USA
+18016680737 (phone)
amills@voyageacademyutah.org

Quote Number: OE25019810
Quote Date: 12/17/2025

Valid For: 30 Days From Quote Date

Kinder Option 1 PB Unit

Product line: PlayBuilders Age group: 5-12_ASTM

Global defaults

Infinity 1 Plastic Clr	CHARTREUSE
Infinity 2 Plastic Clr	SKY
Laminated Panel	BLUE WHITE BLUE LAMINATE
PB Ground Cover	BURIED
PB Panel/Crawl Tunnel Color	CHARTREUSE
PB Slide Color	SKY
PB Vinyl Clr	GRAY
Plastic Steering Wheel	CHARTREUSE
Play Builder Accent Color	RED
Play Builder Post Color	BLUE

Components

Part Number	Description	Qty	Weight	Volume	Unit Price	Total
100005274	Square Deck	2.00	77.00	2.92	983.00	1,966.00
100005350	Half-Square Deck	2.00	75.00	1.51	886.00	1,772.00
100005640	Triangle Deck	2.00	30.00	4.01	739.00	1,478.00
200054508	Sliding Pole, 1625mm (64") deck	1.00	51.00	15.48	843.00	843.00
200063639	Crawl Tunnel, arch top	1.00	100.00	35.06	2,141.00	2,141.00
200072938	TOOL BOX F/PLAY BUILDERS (MM)	1.00	5.00	0.36	0.00	0.00
200122443	Spiral Slide, 1625 mm (64")	1.00	378.00	187.69	6,840.00	6,840.00
200200196	Deck-To-Deck, 205 mm (8") with faces (accent color)	2.00	14.00	0.40	188.00	376.00
200200202	Deck-To-Deck, long, 205 mm (8") f/ split deck, with faces (accent color)	1.00	19.00	0.50	245.00	245.00
200200330	Double Wide Slide, 1220 mm (48") CSA	1.00	167.00	70.00	1,821.00	1,821.00
200200433	Transfer Station, 1220 mm (48") w/ safety rails	1.00	368.00	32.92	4,420.00	4,420.00
200200531	KIT MAINTENANCE PB W/O LIST PRICE	1.00	0.00	0.00	0.00	0.00
200200637	Infinity Boomerang 1015 mm (40")	1.00	245.00	415.00	4,933.00	4,933.00
200200650	Telescope Panel, PB, deck mt.	1.00	60.00	4.00	1,713.00	1,713.00

200200732	Steel Matching Game Panel, PB	1.00	40.00	4.00	2,272.00	2,272.00
200200973	Crawl Thru Panel PB, flat top (below deck only)	1.00	16.00	0.00	723.00	723.00
200201049	Balcony Deck w/ Rail with Telescope (telescope included)	1.00	110.00	21.00	2,500.00	2,500.00
200202438	Vertical Pod Climber 48"	1.00	105.00	27.00	2,086.00	2,086.00
200202615	PB 122" POST W/CAP	1.00	44.00	2.00	268.00	268.00
200202616	PB 130" POST W/CAP	5.00	47.00	2.10	276.00	1,380.00
200202617	PB 138" POST W/CAP	1.00	50.00	2.30	285.00	285.00
200202618	PB 146" POST W/CAP	7.00	53.00	2.40	304.00	2,128.00
200203193	Beatblocks Panel	1.00	55.00	2.00	1,531.00	1,531.00
200203206	Boingo	1.00	15.00	2.00	444.00	444.00
200203453	NU-Edge X Culvert Climber 40" PB	1.00	320.00	0.00	3,722.00	3,722.00
200203472	Activity Panel Frame Panel Deck Mount PB	1.00	40.00	0.70	537.00	537.00
200203477	Activity Panel A-Maze-Ing Insert	1.00	13.00	1.20	1,085.00	1,085.00
200203578	Steering Wheel, plastic, post mount PB	1.00	3.00	1.30	337.00	337.00
HW7704-1	HRDW PKG F/CLAMP ELIMINATION S1/1	2.00	1.00	0.00	52.00	104.00

RiskSign_Included

Product line: Freestanding

Global defaults

RISK MGNT SIGN CLR BLUE

Components

Part Number	Description	Qty	Weight	Volume	Unit Price	Total
787Z	RISK MANAGEMENT SIGN - ENGLISH	1.00	0.00	10.00	0.00	0.00

Additional Items

Part Number	Description	Qty	Weight	Volume	Unit Price	Total
105295	BAG ZIPLOCK 12" X 14"	1.00	0.00	0.00	1.03	1.03
200111492	Label, Identification stamped w/rivets	1.00	0.00	0.00	5.64	5.64
200305596	14' MED CRATE (ASSY DOMESTIC)	1.00	277.00	0.00	0.00	0.00
200305597	14' LARGE CRATE (ASSY DOMESTIC)	4.00	385.00	0.00	0.00	0.00
925603	LABEL P/C (5 TO 12 YRS) PPLT	3.00	1.00	0.00	8.14	24.42
925960	THUMB DRIVE 2GB - PPLT	1.00	0.00	0.00	0.00	0.00
INSTALL BK	INSTALL BOOK FOR PP ORDERS	1.00	0.00	0.00	0.00	0.00

Parts By Other

Part Number	Description	Qty	Weight	Volume	Unit Price	Total
EWF	Engineered Wood Fiber per Cubic Yard installed Enough to add 12" Depth across 1716 sq ft Area of new kinder playground and 3" depth across existing playgrounds 1978 sq ft area.	110	0.00	0.00	92.00	10,120.00
Fabric	Sq ft of landscape fabric installed under wood mulch Landscape fabric	1716	0.00	0.00	0.45	772.20

Totals:

Equipment Weight:	5,024.00 lbs
Equipment Volume:	879.49 ft ³
Equipment List:	\$47,981.09
Discount Amount:	-\$19,192.43
Equipment Price:	\$28,788.66
Products Subtotal:	\$28,788.66
Products by Other:	\$10,892.20
PBO Freight:	\$150.00
Installation:	\$15,800.00
Estimated Sales Tax*:	\$0.00
Freight:	\$5,518.80 Code: FTL
Grand Total:	\$61,149.66

Make Purchase Orders Out To:

PlayPower LT Farmington, Inc.
Remit Purchase Orders by email to:
mike@primaryparkandplay.com
PlayPower LT Farmington, Inc.
Attention: Sales Administration
878 E US Hwy 60
Monett, Missouri, USA 65708
1-800-325-8828

Make Checks Payable To:

PlayPower LT Farmington, Inc.
Remit Checks To:
PlayPower LT Farmington
PO Box 734155
Dallas, TX 75373-4155

NOTE:* Applicable sales taxes will be confirmed once order and any tax certificates are received

† Denotes drop ship item.

Unloading, storage, installation, surfacing and site work are not included unless specifically noted on quotation.

Not responsible for filter cloth, irrigation rerouting, grass damage, or checking for underground utilities.

If installation is quoted, it is assumed that the site has been prepared and that any grade slope in any direction does not exceed 2%. In the event that unexpected soil conditions, such as subsurface rock, are encountered during installation, additional costs to the customer will be applicable.

The acceptance signature below serves as authorization to order the items quoted and indicates acceptance of the prices listed. All terms are subject to credit approval.

COMMENTS: The Little Tikes Commercial playground equipment on this bid is available for purchase through the Utah State contract. NASPO Value Point Master Contract # 6485: Parks and Recreation Equipment and Related Services, State of UT Addendum MA2568

This playground contains 23.21% recycled content

This playground qualifies for 2 LEED point(s)

This Quote shall not become a binding contract until signed and delivered by both Customer and PlayPower LT Farmington Inc ("PPLT"). Sales Representative is not authorized to sign this Quote on behalf of PPLT or Customer, and signed Quotes cannot be accepted from Sales Representative. To submit this offer, please sign below and forward a complete signed copy of this Quote directly to "PPLT Sales Administration" via fax (417)354-2273 or email mike@primaryparkandplay.com. Upon acceptance, PPLT will return a fully-signed copy of the Quote to Customer (with copy to Sales Representative) via fax or e mail.

THIS QUOTE IS LIMITED TO AND GOVERNED BY THE TERMS CONTAINED HEREIN. PPLT objects to any other terms proposed by Customer, in writing or otherwise, as material alterations, and all such proposed terms shall be void. Customer authorizes PPLT to ship the Equipment and agrees to pay PPLT the total amount specified. Shipping terms are FOB the place of shipment via common carrier designated by PPLT. Payment terms are Net-30 days from invoice date with approved credit and all charges are due and payable in full at PO Box 734155, Dallas, TX 75373-4155, unless notified otherwise by PPLT in writing. Customer agrees to pay all additional service charges for past due invoices. Customer must provide proper tax exemption certificates to PPLT, and shall promptly pay and discharge all otherwise applicable taxes, license fees, levies and other impositions on the Equipment at its own expense.

CUSTOMER HEREBY SUBMITS ITS OFFER TO PURCHASE THE EQUIPMENT ACCORDING TO THE TERMS STATED IN THIS QUOTE AND SUBJECT TO FINAL APPROVAL BY PPLT.

Submitted By	Printed Name and Title	Date
THE FOREGOING QUOTE AND OFFER ARE HEREBY APPROVED AND ACCEPTED BY PLAYPOWER LT FARMINGTON INC.		

By: _____

Date: _____

ADDITIONAL TERMS & CONDITIONS OF SALE

Use & Maintenance. Customer agrees to regularly inspect and maintain the Equipment, and to provide, inspect and maintain appropriate safety surfacing under and around the Equipment, in accordance with PPLT's product literature and the most current Consumer Product Safety Commission Handbook for Public Playground Safety.

Default, Remedies & Delinquency Charges. Customer's failure to pay any invoice when due, or its failure to otherwise comply with the terms of this Quote, shall constitute a default under all unsatisfied invoices ("Event of Default"). Upon an Event of Default, PPLT shall have all remedies available to it at law or equity, including, without limitation, all remedies afforded a secured creditor under the Uniform Commercial Code. Customer agrees to assist and cooperate with PPLT to accomplish its filing and enforcement of mechanic's or other liens with respect to the Equipment or its location or its repossession of the Equipment, and Customer expressly waives all rights to possess the Equipment after an Event of Default. All remedies are cumulative and not alternative, and no exercise by PPLT of a remedy will prohibit or waive the exercise of any other remedy. Customer shall pay all reasonable attorneys' fees plus any costs of collection incurred by PPLT in enforcing its rights hereunder. Subject to any limitations under law, Customer shall pay to PPLT as liquidated damages, and not as a penalty, an amount equal to 1.5% per month of any payment that is delinquent in such month and is not received by PPLT within ten (10) days after the date on which due.

Limitation of Warranty/ Indemnity. PPLT MAKES NO EQUIPMENT WARRANTIES EXCEPT FOR THOSE STANDARD WARRANTIES ISSUED WITH THE EQUIPMENT, WHICH ARE INCORPORATED HEREIN BY THIS REFERENCE. PPLT SPECIFICALLY DISCLAIMS ANY IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE AND ANY LIABILITY FOR INCIDENTAL OR CONSEQUENTIAL DAMAGES. CUSTOMER AGREES TO DEFEND, INDEMNIFY AND SAVE PPLT HARMLESS FROM ALL CLAIMS OF ANY KIND FOR DAMAGES OF ANY KIND ARISING OUT OF CUSTOMER'S ALTERATION OF THE EQUIPMENT, ITS FAILURE TO MAINTAIN THE EQUIPMENT, ITS FAILURE TO PROPERLY SUPERVISE EQUIPMENT USE, OR ITS FAILURE TO PROVIDE AND MAINTAIN APPROPRIATE TYPES AND DEPTHS OF SAFETY SURFACING BENEATH AND AROUND THE EQUIPMENT IN ACCORDANCE WITH PPLT'S INSTALLATION AND OWNER'S MANUALS AND THE MOST CURRENT CONSUMER PRODUCT SAFETY COMMISSION HANDBOOK FOR PUBLIC PLAYGROUND SAFETY. 12/17/2025 Page 4 of 4

Restrictions. Until all amounts due hereunder are paid in full, Customer shall not: (i) permit the Equipment to be levied upon or attached under any legal process; (ii) transfer title to the Equipment or any of Customer's rights therein; or (iii) remove or permit the removal of the Equipment to any location not specified in this Quote.

Purchase Money Security Interest. Customer hereby grants, pledges and assigns to PPLT, and PPLT hereby reserves a purchase money security interest in, the Equipment in order to secure the payment and performance in full of all of Customer's obligations hereunder. Customer agrees that PPLT may file one or more financing statements, in order to allow it to perfect, acquire and maintain a superior security interest in the Equipment.

Choice of Law and Jurisdiction. All agreements between Customer and PPLT shall be interpreted, and the parties' obligations shall be governed, by the laws of the State of Missouri without reference to its choice of law provisions. Customer hereby consents to the personal jurisdiction of the state and federal courts located in the city and county of St. Louis, Missouri.

Title; Risk of Loss; Insurance. PPLT Retains full title to all Equipment until full payment is received by PPLT. Customer assumes all risk of loss or destruction of or damage to the Equipment by reason of theft, fire, water, or any other cause, and the occurrence of any such casualty shall not relieve the Customer from its obligations hereunder and under any invoices. Until all amounts due hereunder are paid in full, Customer shall insure the Equipment against all such losses and casualties.

Waiver; Invalidity. PPLT may waive a default hereunder, or under any invoice or other agreement between Customer and PPLT, or cure such a default at Customer's expense, but shall have no obligation to do either. No waiver shall be deemed to have taken place unless it is in writing, signed by PPLT. Any one waiver shall not constitute a waiver of other defaults or the same kind of default at another time, or a forfeiture of any rights provided to PPLT hereunder or under any invoice. The invalidity of any portion of this Quote shall not affect the force and effect of the remaining valid portions hereof.

Entire Agreement; Amendment; Binding Nature. This fully-executed Quote, as supplemented by Change Orders and invoices containing exact amounts of estimates provided herein, constitutes the complete and exclusive agreement between the parties. A Change Order is a written instrument signed by the Customer and PPLT stating their agreement as to any amendment in the terms of this Quote. Customer acknowledges that Change Orders may result in delays and additional costs. The parties agree that all Change Orders shall include appropriate adjustments in price and time frames relating to any requested amendments. Upon full execution, this Quote shall be binding upon and inure to the benefit of the parties and their successors and assigns.

Counterparts; Electronic Transmission. This Quote, any invoice, and any other agreement between the parties, may be executed in counterparts, each of which shall constitute an original. The facsimile or other electronic transmission of any signed original document, and retransmission of any signed facsimile or other electronic transmission, shall be the same as the transmission of an original. At the request of either party, the parties will confirm facsimile or other electronically transmitted signatures by signing an original document.










GENERAL NOTES

AGE GROUP

- 2-5 YRS 5-12 YRS 13-17 YRS 1. THE AGE GROUPS WITH DISABILITIES ACT (ADA) MAY REQUIRE THAT YOU MAKE YOUR PARK AND/OR PLAYGROUND ACCESSIBLE WHEN VIEWED IN ITS ENTIRETY. PLEASE CONSULT YOUR LEGAL COUNSEL TO DETERMINE IF THE ADA APPLIES TO YOU.
2. ALL PLAYGROUND EQUIPMENT MUST BE UTILIZED IN APPROPRIATE AREAS.
3. ALL EQUIPMENT MUST BE UTILIZED IN APPROPRIATE AREAS. THE APPROPRIATE NUMBER OF GROUND LEVEL EVENTS IS SHOWN. CONSIDERING EXISTING PLAY COMPONENTS.
4. ALL DECK HEIGHTS ARE MEASURED FROM TOP OF GROUND COVER. FALL ABSORBING GROUND COVER IS REQUIRED.
5. ALL PLAY EQUIPMENT MUST BE UTILIZED IN APPROPRIATE AREAS.
6. ALL PLAY EQUIPMENT MUST BE UTILIZED IN APPROPRIATE AREAS. FALL ZONE AROUND THE ENTIRE PLAYSTRUCTURE IS SHOWN. HAZARDOUS (I.E. ROOTS) ROCK BONDERS.
7. MATERIAL ETC. ALL POST LENGTHS ARE IDENTIFIED BY TEXT. POST LENGTHS (I.E. 16' REPRESENTS A 16' INCH POST).
8. NOT ALL EQUIPMENT MAY BE APPROPRIATE FOR ALL CHILDREN. SUPERVISION IS REQUIRED.

Existing Playground pit here



Add 8" wide curb on 3 sides. Height varies from 12" tall up to 24" tall based on surrounding ground elevation

47 ft. 8 in.

Inside Curb Size 36'X47'8"

36 ft. 0 in.

Remove Curb between play pits

Existing ADA Entry Ramp / Sidewalk

THE PLAY COMPONENTS IDENTIFIED IN THIS PLAN ARE IPEDMA CERTIFIED. THE USE AND LAYOUT OF THE COMPONENTS CONFORM TO THE REQUIREMENTS OF ASTM F1487.



THIS PLAYGROUND DESIGN MEETS THE FINAL ACCESS BOARD REGULATION.

- ☒ ASTM F1487 - PLAYGROUND EQUIPMENT FOR PUBLIC USE
- ☒ CPSC HANDBOOK FOR PUBLIC PLAYGROUND SAFETY

PLAYGROUND LAYOUT COMPLIANCE:

PROJECT: Voyage Academy Kinder Opt 1
Clinton, Utah
LTCPS REP: Mike Felder
PRIMARY PARK AND PLAY, LLC
801-855-6213

GROUND SPACE: 22'-6" x 28'
PROTECTIVE AREA: 34' x 39'-6"

DRAWN BY: Mike Felder
DATE: 12/16/2025
PROJECT: 25016372

LTCPS - FARMINGTON
878 EAST HIGHWAY 60
MONETT MO 65708
VOICE: 1-800-325-8828
FAX: 417-354-2273



SPECIFICATIONS – PLAYGROUND EQUIPMENT – KINDER OPT. 1

PART 1 – GENERAL

- 1.1 Description: OE25019810 Voyage Academy Kinder Playground
- 1.2 Quality Assurance:
 - 1 Equipment and Design Qualifications:
 - 1 All playground equipment shall comply will all the requirements of CPSC, ASTM, ADA and will be IPEMA certified.
 - 1 All safety fall zones shall be determined in accordance with ASTM 1487-07 and CPSC Handbook for Public Playground Safety Publication number 325. All playground equipment designs shall be evaluated and signed off by a NPSI certified playground inspector.
- 1.3 Manufacturer Qualifications:
 - 1 The manufacturer of the playground equipment must carry a minimum of 5 million dollars of liability insurance with an AM best rating. The manufacturer of the playground equipment must have a minimum of 10 years experience in manufacturing commercial playground equipment.
- 1.4 Applicable Standards
 - 1.4.1 ASTM F1487-07
Standard consumer performance specification for playground equipment for public use.
 - 1.4.2 CPSC Handbook for Public Playground Safety, publication number 325.
 - 1.4.3 CSA Z614-20
 - 1.4.4 EN 1176-98 (if requested) European Standard for Playground equipment
 - 1.4.5 All manufactured components must be IPEMA certified International Playground Equipment Manufacturers Association.

PART 2 – PRODUCTS

2.1	
Part Number	Description
100005274	Square Deck
100005350	Half-Square Deck
100005640	Triangle Deck
105295	BAG ZIPLOCK 12" X 14"
200054508	Sliding Pole, 1625mm (64") deck
200063639	Crawl Tunnel, arch top
200072938	TOOL BOX F/PLAY BUILDERS (MM)
200111492	Label, Identification stamped w/rivets

200122443	Spiral Slide, 1625 mm (64")
200200196	Deck-To-Deck, 205 mm (8") with faces (accent color)
200200202	Deck-To-Deck, long, 205 mm (8") f/ split deck, with faces (accent color)
200200330	Double Wide Slide, 1220 mm (48") CSA
200200433	Transfer Station, 1220 mm (48") w/ safety rails
200200531	KIT MAINTENANCE PB W/O LIST PRICE
200200637	Infinity Boomerang 1015 mm (40")
200200650	Telescope Panel, PB, deck mt.
200200732	Steel Matching Game Panel, PB
200200973	Crawl Thru Panel PB, flat top (below deck only)
200201049	Balcony Deck w/ Rail with Telescope (telescope included)
200202438	Vertical Pod Climber 48"
200202615	PB 122" POST W/CAP
200202616	PB 130" POST W/CAP
200202617	PB 138" POST W/CAP
200202618	PB 146" POST W/CAP
200203193	Beatblocks Panel
200203206	Boingo
200203453	NU-Edge X Culvert Climber 40" PB
200203472	Activity Panel Frame Panel Deck Mount PB
200203477	Activity Panel A-Maze-Ing Insert
200203578	Steering Wheel, plastic, post mount PB
200305596	14' MED CRATE (ASSY DOMESTIC)
200305597	14' LARGE CRATE (ASSY DOMESTIC)
787Z	RISK MANAGEMENT SIGN - ENGLISH
925603	LABEL P/C (5 TO 12 YRS) PPLT
925960	THUMB DRIVE 2GB - PPLT
HW7704-1	HRDW PKG F/CLAMP ELIMINATION S1/1
INSTALL	INSTALL BOOK FOR PP ORDERS
BOOK	

- 2 Manufacturer: PlayPower Operations, Monett, Missouri
- 2 General Equipment Specifications:
 - 2 Plastic Caps shall fit snugly into 127 mm (5") and 33 mm (1.315") tube ends and shall be injection molded Low Density Polyethylene. This plastic shall be stabilized against ultraviolet (UV) degradation and shall have color molded in. All caps will be installed at the factory and 127 mm (5") caps will be secured with aluminum hammer drive pins.
 - 2 Aluminum Caps shall fit snugly into 127 mm (5") tube ends. The Aluminum cap shall be made from SAE 413 aluminum with a minimum wall thickness of 4 mm. Prior to insertion into the post, all caps shall be painted per PPLT PAINT Specification. All caps will be installed at the factory and 127 mm (5") caps will be secured with aluminum hammer drive pins.

- 2.3.3 PPLT PAINT Specification: Primer shall be electrostatically applied and cured in an infrared oven. Paint shall be an electrostatically applied polyester TGIC (triglycidyl isocyanurate) powder coating which shall be cured at temperatures between 400 and 500 degrees Fahrenheit. The thickness of the combined primer/paint shall be between 5 mils and 11 mils. The polyester powder shall comply with ASTM standards: D-2794 (Impact Resistance Test), B-117 (Salt Spray Resistance Test), G26 (Weatherability Test), and D3359B (Adhesion Crosshatching Test). Page 3 of 8
- 2.3.4 PlayPower Operations ROTO Specification: Rotationally Molded Plastic Parts shall be molded from linear low density polyethylene with ultraviolet (UV) light stabilizers, anti-static guard (for Molding purposes) and color molded in. This material shall comply with ASTM-D-790 (Flex Modulus), ASTM -D-638 (Tensile Strength), ASTM-D-648 (Heat Deflection Temperature), ARM-STD (Low Temperature Impact) and rated UL 94.
- 2.3.5 PPLT PVC Specification: Textured Poly-Vinyl-Chloride coating shall be an average of 3 mm (.125") thick. Poly-vinyl-chloride coating shall be oven cured and textured for added traction when wet or dry.
- 2.3.6 Hardware: Bolts, Nuts, Screws, Threaded Spacers, Washers and Other Hardware used in the assembly of components shall be metric stainless steel and tamper resistant. All necessary hardware shall be provided.
- 2.3.7 Deck Clamp assemblies shall consist of two steel half-clamps. Clamp profiles shall be designed to eliminate protrusions. Clamps shall be die formed from 12 gauge HRPO steel. Clamps shall have a 6 mm (.25") radius rib formed in the top and bottom of the clamp for structural integrity. The clamp attachment bracket shall be formed from 11 gauge sheet steel and shall be welded securely to the clamp half. All clamp halves shall be zinc plated, yellow dichromate coated and phosphate coated before being TGIC (triglycidyl isocyanurate) polyester powder coated. Tamper-resistant fasteners shall be used to retain clamps and shall consist of M10 six lobe socket head stainless steel cap screws and M10 slab-base Tee nuts. All clamps shall be provided with aluminum hammer drive pins to protect against slippage.
- 2.3.8 Rail Clamp assemblies shall consist of two steel half-clamps. Clamp profiles shall be designed to eliminate protrusions. Clamps shall be die formed from 12 gauge HRPO steel. Clamps shall have a minimum 6 mm (.25") radius rib formed in the top and bottom of the clamp for structural integrity. All clamp halves shall be zinc plated, yellow dichromate coated and phosphate coated before being TGIC (triglycidyl isocyanurate) polyester powder coated. Tamper-resistant fasteners shall be used to retain clamps and shall consist of M10 six lobe socket head stainless steel cap screws and M10 slab-base Tee nuts. All clamps shall be provided with aluminum hammer drive pins to protect against slippage.

- 2.3.9 Wing and Panel Clamp assemblies shall consist of two steel half-clamps. Clamp profiles shall be designed to eliminate protrusions. Clamps shall be die formed from 12 gauge HRPO steel. Clamps shall have a 6 mm (.25") radius rib formed in the top and bottom of the clamp for structural integrity. The clamp wing bracket shall be formed from 7 gauge sheet steel and shall be welded securely to the clamp half. All clamp halves shall be zinc plated, yellow dichromate coated and phosphate coated before being TGIC (triglycidyl isocyanurate) polyester powder coated. Tamper-resistant fasteners shall be used to retain clamps and shall consist of M10 six lobe socket head stainless steel cap screws and M10 slab-base Tee nuts. All clamps shall be provided with aluminum hammer drive pins to protect against slippage. Page 4 of 8
- 2.3.10 All Steel Tube Components shall comply with ASTM standards: A-500, Or A-513. The steel tube components contain five layers including an inside galvanized coating, high tensile strength cold formed steel, hot dipped pure zinc meeting ASTM B-6 applied at 3.5 tenths of an ounce per square foot, and a proprietary conversion and advanced polymer coatings. The components are freed of excess weld spatter and shall be cleaned in a multiple bath system which shall include a rust-inhibitive iron phosphate wash prior to painting. Exceptions: 127 mm (5") O.D. aluminum posts.
- 2.3.11 Brackets shall be fabricated from punched and formed 4.5 mm pre-galvanized sheet steel.
- 2.3.12 Gaskets shall be rubber injection molded from ultraviolet (U.V.) protected synthetic rubber. Rubber gaskets shall provide an aesthetic seal around the wonder fastener and bracket.
- 2.3.13 Footing for 127 mm (5") diameter upright posts shall be 305 mm (12") diameter x 940 mm (37") depth. Galvanized steel posts shall be 127 mm (5") O.D., 11 gauge pre-galvanized round tubing. Minimum tensile strength shall be 330MPa (48,000 psi). Minimum yield point shall be 310MPa (45,000 psi). The bottom portion of all upright posts shall be crimped slightly
- 2.3.14 Component Specifications:
- 2 360° SPIRAL SLIDE (U.S. Patent #D335,517) WITH HOOD shall be two piece with a seamless bedway, rotationally molded per PPLT ROTO Specification. Slide side rails shall be a minimum of 355 mm (14) high from the slide surface. Center post shall be 89 mm (3.5) pre-galvanized tubing. Spiral slide shall provide a full 360° of rotation. Slide transition decks shall be fabricated from punched sheet steel and shall cover a minimum of 0.7 square meters (1,080 square inches) of top surface. This assembly shall be coated per PPLT PVC Specification. Slide enclosures shall be

fabricated from 33 mm (1.315") O.D. and 3/4 X 1 FSO pre-galvanized steel tubing. Slide enclosures shall have no gaps greater than 76 mm (3") and less than 254 mm (10"), especially between vertical rungs and posts. All steel components shall be painted per PPLT PAINT Specification.

- 2 ACTIVITY PANEL INSERTS shall be fabricated from a combination of routed high density polyethylene, 4.7mm (3/16) screen printed polycarbonate, and 6.35mm (1/4) mirrored polycarbonate. Hardware used shall be stainless steel and tamper resistant.
- 2 BEATBLOCKS PANEL shall be constructed from 19mm (3/4") thick high density polyethylene sheet. Support shall be constructed from 33mm (1.315") O.D. and 25mm (1") O.D. pre-galvanized steel tubing welded to 7ga. (4.5mm) thick plates and painted per PPLT PAINT Specification.
- 2 Boingo Drum shall be rotationally molded per PPLT ROTO Specification. Support ring shall be constructed from 19mm (3/4") thick high density polyethylene sheet. Support shall be constructed from 33mm (1.315") O.D. pre-galvanized steel tubing welded to 7ga. (4.5mm) thick plates and painted per PPLT PAINT Specification.
- 2 COLORED KICK PLATE AND DECK TO DECK ACTIVITY PLATES shall be fabricated from 13 gauge (2.3 mm) pre-galvanized sheet steel for the 8", 12", and 16" models and shall have fun faces laser cut into them. The 24", 28", and 32" models shall be fabricated from 11 gauge (3.0 mm) pre-galvanized sheet steel. After fabrication, deck to deck plates shall be painted per PPLT PAINT Specification. 24", 28" and 32" plates shall have grooves cut into them with optional slider "Parachute/shapes" fabricated from CNC Routed high density polyethylene sheet.
- 2 CRAWL TUNNELS shall have an approximate internal diameter area of 762 mm (30). Tunnel and panel shall be rotationally molded per PPLT ROTO Specification.
- 2 DOUBLE WIDE SLIDES shall be rotationally molded per PPLT ROTO Specification. Plastic double wide slide sides shall be 203 mm (8) high from the slide surface and slide bedway shall be designed with a 406 mm (16") minimum width. Double wide slide shall be a one-piece design with a center divider having no seams, joints or gaps. Slide end support shall be fabricated from 38 mm (1.5) square tubing. Mid support shall be fabricated from 60.3 mm (2.37) tubing. All steel tubing shall be painted per PPLT PAINT Specification.

2.3.15. ~~Identification~~ label shall be fabricated from aluminum sheet .016 (4 mm) thick and attached with aluminum pop rivets. Page 6 of 8

2.3.15. ~~INFINITY CLIMBER BOOMERANG~~ climbers shall be rotationally molded per PPLT ROTO Specification. The Support posts shall be fabricated from 88.9mm (3.5") 11 ga pre-galvanized tubing with 11 ga pre-galvanized sheet steel tabs. Enclosure shall be fabricated from 33.4 mm (1.312) O.D. and 42.2 mm (1.66) O.D. pre-galvanized steel tubing with 11 ga pre-galvanized sheet steel tabs. The Support posts and Enclosures shall be painted per PPLT PAINT Specification.

2.3.15. ~~PB~~ ACTIVITY PANEL FRAME shall be fabricated from routed 19 mm (3/4) high density polyethylene. Mounting tabs shall be fabricated from pre- galvanized 4.5 mm (.18) 7 gauge sheet steel. Hardware used shall be stainless steel and tamper resistant. All steel shall be painted per PPLT PAINT Specification.

2.3.15. ~~PB~~ Balcony Decks w Handrails: Decks shall be fabricated from 11 gauge hot rolled steel which shall be punched, formed and welded. This assembly shall be coated per PPLT PVC Specification.. Handrails shall be fabricated from 33.4 mm (1.3) and 25.4 mm (1) x 19 mm (3/4) ob-round pre-galvanized steel tubing and 11 ga pre-galvanized sheet steel with laser cut detailing and shall be an all welded construction. Handrails shall be painted per PPLT PAINT Specification.

2.3.15. ~~PB~~ CULVERT CLIMBER pods shall be made from pre-galvanized 305 mm (12") 16ga corrugated metal pipe and shall be welded to plates made from 7 ga and 11 ga pre-galvanized sheet steel. The top of the pods shall be covered with CNC routed HPDE. Handrails (when necessary) shall be fabricated from 42.2 mm (1.7") O.D. pre-galvanized tubing. Enclosures shall be fabricated from 33 mm (1.315) O.D. pre-galvanized steel tubing and 3 mm (11 ga) pre-galvanized sheet steel. All steel components shall be painted per PPLT PAINT specification.

2.3.15. ~~PB~~ Telescope Panels shall be fabricated from a combination of 33.4 mm (1.312") O.D. pre-galvanized steel tubing, 19mm X 25.4mm obround pre- galvanized steel tubing, and laser cut plates fabricated from 3.0mm (11 gauge) pre-galvanized sheet steel. Telescopes shall be molded per PPLT ROTO Specification. Panels shall be painted per PPLT PAINT Specification.

2.3.15. ~~PB~~ WEATHER PANEL shall be fabricated from 33.4 mm (1.312") O.D. and 25.4 mm (1) O.D. pre-galvanized steel tubing. Panel and side plates shall be fabricated from 3 mm (11 gauge)

sheet steel. Assembly shall contain a specific weather activity insert assembled from various thickness of compression molded polyethylene and polycarbonate routed with various weather activities. Prior to assembly, panel shall be painted per PPLT PAINT Specification.

- 2 SLIDING POLE shall be fabricated from 42.2 mm (1.66) O.D. pre-galvanized steel pipe. Enclosure shall be fabricated from 33 mm (1.315) O.D. and 3/4 X 1 FSO pre-galvanized steel tubing. After fabrication all components shall be painted per PPLT PAINT Specification.
- 2 SQUARE VINYL CLAD METAL DECK shall cover a minimum of 1.03 square meters (1,596 square inches) of top surface area. Metal decks shall be fabricated from punched and formed 11 gauge hot rolled sheet steel. This assembly shall be coated per PPLT PVC Specification.
- 2 STEEL POST shall be 89 mm (3.5") O.D., 11 gauge pre-galvanized round tubing. Minimum tensile strength shall be 380MPa (55,000 psi). Minimum yield point shall be 345MPa (50,000 psi). Plastic caps shall be positioned in the top of each post. Posts shall be painted per PPLT PAINT Specification.
- 2 The plastic panel shall be molded per PPLT ROTO Specification. Panel mounting brackets shall be fabricated from 7 gauge, pre-galvanized sheet steel and dichromate washed. After fabrication, all steel components shall be painted per PPLT PAINT Specification
- 2 TRANSFER STATION WITH SAFETY RAIL shall consist of two triangular decks and step assemblies for the handrails. Each triangular deck shall be fabricated from 11 gauge sheet steel, covering .37 square meters (575 square inches) and have three 25 x 152 mm (1" x 6") hand slots incorporated into the deck surface for aid in user transition. The step assemblies provide access from the transfer decks to a 915 mm (36"), 1016 mm (40), 1220 mm (48), 1422 mm (56), 1625 mm (64) deck height. Each step shall have a tread depth of 406 mm (16") and a tread width of 953 mm (37.5"), with each rise 203 mm (8") or less. Each step assembly shall have an all welded construction from 13 gauge sheet steel. Each step assembly and Transfer Deck shall be coated per PPLT PVC Specification. Transfer Station handrails shall be fabricated from 33 mm (1.315") O.D. pre-galvanized, 14 gauge tubing and 3/4 X 1 FSO pre-galvanized tubing. Safety rails shall provide an enclosure and shall have no gaps greater than 80 mm (3.15") and less than 254 mm (10"), especially between vertical rungs and posts. Transfer Station loops shall be fabricated from 42.2 mm

(1.66") O.D., pre-galvanized, 10 gauge tubing. All welded handrail assemblies shall be painted per PPLT PAINT Specification.

2.3.15. ~~VERTICAL~~ VERTICAL POD CLIMBERS shall be fabricated from 42.2 mm (1.66") x 11 gauge pre-galvanized steel tubing. Plates shall be fabricated from 3 mm (.12") sheet steel. Pods shall be fabricated from E.P.D.M. 50 duro rubber with a steel insert molded inside. Enclosures shall be fabricated from 33 mm (1.315) O.D. pre-galvanized steel tubing and 3 mm (11 gauge) pre-galvanized sheet steel. After fabrication all steel parts shall be painted per PPLT PAINT Specification. Page 8 of 8

2.3.15. ~~VINYL~~ VINYL CLAD HALF DECK shall cover a minimum of .52 square meters (798 square inches) of top surface area. Metal decks shall be fabricated from punched and formed 11 gauge hot rolled sheet steel. This assembly shall be coated per PPLT PVC Specification.

2.3.15. ~~VINYL~~ VINYL CLAD TRIANGLE DECK shall cover a minimum of .45 square meters (680 square inches) of top surface area. Metal decks shall be fabricated from punched and formed 11 gauge hot rolled sheet steel. This assembly shall be coated per PPLT PVC Specification.

WARRANTY

Little Tikes Commercial warrants its products against structural failure due to defects in materials and workmanship for the warranty periods and material categories prescribed below.

Buyer agrees that products sold by PPLT Farmington, Inc. (PlayPower Little Tikes Commercial) carry only the following warranties:

1. LIMITED WARRANTY FOR AS LONG AS YOU OWN THE

PRODUCT: Aluminum deck posts, steel deck posts, stainless steel hardware, cast aluminum parts, and KidBuilder® steel clamps.

LIMITED FIFTEEN (15) YEAR WARRANTY: All rigid steel playground components, decks, steps, and weldments, rotationally molded and sheet plastic components, plastic lumber, roof panels, and stainless steel slides, except as otherwise specified below.

3. LIMITED TEN (10) YEAR WARRANTY: Fabric shade steel frames, Naturtek™ products, Shadesure™ and Colourshade FR fabrics (Note Exception: Limited Five (5) Year Warranty on Shadesure™ fabrics in colors Red, Yellow, Electric Purple, Zesty Lime, Cinnamon, and Olive.)

4. LIMITED EIGHT (8) YEAR WARRANTY:

- Fiberglass signage, precast PolyFiberCrete or precast concrete products.
- Integrated Shade fabric and components against rot, UV deterioration and defects in materials and workmanship (Note Exception: Limited Three (3) Year Warranty for fabric in shade of red).

5. LIMITED FIVE (5) YEAR WARRANTY:

- Clever Climbers™ products, including, but not limited to polyethylene slides, enclosures, main structure, decks, and plastic components.
- PVC coating and PE coating against cracking or peeling.
- Park and Site Amenities (i.e. benches, tables, trash receptacles, etc.).
- GFRP (Glass Fiber Reinforced Polymer) Products.
- Steel core cable nets and rope fittings and connections (Note Exception: Warranty does not cover normal wear and tear such as fraying or fading of cable coating).
- Accessible swing seats latch and hinge mechanism.
- Concerto products (Note Exception: Warranty does not cover mallets or Tall Chime cable assemblies).

6. LIMITED THREE (3) YEAR WARRANTY: KidTiles®, Playground Sculptures, products flexible belting, plastic border timbers and accessories, and electronic panel speakers, sound chips, and circuit boards.

7. LIMITED ONE (1) YEAR WARRANTY:

- Learning Lab Sensory Tables and Tot Tree plastic components.
- Belt Swing Seats, and Bucket Tot Swing Seats.
- All other products, components and custom pieces that are not specifically listed above, including, without limitation, all moving parts, such as swing hangers and bearings, swivels, chains, whirly, springs and flexible components, and all high wear items, such as trolleys, cables, wheels, and bumper stops related to rail and cable ride products.

8. LIMITED SIX (6) MONTH WARRANTY:

- PlaySoleil™ solar-powered light.

BUYER'S REMEDY: If any products prove defective or non-conforming under normal use and within the above-prescribed warranty periods and material categories, Buyer must promptly notify Little Tikes Commercial in writing at 878 E. Hwy 60, Monett, MO 65708 USA. Little Tikes Commercial does not warrant that any particular color will be available for any period of time, and reserves the right to discontinue any color for any reason, without recourse by the Purchaser or Owner of the discontinued color. Little Tikes Commercial may elect to inspect the alleged defect at Buyer's site or at Little Tikes Commercial's facility. Buyer shall not return products to Little Tikes Commercial unless authorized by Little Tikes Commercial to do so.

Authorized returns must be properly packaged and shipped prepaid and insured, at Buyer's expense. Upon verification of warranty coverage, Little Tikes Commercial may elect, in its sole discretion, to repair defective or non-conforming products, or replace them by delivering products or part(s) of similar functionality free of charge to the site. Little Tikes Commercial's limited warranties do not cover the cost of labor to remove defective or non-conforming part(s) or to install repaired or replacement part(s). By use of these limited warranties, Buyer accepts their terms and limitations, and waives any rights it would otherwise have to claim or assert that such warranties fail of their essential purpose. Buyer agrees that venue for any court action to enforce these limited warranties shall be in Barry or Greene Counties in the State of Missouri.

LIMITATIONS: All warranty periods begin on the date of Little Tikes Commercial's invoice. Repaired and/or replacement part(s) are warranted only for the balance of the original limited warranty period. Warranties extend only to the original Buyer/end user for products purchased from Little Tikes Commercial or a Little Tikes Commercial authorized reseller and are not transferable.

Warranties apply only to Little Tikes Commercial products that are erected and installed in conformance with Little Tikes Commercial's installation instructions, and that are maintained and inspected in conformance with Little Tikes Commercial maintenance and operational instructions.

Warranties specifically do not cover Little Tikes Commercial products:

- for cosmetic damage or flaws occurring under normal use, such as surface scratches, minor chips, hairline cracks, dents, marring, efflorescence, color fade (except for shade fabric as noted above), discoloration, corrosion/rust, fraying, or warping of recycled plastic lumber;
- that have been modified, altered, or repaired by unauthorized third parties;
- that have not been used as designed or intended, or misused;
- to which non-Little Tikes Commercial parts have been added or substituted;
- that have been removed from their original location and re-installed elsewhere, without pre-approval by Little Tikes Commercial;
- or that have been damaged due to excessive wear and tear, vandalism, abnormal use, abuse, negligence, environmental factors (such as windblown sand, salt spray, or airborne emissions from industrial sources), extreme weather (such as hail, flooding, lightning, tornados, sandstorms, earthquakes, or wind storms), and acts of God.

Little Tikes Commercial does not warrant that any particular color will be available for any specific period of time, and reserves the right, in its sole discretion, to discontinue any color for any reason.

THE FOREGOING LIMITED WARRANTY IS THE SOLE AND EXCLUSIVE WARRANTY FOR SELLER'S PRODUCTS, AND IS IN LIEU OF ALL OTHER WARRANTIES, EXPRESS OR IMPLIED, IN LAW OR IN FACT. SELLER SPECIFICALLY DISCLAIMS ALL OTHER WARRANTIES, EXPRESS OR IMPLIED, INCLUDING, WITHOUT LIMITATION, ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR USE OR PURPOSE, AND ANY IMPLIED WARRANTIES ARISING OUT OF COURSE OF DEALING OR PERFORMANCE OR TRADE USAGE. SELLER SHALL NOT BE LIABLE FOR ANY INCIDENTAL, CONSEQUENTIAL, EXEMPLARY, SPECIAL, OR PUNITIVE DAMAGES, OR ANY LOSS OF REVENUE, PROFIT OR USE, ARISING OUT OF A BREACH OF THIS WARRANTY OR IN CONNECTION WITH THE SALE, INSTALLATION, MAINTENANCE, USE, OPERATION OR REPAIR OF ANY PRODUCT. IN NO EVENT WILL SELLER BE LIABLE FOR ANY AMOUNT GREATER THAN THE PURCHASE PRICE OF A DEFECTIVE PRODUCT.



IPEMA ASTM F1292-22 CERTIFICATE OF COMPLIANCE

ISSUE DATE: December 17, 2025

Requested By: Primary Park and Play

Project: Voyage Academy

In the interest of public playground safety, IPEMA provides a third-party certification service whereby TOV SOD American validates a manufacturer's certification of conformance to ASTM F-1292-22 Standard Specification for Impact Attenuation of Surfacing Materials within the Use Zone of a Playground.

The manufacturers listed below have received written validation from TOV SOD America that the products listed conform with the requirements of ASTM F1292-22.

TOV SOD America validates that the impact attenuating performance criterion specified by ASTM F1292-22 has been met or exceeded.

MODEL # COMMERCIAL NAME OF PRODUCT

SWSPS1 PlaySoft

PRODUCT LINE THK/HT MANUFACTURER

PlaySoft

12" / 12' Pioneer Landscape Centers