



## NOTICE AND AGENDA

### BRIGHAM CITY COUNCIL MEETING

Thursday, February 5, 2026 5:30 PM

City Council Chambers, 20 North Main

To View Live Meeting Visit:

<https://www.bcutah.gov/mayor-and-city-council.htm> or

[www.youtube.com/brighamcitycorp](http://www.youtube.com/brighamcitycorp)

**5:30 WORK SESSION ANNUAL TRAINING ON OPEN AND PUBLIC MEETINGS, NETWORK SECURITY, CONFLICT OF INTEREST AND ETHICS STATEMENT**

**6:00 REGULAR COUNCIL MEETING**

Thought, Reading, or Invocation: Bishop Eric Olsen, Brigham City 21<sup>st</sup> Ward  
Pledge of Allegiance

**6:03 CONSENT**

1. Approval of January 15, 2026 City Council Meeting Minutes
2. Appointment of Vice Chair of Planning Commission and Joint Advisory Board

**6:04 EMPLOYEE RECOGNITION**

1. New Hire in the Power Department

**6:05 PUBLIC COMMENTS** <sup>1</sup> *(Per Utah Code, Council will receive input only, no decision can be made)*

**6:10 COUNCILMEMBER COMMENTS**

**6:15 ACTION ITEMS**

1. Consideration of Approval of Updates to the Power Standards Manual – Tom Cooper
2. Consideration of Resolution Declaring Certain Two-Way Radio Equipment Surplus and Authorizing Donation to Box Elder County – Tom Kotter

**6:35 CLOSED SESSION**

Consideration to enter a closed session to discuss: purchase/exchange/lease of real property; pending litigation; cyber security; or character/professional competence or physical/mental health of an individual.

Assigned times may vary depending on discussion length or agenda alteration. ADA Notice: Individuals needing special accommodations should contact the City Recorder at 435-734-6621 at least 48 hours before the meeting. Councilmembers may participate electronically.

**CERTIFICATE OF POSTING**

The undersigned duly appointed City Recorder certifies the above notice was posted in three public places within the Brigham City limits, and on the City and State Public Meeting Notice websites on February 4, 2026. A copy was also provided to the Box Elder New Journal.

Kristina Rasmussen, City Recorder

---

<sup>1</sup> Each individual is limited to three minutes. Total input period is limited to 15 minutes.

1  
2  
3  
4  
**REGULAR SESSION OF THE  
BRIGHAM CITY COUNCIL  
JANUARY 15, 2026  
6:00 p.m.**

5 **PRESENT:** DJ Bott Mayor  
6 Dave Hipp Councilmember  
7 Dave Jeffries Councilmember  
8 Matthew Jensen Councilmember  
9 Ryan Smith Councilmember  
10 Robin Troxell Councilmember

11 **ALSO PRESENT:** Mark Bradley City Planner  
12 Tom Cooper Power Director  
13 Nicole Cottle City Attorney – *Arrived at 6:07*  
14 Tom Kotter Community and Economic Development Director  
15 Derek Oyler City Administrator  
16 Tyler Pugsley Assistant City Administrator  
17 Kristina Rasmussen City Recorder  
18 Chief Reyes Police Chief  
19 Chief Thueson Fire Chief

20 Mayor Bott called the meeting to order at 6:00 p.m. The invocation was offered by Bishop Mark Wilcox  
21 of the Brigham City 7th Ward. The Pledge of Allegiance followed.

22 **SWEARING IN OF NEWLY ELECTED CITY COUNCIL MEMBERS AND MAYOR**

23 The Mayor opened the meeting with the Swearing In and Oaths of Office for re-elected City Council  
24 members and the Mayor. He stated that Judge Morgan, a longtime friend of the City, had been invited to  
25 administer the oaths. Council Member Jensen and Council Member Smith were invited to join the Mayor  
26 at the front of the chambers. Judge Morgan administered the oath of office.

27 **ELECTION OF MAYOR PRO TEMPORE**

28 The Mayor then moved to the Election of the Mayor Pro Tempore for the new year and asked for  
29 nominations from the Council. Councilmember Jensen nominated Councilmember Hipp, and the motion  
30 was seconded by Councilmember Smith. The motion was approved.

31 **CONSENT AGENDA**

32 Mayor Bott introduced five consent items:

- 33 1. Approval of the December 18, 2025 City Council Meeting Minutes.  
34 2. Request to Write Off Utility Accounts totaling \$7,208.60 due to accounts being sent to  
35 collections.  
36 3. Appointments to the Planning Commission  
37 4. Request for Acceptance of Petition for Annexation of 5.59 Acres (Parcel No. 03-074-0007) Located  
38 at Approximately SR 13 and 2400 West  
39 5. Request for Acceptance of Petition for Annexation of 495.17 Acres (Parcel Nos. 04-002-0020, 04-  
40 002-0022, 04-002-0024, 03-257-0004, 03-075-0054, 03-003-0050, 03-067-0029 and 03-075-0023)  
41 located at approximately SR-13 and 1200 West and the north side of the Brigham City Airport.  
42

43 Councilmember Jensen made a motion to approve the consent item as presented. Councilmember Hipp  
44 seconded the motion. The vote was unanimous in favor.

45 **EMPLOYEE RECOGNITION**

46 The Mayor recognized four new employees: Jorge Morales, Equipment Operator in Public Works; Ryan  
47 Hamblin, Park Lead in Parks; Allison Cervantes, Utility Billing Clerk in Finance; and Mikel De La Luca,  
48 Recreation Administrative Assistant in Public Works.

49 **PUBLIC HEARING**

50 **Consideration of Ordinance Adopting Compensation Increase for Executive Municipal Officer and**  
51 **Oath of Office For New Community and Economic Development Director**

52 Derek Oyler explained that the Community and Economic Development Director is an appointed  
53 position, and that recent changes to state code now require a public hearing and ordinance whenever  
54 compensation changes are proposed for appointed or elected officials.

55 Mr. Oyler stated that the Mayor would be appointing Tom Kotter as the new Community and Economic  
56 Development Director for Brigham City Corporation. He explained that the compensation adjustment  
57 being considered was tied to an expanded scope of responsibilities associated with the position.

58 In response to Council questions, Mr. Oyler confirmed that no budget revision was required for the  
59 proposed compensation adjustment. He explained that the department head's salary is allocated across  
60 multiple General Fund budgets and that the adjustment would be absorbed within existing appropriations.

61 **MOTION:** Councilmember Smith made a motion to open the public hearing regarding  
62 compensation Increase for Executive Municipal Officer – Economic Development Director.  
63 Councilmember Jensen seconded the motion.

64 There were no public comments.

65 **MOTION:** Councilmember Jeffries made a motion to close the public hearing. Councilmember  
66 Jensen seconded the motion. The motion passed unanimously.

67 **MOTION:** Councilmember Troxell made a motion to approve the ordinance adopting a  
68 compensation increase for an executive municipal officer – Community and Economic  
69 Development Director. Councilmember Hipp seconded the motion. The motion passed  
70 unanimously.

71 **Roll Call:** Councilmember Jensen – Aye; Councilmember Jeffries – Aye; Councilmember Hipp –  
72 Aye; Councilmember Troxell – Aye; Councilmember Smith – Aye

73 **MOTION:** Councilmember Hipp made a motion to appoint Tom Kotter as the Community and  
74 Economic Development Director. Councilmember Jeffries seconded the motion. The motion  
75 passed unanimously.

76 The swearing in/Oath of Office was administered to Tom Kotter by City Recorder, Kristina Rasmussen.

77 **Consideration of Ordinance Amending the General Plan - Transportation Master Plan**

78 Derek Oyler explained the item had previously been reviewed by the Planning Commission and that the  
79 proposed amendment is tied to long-term planning for the area around Lakeview Elementary (south end  
80 of town). He shared that the School District currently anticipates Lakeview Elementary will likely remain

81 in service for approximately 5–10 years, but City staff began evaluating the block due to potential future  
82 redevelopment if the school were no longer used as a school.

83 Mr. Oyler described the area as challenging for traffic circulation and noted an existing partial street  
84 segment that dead-ends, reflecting long-standing connectivity issues. He reviewed general zoning in the  
85 area and explained the City requested the amendment because staff were concerned about future  
86 development in a General Commercial area without adequate public street access.

87 Mr. Oyler emphasized that a Transportation Master Plan amendment is long-range planning and does not  
88 mean the City would build a road immediately. Instead, roadway improvements would be evaluated and  
89 potentially required as redevelopment occurs through the normal review process. He clarified that  
90 “change of use” (not change of ownership) is what could trigger roadway requirements, and that existing  
91 residents can continue existing nonconforming residential use unless a change of use is proposed.

92 He also explained that the master plan does not set exact road width or final alignment; those details  
93 would be determined later through engineering, staff review, and coordination with property owners as  
94 specific projects come forward. Councilmembers asked clarifying questions about change of use,  
95 redevelopment of the school site, impacts to existing businesses, and ADU-related concerns previously  
96 discussed at Planning Commission. Mr. Oyler reiterated that impacts would be addressed case-by-case  
97 based on specific applications and code requirements.

98 **Key points highlighted by staff:**

- 99 • The amendment is intended to improve north–south connectivity in the block over time.
- 100 • The plan does not require immediate construction; it guides future redevelopment review.
- 101 • Roadway obligations, if any, would generally be triggered by a change of use.
- 102 • Existing homes and businesses may continue current use without change; details would be  
103 handled case-by-case during permitting.

104 **MOTION:** Councilmember Hipp made a motion to open the public hearing for the consideration of  
105 Ordinance Amending the General Plan: Transportation Master Plan. Councilmember Jensen seconded  
106 the motion. The motion passed unanimously.

107 **Dennis Gailey** - expressed strong opposition to the proposed amendment. He stated that the City was  
108 planning for a need far in the future and placing unnecessary restrictions on current property owners. He  
109 emphasized that zoning in the area had changed over time and argued that long-term speculative planning  
110 should not limit what property owners can do today. Mr. Gailey felt the proposal created uncertainty and  
111 unfairly constrained property rights without a clear or immediate need.

112 **Monty Worthy** - owner of several businesses in the area, including Burgers and Scoops and the Arby’s  
113 property, acknowledged staff’s detailed explanations but expressed concern that placing the roadway on  
114 the Transportation Master Plan could negatively affect property value and marketability. He stated that  
115 the uncertainty could impact his plans to sell and retire and asked the Council to consider delaying action  
116 until there is more clarity regarding the future of Lakeview Elementary and potential roadway design.

117 **Randy Navarro** - owner of property in the affected area, stated that he felt constrained in his ability to  
118 redevelop his property. He indicated that had he known about the proposed planning amendment earlier,  
119 he may have reconsidered purchasing the property. Mr. Navarro expressed concern that the amendment  
120 limited investment and redevelopment opportunities.

121 **Randy Dea** -, speaking on behalf of his sister as power of attorney and associated with the Brighton  
122 Beaker Plaza, expressed concern about the lack of detailed engineering information. He stated that

123 without knowing exact road placement or design, it was difficult to assess how access, parking, and  
124 existing business operations might be affected.

125 **Julianna Larson** - spoke about process and transparency. She emphasized the importance of ensuring  
126 affected property owners are fully informed and understood how long-term planning decisions could  
127 impact property values and future use.

128 **MOTION:** Councilmember Hipp made a motion to close the public hearing. Councilmember  
129 Jeffries seconded the motion. The motion passed unanimously.

130 Following closure of the public hearing, the Council engaged in discussion and asked clarifying questions  
131 of Mr. Oyler regarding how roadway requirements would be triggered if only one property within the  
132 affected block were to change use.

133 Mr. Oyler explained that development requirements would generally apply parcel by parcel, not  
134 automatically cascade to neighboring properties. If a property experienced a change of use, the owner  
135 would typically be required to construct the portion of the public roadway adjacent to their frontage,  
136 subject to engineering and utility constraints. Other parcels would not be forced to redevelop unless they  
137 independently proposed a change of use.

138 Mr. Oyler further explained that some parcels in the area currently lack public road access and would be  
139 unable to redevelop without addressing access issues. He stated that roadway construction would likely  
140 occur in segments over time, as redevelopment occurs, similar to how partial roadways have historically  
141 been constructed and stopped where development ended.

142 Discussion continued regarding concerns raised during public comment, including the potential impact on  
143 long-time property owners, uncertainty surrounding the future of Lakeview Elementary, and the difficulty  
144 of making long-term decisions based on unknown future conditions. Several Councilmembers expressed  
145 concern about placing additional constraints on existing properties when redevelopment timing remains  
146 uncertain.

147 Councilmembers acknowledged that the issue of roadway connectivity in the area has been discussed  
148 previously due to fire access, emergency services, and traffic circulation concerns, but also recognized the  
149 unique challenge posed by existing development and ownership patterns.

150 **MOTION:** Councilmember Smith made a motion to table the consideration of the ordinance  
151 amending the General Plan – Transportation Master Plan, requesting additional information be  
152 brought before approval. Councilmember Jensen seconded the motion. All councilmembers voted  
153 in favor of tabling.

#### 154 **PUBLIC COMMENT**

155 **Andrew Lewis** - thanked the Council for the opportunity to provide public comment and expressed  
156 appreciation for positive things he has seen and heard about the City. He shared general concerns about  
157 issues that may not always be visible and emphasized the importance of inclusion, transparency, and  
158 recognizing that every individual's voice matters within the community.

#### 159 **COUNCILMEMBER COMMENTS**

160 **Councilmember Smith** - reported he had attended a Chamber of Commerce meeting and noted the  
161 Chamber is preparing for a business summit in March, including classes and programming that may

162 benefit small and large businesses in the county. He thanked those who attended and spoke during the  
163 meeting, stating public input helps the Council.

164 **Councilmember Troxell** – thanked Mr. Lewis for coming forward and speaking, noting that public  
165 comments matter and that transparency and openness are important. She invited Mr. Lewis and other  
166 residents to contact her directly to discuss concerns and stated she believes the Council is committed to  
167 communicating with community members.

168 **Councilmember Hipp** - commented that the Council is starting the year by hearing from residents in  
169 multiple settings and that public input helps Council better understand how decisions affect individuals.  
170 He referenced the earlier discussion and the Council’s decision to table the transportation master plan  
171 item to allow more consideration. Councilmember Hipp also thanked the City’s public safety leadership  
172 and staff, referencing recent discussion about changes involving the dispatch center. He stated that  
173 although public safety leaders may face criticism on social media, he believes the changes are in the best  
174 interest of the community and employees, and he expressed appreciation for the Mayor and Council  
175 taking a stand.

176 **Councilmember Jeffries** - shared that the Boys and Girls Club’s new gym floor was scheduled to begin  
177 installation the following day and announced a Boys and Girls Club casino night event on Saturday,  
178 February 7. He thanked those who attended the ribbon cutting and grand opening the previous week.  
179 Councilmember Jeffries also addressed his new job responsibilities requiring frequent travel between  
180 Brigham City and Seattle and reaffirmed his commitment to continue serving on the City Council.

181 **Councilmember Jensen** - referenced a letter to the editor by Sarah Yates regarding the food pantry and  
182 commented on the number of meals served, noting the significant volunteer effort and the benefit to those  
183 in need. He also shared that he and Councilmember Hipp attended a presentation at Utah State University  
184 and encouraged residents to review upcoming lecture series and symposiums, referencing a recent  
185 presentation on the Constitution and the Declaration of Independence. Councilmember Jensen concluded  
186 by reiterating Council support for the City’s chiefs and stated the Council fully backs them.

187 **Mayor Bott** – shared comments regarding recent decisions involving City leadership, public safety, and  
188 Council deliberations. He referenced a phrase printed on the City employee T-shirts given as a gift from  
189 the Mayor, stating his guiding principle is to “do what is right and let the consequences follow.” He noted  
190 that consequences are not always punitive, but can include standing alone when making difficult but  
191 correct decisions.

192 The Mayor explained that decisions in Brigham City are made through open discussion with senior staff  
193 and department directors, where differing opinions are encouraged and considered without prejudice. He  
194 stated this collaborative process led to the City’s recent decisions regarding police, fire, and dispatch  
195 services, emphasizing that those actions were taken based on professional expertise and what leadership  
196 believed was in the best interest of the community.

197 The Mayor also referenced the Council’s decision earlier in the meeting to table the Transportation  
198 Master Plan amendment, noting it demonstrated that decisions are not predetermined and that Council  
199 deliberation occurs publicly, as required by law and expected by residents. He expressed appreciation for  
200 the Council’s willingness to listen, deliberate, and take the time necessary to make informed decisions.

201 The Mayor concluded by expressing gratitude to City employees, department chiefs, and their families for  
202 the trust placed in City leadership. He stated that he takes seriously the responsibility of serving as Mayor  
203 and supporting the professionals who serve the community, emphasizing unity, transparency, and  
204 accountability in City governance.

205 **CITY ADMINISTRATOR COMMENTS**

206 There were no comments made by City Administrator.

207 **ACTION ITEMS**

208 **Consideration of Approval of Fire Departmental Policy 205 – Revision to Bereavement Leave**

209 Tom Kotter explained that staff had recently completed a review of the City’s employee handbook and  
210 personnel policies and identified that the existing bereavement leave policy did not adequately account for  
211 Fire Department employees. He noted that Fire Department personnel work a 48/96 schedule, meaning  
212 two days on duty followed by four days off, which differs from the schedules of other City departments.

213 Mr. Kotter stated that the proposed revision would ensure Fire Department and EMS employees receive  
214 bereavement leave equivalent to that provided to other City employees, adjusted appropriately to reflect  
215 their work schedule. He emphasized that the revision was intended to ensure fairness and consistency  
216 across departments.

217 **MOTION:** Councilmember Jensen made a motion to approve the revision to Employee Policy 9-  
218 7, Bereavement Leave. Councilmember Hipp seconded the motion. The motion passed  
219 unanimously.

220 At 7:34 PM Councilmember Smith made a motion to proceed into closed session to discuss the  
221 purchase/exchange/lease of real property. The motion was seconded by Councilmember Jeffries.

222 **Roll Call:**  
223 Councilmember Hipp – Aye; Councilmember Jensen – Aye; Councilmember Smith – Aye;  
224 Councilmember Troxell– Aye; Councilmember Jeffries – Aye

225 At 8:55 PM The council returned to opened and a motion was made by Councilmember Smith to adjourn.  
226 Seconded by Councilmember Hipp and approved unanimously.

227 *The undersigned duly appointed Recorder for Brigham City Corporation hereby certifies that the*  
228 *foregoing is a true, accurate and complete record of the January 15, 2026 City Council Meeting.*

229  
230 *Dated this 6th of February, 2026.*

231  
232  
233  
234 *Kristina Rasmussen, City Recorder*

235  
236 *\*\* These meeting minutes were generated with the assistance of artificial intelligence and have been*  
237 *reviewed, edited and approved by Brigham City Staff.*

**BRIGHAM CITY  
AGENDA ITEM FOR CITY COUNCIL MEETING**

- 1. INITIATED BY: DJ Bott
  
- 2. DEPARTMENT OR DIVISION: Mayor's Office
  
- 3. DATE INITIATED: 1/27/26
  
- 4. BRIEF EXPLANATION OF PROPOSED ACTION (ATTACH OTHER DOCUMENTATION AS NECESSARY):


Appointment of Garl Waldron as Vice Chair of the Planning Commission. *and as a member of the Joint Advisory Board.*

- 5. ESTIMATED TIME NEEDED: 2min
  
- 6. PROPOSED DATE FOR COUNCIL ACTION: 2/5/26
  
- 7. EXPLANATION OF DEADLINE, IF APPLICABLE:

8. REVIEW

<u>Date</u>	<u>Name</u>	<u>Signature</u>	<u>Attachment</u>
_____	_____	_____	_____
_____	_____	_____	_____

9. MAYOR'S SIGNATURE:

  
\_\_\_\_\_

**BRIGHAM CITY  
AGENDA ITEM FOR CITY COUNCIL MEETING**

1. INITIATED BY: Angie Johnsen
  
2. DEPARTMENT OR DIVISION: Human Resources
  
3. DATE INITIATED: January 27, 2026
  
4. BRIEF EXPLANATION OF PROPOSED ACTION (ATTACH OTHER DOCUMENTATION AS NECESSARY):

New Hire:

Braxton Wood  
Power Department  
Electronic Metering Technician

5. ESTIMATED TIME NEEDED: 3-5 minutes
  
6. PROPOSED DATE FOR COUNCIL ACTION: February 05, 2026
  
7. EXPLANATION OF DEADLINE, IF APPLICABLE:

8. REVIEW

<u>Date</u>	<u>Name</u>	<u>Signature</u>	<u>Attachment</u>
January 27, 2026	Angie Johnsen	 <small>*Signed via GovOS.com Key: 323621ea-7128-4d35-b69a-a3d9065a4ef9</small>	

9. MAYOR'S SIGNATURE:

  
\*Signed via GovOS.com  
Key: 605b8e0c-e8b3-440c-bd39-2708b148112c

**BRIGHAM CITY  
AGENDA ITEM FOR CITY COUNCIL MEETING**

1. **INITIATED BY:** Tom Cooper
  
2. **DEPARTMENT OR DIVISION:** Brigham City Power
  
3. **DATE INITIATED:** January 26, 2026
4. **BRIEF EXPLANATION OF PROPOSED ACTION (ATTACH OTHER DOCUMENTATION AS NECESSARY):**  
Changes to Public Power Standards Manual

5. **ESTIMATED TIME NEEDED:** 10 mins.

6. **PROPOSED DATE FOR COUNCIL ACTION:** February 05, 2026

7. **EXPLANATION OF DEADLINE, IF APPLICABLE:**

8. **REVIEW**

<u>Date</u>	<u>Name</u>	<u>Signature</u>	<u>Attachment</u>
January 26, 2026	Tom Cooper	 <small>eSigned via GovOS.com Key: 323521ea-7128-4d35-b69a-e3a90f0adef6</small>	✓

9. **MAYOR'S SIGNATURE:**

  
eSigned via GovOS.com  
Key: 605b890c-4fd3-440c-bdc8-2708ba4fb2c

BRIGHAM CITY PUBLIC POWER  
ELECTRICAL REQUIREMENTS  
AND  
STANDARDS MANUAL



FEBRUARY 2026

## TABLE OF CONTENTS

SECTION 1 GENERAL .....	1
1.01 Ordinances Govern .....	1
1.02 Conformance with Federal, State, and Local Laws.....	1
1.03 Definitions .....	1
1.04 Easements .....	2
1.05 Traffic Control .....	2
1.06 Survey .....	2
1.07 Temporary Controls .....	2
SECTION 2 IMPROVEMENT REQUIREMENTS .....	3
2.01 General .....	3
2.02 Variations, Substitutions, Exceptions and Changes.....	3
2.03 Protection of Existing Improvements.....	3
2.04 New Materials .....	3
2.05 City Furnished Products .....	3
2.06 Product Delivery and Handling .....	3
2.07 Product Storage and Protection.....	3
2.08 Other Specifications and Standards .....	4
SECTION 3 SPECIALIZED ENGINEERING.....	4
3.01 General .....	4
SECTION 4 CONSTRUCTION PLANS .....	4
4.01 General .....	4
4.02 Electric Plans.....	4
SECTION 5 POWER UTILITY IMPROVEMENTS .....	5
5.01 General .....	5
5.02 Electric.....	5
SECTION 6 INSPECTION AND TESTING.....	5
6.01 Quality Control .....	5
6.02 Inspection and Testing Notification.....	5
6.03 Work Without Required Inspection and Testing.....	6
6.04 Inspection and Testing Fees .....	6
6.05 Weekly Progress Meetings.....	6
6.06 As-Built Survey.....	6
6.07 Earthwork: Compaction and Moisture Content Tests .....	6
6.08 Inspections.....	6
SECTION 7 PORTLAND CEMENT CONCRETE WORK .....	7
7.01 General .....	7
SECTION 8 EARTHWORK AND TRENCHES .....	7
8.01 Excavation .....	7
8.02 Subsurface Pipe Installation .....	8
8.03 Fill Material.....	8
8.04 Installation and Compaction of Earth Materials .....	9
SECTION 9 GENERAL.....	10
9.01 Standards and Specifications .....	10
9.02 Construction Costs .....	10

9.03	Attaching to Existing City Facilities Prohibited .....	10
9.04	Unusual Service Extensions .....	10
9.05	Permits and Inspections .....	10
9.06	Access to Premises .....	11
9.07	Electrical Plan Drawings .....	11
9.08	Electrical Box Clearance .....	11
9.09	Overhead Electrical Power Line Clearances .....	12
<b>SECTION 10 VOLTAGE AND ENERGY REGULATION .....</b>		<b>13</b>
10.01	Available Voltages .....	13
10.02	Phase Service .....	13
10.03	Power Factor Correction .....	13
10.04	Load Control .....	14
10.05	Voltage Control .....	14
10.06	Fluctuating Load Limitations .....	14
10.07	Penalties .....	14
<b>SECTION 11 MATERIALS .....</b>		<b>14</b>
11.01	Materials .....	14
11.02	Conduit .....	14
11.03	Enclosures .....	15
11.04	Soils & Compaction .....	15
<b>SECTION 12 INSTALLATION .....</b>		<b>15</b>
12.01	General .....	15
12.02	Underground Lines .....	16
12.03	Conduit Depths .....	16
12.04	Pull Strings .....	16
12.05	Identification Tape and Stub Markers .....	16
12.06	Underground Metal Conduit .....	17
12.07	Road Crossings .....	17
12.08	Berms, Slopes, and Hillside Conditions .....	17
12.09	Labels .....	17
<b>SECTION 13 SYSTEM REQUIREMENTS .....</b>		<b>17</b>
13.01	Additional Capacity Requirements .....	17
13.02	Substations .....	18
<b>SECTION 14 SERVICES .....</b>		<b>18</b>
14.01	Point of Service .....	18
14.02	Service Entrance Requirements .....	18
14.03	Underground Residential Service Requirements .....	19
14.04	Overhead Residential Service Requirements .....	21
14.05	Underground Service Requirements for Multi-Family Dwelling Units .....	24
14.06	Underground Service Requirements for Commercial & Industrial Applications ..	24
<b>SECTION 15 METERING .....</b>		<b>27</b>
15.01	General .....	27
15.02	Location .....	27
15.03	Meter Base .....	28
15.04	Commercial Meters .....	28

15.05	Location of Multiple Meters .....	29
15.06	Meter Location Regarding Remodeling.....	29
15.07	Meter Accessibility .....	29
15.08	Outdoor Meters for Non-Residential General Service .....	29
15.09	Instrument Transformer for Metering.....	29
15.10	Current Transformer Cabinet .....	30
15.11	Unacceptable Meter Locations .....	30
SECTION 16 LIGHTING AND SIGNAL POLES .....		31
16.01	General .....	31
16.02	Dark Sky .....	31
16.03	Location .....	31
16.04	Orientation .....	31
16.05	Grounding & Bonding.....	32
16.06	Wiring & Fusing .....	32
SECTION 17 VEGETATION MANAGEMENT .....		33
17.01	Overview .....	33
17.02	Professionalism .....	33
17.03	Safety.....	33
17.04	Fire Protection .....	34
17.05	Species of concerns .....	34
17.06	Bird Protection .....	34
17.07	Tree Removal .....	36
17.08	Debris Disposal.....	37
17.09	Directional Pruning.....	37
17.10	Tree Houses.....	38
17.11	Distribution Cycle Maintenance .....	38
17.12	Transmission procedures.....	41
17.13	Chemical Procedures .....	42
17.14	Approved Herbicides .....	44

ELECTRICAL CONSTRUCTION STANDARD DRAWINGS .....	45
E1 Electric General Information .....	46
E2 Residential Underground Service 200 Amps or Less.....	47
E3 Residential Overhead Service 200 Amps or Less.....	48
E4 Electric Conduit Trench Detail.....	49
E5 Secondary Junction Pedestal .....	50
E6 Single Phase Pad Mount Transformer .....	51
E7 200-Amp 1-Phase Sectionalizer.....	52
E8 200-Amp 1- and 3-Phase Fiberglass Sectionalizer.....	53
E9 600-Amp 3-Phase Fiberglass Sectionalizer.....	54
E10 Electrical Box Backfill & Compaction .....	55
E11 Conduit Routing.....	56
E12 3-Phase Transformer & Concrete Pad .....	57
E13 600 Amp PSE 9/11 Switchgear.....	58
E14 600 Amp PSE 3/5 Switchgear.....	59
E15 Secondary Pedestal, Wire & Connections .....	60
E16 Decorative Street Light Pole Footing Detail .....	61
E17 Street Light Poles and Fixtures.....	62
E18 Temporary Service for Overhead & Underground Lines .....	63
E19 3-Phase Underground Service 201-800 Amps .....	64
E20 Typical Riser Pole .....	65
E21 Overhead Power Line Clearances over 600 Volts to 22,000 Volts .....	66
E22 1-Phase Free Standing Meter Base & 3-Phase Free Standing Meter Base .....	67
E23 Photovoltaic Single-Phase System Diagram Central Inverter (Residential) .....	68
E24 Photovoltaic Single-Phase System Diagram Micro Inverter (Residential) .....	69
E25 Photovoltaic Single-Phase System Diagram Energy Storage – Central Inverter....	70
E26 Photovoltaic Single-Phase System Diagram Energy Storage – Micro Inverter (Residential).....	71
E27 Photovoltaic Three-Phase System Diagram Using Multiple Two-Line Single-Phase Inverters with Neutral Connection .....	72
E28 Photovoltaic Single-Phase System Diagram Using a Single Three-Phase Inverter	73
E29 PV Disconnect Labels & PV Service Panel Warning Labels.....	74
E30 EUSERC Dwg No. 501 - AC Disconnect Guidelines .....	75
V1 Tree and Vegetation Trimming and Clearing Details.....	76
V2 Tree Planting and Electrical Box Clearance Details.....	77

## GENERAL

## SECTION 1 GENERAL

## 1.01 Ordinances Govern

Nothing in this document shall be construed to be contrary to Brigham City Ordinances. Should a conflict exist between this document and the Ordinances, the Ordinances shall govern.

## 1.02 Conformance with Federal, State, and Local Laws

Nothing in this document shall relieve the Developer, Engineer, or Contractor from abiding by any and all Federal, State and local laws

## 1.03 Definitions

- A. APWA. The American Public Works Association
- B. City. The City of Brigham City, Utah.
- C. County. Box Elder County, Utah
- D. Construction Plans. Construction plans include drawings showing all required improvements for a development showing their location, size, grade, and elevations.
- E. Customer. A person or company receiving service from any City utilities
- F. Contractor. A person or company hired by the city or a Developer to perform construction in or for the city, having appropriate state licenses to perform said work.
- G. Council or City Council. The governing body of the city.
- H. Development Review Team. The Review Team (DRT) of Brigham City.
- I. Developer. Person, persons, partnership or corporations developing residential, commercial or industrial property.
- J. Improvements. Includes roads, streets, curbs, gutters, sidewalks, grading, landscaping, water and sanitary sewer systems, irrigation systems, drainage systems, power systems, fences, public facilities, trees or other requirements by this chapter or by the city.
- K. Land Surveyor. A person licensed with the State of Utah to practice as a licensed land surveyor.
- L. Lot. A parcel or tract of land within a subdivision.
- M. MUE. A Municipal Utility Easement acquired by the city for city utilities.
- N. MUTCD. Manual on Uniform Traffic Control Devices.
- O. NEC. The National Electrical Code is a United States standard for the safe installation of electrical wiring and equipment.
- P. NEMA. National Electrical Manufacturers' Association
- Q. NESC. The National Electrical Safety Code
- R. Net billing. A debit and credit metering process in an account.
- S. Offsite Facilities. Facilities outside of the boundaries of the subdivision or development.

- T. Onsite Facilities. Facilities installed within or on the perimeter of the subdivision or development site.
- U. OSHA. The Occupational Safety and Health Administration.
- V. Power Department. The division of City government responsible for the city owned Electric utilities.
- W. Public Power Director. The Public Power Director for Brigham City or authorized representative.
- X. Public Utility Easements. The easements required to place public utilities across any privately owned property.
- Y. ROW. Right of Way

1.04 Easements

Developers shall provide municipal utility easements (MUEs) for all utility extensions through private property and for 10 feet along public right-of-ways. Developments other than single family home developments shall provide 10-foot MUEs along all property lines. If setbacks are less than 10 feet, then MUEs shall be the extent of the setback. Single family lots shall have 10-foot MUEs along public right-of-ways or streets and not necessarily along the other property lines unless a utility is planned there. Developer shall not be allowed to nor shall they include any type of protection easement intended to provide exclusivity to their development.

1.05 Traffic Control

A traffic control plan shall be submitted to the City prior to construction in or along public streets. All traffic control shall comply with APWA 01 55 26 (Traffic Control) and the MUTCD.

1.06 Survey

The alignment of the side property lines for each lot in a subdivision shall be marked in the top back of curb with a lot line witness marker that meets the requirements and specifications of APWA 31 05 10 (Boundary Markers and Survey Monuments). Developers shall provide survey benchmarks and monuments as required by the Public Power Director.

1.07 Temporary Controls

Temporary controls such as noise, dust, mud, surface water, ground water, pollution and erosion controls shall be made. Controls shall meet the requirements and specifications of APWA 01 57 00 (Temporary Controls). Pumping groundwater into the sanitary sewer system is prohibited. Ground water and/or surface water must be kept on the construction site. If either leave the site by any manner, additional temporary controls must be implemented to protect the storm water drain system. A Storm Water Pollution Prevention Plan (SWPPP) and Notice of Intent (NOI) may also be required. See Brigham City's SWPPP Requirements on the public website for more information.

---

**SECTION 2 IMPROVEMENT REQUIREMENTS****2.01 General**

This policy defines the general requirements for improvements to be built by the Developer, sub-divider, owner, or Contractor for all types of construction (including residential, commercial, industrial, institutional, governmental and professional office). All improvements which are in areas that are or will become public rights-of-way and/or easements, or that will be under the responsibility of a homeowner's association, shall meet the requirements of these specifications.

**2.02 Variations, Substitutions, Exceptions and Changes**

Any variation, substitution or exception from the standards in this policy must be authorized in writing by the Public Power Director. Product options and substitutions must meet the requirements of APWA 01 25 00 (Product Options and Substitutions). Any item of construction not covered in these standards must have plans and specifications approved by the Public Power Director. Requests for changes to the Construction Standards shall be made in writing to the Public Power Director. These requests will be reviewed during the revision process conducted in conjunction with the APWA, NESC and NEC revisions. There is no appeal from the decision of the Public Power Director.

**2.03 Protection of Existing Improvements**

The Contractor shall be responsible for the protection of any existing improvements on public or private property at the start of work or placed there during the progress of the work. Existing improvements shall include but are not limited to permanent surfacing, curbs, ditches, driveways, culverts, fences, walls and landscaping. Any surface improvements damaged because of construction shall be restored or replaced to an equal or better condition than before. This shall be accomplished in a timely manner.

**2.04 New Materials**

Only new materials may be used during construction unless otherwise authorized by the Public Power Director.

**2.05 City Furnished Products**

If the City furnishes any products the Contractor shall conform to requirements and specifications of APWA 01 64 00 (Owner-furnished Products), NESC and NEC.

**2.06 Product Delivery and Handling**

The Contractor shall conform to requirements and specifications of APWA 01 65 00 (Product Delivery and Handling), NESC and NEC.

**2.07 Product Storage and Protection**

The Contractor shall conform to requirements and specifications of APWA 01 66 00 (Product Storage and Protection), NESC and NEC.

## 2.08 Other Specifications and Standards

City standards and ordinances shall supersede all other Standards whenever they conflict.

## SECTION 3 SPECIALIZED ENGINEERING

### 3.01 General

Any specialized engineering beyond the expertise of city staff such as, but not limited to, geotechnical, traffic, environmental, hillside, floodplain, bank stabilization and erosion control will require the review of qualified consultants. All review costs shall be paid by the property owner/developer.

Locate utilities within areas of explorations by notifying the appropriate local one-call state utility locate service (Blue Stakes). Independent private utility locates may be required for utilities not identified by the local one-call service. Complete subsurface explorations in accordance with the minimum requirements outlined in this section.

## SECTION 4 CONSTRUCTION PLANS

### 4.01 General

The following instructions are for the purpose of standardizing the preparation of construction plans to obtain uniformity in appearance, clarity, size, and style. Plans and designs shall meet the standards defined in the specifications and drawings hereinafter outlined. All drawings and/or prints shall be clear and legible and conform to good engineering and drafting room practice.

Include the following in construction plans for all developments:

1. A copy of the proposed final plat or site plan.
2. A plan view of the entire project showing all utilities, roads, and appurtenances.
3. Plan and profiles of all storm, land and groundwater drains, sanitary sewer, curb, gutter, and irrigation.
4. Detail drawings of street cross sections according to the standard drawings and other detail drawings only for items not found in the city standard drawings. Detail drawings shall be to scale and completely dimensioned and described. All items shall be designed in accordance with minimum requirements established by the Public Works Standards.
5. Complete plans for all off-site work to be done in conjunction with the project.
6. A stamp and signature of a Civil Engineer licensed in the state of Utah on each plan sheet, detail drawing, and design sheet.

### 4.02 Electric Plans

Construction plans must include the location of all existing poles, transformers, secondary junction boxes, sectionalizers, and overhead electrical wire. After plans

are updated to meet the approval of the DRT, the Developer shall submit a computer aided design (CAD) file of the plans to the Power Department. CAD file must be in a .dwg or .dxf format. Thereafter the Power Department will design and make available plans for the proposed electric lines for the development. City electrical utility design shall supersede any design provided by developer.

## SECTION 5 POWER UTILITY IMPROVEMENTS

### 5.01 General

It shall be the responsibility of the Developer to connect to existing utilities or improvements wherever they are located and extend those improvements to and through the development. This requirement includes hooking up existing homes within the development to all utilities. Existing buildings impacted by development which are currently fed overhead shall be required to be rerouted and metering directly connected to new underground electrical grid at developer's expense. Workmanship and details of construction shall be in accordance with the Public Power Standards and/or other codes adopted by the City. All work shall be done under the supervision of the Public Power Director.

### 5.02 Electric

Electrical lines shall be underground except when the Public Power Director feels that such underground lines are not in the best interest of the City.

## SECTION 6 INSPECTION AND TESTING

### 6.01 Quality Control

The following work shall be subject to the inspection and testing requirements of this chapter:

1. Work on existing or proposed City property.
2. Work on property that will be owned by a property owners association.
3. Work on existing or proposed streets, easements, or right-of-ways.
4. Work on existing or proposed City utilities.

The Contractor is responsible for performing all inspection and testing required to verify installed materials meet these standards and must verify the materials are accepted by the Public Power Director. The Contractor must also ensure that any additional inspection and testing required by the city or a testing company is performed and accepted by the City.

### 6.02 Inspection and Testing Notification

The City may contract with a private company to conduct any inspections or testing specified to be performed by the City. All inspections and tests must be scheduled with the City or company contracted by the City a minimum of 1 full business day

before needed. Requests for inspection on work requiring continuous inspection shall be made 3 full business days prior to commencing the work.

6.03 Work Without Required Inspection and Testing

Failure to provide proper notification or to perform work without inspection will result in rejected material. Rejected material will be subject to additional verification requirements including, but not limited to, post-placement sampling and laboratory testing for material conformance, in-place testing for concrete strength and air content. All post-placement testing for uninspected work will be at no additional cost to the city.

Additionally, any work performed without required inspection or testing will give the city the option to hold the bond covering that portion of the improvements in violation, or require the removal and replacement of the uninspected work. The City shall have the option of retaining part or all the bond for up to 10 years after installation of improvements constructed without required inspection or testing. The Public Power Director may also accept the work at a reduced price.

6.04 Inspection and Testing Fees

Connection fees required shall be paid and permits required shall be obtained prior to the preconstruction meeting.

6.05 Weekly Progress Meetings

The City may require, at their discretion, construction projects in the City to have a weekly progress meeting at the Public Power office. The Public Power Director, City inspectors, the Contractor, and subcontractors shall be in attendance.

6.06 As-Built Survey

The Contractor shall notify the City to survey all underground utilities either installed or uncovered during construction. Contractor shall give the City 24-hour notice to survey utilities.

6.07 Earthwork: Compaction and Moisture Content Tests (Refer to Sheet E10)

The city will test all sub-grade and fill material for compaction and moisture content. Test locations shall be determined by the city.

6.08 Inspections

6.08.1 Conduit Inspections

The Public Power Director must inspect all conduit before backfilled.

6.08.2 Service Stub Inspections

The Public Power Director must inspect all service stubs before backfilled.

6.08.3 Street Light Base Inspections

The Public Power Director must inspect all street light bases prior to concrete placement and before they are backfilled around.

6.08.4 Bedding Inspections

The Public Power Director must inspect the bedding in all electrical trenches.

6.08.5 Final Electrical Inspection

Once all electrical work for a development is completed to City standards, a final electrical inspection must be done by the Public Power Director prior to permanent power installation.

SECTION 7 PORTLAND CEMENT CONCRETE WORK (Refer to Sheets E5-E9, E12-E14 and E16)

7.01 General

All materials and processes involved in concrete work shall be subject to inspection and testing as detailed in general compliance with ASTM E105-54T. For additional information refer to the Public Works Standards manual.

SECTION 8 EARTHWORK AND TRENCHES (Refer to Sheets E4 and E5)

8.01 Excavation

8.01.1 General

Excavation shall meet the requirements and specifications of APWA 31 23 16 (Excavation) unless otherwise indicated.

8.01.2 Safety

All construction shall be done in accordance with the provisions of the Utah State Industrial Commission, OSHA regulations and APWA 31 23 16 (Excavation). No trenches deeper than 4 feet shall be left open at any time unless construction is in process. When construction is in process only 200 feet of trench may be open at one time and must be completely backfilled before proceeding. Any variation will require the approval of the Public Power Director. No trenches shall be left open at any time unless guarded with adequate barricades, warning lamps and signs.

Any injury or damage resulting from lack of adequate bracing and shoring shall be the responsibility of the Developer/Contractor and the Developer/Contractor shall, at his/her own expense, affect all necessary repairs or reconstruction resulting from such damage. No inspections will be done in unsafe trenches and will be the cause for immediate shutdown of the project until the trench is deemed to be safe by the Public Power Director.

## 8.02 Subsurface Pipe Installation

### 8.02.1 General

Pipes, conduits or casings, 4 inches in diameter or less, may be bored, jacked, augured or jetted under sidewalk, curb, gutter if authorized by the Public Power Director. The resulting hole diameter shall not exceed 1 inch plus the outside diameter of the pipe or sleeve installed.

### 8.02.2 Boring or Jacking

Boring or jacking work shall meet the requirements and specifications of APWA 33 05 23 (Trenchless Utility Installation).

### 8.02.3 Tunneling

Where sidewalk, curb, and gutter exist, excavation may be made by tunneling provided the following requirements are met:

1. Excavation shall be vertical and as near to the curb or sidewalk as possible.
2. The length of the tunnel shall not exceed the width of the sidewalk, curb, and gutter.
3. Where a separate sidewalk and curb exist, an excavation shall be made between the sidewalk and the curb.
4. At least three feet of undisturbed earth shall be left under the sidewalk or curb; and
5. Where the sidewalk has been tunneled, the hole shall be filled from each end with flowable fill. Where the excavation cannot meet these requirements, a section of sidewalk, curb, or gutter, from joint to joint shall be removed and replaced.

## 8.03 Fill Material

### 8.03.1 General

All fill material shall be placed on sub-grade prepared according to the specifications of this chapter. All fill material shall be compacted according to the specifications of this chapter.

All fill material under and within a foot of electrical boxes shall be untreated base course. In other areas native excavated material may normally be used unless such material cannot be properly compacted according to specifications in this chapter. All fill material, including native fill material, must be free from debris, organic material, and rocks larger than 6 inches in diameter.

### 8.03.2 Bedding Material

Use sand as a bedding material for electrical conduit. Bedding sand must compact sufficiently to support the pipe and shall meet the following gradation:

#### Sand Gradation

Sieve/Screen Size	% Passing
No. 4	100
No. 200	10 to 20

### 8.04 Installation and Compaction of Earth Materials

#### 8.04.1 General

The installation of all fill material shall meet the requirements and specifications of APWA 33 05 20 (Backfilling Trenches), APWA 31 23 23 (Backfilling Structures), APWA 32 05 10 (Backfilling Roadways) and APWA 31 23 26 (Compaction). Fill material outside of pavement areas, as defined by APWA 32 05 10 (Backfilling Roadways), and more than 24 inches from any utility box shall be compacted to not less than 90% of the maximum dry density.

#### 8.04.2 Backfill in Trenches

Backfill shall be carefully placed around and over pipes and shall not be permitted to fall directly on a pipe from such a height or in such a manner as to cause damage.

#### 8.04.3 Conduit Zone (Refer to Sheet E11)

The conduit zone includes the full width of trench from 3 inches below the conduit to 12 inches above the conduit for all conduit. Electrical conduit may be placed to 3" off the sides of trenches. Trenches shall be wide enough to compact fill material according to the specifications in this chapter.

---

## Electrical Service

### SECTION 9 GENERAL

#### 9.01 Standards and Specifications

All electrical work shall be installed in accordance with these development standards, the most current edition of the National Electrical Code (NEC) and the National Electric Safety Code (NESC), and applicable State, County and OSHA codes and ordinances.

These specifications cover the installation of the electrical system. See Section 2 for improvement and design requirements, Section 6 for inspection and testing requirements, and Section 8 for earthwork and trench requirements. See standard drawings related to electrical system.

#### 9.02 Construction Costs

All costs to install or relocate facilities to provide electrical service shall be paid by the Customer.

If a temporary electrical service is needed the contractor/developer is responsible for providing and installing the required conduit, grounding, transformer pad, and metering equipment as directed by the City. There will be a rental fee for the transformer needed that will be determined based off of the length of time the unit is needed. Brigham City Power will provide and install all primary wiring and transformer at the developers/contractor's expense. Any fees paid to the City for these purposes will not be refundable or be applied to any other electrical fees.

#### 9.03 Attaching to Existing City Facilities Prohibited

Customer shall install no wiring or attachments on poles or other equipment of the City unless specifically authorized, in writing, by the City.

#### 9.04 Unusual Service Extensions

Special and unusual service extension requirements for equipment or structures are treated as separate items and are not included in these standards.

#### 9.05 Permits and Inspections

Service will not be established until all necessary permits have been obtained and not until Customer's wiring installation has been inspected and approved by the Public Power Director. Any variations of this must be preapproved by the Public Power Director. The City reserves the right to inspect wiring and to refuse service to any installation that is, in the opinion

of the Public Power Director, unsafe or if the operation of same may be detrimental to the service furnished to other Customers or the City. All conduits shall be inspected prior to backfilling. All concrete street light bases, concrete transformer pads and other required concrete shall be inspected prior to pouring concrete. A compaction test shall be taken by the City or an approved engineering firm prior to setting any electrical enclosures, cabinets, or other structures. In addition, a test shall be taken on the concrete used for electrical pole bases, and pads.

9.06 Access to Premises

Any properly identified representative of the City shall, at all hours, have free access to and from the premises of the Customer for the purpose of inspecting Customer's installations and electric equipment and for the purpose of reading, repairing, testing, or removing the City's meter or its other property. When, as declared by the Public Power Director, emergency conditions exist with respect to City's service, City's representative shall have immediate and free access to Customer's premises.

9.07 Electrical Plan Drawings

Brigham City Public Power shall design the electrical system and provide approved electrical plan drawings. Requests for any changes to these drawings can be made by contacting Brigham City Public Power with a proposal. Approved electrical drawings must be initialed by an approved electrical division supervisor and signed by Brigham City Public Power to be valid for construction of the electrical system improvements. Photocopies of approved drawings will not be considered valid. Revisions, if needed, must also include the date the revision was approved.

9.08 Electrical Box Clearance

All electrical boxes shall have 12 feet clearance to the front and 3 feet clearance to the back and on either side. Secondary pedestals shall only require 3 feet of clearance on all sides. Switchgears shall have 12 feet clearance in front of the doors and 3 feet of clearance on the sides. Meters, metering cabinets & enclosures, service disconnect cabinets & enclosures, & CT cabinets, shall have a minimum of 8 feet of clearance in front of said cabinets & enclosures. All electrical sectionalizers, transformers, switchgear, etc. shall have a clear and level working space around them. The area shall be backfilled and leveled a minimum of 12 feet in all directions from the respective electrical device.

Meters, meter cabinets, services and related electrical cabinets shall not be enclosed by carports, sheds, out buildings, additions or remodels or other such buildings. Brigham City Public Power shall have ready access to such equipment for safety & maintenance. The City reserves the right to

disconnect the City electrical service to meter bases, services, etc. if in the opinion of the City the service is inaccessible or unsafe until the service & safety issues are resolved to the City's satisfaction. This may include, but is not limited to relocating the service, or upgrading the service to meet current City codes.

9.09 Overhead Electrical Power Line Clearances (Refer to Sheet E21)

As set forth in Section 54-8c-1 through Section 54-8c-7 of the Utah Code, no person or thing may be brought within 15 feet of any high voltage overhead power line unless:

The responsible party has notified Brigham City Public Power of the intended activity; and

The responsible party and Brigham City Public Power have completed mutually satisfactory safety precautions for the activity; and

The responsible party has made prior arrangements to pay Brigham City Public Power for the mutually satisfactory safety precautions (if applicable).

No building, dwelling, sign, bridge, antennae, or structure shall be constructed, or placed underneath any overhead electrical power lines, and shall meet current NESC/NEC and City clearance requirements, both vertically and horizontally, from said power lines. Variances shall only be allowed at the City's discretion.

If existing buildings or structures exist under power lines, those same buildings or structures shall not be modified, remodeled or constructed to further encroach upon the clearances from said power lines.

In general, for overhead high voltage open supply conductors operating from 750 volts to 22,000 volts nominal, the space extending from grade level to the height of the conductor vertically and 15 feet horizontally from the further most outside conductor from the pole shall be kept clear from the power lines. Furthermore, for overhead high voltage open supply conductors operating from 22,001 volts to 138,000 volts nominal, the space extending from grade level to the height of the conductor vertically, and 30 feet horizontally from the further most outside conductor from the pole shall be kept clear from the power lines. Open water, swimming pools, combustible materials or hazardous locations may have additional clearances required.

Additional clearances may be required depending on the installation or application.

SECTION 10 VOLTAGE AND ENERGY REGULATION (Refer to E19)

10.01 Available Voltages

Standard Electrical Services

Residential	Commercial and Industrial
1 Phase	3 Phase
3 Wire	4 Wire
120/240 Volts	208Y/120 or 480Y/277 Volts

Developers must contact the Public Power Director regarding the availability of other service options.

The Public Power Director reserves the right to deny a customer 3-phase service if the Public Power Director determines that single-phase service will adequately supply Customer's load requirements. The Public Power Director reserves the right to deny a customer single phase service if the Public Power Director determines 3-phase service is in the best interest and beneficial to the City's electrical system.

10.02 Phase Service

3 phase service may, at the City's option, be furnished where 3 phase facilities of adequate capacity are already installed immediately adjacent to the point where service is to be delivered to Customer, or where, as determined by the City, it is economically feasible to extend such 3 phase facilities.

The City reserves the right to refuse to extend or install 3 phase facilities to serve motors individually rated at 20 HP or less and to furnish only single-phase service for such motors. In such an event, Customer may elect to install single- phase to 3 phase conversion equipment to operate 3 phase motors.

10.03 Power Factor Correction

The City reserves the right to require the Customer to install power factor corrective equipment. This equipment shall maintain the power factor on all of Customers electric power meters to not less than 95% lagging at all times.

#### 10.04 Load Control

The Public Power Director reserves the right to require developers to install equipment to limit load and reduce voltage fluctuations.

#### 10.05 Voltage Control

Where Customer installs power factor corrective equipment, the City reserves the right to require Customer to install controls and equipment to prevent voltage, frequency, and/or harmonics problems that may be detrimental to other Customers or the City.

#### 10.06 Fluctuating Load Limitations

Where large fluctuating single-phase loads, such as spot welders, are involved, the City reserves the right to require such loads to be supplied by means of a 3 phase to a single-phase converter or other similar equipment. All conversion equipment shall be installed, owned, operated and maintained by the Customer.

In the event a separate service or transformer installation or additional transformer capacity is required to adequately serve fluctuating loads (such as X-ray equipment, welders, etc.). Such equipment costs and installations shall be the responsibility of the Customer.

#### 10.07 Penalties

If, such voltage control equipment is not installed by Customer, Customer may be required to pay a power factor penalty and/or all electric service shall be subject to disconnection as provided by Title 50 of the Brigham City Public Power Municipal Code. Customer's wiring used to supply such fluctuating loads shall be installed in a continuous run of rigid conduit and cable as approved by the City.

### SECTION 11 MATERIALS

#### 11.01 Materials

Only electrical grade materials and apparatus shall be used. The materials and apparatus shall be UL Listed and designed for their purpose.

#### 11.02 Conduit

All conduits shall be electrical grade conduit. Conduit shall be Schedule 40 PVC unless otherwise specified by the Public Power Director. Electrical grade Schedule 40 fiberglass and/or PVC conduit shall be used under collector and arterial streets and for all sweeps. Fiberglass conduits shall not be used for riser poles. All conduits extending out of the ground outside of an enclosure shall be rigid metal and the elbows attaching to those risers shall be either rigid metal or fiberglass. All conduits entering any cabinet,

enclosure, vault, or ground sleeve shall have end bells attached to the ends of conduits to protect wire from damage. All buried metal conduit shall be coated with anti-corrosion tape. Tape shall be a minimum of 2 inches wide. Tape shall extend 6 inches above finished grade.

#### 11.03 Enclosures (Refer to Sheets E5-E9 and Sheets E12-E14)

All enclosures, including primary and secondary junction boxes, shall be level. Opening mechanisms and locking devices on all transformer equipment shall be 4 to 6 inches above final grade. Opening mechanisms and locking devices on all primary sectionalizers, switchgear and secondary junction boxes shall be 10 inches above final grade. Only approved enclosures, pads, and vaults shall be used.

#### 11.04 Soils & Compaction (Refer to Sheet E10)

All soils under enclosures shall be approved road base and be compacted to 95% of dry density. The compaction area must extend at least 1 foot past the enclosure in all directions and be a minimum of 1 foot in depth under the enclosure. A compaction test shall be required before any enclosure, box, sleeve, or pad is set into place. The compaction test shall be taken by the City or by the City's approved engineering firm. If ground sleeves or pads settle, Developer shall be required to re-level to the above specifications. If primary enclosures or transformers settle after being energized, the City shall re-level the equipment at the Developer's expense.

### SECTION 12 INSTALLATION (Refer to Sheets E5 – E9 and Sheets E12-E14)

#### 12.01 General

All electrical facilities shall be installed under the supervision of a licensed electrical contractor or journeyman lineman. **A certified journeyman electrician or lineman shall be on site during all conduit installation, cable pulling and connecting of electrical wiring.** All electrical installation & equipment shall be installed in a neat and workmanlike manner.

Curb & gutter shall be installed before excavation of electrical trenches. The curb should have property corners pinned in the top of the curb by approved methods. The curb will give reference for proper conduit depths & locations, and proper placement of electrical and communications boxes. Developer required to notify communication company and give up to 1 week to install communication lines. Open trench will be backfilled up to communication lift during waiting period.

Contractor shall construct all electrical facilities in a development except for the following which shall be completed by the Utility:

1. Pulling high voltage underground cable.
2. Installing high voltage cable terminations.

3. Setting transformers and switch gears (contractor shall furnish & install sectionalizers).
4. Secondary connections shall be connected in transformers (exception: contractors shall connect secondary connectors in 3 phase transformers);

All overhead facilities, including extension of risers as shown in the standard drawings. (Refer to Sheet E20)

12.02 Underground Lines

All new facilities shall be constructed underground unless otherwise authorized by the City. Existing buildings & facilities that have a change of use, or extensive remodeling, may, at the Public Power Director’s discretion, be required to install underground power lines. No overhead power will be allowed unless required or approved by the Utility.

12.03 Conduit Depths

High voltage (12.47kV) primary conduits shall always be installed below secondary (600 volts or less) conduits & communications conduits if installed in a joint trench application. No primary high voltage conduits shall be installed at less than 4 feet in depth to top of conduits unless otherwise approved.

In general, the following table of depths shall be used for electrical conduit: (Note: depths are to the top of conduits)

Table 12.03.A  
Electrical Conduit Depths

Conduit Size	Depth to Top of Conduit
1" Street Light	2 Feet
2" Secondary	2 Feet
3" & 4" Secondary	2 Feet
4" Primary	4 Feet
6" Primary	4 Feet*

\*Depths may increase depending upon application.

12.04 Pull Strings

All primary conduits shall have 1,350 lb. mule tape in the conduit securely tied off in each pad or enclosure.

12.05 Identification Tape and Stub Markers

All conduits shall have a caution tape buried 12 inches below grade directly above conduit. Tape shall meet the requirements and specifications of APWA

23 20. The end of each stubbed conduit, including service laterals, shall be marked to the surface according to the standard drawings.

12.06 Underground Metal Conduit

If underground metal conduit were allowed, all buried metal conduit shall be coated with anti-corrosion protective tape. Tape shall extend 6 inches above finished grade.

12.07 Road Crossings

Conduit shall be schedule 80 gray PVC or rigid fiberglass conduit. Shadow conduit shall be installed at road crossings at Public Power Director's discretion.

12.08 Berms, Slopes, and Hillside Conditions

For installation instructions around berms, slopes, and hillsides contact Brigham City Public Power.

12.09 Labels

A label shall be securely taped to the end of each conduit run where it emerges into any cabinet or enclosure. The label shall indicate whether the conduit run is primary or secondary and the direction & footage of conduit.

SECTION 13 SYSTEM REQUIREMENTS

13.01 Additional Capacity Requirements

In the event a Customer makes application for additional capacity, subject to provisions of the applicable rate schedule, Customer shall install the necessary transformer capacity, service wires and other equipment required to adequately serve Customer's requirements. Customer will be required to submit a Brigham City Load Sheet to be completed by electrical engineer, architect, or master electrician. Report shall include all existing and future load.

Customer shall be required to participate in system load study to ensure needed capacity is available through City's transmission system. Customer shall be responsible for all costs associated with said study.

All applications for service involving the furnishing of additional capacity or equipment by the City may be required of the Customer. The application shall state that any service entrance wiring and main switches required for the utilization of such additional capacity to be furnished by Customer, shall be considered as permanent fixtures belonging to the property being served and property except for replacement or enlargement if necessary.

### 13.02 Substations

Substation may be required of Customer. The City reserves the right, where unusual substation capacity or voltage is involved, to require the Customer to install the necessary complete substation as provided for in City's rate schedule.

Where the Customer furnished the necessary complete substation equipment to take service at primary service voltage, such equipment shall be owned and maintained by the Customer and shall include the necessary transformers, structure, controls, and protective equipment, and shall be of such quality and construction as meets City approval. Customer shall supply main transmission breaker to City for ownership and operation providing interconnection to transmission system. Operation of said breaker will be controlled by the city.

## SECTION 14 SERVICES

### 14.01 Point of Service

The Public Power Director determines the point of delivery for all developments. Public Power Director reserves the right to meter service at either primary or secondary voltage. For large or unusual loads, Public Power Director reserves the right to require Customer to take service at primary voltage and to require Customer to furnish the necessary complete substation equipment. The Public Power Director will decide if multiple buildings, business and residential, or portions of buildings will be metered from one or from multiple metering points. Each building or structure served shall be supplied by only one service. Multiple services are only allowed at the Public Power Director's discretion.

### 14.02 Service Entrance Requirements

The service entrance shall be defined as the facilities that consist of approved service entrance conduit and cable enclosing conductors and apparatuses. Said conductors shall extend from the point of contact with the City's secondary point of service and thence to and include Customer's service entrance safety switch or disconnection means.

Customer shall install all conduit and wire from the building to the pole or transformer according to the City standards.

1. Service Entrance Safety Switch or Main Disconnect for new construction and remodel. A residential service safety switch shall be an exterior service combination meter base and main disconnect device. For commercial & industrial installations a service safety switch shall be an exterior service main disconnect device or devices, which will always

remain accessible. This device shall be a main breaker, but minimum requirement shall be a safety switch, which will disconnect all service power from the premise wiring to the entire facility. The location of the main disconnecting device shall be approved by the City.

2. Identification. (Current NEC) Where a building or structure is supplied by more than one service, or any combination of branch circuits, feeders, and services, a permanent plaque or directory shall be installed at each service disconnect location denoting all other services, feeders, and branch circuits supplying that building or structure and the area served by each.
3. Service Entrance Conductors. All service entrance conductors and any conduit enclosure shall be continuous, unbroken, and completely exposed for external inspection throughout their entire length, extending from said point of contact with City's service wires to the meter socket (or meter cabinet if installed) and thence to Customer's service entry safety switch or main disconnecting means. Service entrance conductor type & size shall meet current NEC, NESC, and City Standards. Brigham City Public Power reserves the right to make an allowance as needed.

Underground service lateral conductors from the City's Secondary service point up to the line side of the main disconnecting means shall be installed, maintained, and owned by the Customer. The City assumes no liability for replacement of secondary service lateral conductors.

14.03 Underground Residential Service Requirements (Refer to Sheets E2 and E15)

14.03.1 Conductor,\* conduit sizes, & conduit depths

Refer to following table:

Service Size	Service Conductor Size (AWG)	Conduit Size	Conduit Depth
100 amp	2/0 alum.	3"	2'
125 amp	2/0 alum.	3"	2'
150 amp	2/0 alum.	3"	2'
200 amp	2/0 alum.	3"	2'
201-400 amps	Contact Brigham City Public Power	Contact Brigham City Public Power	Contact Brigham City Public Power

\*Table 14.03.1.A Note: The current National Electric Code may supersede these conductor sizes based upon service size. Refer to current NEC for service conductor sizes for other types of conductors & installations.

- 14.03.2 Conduit (Refer to Sheet E11)
- Only continuous factory lengths of conduit shall be used. Conduit may be cut or spliced; however the couplers & bends shall not exceed a 360-degree pull on the overall length of the conduit run. Conduit shall be installed in a neat and workman-line manner. All service lateral conduits shall be inspected prior to backfilling.
- 14.03.3 Materials
- Only electrical grade materials shall be used. Rigid metal conduits (RMC), schedule 40 fiberglass and schedule 40 PVC shall be used for any elbows or bends 45 degrees or greater. RMC shall be coated with an anti-corrosion tape below grade and tape shall extend 6 inches above finished grade. RMC shall be used for all above grade service entrance conduits. Customer shall provide and install service wire from house to junction box, transformer or pole according to City standard drawings. Service wire type shall be approved by Brigham City Public Power.
- 14.03.4 Trenching
- Service lateral trenches shall be 24 inches in depth. Trenches shall be as straight as possible from the secondary service point to the Customer disconnect or meter base. The bottom of the trench shall be as level as possible and free from rocks & debris. Backfill placed directly on conduits shall be free from large rocks.
- 14.03.5 Service Entrance Conduits Support and Attachments
- Service Entrance conduits shall be securely attached to the foundation of house or building by means of unistrut, concrete anchors, and unistrut type clamps. Unistrut shall be securely attached to foundation by a minimum 3/8 inches x 3 inches concrete anchors. Unistrut shall typically be 24 inches. Service entrance conduits shall be one continuous, unbroken conduit from the elbow to the point of attachment at the meter base hub.
- 14.03.6 Location(s)
- Note: Refer to 15.02 Metering for additional requirements. Meter/main disconnect shall be located within the front 6 feet of the side of a residential dwelling. Meter/main disconnect shall always be accessible. Meter/main disconnect shall be kept a minimum of 36 inches from any natural gas meters, window wells, windows, doors, stairs and any material deemed

to be combustible or hazardous. For remodels, service upgrades, building additions or other instances or applications affecting the existing electrical service, CT cabinet, meter base, meter and disconnect contact the Brigham City Public Power for requirements. Brigham City Public Power will require a meter main disconnect to be installed anytime electrical upgrade work is performed on the residence. The service, meter, meter base, or disconnect may be required to be relocated to meet current Standards and Codes. Meter/main disconnect shall meet all applicable NEC and NESC codes. The Public Power Director reserves the right to accept or reject any locations of meter base/main disconnects.

14.03.7 Temporary Underground Service (Refer to Sheet E18)

For temporary service furnished to individual small single-phase loads, such as house trailers, small construction projects (such as house and small buildings, portable tools, etc.) City will install a standard temporary service drop, at Customer's expense. City's General Service Rate shall apply.

Where the temporary service installation requires additional facilities more than the previously mentioned standard service drop (such as an extension of the City's primary line), such installation will be at the Customers' expense.

14.04 Overhead Residential Service Requirements (Refer to Sheet E3)

14.04.1 General

Overhead services shall also include mast knob and service grips. Wiring shall meet load and installation requirements as indicated in the NESC/NEC.

14.04.2 Service Drop Support and Attachments

For one story buildings, or where conditions will not permit proper ground clearance to be maintained by City's service wires, Customer shall install, at Customer's expense, suitable conduit or service entrance mast pipe or other structure or support that will properly support the City's service drop conductors and to maintain the minimum ground clearance as required by the NESC/NEC. If clearances cannot be met, the service may be required to be relocated or otherwise rerouted underground.

14.04.3 Service Entrance Weather head Clearance

The service entrance weather head shall be located to meet or to exceed NESC/NEC clearance from readily accessible

windows, doors, or porches. The weather head must also be located so that when the service drop conductors are attached to the building structure or other service drop support, adequate clearance will be maintained away from telephone or other wires, windows, awnings, drainpipes, chimneys, or other obstructions.

14.04.4 Service Entrance Mast Pipe

This installation shall be made by Customer, at his/her expense, and shall conform to City's specifications. The service entrance mast pipe shall be of electrical grade galvanized rigid steel of not less than 2 inches inside diameter and shall be attached to the wall of the building by means of an adequate number of approved fastening devices. All service conduits shall be 2 inches in diameter, or larger.

The mast pipe and/or conduit shall be continuous, extending from the service entrance weather head located at the top of the mast pipe to Customer's meter socket base.

The service entrance mast pipe shall extend above the roof surface (through weatherproof roof flashing) so that the point of attachment of City's service wires to the mast pipe will be not less than 18 inches above said roof line, and not to exceed 36 inches without guy support to structural frame plus such additional height as is necessary so that the point of attachment of City's service wires will maintain minimum ground clearance, specified in the NESC/NEC.

14.04.5 Service Drop Attachments to Buildings

The Customer will furnish and the city will install the necessary attachment brackets and apparatuses to attach City's service wires to Customer's service drop termination facilities.

The City further reserves the right to require that the installation of the necessary mast pipe or equivalent facilities required supporting city's service wires, be made by Customer during the course of building construction.

Where the exterior of buildings is finished with brick facing, concrete, plastered metal lathe, sheet iron, stucco, tile or similar material, suitable facilities of adequate strength to hold City's wires and attachments, shall be installed by Customer at Customer's expense.

- 14.04.6      Service Drop Conductor Ground Clearance
- The service drop conductors must be located at such height as will enable adequate clearance to be maintained through the entire service drop length. The minimum ground clearance shall be as specified by the NESC/NEC, but not less than 12 feet over driveways not subject to truck traffic; 16 feet over commercial areas, parking lots and other areas subject to truck traffic; and 22 feet over public streets, alleys and roads. The final height attachment determination shall take into consideration conductor sag due to weather fluctuations & lengths of spans.
- 14.04.7      Service Entrance Conductor Specifications
- The service entrance conductors may be either copper or aluminum, and shall be continuous without any joints, splices or connections, extending from the point of connection with service drop conductors to the termination of same at the meter socket or meter cabinet and thence same shall continue without joints, etc., to Customer's service entrance safety switch.
- The Customer shall have electrical Contractor provide at the service entrance weather head, sufficient excess service entrance conductor length or "tails" (18 inch minimum) so that the City can connect directly to the service drop conductors. The service entrance installation shall conform in every respect to City's specifications, as to conductor connectors, and the method of making connections and all other related matters involved.
- The service entrance conductor size for the ampere load to be carried shall be based on a maximum conductor operating temperature of 75°C (type RH, RHW, XHHW, or equivalent.) Note: Refer to Table 14.03.1.A regarding service conduit & conductor sizes.
- 14.04.8      Main Breaker or Disconnect
- The entrance safety switch or main breaker ampacity shall not be less than the rated ampacity of the service conductors. Other specifications, including conductors, shall conform to the latest edition of the NEC.
- Upon special application, City may permit 2 or 3 wire service entrance installations of less than 100 ampere capacity for signs, etc., where the load requirements, as determined by

City, justify the same. In no event will 2 wire service be furnished except at city's option.

14.04.9 Temporary Service Drops (Refer to Sheet E18)

For temporary service furnished to individual small single-phase loads, such as house trailers, small construction projects (such as house and small buildings, portable tools, etc.) City will install a standard temporary service drop, at Customer's expense. City's General Service Rate shall apply.

Where the temporary service installation requires additional facilities more than the previously mentioned standard service drop (such as an extension of the city's primary line), such installation will be at the Customers' expense.

14.04.10 Service to Mobile Homes and Trailer Courts through one meter

For service to trailer courts where more than 1 dwelling unit, mobile home, or trailer exists, the campus shall be supplied through 1 meter and the furnishing of such service shall be provided and installed by the facility owner.

14.04.11 Load to be Balanced on Circuits

The Customer shall use reasonable care in designing electric wiring and circuits; also, the connection of the loads to the circuits, so that the loads on the individual phases and circuits of City's service are properly balanced at all times.

14.04.12 Temporary Service to be Installed on Customer's Pole

All such temporary service drops shall be supported on a pole or post as approved by the Public Power Director and shall be installed by Customer at his/her expense.

14.05 Underground Service Requirements for Multi-Family Dwelling Units

14.05.1 General

Service lateral conduits from the City's point of secondary service shall be 4 inches minimum for multi-family dwelling units. A load calculation study shall be performed for multi-family dwellings units and submitted to Brigham City Public Power. All other residential service requirements apply.

14.06 Underground Service Requirements for Commercial & Industrial Applications

14.06.1 General

Service entrance conductors & conduits shall be sized according to applicable NEC and NESC codes. The City shall

approve all locations & installations of conduits, service disconnection means, and meters.

- a. All commercial & industrial buildings shall have an accessible, exterior main disconnecting means that is capable of disconnecting (opening) all service entrance conductors from the building or structure premises wiring.
- b. All services rated 801 amps or more supplied by a 4-wire three phase 480Y/277 volt connected system shall have a ground fault test performed for protection of equipment.
- c. All services, equipment, cabinets, conduits, etc. shall be grounded & bonded according to applicable NEC & City codes.
- d. The service disconnecting means shall be identified as suitable for use as service equipment.
- e. A building or structure may only be served by one service lateral or service drop, unless otherwise approved by Brigham City Public Power.
- f. There shall not be more than 6 service disconnects for each service. Each service disconnect shall be permanently marked to identify it as part of the service disconnecting means. All service disconnecting means for each service shall be grouped together.
- g. The center of the operating handle of switch or breaker, when in its highest position, shall not be more than 5 feet and not less than 4 feet above finished grade.

#### 14.06.2 Materials

Only electrical grade & UL listed materials shall be used. Rigid metal conduits (RMC), schedule 40 fiberglass and schedule 40 PVC shall be used for any elbows or bends 45 degrees or greater. RMC shall be coated with an anti-corrosion tape below grade and tape shall extend 6 inches above finished grade. RMC shall be used for all above grade service entrance conduits. Customer shall provide service wire from building to utility transformer or pole. All electrical equipment, cabinets, panels, etc. shall be UL listed and approved for the installation.

#### 14.06.3 Trenching

Service lateral trenches shall be 2 feet in depth. Trenches shall be as straight as possible from the secondary service point to the Customer disconnect or meter base. The bottom of the trench shall be as level as possible and free from large rocks & debris

- 14.06.4      Service Entrance Conduits Support and Attachments
- Service Entrance conduits shall be securely attached to the foundation of building by means of unistrut concrete anchors, unistrut type clamps or other approved methods. Unistrut shall be securely attached to the foundation by a minimum 3/8 inches x 3 inches concrete anchors. Service entrance conduits shall be one continuous, unbroken conduit from the elbow to the point of attachment at the meter base, CT cabinet, or main disconnect cabinet. Service lateral conduits shall be installed at a depth of 2 feet to top of conduits. All installations shall be installed in a neat and workman-like manner.
- 14.06.5      Locations
- Locations of service lateral conduits shall be approved by the Public Power Director. Locations of outside main disconnecting equipment shall be approved by the Public Power Director. Meter/main disconnect shall always be accessible. Meter/main disconnect shall be kept a minimum of 36 inches away from any natural gas meters, window wells, windows, doors, stairs and any material deemed to be combustible. Meter/main disconnect shall meet all applicable NEC and NESC codes. The Public Power Director reserves the right to accept or reject any locations of meter base main disconnects. If the Public Power Director determines the service location is inaccessible or otherwise unsafe, the Customer shall relocate or upgrade service to City standards at Customer's expense. The Public Power Director further reserves the right to disconnect electrical power to the Customer's service until the service is brought into compliance.
- 14.06.6      Ownership of Conductors
- For commercial underground installations the secondary service conductors and conduit paths shall be owned & maintained by the Customer from the secondary connections inside the transformer up to the termination point of the service disconnect. For commercial overhead installations the secondary service conductors shall be owned & maintained up to the overhead secondary connection point. City shall own the overhead drop up to the connections at the service mast.
- 14.06.7      Energizing Development
- Developments may be energized when the following is completed and accepted by the city.

1. Curb, gutter and an all-weather road surface.
2. Electric conduit.
3. Electrical boxes and proper access to the boxes.
4. Secondary wiring, except that required for street lighting.

## SECTION 15 METERING (Refer to Sheet E22)

### 15.01 General

The city will furnish and install all electric revenue meters. Normally outdoor socket-mounted meters will be used by the city whenever practical. The meter base will be furnished and installed by Customer's electrical contractor for all normal residential installations. The meter base with test switch shall be provided by the City and installed by Customer's electrical contractor for commercial or industrial applications.

If instrument transformers are required, the City reserves the right to require customers to furnish and install a suitable steel cabinet to house City's instrument transformers and accessories. Said cabinet shall contain only the City's metering equipment and shall be equipped so that it can be sealed and locked by the City. The City shall have sole access to this cabinet.

### 15.02 Location

The City shall approve the location of service entrance and meter. The following conditions must be met for the location of all meters & services:

1. **Visibility.** All entrance wiring connections shall not be concealed and shall always be in plain view for inspection by the City.
2. Residential properties shall have the point of service externally installed on the primary residence of the property. If a residential property needs multiple services the amount of services must be approved by the City and be contained in one location inside one meter base that is located on the exterior of the primary residence. Any variation of this may be approved by the Public Power Director.
3. Industrial/Commercial businesses are allowed to have up to two points of service with multiple meters at each location. If more than two points of service are required due to the original design of the property or the property is expanded, then the campus will be required to install a primary metering cabinet. Electrical service to the property will be delivered at the City's distribution voltage. The location of the primary metering cabinet will be determined by the city. The City will maintain ownership and control of the metering cabinet but all conductors feeding out of the metering cabinet will be owned and maintained by the property owner.

4. A property that is undergoing renovation and has pulled a building permit or new construction will be required to relocate the electrical meter and main disconnect point (MDP) of the building to the outside of the building. The metering equipment and MDP shall be mounted to the building if under 801 amps. If service is 801 amps or greater than a freestanding MDP switchgear cabinet will be required. The MDP switchgear cabinet will need to be approved by the Public Power Director before equipment order is placed by the contractor.
5. Protection. No meter or service equipment shall be installed in any location where it may be unnecessarily exposed to heat, cold, dampness or other cause of damage, or in any unduly dirty or inaccessible location.
6. Height. The meter socket shall be mounted at a height of not less than 4½ feet, no more than 6 feet above finished grade, as the case may be. Where multiple meters are installed, care shall be taken to ensure the lowest meter is no less than 4 ½ feet and no higher than 6 feet from finished grade.

When a combination 3 phase and single-phase service is supplied to the same premises, all meters and service entrance switches shall be at the same location.

#### 15.03 Meter Base

Residential meter bases shall be furnished and installed by the Contractor according to City standard drawings. No smaller than a 100-amp service entrance will be accepted other than by approval from the Public Power Director. The meter base shall always be kept sealed and under the control of the City.

#### 15.04 Commercial Meters

Single-phase and three-phase self-contained meter bases shall be installed by the Developer and shall have bypass capability in the meter base. For details and specific information regarding this requirement, please contact Brigham City Public Power. For services rated 200 amps up to 800 amps, the Brigham City Public Power will supply the meter base & test switch for contractor to install at Customer's expense. No smaller than a 200-amp 3 phase service entrance will be accepted unless otherwise approved by the Public Power Director. For services rated over 800 amps, a manufacturer's shop drawing of the MDP switchgear cabinet with main disconnect and adequate metering provisions will need to be provided for approval. Contact Brigham City Public Power for specific requirements and submission details.

The Contractor's portion shall be completely installed, inspected, and the electrical hook-up fee paid before the City will complete the final electrical hookup.

#### 15.05 Location of Multiple Meters

Where more than one meter is required for a building, such as an apartment complex, all meter sockets shall be located side by side at an outside location as determined by the Public Power Director.

#### 15.06 Meter Location Regarding Remodeling

When remodeling, where 2 or more houses or dwelling units are combined to form one building, the meter socket shall be moved to a single location. Meter and service locations shall first be approved by Brigham City Public Power. Existing meters and services may require relocation to meet current City standards. In all remodeling where the meter is changed or moved, or wiring changes made, outdoor meter sockets and an approved new service entrance shall be installed by Customer at Customer's expense.

#### 15.07 Meter Accessibility

In the event a structural change is made by the owner that results, in the opinion of the Public Power Director, to be an undesirable meter location, the meter socket, meter cabinet, and/or service entrance installation shall be moved by the Customer at his/her expense to an accessible location as determined by the City.

Whenever the construction of a building on an adjacent lot prevents proper access to any meter, or access to the point of attachment of service drop conductors, or results in inadequate service drop clearance, the Customer shall move, at Customer's expense, the meter socket and service entrance to a location that is acceptable to City. The meter shall not be enclosed by any portion of a building. The meter shall not be placed under carports or enclosed by sheds, garages, outbuildings or other buildings. The meter shall always remain readily accessible to the City.

#### 15.08 Outdoor Meters for Non-Residential General Service

All single-phase meters installed for non-residential use shall be socket type. The meter base shall have bypass links installed. The meter socket shall be furnished and installed by Customer at Customer's expense.

#### 15.09 Instrument Transformer for Metering

In all outdoor installations requiring current transformers, whether single phase or 3 phase, the Customer shall provide an approved meter loop for meter connections. The City shall furnish any instrument transformers, meter bases, or other devices required, to properly meter the Customer's electrical needs at the Customer's expense. Such instrument transformers and devices shall be installed by the City.

## 15.10 Current Transformer Cabinet (Refer to Sheet E19)

Any cabinets required to house said instrument transformers and accessory equipment shall be furnished and installed by Customer at Customer's expense. This requirement applies to all installations. All cabinets shall be approved by the City.

Such metering or instrument cabinets are for the exclusive use of City, and shall always be under the control of, and kept sealed by City.

## 15.11 Unacceptable Meter Locations

For reasons of public safety, maintenance of service equipment, and reliability of metering, meters shall not be installed in any of the following locations:

1. Inside any building, unless located within an acceptable meter room.
2. In any location that is not readily accessible.
3. Directly over any stairway, ramp or steps.
4. In any substation or transformer vault.
5. Accessible only by a trap door or in any location which may be hazardous to personnel.
6. On any surface subject to excessive vibration.
7. In or accessed through any rest, bath, shower, powder, or toilet room.
8. In any elevated area.
9. In any location not providing a clear and continuously unobstructed working space extending a minimum of eight (8) feet from the face of the meter panel and having a width to permit ready access to the complete metering installation.
10. In any location where moisture, fumes, or dust may interfere with the operation of the meter or damage it.
11. In any location giving less than three feet clearance to any property line, or with less than three feet clearance to any sidewalk, alley or driveway giving access to non-residential or industrial property.
12. In any basement or depressed area.
13. Within carport or patio areas which are or can become enclosed, when served overhead or underground.
14. Mounted on BCPP poles.
15. In a room containing mechanical equipment.
16. In any elevator shaft or hatchway.
17. Mounted on any trees.
18. In any unsanitary areas in reference to farm animals and products.
19. In a plenum or any portion of a return or supply air ducting system.
20. Areas where entry may be restricted or controlled because of medical, health, environmental or other safety-related issues.

## SECTION 16 LIGHTING AND SIGNAL POLES (Refer to Sheets E16-E17)

## 16.01 General

The City shall provide the street light poles, fixtures & associated parts to install the streetlights. The contractor is responsible for transport of the streetlights from the Public Power Department to their respective developments. Furthermore, the contractor shall be responsible for pouring the concrete bases, assembling and erecting the streetlights.

All local streets, minor & major collectors, and arterial streets shall have the decorative streetlight as shown in the standard drawings or as designed. 25-foot steel galvanized poles with a 6-foot arm, and either a 100-watt or a 250-watt equivalent LED cobra head type fixture may be used or substituted for a decorative type pole & fixture at the City's discretion. All fixture types will be of the Luminaire type with 90-degree cutoff lens.

All traffic signal poles shall be powder coated black.

## 16.02 Dark Sky

All street and parking lot lighting shall meet the IDA (International Dark-Sky Association) recommendation and City ordinance for dark sky compliance. This will require that all lighting, streetlight, parking lot lighting, walkway lighting, etc., cannot broadcast light above 180° from the parallel ground surface. It is advised that all lighting on buildings, such as security lighting, also meets this requirement.

## 16.03 Location

In general, streetlights will be installed at all intersections except where a four-way intersection has an offset of less than 100 feet from another intersection. Streetlights shall be installed on the top of all traffic signal poles. Streetlights for local streets will be installed with a maximum spacing of 400 feet between lights. All mid-block streetlights shall be installed 18 inches from a property line. Collector and arterial streets shall have lights spaced at 175 feet apart on alternating sides of the street. In addition to the typical location design and layout, street light locations may also be designed by Brigham City Public Power. Commercial right-of-way lighting needs to be staggered 125 feet with a maximum of 250 feet of spacing on each side of the ROW.

Each streetlight will be installed so that the street light pole is centered in the planter strip or within 18 inches of the sidewalk if no planter strip exists.

## 16.04 Orientation

Streetlights at intersections of local streets shall aim at the center of the intersection. On collector or arterial streets streetlights shall be set at a 90-degree angle at regular intervals determined by the City.

16.05 Grounding & Bonding

A bonding wire shall be connected from the rebar “Ufer” rings in the concrete pole base to the street light pole grounding/bonding screw or termination point using NEC approved methods and a separate grounding wire will be installed from the pole to the closest secondary pedestal or transformer. The grounding conductor shall be terminated with the neutral conductor.

16.06 Wiring & Fusing

A 10-amp in-line fuse & fuse holder shall be installed in the junction box on the 120/240-volt ungrounded conductors.

---

## VEGETATION MANAGEMENT

### SECTION 17 VEGETATION MANAGEMENT

#### 17.01 Overview

When feasible, BCPP prioritizes the removal of tall-growing trees and vegetation to prevent future conflicts with overhead power lines, while supporting the establishment of low-growing species that will never interfere with the high-voltage lines. Considering the interests of property owners and other land use objectives, it is not always possible to remove incompatible trees.

Tall-growing trees that cannot be removed must be pruned to maintain clearance around power lines through use of arboriculturally sound pruning practices.

#### 17.02 Professionalism

In accordance with ANSI Z133, all personnel working in proximity to overhead conductors at any time are required to hold one of the following designations: Qualified Line Clearance Arborist or Qualified Line Clearance Arborist Trainee.

#### 17.03 Safety

The safety of workers and the public should always be given the highest priority. Federal and state requirements governing vegetation management activities shall always be followed, including all OSHA requirements. ANSI Z133 (2107 or most current) and OSHA 1910.269 are examples of these requirements. Activities shall be conducted to minimize tree crew and public safety risks.

Table 17.03.A Minimum approach distances for Qualified Line Clearance Arborists and Qualified Line Clearance Arborist Trainees.

Voltage (kV) (Phase-to-Phase)	Minimum Approach Distance Sea Level to 5,000 ft.	Minimum Approach Distance 5,000 to 10,000 ft.	Minimum Approach Distance 10,000 to 14,000 ft.	Source*
0.05-0.300	Avoid contact	Avoid contact	Avoid contact	APM/Z133
0.301-0.750	1' - 6"	1' - 7"	1' - 7"	APM/Z133
0.751-15.0	2' - 6"	2' - 7"	2' - 10"	APM/Z133
15.1-46.0	3' - 6"	3' - 7"	3' - 8"	APM/Z133
46.1-72.5	3' - 6"	4' - 0"	4' - 4"	Z133
72.0-121.0	3' - 11"	4' - 6"	4' - 10"	Z133
121.1-145.0	4' - 6"	5' - 2"	5' - 7"	Z133
145.1-169.0	5' - 1"	5' - 9"	6' - 3"	Z133
169.1-242.0	7' - 0"	7' - 11"	8' - 7"	Z133
242.1-362.0	11' - 9"	13' - 6"	14' - 7"	Z133
362.1-420.0	14' - 8"	16' - 9"	18' - 2"	Z133
420.1-550.0	17' - 6"	20' - 0"	21' - 8"	Z133
550.1-800.0	23' - 9"	27' - 2"	29' - 5"	Z133

#### 17.04 Fire Protection

Federal, state, and local fire protection laws and regulations shall be followed, and the Tree Crew Foreman performing the work must obtain necessary work permits. Crews shall have all fire suppression tools and equipment required by the governmental agency responsible. Tree Crew Foreman shall also adhere to fire restrictions concerning work hours, fire watch following work, and other policies of the pertinent jurisdiction. Tree Crew Foreman with crews working in fire-prone rural areas shall provide basic fire prevention and suppression training to their crews annually. Documentation of this training shall be submitted annually to the BCPP Director July 1<sup>st</sup>.

#### 17.05 Species of concerns

Vegetation maintenance shall not disturb or harm any rare, threatened, endangered, or protected plant or animal species. Nesting season work restrictions exemplify important scheduling considerations necessary to accommodate protected species. If there are rare, threatened, endangered, or protected plant or animal species present at a location where work is planned, the Tree Crew Foreman must stop work and immediately inform the BCPP Director.

#### 17.06 Bird Protection

Migratory birds are protected by the Migratory Bird Treaty Act of 1918 (16 USC 703-712) (MBTA). Most bird species are protected under the MBTA; therefore, in an abundance of caution, all bird species should be considered subject to

the law's provisions. The Tree Crew Foreman shall conduct vegetation maintenance consistent with the MBTA.

The MBTA prohibits removal of bird nests that have eggs or chicks and killing any birds which are members of any protected species. Active nests may not be disturbed unless the BCPP Director, after consultation with U.S. Wildlife Services has provided authorization. If tree crews identify a possible immediate risk (e.g., active nest in the vicinity of vegetation listed for work), the Tree Crew Foreman shall contact the BCPP Director. The Director will consult with U.S. Wildlife Services regarding whether work may proceed. If work is postponed until after young have left the nest, the location must be recorded and tracked to ensure completion at the appropriate time.

The nests of eagles threatened and endangered species, and colonial waterbird nests (such as those of herons) may not be disturbed – whether or not they are active. Eagles are subject to additional protection; it is illegal to disturb them near their nests or winter roosting sites. If large stick nests, suspected to be protected nests, are in vegetation identified for removal, the Tree Crew Foreman must contact the BCPP Director who will consult with the U.S. Wildlife Services.

Raptors (birds of prey) and herons require buffers around active nests to prevent them from being disturbed, unless instructed otherwise by U.S. Wildlife Services or applicable regulatory authority.

Table 17.06.A Work buffers around active nests of eagles, hawks, and herons.

Species	Work buffer
Bald Eagles (Jan 1-Aug 31)	660 feet
Bald Eagle roosts (Nov 1-Mar 31)	0.25 mile
Golden Eagles (Jan 1-Aug 31)	0.25 mile
Hawks (exceptions below)	600 feet
Ferruginous hawk	0.5 mile
Northern goshawk (Mar 1-Aug 31)	0.5 mile
Swainsons hawk	0.25 mile
Owls	300 feet
Great Gray Owl	0.25 mile
Northern Spotted Owl	0.25 mile
Osprey	600 feet
Herons/Colonial Nesters	600 feet
Songbirds	50 feet

In general, if a bird leaves a nest and does not return within an hour, it is being disturbed, and the buffer should be increased. In these cases, U.S.

Wildlife Services should be contacted within 24 hours to monitor the nest and respond appropriately if the adults fail to return.

Active bird nests and inactive bird nests should be reported to the BCPP Director and U.S. Wildlife Services.

#### 17.07 Tree Removal

In certain circumstances, it is necessary or appropriate to remove trees (i.e., removed the threat posed to electrical infrastructure or remove the tree from the “inventory” of future work). When a tree is removed, the stump shall be cut to within 6 inches of the ground or as close to it as practical (for example, at the top of a barbed wire fence that has become imbedded in the trunk). Stumps of all deciduous trees, brushes, and vines that are removed shall be treated with an approved herbicide, unless otherwise indicated by landowner or restricted by the land managing agency. Tree removal may be discretionary or necessitated by the presence of Hazard Trees.

##### 17.07.1 Hazard Trees

“Hazard Trees” are defined as a tree in whole or in part, that might fail, and which is identified as a likely source of harm. Trees that are dead, dying, diseased, deformed, or unstable, which have a high likelihood of falling and contacting a specific target (electrical infrastructure) should be assessed for removal. The Tree Crew Foreman shall conduct a visual assessment, consistent with ANSI A300. Hazard Trees pose a safety and reliability risk and must be removed (or pruned to the extent that the tree is no longer a Hazard Tree). BCPP reserves the right to deny chipping of any dead wood and will leave the dead wood on property for customer to clear. Federal and state agencies sometimes request that trees subject to removal be topped to create “wildlife trees.” BCPP may honor such requests, provided the safety of the tree workers or the integrity of facilities are not compromised. Any Hazard Trees removed to accommodate this request should be reduced to a height so that the tree would never contact any BCPP Facilities should it fall.

##### 17.07.2 Discretionary Tree Removal

Discretionary tree removal reduces the total tree inventory and can, therefore, reduce long-term risks to safety and reliability; improve access to facilities, clear lines of sight, and moderate future workloads. In general, removal of trees near power lines are encouraged and are to be pursued by the Tree Crew Foreman.

## 17.08 Debris Disposal

Before leaving a particular worksite, all debris must be brought to ground, with no severed limbs left in the tree canopy (hangers). Work locations shall be left in a safe and orderly condition at the end of the workday. “Debris” is cut vegetation remaining after maintenance operations.

Debris is typically disposed of in multiple ways. First, debris may be chipped using a mechanical chipper and then transported off-site. Second, debris may be chipped using a mechanical chipper and then broadcast on-site. Third, debris may be lopped into maximum lengths of 3 feet and scattered (if necessary to pile debris, piles shall be no more than 18 inches high). The appropriate method of disposal depends on the area where vegetation maintenance is being performed. Additional debris management requirements may be identified by land managing agencies.

### 17.08.1 Inaccessible Areas

In remote off-road areas without reasonable vehicle access, debris can be disposed of on-site. Use the lop and scatter method mentioned above.

## 17.09 Directional Pruning

Directional pruning is a natural target pruning applied to redirect tree growth away from utility lines (Gilman 2012). ANSI A300 and ISA’s best management practices (Kempter 2004) instruct that pruning to clear the utility space involves thinning cuts: removing at natural targets entire branches that are growing toward (or once cut will produce sprouts that will grow toward) the power lines.

While heading cuts produce sprouts that grow quickly back into the power lines, branch removal and reduction promote growth away from conductors. Because one objective of utility pruning is to train trees away from power lines wherever practical, branches growing away from the electric facility should not be pruned. Instead, these stems should be allowed to develop to their natural height or length, provide that growth does not create unreasonable safety risks. This cannot be accomplished with strongly excurrent trees trapped directly beneath conductors.

Topping, round-overs, flush cuts, branch tipping, and rip cuts are improper as they result in damage to the trees. Directional pruning is consistent with natural tree structure. Remaining branches retain their taper, strong attachments, growth regulators, and spacing. They continue to grow and function normally, allowing the tree to reach its natural height.

“V” shapes often result in properly pruned trees growing under power lines, particularly on decurrent, deciduous trees (Gilman 2012; Kempter 2004;

Miller 1998; Shigo 1990). Limbs growing upward and toward the facility should be cut back to the trunk or to limbs growing away from the conductors. Remaining branches should have sufficient clearance, so they do not damage the conductors in inclement weather common for the locality (high wind, freezing rain, snow, or other conditions). Excurrent trees (such as main conifers) are more problematic but should be reduced to appropriate laterals or whorls. “L” or one-sided shapes often result in properly pruned trees to the side of conductors (Shigo 1990; Gilman 2012). Limbs on the wire side of trees located adjacent to facilities should be cut back to the trunk; or to limbs growing vertically, sideways or downward; depending on the distance to the line or available natural target.

#### 17.10 Tree Houses

Tree houses built in trees growing near power lines present electric safety risks. Children or others may contact the line, either directly or indirectly, if a tree house is built too close to conductors. Indirect contact may occur through any conductive object, including a tree or tree parts that are contacting power lines. Minimum tree house distances are set at twice the “Minimum approach distances to energized conductors for arborists not qualified by training and experience to work within 10 feet of electrical conductors” as established in Table 1 of ANSI Z133.

#### 17.11 Distribution Cycle Maintenance

Trees and vegetation are pruned from distribution facilities on scheduled cycles. Facilities are worked systematically, either by circuit or grid. The duration of a cycle is dependent on local conditions, as determined by BCPP. BCPP typically schedules distribution cycle maintenance work on a three-year cycle for most circuits in BCPP service territories.

Refer to Sheet V-1.

In performing distribution cycle maintenance, the Tree Crew Foreman is required to:

- Systematically prune and remove trees and other vegetation at a specified distance from all primary conductors and non-primary conductors, consistent with this section,

- Comply with all other specifications generally applicable to all vegetation maintenance under these SOPs, including without limitation

- Identify and remove (or remediate) Hazard Trees and discretionary tree removals.

- Identify and correct readily climbable trees that are too close to power lines.

Identify and remedy or remove tree houses violating the criteria.

Remove all brush, which include volunteer trees (naturally seeded, non-landscaped trees) and woody plants (including vines).

17.11.1 Distribution Cycle Maintenance - Clearance Distances – Primary (Refer to sheets V-1 and V-2)

Each work cycle, trees and other vegetation are pruned or removed to achieve clearance distances to comply with the NESC, state regulation clearance requirements, and BCPP guidelines.

Specified vegetation clearance distances from primary conductors in the distribution system should allow sufficient space to prevent contact with primary conductors or regulatory mandated clearance distances throughout the cycle.

The Tree Crew Foreman is responsible for identifying all vegetation that would encroach upon conductors, BCPP required distances, or regulatory mandated minimum clearance distances throughout the cycle.

Neutral conductors in a raised position, which includes above or on a crossarm, are treated as primary-conductors for purposes of this section. Low neutral position is treated as a hot conductor.

17.11.2 Distribution Cycle Maintenance – Clearance Distances – Non-Primary

17.11.2.1 A secondary line is a line typically energized to less than 750 volts. Specified distances from secondary conductors in the distribution system are designed to prevent strain (severe deflection) or abrasion. The “Work Threshold,” which is the point at which action must be taken) and Post Work Clearance distances for non-primary are set forth as follows:

Table 17.11.2. A non-primary wire vegetation clearance distances.

Line Type	Work Threshold	Minimum Post-Work Clearance
Non-insulated wire pole-to-pole secondary	N/A	3 feet
Neutral low position	Contact	2 feet
Insulated pole-to-pole secondary	Deflection or abrasion	2 feet
Non-insulated secondary service line/streetlight	N/A	1 foot
Insulated secondary service/streetlight	Deflection or abrasion	1 foot
Guy wire	2-inch or graded diameter limb applying pressure	Relieve pressure

These practices can be changed at any time at the discretion of the BCPP Director.

In addition to the specification clearances (Table 17.11.2.A), the following requirements also apply to distribution cycle maintenance work on distribution non-primary.

**17.11.2.2 Tree Limbs Between Conductors.** Any tree limbs between a primary conductor and any secondary conductor, regardless of type, shall be removed or pruned to Post-Work Clearances for primary.

**17.11.2.3 Customer Work.** If a customer expresses a desire to remove other limbs or trees around any non-primary, in addition to the work to complete under these specifications, vegetation maintenance workers should inform the customer to call BCPP to arrange for a temporary disconnection of the facilities to allow safe completion of the desired tree work, as required by law.

## 17.11.3 Distribution Cycle Maintenance – Other Facility Clearances

In addition to pruning trees to maintain clearances, certain vegetation maintenance is required on utility poles (and supporting guy wires) as part of distribution cycle maintenance work. One-third of the circumference around poles shall be cleared of vegetation to 5 feet from the pole to allow linemen a climbing path. The remaining two-thirds of the pole circumference should be cleared of all vegetation 1 foot from the pole.

Vines growing on poles and guy wires shall be:

Cut at ground level

Treated with an approved herbicide

Removed from the bottom 5 feet of the pole or guy wire

Reported as brush or tree removed

Vines clearly part of a landscape and rooted well away from the pole may be:

Pruned to provide sufficient climbing path and 5 feet of separation (e.g., 5 feet of separation between the top of a fence and facility)

Reported as brush pruned (not to exceed 100 brush ft. pruned)

Where vines remain on facilities after work is completed, the Tree Crew Foreman will document the exception and report it to BCPP Director to clear the remainder of the pole.

## 17.12 Transmission procedures

Transmission facilities are overhead lines energized at a higher voltage. Typical transmission voltages on BCPP's system are 46kV and 138kV. Facility voltage and type determine the amount of transmission clearance needed. Vegetation maintenance performed on transmission lines shall comply with ANSI A300. In addition, vegetation maintenance performed on transmission lines shall conform with the NERC Reliability Standard FAC-003-5. Consistent with requirement R4 of NERC Standard FAC-003-5 and the procedures set forth in BCPP transmission grid operations. BCPP line patrolmen are responsible to complete inspections on certain transmission lines. When doing their inspections, line patrolmen will identify any vegetation that poses a threat of causing a transmission outage. In addition, BCPP vegetation management department completes vegetation inspections of the Right of Way for transmission lines. BCPP vegetation management completes an annual vegetation inspection on main grid transmission lines. All other transmission lines are inspected at least once

every year. Vegetation maintenance on transmission lines is then scheduled according to the results of those inspections.

#### 17.12.1 Transmission Clearances

The objective of systematic transmission work is to safeguard the reliability of BCPP transmission system by preventing outages from contact with vegetation. Clearance work on a transmission line is guided by three concepts: Minimum Vegetation Clearance Distances, Action Thresholds, and Minimum Clearances Following Work.

Minimum Vegetation Clearance Distance (MBVCD) represents radial distances from the conductors inside of which trees shall not encroach.

### 17.13 Chemical Procedures

Herbicides and tree growth regulators (TGR) are an important part of BCPP Vegetation Management Program. Herbicides are chemicals used to manipulate or control undesirable vegetation. When safely used, herbicides are effective and efficient, minimize soil disturbance, and enhance plant and wildlife diversity. Herbicide applications can benefit wildlife by improving forage as well as escape and nesting cover. In some instances, noxious weed control is a desirable objective in utility ROW that can be accomplished through herbicide treatment. Herbicide use can control individual plants that are prone to resprout or sucker after removal. When trees that resprout or sucker are removed without herbicide treatment, dense thickets develop, impeding access, swelling workloads, increasing costs, blocking lines-of-site, and deteriorating wildlife habitat (Yahner and Hutnik 2004). Treating suckering plants allows early successional, compatible species to dominate the ROW and out-compete incompatible species, reducing work. “Tree growth regulators” refers to chemical treatments that slow the growth of some tree species.

Chemical applications shall always be performed according to federal, state, and local regulations and consistent with all labeling requirements.

#### 17.13.1 Notification to Property Owners

Before chemical use on a property, Tree Crew Foreman shall give notice to the property owner(s). Notice shall be provided at least five days before work but no more than six weeks in advance, whenever chemicals are to be used on their property.

#### 17.13.2 Licensed Applicators

Crew members in Brigham City service territory shall hold a valid Commercial pesticide applicator License. The Tree Crew

Foreman performing work is always responsible to ensure that any application of chemicals is performed by an applicator with a valid applicator's license, as required by state law where the property is located.

17.13.3 Closed Chain of Custody

The Tree Crew Foreman making the application is responsible for chemical purchase, storage, and container disposal. Closed chain of custody is required, including the use of returnable, reusable supply containers.

17.13.4 Chemical Reporting

All chemical applications shall be documented as required by law for a licensed applicator. In addition, chemical applications shall be documented as instructed by BCPP. The Tree Crew Foreman making the application shall be responsible for maintaining reports and shall produce reports for review by the state departments of agriculture upon request.

17.13.5 Herbicide Application Efficiency

Ninety-five percent control shall be assumed on all herbicide applications to be considered effective.

17.13.6 Wetland and Waterbodies

Product label shall be followed and approved for use near wetlands and waterbodies.

17.13.7 Spills

Applicator is responsible for preventing any chemical spills from occurring. Special attention should be made while mixing, loading, and cleaning equipment, which are activities that carry more risk for accidents or spills. Spills can be avoided by using closed chain of custody best management practices. Spill kits are required on every truck when any herbicide is used or being transported.

In the event of a spill:

1. Stop, contain and isolate the spill
2. Report the spill to the BCPP Director, who will notify the environmental services; the following information must be provided to the TREE CREW FOREMAN:
  - a. Caller and manager
  - b. Name
  - c. Date and time of spill

- d. Location (address or longitude and latitude)
  - e. EPA number (product spilled)
  - f. Cause of spill
  - g. Amount of spill
  - h. Types of surfaces contaminated
  - i. Containment and/or clean-up activities performed so far
3. Remediate the spill
  4. Cleanup at or near BCPP generating sites or substations must comply with site-specific spill prevention and remediation plans.

17.14 Approved Herbicides

In all circumstances, the licensed applicator is responsible for following label requirements. In addition, specific chemical products must be approved by the BCPP Director, based on pre-approved chemical products. Any approved chemical products must be based on one or a combination of the following active ingredients:

Stump Application

- 2, 4-D
- Glyphosate
- Picloram
- Triclopyr

Low Volume Basal Application

- Imazapyr
- Triclopyr

Foliar Application

- 2, 4-D
- Aminopyralid
- Fosamine ammonium
- Glyphosate
- Imazapyr
- Metasulfuron methyl
- Picloram
- Sulfometuron methyl
- Triclopyr

Soil Application

- Diuron
- Indaziflam
- Imazapyr
- Picloram
- Sulfentrazone
- Tebuthiuron

Tree Growth Regulators (TGR)

- Fluprimidol
- Paclobutrazol

17.14.1 Substations Herbicide Treatment

Substations will be sprayed and treated multiple times throughout the year.

# BRIGHAM CITY PUBLIC POWER DEPARTMENT ELECTRICAL CONSTRUCTION STANDARD DRAWINGS

*Index of Drawings (32 Sheets)*

**SUBMITTED & RECOMMENDED**

ENGINEER

**APPROVAL**

TOM COOPER  
PUBLIC POWER DIRECTOR

DATE

TROY DAHLGREN  
PUBLIC POWER SUPERINTENDENT

DATE

CASEY SMITH  
PUBLIC POWER SUPERINTENDENT

DATE

KRISTINA RASMUSSEN  
ATTIST, CITY RECORDER

DATE

**ELECTRICAL CONSTRUCTION STANDARDS**

- E1.....ELECTRIC FRONT PAGE-INFORMATION
- E2.....RESIDENTIAL UNDERGROUND SERVICE 200 AMPS OR LESS
- E3.....RESIDENTIAL OVERHEAD SERVICE 200 AMPS OR LESS
- E4.....ELECTRIC CONDUIT TRENCH DETAIL
- E5.....SECONDARY JUNCTION PEDESTAL
- E6.....SINGLE PHASE PAD MOUNT TRANSFORMER
- E7.....200-AMP 1-PHASE SECTIONALIZER
- E8.....200-AMP 1 AND 3-PHASE FIBERGLASS SECTIONALIZER
- E9.....600-AMP 3-PHASE FIBERGLASS SECTIONALIZER
- E10.....ELECTRICAL BOX BACKFILL & COMPACTION
- E11.....CONDUIT ROUTING
- E12.....5-PHASE TRANSFORMER & CONCRETE PAD
- E13.....600 AMP PSE 9/11 SWITCHGEAR
- E14.....600 AMP PSE 3/5 SWITCHGEAR
- E15.....SECONDARY PEDESTAL, WIRE & CONNECTIONS
- E16.....DECORATIVE STREET LIGHT POLE FOOTING DETAIL
- E17.....STREET LIGHT POLES AND FIXTURES
- E18.....TEMPORARY SERVICE FOR OVERHEAD & UNDERGROUND LINES
- E19.....3-PHASE UNDERGROUND SERVICE 201-800 AMPS
- E20.....TYPICAL RISER POLE
- E21.....OVERHEAD POWER LINE CLEARANCES OVER 600 VOLTS TO 22,000 VOLTS
- E22.....1-PHASE FREE STANDING METER BASE & 3-PHASE FREE STANDING METER BASE
- E23.....PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM CENTRAL INVERTER (RESIDENTIAL)
- E24.....PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM MICRO INVERTER (RESIDENTIAL)
- E25.....PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM ENERGY STORAGE - CENTRAL INVERTER (RESIDENTIAL)
- E26.....PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM ENERGY STORAGE - MICRO INVERTER (RESIDENTIAL)
- E27.....PHOTOVOLTAIC THREE-PHASE SYSTEM DIAGRAM USING MULTIPLE TWO-LINE SINGLE-PHASE INVERTERS WITH NEUTRAL CONNECTION
- E28.....PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM USING A SINGLE THREE-PHASE INVERTER
- E29.....PV DISCONNECT LABELS & PV SERVICE PANEL WARNING LABELS
- E30.....EUSERC DNG NO. 501 - AC DISCONNECT GUIDELINES

**ELECTRICAL - VEGETATION MANAGEMENT STANDARDS**

- V1.....TREE AND VEGETATION TRIMMING AND CLEARANCE DETAILS
- V2.....TREE PLANTING AND ELECTRICAL BOX CLEARANCE DETAILS




**SPECIAL STANDARD NOTES:**

- A. AT THE BRIGHAM CITY PUBLIC POWER'S SOLE DISCRETION, ALTERNATE METHODS OF CONSTRUCTION OR DEVIATIONS FROM THESE STANDARDS MAY BE REQUIRED OR APPROVED BY THE CITY PUBLIC POWER DIRECTOR AND PUBLIC POWER SUPERINTENDENT (OR THEIR DESIGNEE), WHEN SUCH ARE NECESSARY TO MEET THE BEST INTERESTS OF THE CITY.
- B. WHEN BRIGHAM CITY PUBLIC POWER APPROVAL IS REQUIRED, IT SHALL MEAN APPROVAL FROM THE CITY PUBLIC POWER DIRECTOR, PUBLIC POWER SUPERINTENDENT, CITY ENGINEER, OR THEIR DESIGNEE.
- C. ANY VARIANCE, DEVIATION, OR WAIVER TO THE CITY ELECTRICAL STANDARDS SHALL BE AS APPROVED BY THE PUBLIC POWER DIRECTOR OR SUPERINTENDENT.

**FEBRUARY 2026**






NOTES:

1. ALL MATERIALS TO BE SUPPLIED BY CUSTOMER EXCEPT METER.
2. ALL TEMPORARY/PERMANENT EQUIPMENT SHALL COMPLY WITH CURRENT N.E.C., N.E.S.C. AND CITY PUBLIC POWER STANDARDS.
3. BRIGHAM CITY PUBLIC POWER WILL FURNISH AND INSTALL METER AND CONNECT SERVICE IN TRANSFORMER OR JUNCTION BOX.
4. SERVICE CONDUCTORS SHALL MEET CURRENT NATIONAL ELECTRIC CODE AND BRIGHAM CITY PUBLIC POWER REQUIREMENTS.
5. CORROSION INHIBITING COMPOUND SHALL BE USED ON ALL ELECTRICAL WIRE CONNECTIONS INSIDE METER BASE.
6. GROUND ROD TO BE DRIVEN A MINIMUM OF 6'-0" IN UNDISTURBED SOIL. GROUNDING CONDUCTOR CONNECTED TO GROUND ROD SHALL BE MINIMUM OF #6 COPPER, IF UPDATED SERVICE (2) GROUND RODS SHALL BE INSTALLED AT LEAST 10' APART.
7. UNSTRUT TO BE OF ONE PIECE AND OF 2'-0" IN LENGTH.
8. ENOUGH WIRE SHALL BE PROVIDED TO EXTEND A MINIMUM OF 4' PAST THE TRANSFORMER OR SECONDARY PEDESTAL GROUND SLEEVE.
9. ALL RIGID METAL CONDUIT INSTALLED BELOW GRADE SHALL BE WRAPPED WITH 10-MIL COMPOSION-RESISTANT TAPE. TAPE SHALL EXTEND 8" MIN. ABOVE FINISH GRADE.
10. ALL POWER SERVICE LATERAL CONDUITS SHALL BE 3".
11. METER BASE SHALL BE LOCATED WITHIN THE FRONT 10'-0" OF THE SIDE OF THE HOUSE. OTHER LOCATIONS SHALL BE AS APPROVED BY BRIGHAM CITY PUBLIC POWER.
12. METER SOCKET SHALL BE PLACED A MINIMUM OF 5'-0" AND A MAXIMUM OF 6'-0" TO CENTER OF SOCKET FROM FINISHED GRADE.
13. CONTACT BRIGHAM CITY PUBLIC POWER TO SCHEDULE APPOINTMENT FOR ASSISTANCE IN PULLING IN WIRE INTO ENERGIZED TRANSFORMERS.
14. MAIN DISCONNECT BREAKER TO BE INSTALLED AT TIME OF INSPECTION.
15. IN GENERAL ONLY CONTINUOUS LENGTHS OF CONDUIT SHALL BE USED. NO JOINTS OR COUPLERS ARE PERMITTED IN SERVICE CONDUITS UNLESS OTHERWISE APPROVED.
16. ALL TRENCHES SHALL BE BACKFILLED AND COMPACTED PRIOR TO FINAL POWER INSPECTION.
17. FIBERGLASS OR GALVANIZED RIGID STEEL CONDUIT (RSC) SHALL BE USED FOR BONDS 45 DEGREES AND GREATER ON ALL CONDUITS EXTENDING OUT OF THE GROUND OUTSIDE OF AN ENCLOSURE.

**SURFACE MOUNT FRONT VIEW**

DATE	01/09/2026	SCALE	N.T.S.	DESIGNED BY	BEJ	CHECKED BY	TD & CS
DRAWN BY		PROJECT NO.		DATE		BY	TC
REV.		BRIGHAM CITY PUBLIC POWER 1650 DOWNEY AVENUE BRIGHAM CITY, UT 84302 TEL: (435) 734-4000 WWW.BRIGHAMCITY.PU BRIGHAM CITY PUBLIC POWER STANDARDS ELECTRICAL CONSTRUCTION STANDARDS RESIDENTIAL UNDERGROUND SERVICE 200 AMPS OR LESS					
SHEETS <b>E2</b> OF 5 SHEETS							




SERVICE OR FEEDER RATING (AMPERES)	NEC WIRE SIZE		CONDUIT SIZE
	COPPER	ALUMINUM OR COPPER-CLAD ALUMINUM	
100 AMP	4	2	2"
110 AMP	3	1	2"
125 AMP	2	1/0	2"
150 AMP	1	2/0	2"
175 AMP	1/0	3/0	2"
200 AMP	2/0	4/0	2"
201 AMPS-400 AMPS	SEE PUBLIC POWER DIVISION		--

- NOTES:
1. ALL METER BASE SERVICE LOCATIONS MUST FIRST BE APPROVED BY THE PUBLIC POWER DEPARTMENT.
  2. IN GENERAL, ALL METER BASES SHALL BE LOCATED ON THE FRONT 10'-0" OF THE SIDE OF THE HOUSE.
  3. METER HEIGHT SHALL BE A MINIMUM OF 5'-0" AND A MAXIMUM OF 6'-0" TO CENTER OF METER SOCKET.
  4. METER BASE SHALL BE KEPT A MINIMUM OF 3'-0" FROM DOORS, WINDOWS, STAIRS, GAS METERS, ETC.
  5. ALL BONDING AND GROUNDING SHALL MEET CURRENT NEC AND BRIGHAM CITY PUBLIC POWER REQUIREMENTS. FOR EXISTING HOMES (2) GROUND RODS SHALL BE REQUIRED IN ADDITION TO ANY OTHER NEC GROUNDING REQUIREMENTS.
  6. ALL SERVICE CONDUCTOR SIZES AND TYPES SHALL MEET CURRENT NEC.
  7. IN GENERAL, ONLY CONTINUOUS LENGTHS OF CONDUIT SHALL BE USED. NO JOINTS OR COUPLERS ARE PERMITTED IN SERVICE CONDUITS UNLESS OTHERWISE APPROVED. ALL COUPLERS MUST BE BELOW ROOF LINE.

RESIDENTIAL OVERHEAD SERVICE  
200 AMPS OR LESS

DATE: 01/09/2023	SCALE: N.T.S.	DESIGNER: TP & CS	REVISION: R03	PROJECT: BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS	SHEET: E3
<p>BRIGHAM CITY PUBLIC POWER 140 East Center Street Provo, UT 84601 www.bpp.com</p>				<p>BRIGHAM CITY 100 East Center Street Provo, UT 84601 www.bpp.com</p>	



TYPE OF CONDUIT	CONDUIT SIZE	MIN. DEPTH TO TOP OF CONDUIT
STREET LIGHT	2" SECONDARY	2'-0"
ELECTRICAL SERVICE	3" SECONDARY	4'-0"
SECONDARY	4"	4'-0"
	6"	4'-0"
	8"	4'-0"
PRIMARY	8"	4'-0"

ALL POWER CONDUIT SHALL BE BURED A MINIMUM OF 4" IN DEPTH TO TOP OF CONDUIT. IF HIGH VOLTAGE (12KV) CONDUITS & LOW VOLTAGE (600 VOLT) POWER CONDUITS ARE INSTALLED IN THE SAME TRENCH, THE HIGH VOLTAGE POWER SHALL ALWAYS BE INSTALLED IN THE DEEPER END. LOW VOLTAGE CONDUITS THERE ARE MULTIPLE HIGH VOLTAGE CONDUITS SHALL BE INSTALLED AT THE DEEPER END. ALL HIGH VOLTAGE CONDUITS MAY BE INSTALLED AT THE DEPTH OF THE LARGEST CONDUIT (6")

- NOTES
1. HIGH VOLTAGE PRIMARY CONDUITS SHALL ALWAYS BE BELOW SECONDARY CONDUITS.
  2. REBAR SHALL BE CAPPED UNTIL BACKFILLED.
  3. BACKFILL SHALL MEET THE REQUIREMENTS OF ENTIREWORK AND TRENCHES AND OTHER STANDARDS IN THE CONSTRUCTION AND DEVELOPMENT STANDARDS.
  4. ALL CONDUITS SHALL BE INSPECTED AT EACH "LIFT" AT THE COMPACTION LEVEL AND FOR A FINAL INSPECTION.
  5. A CAUTION TAPE SHALL BE PLACED DIRECTLY ON CONDUIT, AND A CAUTION TAPE SHALL BE PLACED 1' BELOW GRADE FOR CITY POWER.
  6. ONLY CONTINUOUS CONDUIT RUNS ARE PERMITTED. FACTORY JOINTS SHALL BE USED FOR ATTACHING FULL LENGTH CONDUITS TOGETHER UNLESS OTHERWISE APPROVED.

**TYPICAL JOINT TRENCH OF HIGH VOLTAGE, LOW VOLTAGE, & COMMUNICATIONS CONDUITS**

NO.	DATE	BY	CHKD.	REV.
1	01/09/2026	N.T.S.		
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				

BRIGHAM CITY PUBLIC POWER  
ELECTRICAL CONSTRUCTION STANDARDS  
E4  
9 x 11 SHEETS

BRIGHAM CITY CORPORATION  
100 SOUTH 200 WEST  
SALT LAKE CITY, UT 84103  
TEL: (801) 734-6600  
WWW.BCPL.COM

BRIGHAM CITY  
100 SOUTH 200 WEST  
SALT LAKE CITY, UT 84103  
TEL: (801) 734-6600  
WWW.BCPL.COM


BRIGHAM CITY CORPORATION  
100 SOUTH 200 WEST  
SALT LAKE CITY, UT 84103  
TEL: (801) 734-6600  
WWW.BCPL.COM

BRIGHAM CITY CORPORATION  
100 SOUTH 200 WEST  
SALT LAKE CITY, UT 84103  
TEL: (801) 734-6600  
WWW.BCPL.COM









DATE	01/09/2026	BY	TD & CS
REVISION		DESCRIPTION	
1	N.T.S.	BEED	
2		TD & CS	
3		CS	
4		TD & CS	
5		CS	


BRIGHAM CITY PUBLIC POWER	BRIGHAM CITY PUBLIC POWER
140 SOUTH OGDEN STREET	140 SOUTH OGDEN STREET
PROVO, UT 84601	PROVO, UT 84601
TEL: 801.734.8281	TEL: 801.734.8281
FAX: 801.734.8282	FAX: 801.734.8282
WWW.BPP.CO.UT	WWW.BPP.CO.UT

BRIGHAM CITY PUBLIC POWER	BRIGHAM CITY PUBLIC POWER
140 SOUTH OGDEN STREET	140 SOUTH OGDEN STREET
PROVO, UT 84601	PROVO, UT 84601
TEL: 801.734.8281	TEL: 801.734.8281
FAX: 801.734.8282	FAX: 801.734.8282
WWW.BPP.CO.UT	WWW.BPP.CO.UT


  

BRIGHAM CITY PUBLIC POWER	BRIGHAM CITY PUBLIC POWER
140 SOUTH OGDEN STREET	140 SOUTH OGDEN STREET
PROVO, UT 84601	PROVO, UT 84601
TEL: 801.734.8281	TEL: 801.734.8281
FAX: 801.734.8282	FAX: 801.734.8282
WWW.BPP.CO.UT	WWW.BPP.CO.UT



- NOTES:
1. SECTIONALIZER CABINET UNITS FOR 600 AMP 3-PHASE ARE TO BE FABRICATED FROM FIBERGLASS COMPOSITE & MEET BRIGHAM CITY PUBLIC POWER SPECIFICATIONS. CONDUIT OPENINGS MUST BE WITHIN THE GROUND SLEEVE WINDOW OF THE SECTIONALIZER.
  2. BLOW IN 2500 LB MULE TAPE AND TIE SECURELY TO 4 POINT MOUNTING PLATE.
  3. CUSHNET TO BE MDRPC MDR305MIG-PA171-X-Y AND 18" GROUND SLEEVE MDR305MIG-IBEXT.
  4. CONTRACTOR TO FURNISH & INSTALL 600-AMP 4-POINT MOUNTING JUNCTION AND PLATES & 4-POINT JUNCTION P/N: GR4P-0946220150.

REV	DATE	BY	CHKD	DESCRIPTION
E9	01/09/2026	DES	TD	
<p>BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS</p> <p>BRIGHAM CITY CORPORATION 100 East Center Street Provo, UT 84601 www.bcp.com</p>				
<p>600-AMP 3-PHASE FIBERGLASS SECTIONALIZER</p>				



- NOTES:**
1. ALL ELECTRICAL BOXES INCLUDING, BUT NOT LIMITED TO, SECTIONALIZERS, SECONDARY JUNCTION BOXES, TRANSFORMERS AND TRANSFORMER CONCRETE PADS SHALL HAVE UNTREATED BASE COURSE COMPACTED TO A MINIMUM OF 65% UNDER ALL BOXES. FILL SHALL BE A MINIMUM OF 1" IN DEPTH AND SHALL BE SET TO A MINIMUM OF 1" PAST ALL SIDES AND BACK AND 1" IN FRONT (6" IF A SIDEWALK IS PRESENT) OF ALL BOXES OR PADS.
  2. ALL COMPACTION TESTS SHALL BE TAKEN BEFORE ELECTRICAL BOXES ARE SET INTO PLACE.
  3. ALL SAND, ROADBASE AND ENGINEERED FILL SHALL MEET BIRGHAM CITY PUBLIC POWER STANDARDS.
  4. REFER TO "EXPOSURE AND PREVIOUS" SECTION IN THE CONSTRUCTION STANDARDS FOR ADDITIONAL REQUIREMENTS FOR BACKFILL, FINISHING AND COMPACTION.
  5. AREA AROUND ELECTRICAL BOXES SHALL BE BACKFILLED & LEVELED A MINIMUM OF 12" IN ALL DIRECTIONS TO PROVIDE A SAFE WORKING AREA FOR THE ELECTRIC DEPARTMENT.

NO.	DATE	BY	CHKD.	DESCRIPTION
1	01/09/2026	TD	TC	
2				
3				
4				
5				


  

BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS BRIGHAM CITY PUBLIC POWER 400 East 200 North BRIGHAM CITY, UT 84302 TEL: 435-224-6600 WWW.BRIGHAMCITY.UT.GOV	BRIGHAM CITY CITY ENGINEER (435) 773-8888
--	--

BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS BRIGHAM CITY PUBLIC POWER 400 East 200 North BRIGHAM CITY, UT 84302 TEL: 435-224-6600 WWW.BRIGHAMCITY.UT.GOV	BRIGHAM CITY CITY ENGINEER (435) 773-8888
--	--

E11 Conduit Routing



NO.	DATE	BY	CHKD.	SCALE	PROJECT
01					
02					
03					
04					
05					
06					
07					
08					
09					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					

BRIGHAM CITY PUBLIC POWER  
ELECTRICAL CONSTRUCTION STANDARDS  
CONDUIT ROUTING

BRIGHAM CITY PUBLIC POWER  
1000 WEST 1000 SOUTH  
SALT LAKE CITY, UT 84119  
PHONE: 801.468.3333  
WWW.BPP.CO.UT.GOV

BRIGHAM CITY ENGINEER  
1000 WEST 1000 SOUTH  
SALT LAKE CITY, UT 84119  
PHONE: 801.468.3333  
WWW.BPP.CO.UT.GOV

BRIGHAM CITY ENGINEER  
1000 WEST 1000 SOUTH  
SALT LAKE CITY, UT 84119  
PHONE: 801.468.3333  
WWW.BPP.CO.UT.GOV



BRIGHAM CITY ENGINEER  
1000 WEST 1000 SOUTH  
SALT LAKE CITY, UT 84119  
PHONE: 801.468.3333  
WWW.BPP.CO.UT.GOV

BRIGHAM CITY ENGINEER  
1000 WEST 1000 SOUTH  
SALT LAKE CITY, UT 84119  
PHONE: 801.468.3333  
WWW.BPP.CO.UT.GOV

BRIGHAM CITY ENGINEER  
1000 WEST 1000 SOUTH  
SALT LAKE CITY, UT 84119  
PHONE: 801.468.3333  
WWW.BPP.CO.UT.GOV


BRIGHAM CITY ENGINEER  
1000 WEST 1000 SOUTH  
SALT LAKE CITY, UT 84119  
PHONE: 801.468.3333  
WWW.BPP.CO.UT.GOV

BRIGHAM CITY ENGINEER  
1000 WEST 1000 SOUTH  
SALT LAKE CITY, UT 84119  
PHONE: 801.468.3333  
WWW.BPP.CO.UT.GOV



TRANSFORMER KVA RATING	DIMENSIONS					
	A	B	C	D	E	F
75-500 KVA	114"	78"	36"	15"	18"	9"
750-1500 KVA	118"	105"	52"	18"	20"	11"
2000 KVA						


CONTACT POWER DEPT.



- NOTES:**
- 1. SITE PREPARATION & INSPECTIONS:** AFTER EXCAVATION, ALL EXCAVATED AREA 1" PAST PAD SHALL BE LEVEL. THE PAD SHALL BE CONSTRUCTED WITH CONCRETE. THE CONCRETE SHALL BE PLACED AND FINISHED TO A LEVEL AN ADDITIONAL 12" PAST THE EDGE OF THE PAD ON ALL SIDES AND THEN WATER OF ALL PADS SHALL BE INSPECTED PRIOR TO POURING CONCRETE, AND THE GROUND SHALL HAVE A COMPACTION TEST DONE PRIOR TO THE FORM BEING CONSTRUCTED.
  - 2. CONCRETE:** CONCRETE SHALL BE IN ACCORDANCE WITH BRIGHAM CITY PUBLIC POWER STANDARD 4.38.65.040. STEEL REINFORCEMENT SHALL BE #4 BARS PLACED AT 12" CENTERS THROUGHOUT THE PAD AND MUST BE POURED AT LEAST SEVEN DAYS PRIOR TO SETTING THE TRANSFORMER. THE FINISH SURFACE SHALL BE TO THE CITY'S ENGINEERING FIRM PRIOR TO POURING CONCRETE. CONCRETE SHALL CONFORM TO CITY STANDARDS.
  - 3. SUBGRADE:** THE PAD SHALL BE CONSTRUCTED ON THE SITE ACCORDING TO THE SPECIFICATIONS.
  - 4. CONDUIT WINDOW/LANDSCAPE:** LOW VOLTAGE CONDUITS SHALL BE FORMED AS TIGHTLY AS POSSIBLE TO THE CONDUIT WINDOW. THE CONDUIT WINDOW ON THE SMALL PAD SHALL BE 12" FROM THE RIGHT SIDE OF THE CONDUIT WINDOW ON THE SMALL PAD AND 18" FROM THE RIGHT SIDE OF THE CONDUIT WINDOW ON THE LARGE PAD. NO MORE THAN EIGHT CONDUITS WILL BE USED ON THE LOW VOLTAGE SIDE ON 2000 KVA PADS. NO MORE THAN 12 CONDUITS WILL BE USED, DO NOT PUT ANY CONCRETE IN OR OVER THE CONDUITS. ALL CONDUITS ENTERING THE PAD SHALL BE SCHEDULE 40 PVC WITH PVC OR FIBERGLASS (RTRC) ELBOWS.
  - 5. GROUNDING:** A 5/8" X 8' GROUND ROD SHALL BE USED ON THE SMALL PAD AND A 3/4" X 10' GROUND ROD SHALL BE USED ON THE LARGE PAD. THE GROUND ROD SHALL BE INSTALLED ON THE PRIMARY SIDE OF THE TRANSFORMER.
  - 6. CLEARANCES:** THE FRONT OF THE PAD SHOULD ALWAYS FACE AWAY FROM ADJACENT STRUCTURES AND BE FREE OF OBSTRUCTIONS. IF EXISTING STRUCTURES ARE ADJACENT TO THE PAD FROM ANY ADJACENT STRUCTURE, THE EDGE OF THE PAD MUST BE AT LEAST TEN FEET FROM ANY ADJACENT STRUCTURE. IF AN ADJACENT STRUCTURE HAS ANY OVERHANG OR EAVE WITHIN TEN FEET OF THE PAD, THE PAD SHALL BE PLACED IN AN AREA TEN FEET IN LINE WITH OR THREE FEET TO EITHER SIDE OF ANY WINDOW IN AN ADJACENT STRUCTURE.
  - 7. CLEARANCE FOR ALLOWS:** MUST BE TWENTY FEET IN LINE WITH IT AND TEN FEET ON EITHER SIDE. PADS MUST NOT BE PLACED WITHIN FIFTEEN FEET OF ANY VALVE OR WITHIN TWENTY FEET OF ANY PUMPING OR STORAGE FACILITY CONTAINING FLAMMABLE MATERIAL, NO WALLS, FENCES, OR ANY OTHER OBSTRUCTION. THE PAD SHALL BE PLACED WITHIN TEN FEET OF THE SIDE OF THE ROAD OR WITHIN TWELVE FEET OF THE FRONT OF THE PAD. THE AREA SURROUNDING THE PAD MUST HAVE TWELVE FEET OF CLEAR LEVEL, IMPROVING AREA FOR MAINTENANCE OF THE TRANSFORMER. THE PAD SHALL BE PLACED WITHIN TEN FEET OF THE SIDE OF THE ROAD OR WITHIN TWELVE FEET OF THE SURFACE OF THE PAD. ALSO, IT MUST NOT BE PLACED WITHIN 12 FEET VERTICALLY OF A DOOR OR WINDOW.
  - 8. BARRIERS:** IF THE TRANSFORMER PAD IS TO BE LOCATED IN AREAS SUBJECT TO VEHICULAR TRAFFIC, (PARKING LOTS, DRIVEWAYS, ETC.), CONTACT BRIGHAM CITY PUBLIC POWER FOR PROTECTIVE BARRIER REQUIREMENTS.
  - 9. METERING:** IN GENERAL, THE METERING SHALL BE PLACED ON BUILDINGS OR STRUCTURES.
  - 10. CONNECTIONS:** ALL SECONDARY (LOW VOLTAGE) CABLES & SECONDARY CONNECTIONS ARE THE CONTRACTOR'S RESPONSIBILITY. BRIGHAM CITY PUBLIC POWER WILL INSTALL & TERMINATE PRIMARY CABLES & CONNECTIONS ONLY.
  - 11. ANCHORING:** CONTRACTOR TO ANCHOR TRANSFORMER TO PAD WITH MINIMUM OF TWO ANCHOR POINTS.
  - 12. PRECAST TRANSFORMER PADS MUST BE APPROVED BY THE PUBLIC POWER DEPARTMENT.**

**GENERAL TRANSFORMER CLEARANCES**

DATE	E12
PROJECT	BRIGHAM CITY PUBLIC POWER
DESCRIPTION	ELECTRICAL CONSTRUCTION STANDARDS
SCALE	AS SHOWN
DATE	01/09/2026
DESIGNED BY	TD & CS
CHECKED BY	TC
PROJECT NO.	2025000000
PROJECT NAME	3-PHASE TRANSFORMER & CONCRETE PAD
PROJECT LOCATION	BRIGHAM CITY PUBLIC POWER
PROJECT CONTACT	1400 East Power Plant Road Brigham City, UT 84302 Tel: (435) 733-2500 Fax: (435) 733-2509
PROJECT MANAGER	BRIGHAM CITY
PROJECT ENGINEER	BRIGHAM CITY
PROJECT ARCHITECT	BRIGHAM CITY
PROJECT CONSULTANT	BRIGHAM CITY
PROJECT CONTRACTOR	BRIGHAM CITY
PROJECT APPROVED BY	BRIGHAM CITY
PROJECT REVIEWED BY	BRIGHAM CITY
PROJECT CHECKED BY	BRIGHAM CITY
PROJECT DATE	01/09/2026
PROJECT SCALE	N.T.S.
PROJECT DRAWN BY	TD & CS
PROJECT CHECKED BY	TC



NOTES:

1. SWITCH GEAR GROUND SLEEVES SHALL BE PROVIDED BY BRIGHAM CITY PUBLIC POWER AND INSTALLED BY ELECTRICAL CONTRACTOR AS PER CITY SUPPLIED LAYOUT
2. 2500 LB MULE TAP SHALL BE BLOWN INTO CONDUIT AND TIED SECURELY TO EACH (2) GROUND ROD
3. CONDUIT LAYOUT DETAIL SHALL BE GIVEN BY BRIGHAM CITY PUBLIC POWER DURING PRE CONSTRUCTION MEETING
4. TYPICAL FOR SITE DEVELOPMENTS



NO.	DATE	BY	CHKD.	APP'D.	SCALE	REVISIONS
01	01/09/2026	N.T.S.				
02						
03						
04						
05						
06						
07						
08						
09						
10						
11						
12						
13						
14						
15						
16						
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						
28						
29						
30						
31						
32						
33						
34						
35						
36						
37						
38						
39						
40						
41						
42						
43						
44						
45						
46						
47						
48						
49						
50						
51						
52						
53						
54						
55						
56						
57						
58						
59						
60						
61						
62						
63						
64						
65						
66						
67						
68						
69						
70						
71						
72						
73						
74						
75						
76						
77						
78						
79						
80						
81						
82						
83						
84						
85						
86						
87						
88						
89						
90						
91						
92						
93						
94						
95						
96						
97						
98						
99						
100						

BRIGHAM CITY PUBLIC POWER  
ELECTRICAL CONSTRUCTION STANDARDS  
600 AMP PSE 9/11 SWITCHGEAR

BRIGHAM CITY  
100 North Main Street  
Provo, UT 84601  
(801) 734-2000  
www.bcpw.com

BRIGHAM CITY PUBLIC POWER  
20 North Main Street  
Provo, UT 84601  
(801) 734-2000  
www.bcpw.com

BRIGHAM CITY PUBLIC POWER  
ELECTRICAL CONSTRUCTION STANDARDS  
600 AMP PSE 9/11 SWITCHGEAR



- NOTES:
1. SWITCH GEAR GROUND SLEEVE SHALL BE PROVIDED BY BRIGHAM CITY PUBLIC POWER AND INSTALLED BY ELECTRICAL CONTRACTOR AS PER CITY SUPPLIED LAYOUT
  2. 2500 LB JULE PAPE SHALL BE BLOWN INTO CONDUIT AND TIED SECURELY TO CONDUIT LAYOUT DETAIL SHALL BE GIVEN BY BRIGHAM CITY PUBLIC POWER DURING PRE CONSTRUCTION MEETING.
  3. CONDUIT LAYOUT DETAIL SHALL BE GIVEN BY BRIGHAM CITY PUBLIC POWER DURING PRE CONSTRUCTION MEETING.
  4. TYPICAL FOR COMMERCIAL TRANSFORMER PROTECTION FOR 250KVA AND LARGER

NO.	REVISION	DATE	BY	CHKD.	APP'D.
01					
02					
03					
04					
05					
06					
07					
08					
09					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					

BRIGHAM CITY PUBLIC POWER  
ELECTRICAL CONSTRUCTION STANDARDS  
600 AMP PSE 3/5 SWITCHGEAR

BRIGHAM CITY PUBLIC POWER ASSOCIATE ENGINEER  
1400 South State Street  
Brigham City, UT 84302  
PHONE: (435) 733-5600  
FAX: (435) 733-5609  
WWW.BPP.CO.UT


BRIGHAM CITY CORPORATION  
375 North Main Street  
Brigham City, UT 84302  
WWW.BCC.CO.UT

DESIGNED BY: BPP  
CHECKED BY: TD & CS  
DATE: 01/09/2008

SCALE: N.T.S.







**DECORATIVE STREET LIGHT POLE & FIXTURE**

NO.	DATE	BY	CHKD.	SCALE	REVISIONS
1	01/09/2026	TD & CS	TC		
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					


**COBRA HEAD LIGHT POLE & FIXTURE**  
 TO BE DETERMINED - CONTACT BRIGHAM CITY PUBLIC POWER

NO.	DATE	BY	CHKD.	SCALE	REVISIONS
1	01/09/2026	TD & CS	TC		
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					

NO.	DATE	BY	CHKD.	SCALE	REVISIONS
1	01/09/2026	TD & CS	TC		
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					




- NOTES:
1. ALL SERVICE LOCATIONS, MATERIALS, EQUIPMENT SHALL BE APPROVED BY BRIGHAM CITY PUBLIC POWER.
  2. 36" MINIMUM CLEARANCES (SIDES AND ABOVE) FROM DOORS, WINDOWS, STAIRS, GAS METERS SHALL BE OBSERVED. ADDITIONAL CLEARANCES MAY BE REQUIRED.
  3. 8" MINIMUM CLEARANCE SHALL BE REQUIRED IN FRONT OF SERVICES, METERS. ADDITIONAL CLEARANCES MAY BE REQUIRED.
  4. BRIGHAM CITY PUBLIC POWER WILL FURNISH METER BASE & TEST SWITCH FOR CONTRACTOR TO INSTALL. (SEE ELECTRIC DEPT.)
  5. GROUNDING & BONDING OF CABINETS, CONDUITS, & OTHER EQUIPMENT SHALL MEET NEC.
  6. SERVICES 200 AMPS OR LESS SHALL USE A LINK BYPASS METER BASE.
  7. SERVICES SIZED 800 AMPS OR LESS MAY USE STAND ALONE TYPE CT CABINETS. FOR SERVICES LARGER THAN 800 AMPS CONTACT THE ELECTRIC DEPARTMENT.
  8. SERVICES 800 AMPS OR LESS USE CT CABINET MILBANK P/N: CT164811-HC & MOUNTING RACK P/N: K4798 OR AN APPROVED EQUIVALENT.
  9. SERVICE CONDUITS SHALL BE BURIED A MINIMUM OF 4' IN DEPTH, AND MEET BRIGHAM CITY PUBLIC POWER STANDARDS.
  10. ELECTRICAL CONTRACTOR SHALL PROVIDE & INSTALL SERVICE CONDUCTORS, & SHALL MAKE CONNECTIONS IN THE SECONDARY SIDE OF THE TRANSFORMER.
  11. CUSTOMER SHALL OWN & MAINTAIN SERVICE CONDUCTORS FROM TRANSFORMER TO THE CUSTOMER SERVICE DISCONNECT.
  12. ALL RIGID METAL CONDUIT INSTALLED BELOW GRADE SHALL BE WRAPPED WITH 10-MIL CORROSION-RESISTANT TAPE. TAPE SHALL EXTEND 6" MIN. ABOVE FINISH GRADE.
  13. FIBERGLASS OR GALVANIZED RIGID STEEL CONDUIT (RSD) SHALL BE USED FOR RINGS AS DEVICES AND GREATER ON ALL CONDUITS EXTENDING OUT OF THE GROUND OUTSIDE OF AN ENCLOSURE.



NO.	DATE	DESCRIPTION	BY	CHKD.	SCALE	DATE	PROJECT	SHEET
1							BRIGHAM CITY PUBLIC POWER	E19
BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS 3-PHASE UNDERGROUND SERVICE 201-800 AMPS								OF 1 SHEETS 8



E21 Overhead Power Line Clearances over 600 Volts to 22,000 Volts




- NOTES
1. NO BUILDING OR STRUCTURE SHALL BE PLACED, OR CONSTRUCTED IN THE POWER LINE CLEARANCE ZONE.
  2. CLEARANCES GIVEN ARE TYPICAL AND APPLY TO OPEN SUPPLY PRIMARY CIRCUITS OPERATING AT OVER 600 VOLTS UP TO 22,000 VOLTS, AND MAY NOT APPLY TO ALL CASES OR CIRCUMSTANCES.
  3. CLEARANCES DO NOT APPLY TO SECONDARY INSULATED SERVICE CIRCUITS OPERATING AT 600 VOLTS OR LESS.
  4. TYPICAL CLEARANCES INCLUDE THE COMPLETE VERTICAL & HORIZONTAL SPAN, INCLUDING POWER LINES FROM THE OUTSIDE CONDUCTOR TO ANY BUILDING, SIGN, OR STRUCTURE.
  5. TYPICAL CLEARANCES FOR 12KV PRIMARY OVERHEAD DISTRIBUTION CIRCUITS ARE 15' FROM THE OUTSIDE CONDUCTOR IN ANY DIRECTION FROM ANY BUILDING, SIGN, OR STRUCTURE.
  6. TYPICAL CLEARANCES FOR 48KV PRIMARY OVERHEAD TRANSMISSION CIRCUITS ARE 30' FROM THE OUTSIDE CONDUCTOR IN ANY DIRECTION FROM ANY BUILDING, SIGN, OR STRUCTURE.
  7. SPECIAL APPLICATIONS, HIGHER VOLTAGES, RAILROAD TRACKS, SWIMMING POOLS, AND OPEN WATER MAY RESULT IN ADDITIONAL CLEARANCES AND SHALL BE APPROVED BY BRIGHAM CITY PUBLIC POWER.
  8. ANY VARIANCE TO THESE STANDARDS SHALL BE AS APPROVED BY THE PUBLIC POWER DIRECTOR ON A CASE-BY-CASE BASIS.

NO.	DATE	BY	REVISION
01			
02			
03			
04			
05			

PROJECT	BRIGHAM CITY PUBLIC POWER
DATE	07/09/2026
DESIGNED BY	IC
CHECKED BY	IC
SCALE	AS SHOWN
PROJECT NO.	2025-001
PROJECT NAME	OVERHEAD POWER LINE CLEARANCES OVER 600 VOLTS TO 22,000 VOLTS
PROJECT LOCATION	BRIGHAM CITY, UT
PROJECT OWNER	BRIGHAM CITY PUBLIC POWER
PROJECT CONTACT	BRIGHAM CITY PUBLIC POWER
PROJECT PHONE	(801) 224-1234
PROJECT FAX	(801) 224-1234
PROJECT EMAIL	brighamcity@brighamcity.gov
PROJECT WEBSITE	www.brighamcity.gov
PROJECT ADDRESS	100 SOUTH MAIN STREET, BRIGHAM CITY, UT 84302
PROJECT CITY	BRIGHAM CITY, UT
PROJECT STATE	UTAH
PROJECT COUNTY	WASATCH COUNTY
PROJECT ZIP	84302




REV	DATE	BY	CHKD	APP'D	SCALE	DATE	PROJECT	SHEET
1							BRIGHAM CITY PUBLIC POWER	E22
2							ELECTRICAL CONSTRUCTION STANDARDS	OF 1 SHEETS
3							1-PHASE FREE STANDING METER BASE &	
4							3-PHASE FREE STANDING METER BASE DETAILS	

Brigham City Corporation  
 1400 CHURCH ST. 2ND FL.  
 BRIGHAM CITY, UT 84302  
 www.bcpower.com

Brigham City Public Power  
 1400 CHURCH ST. 2ND FL.  
 BRIGHAM CITY, UT 84302  
 www.bcpower.com

**THIS DETAIL SHOWS THE REQUIREMENTS FOR A PHOTOVOLTAIC SINGLE-PHASE BASIC SYSTEM WITH A CENTRAL INVERTER**



**NOTES:**


- A. MAIN SERVICE PANEL MUST COMPLY WITH CEC LATEST REVISION AND OPERATE IN A SAFE MANNER.
    1. BRIGHAM CITY PUBLIC POWER WILL NOT ALLOW INTERCONNECTIONS WITH ANY UNSAFE CONDITIONS.
  - B. PRODUCTION METER TO BE PROVIDED AND INSTALLED BY BRIGHAM CITY PUBLIC POWER AT CUSTOMER EXPENSE. METER SOCKET TO BE PROVIDED BY INSTALLER. BRIGHAM CITY PUBLIC POWER WILL ACTIVATE THE PV SYSTEM AFTER IT MEETS ALL REQUIREMENTS, AND PASSES ALL INSPECTIONS.
  - C. LOCABLE KNIFE-BLADE UTILITY A.C. DISCONNECT TO BE LOCATED WITHIN 10'-0" AND LINE OF SIGHT OF SERVICE PANEL AND MUST COMPLY WITH UL508 AND 600.47.
    1. SEPARATE D.C. DISCONNECT AT GRADE LEVEL REQUIRED ONLY IF INVERTER DOES NOT HAVE AN INTEGRATED D.C. DISCONNECT
  - D. INVERTER MUST COMPLY WITH UL1741 REQUIREMENTS. GROUNDING ELECTRODE SYSTEM MUST HAVE AN INTEGRATED D.C. DISCONNECT
    1. SEPARATE D.C. DISCONNECT AT GRADE LEVEL REQUIRED ONLY IF INVERTER DOES NOT HAVE AN INTEGRATED D.C. DISCONNECT
- NOTE: A LEASED SYSTEM MAY INCLUDE A SEPARATE METER PROVIDED AND INSTALLED BY THE LEASING COMPANY.
- LEASED METER WILL NOT BE INSTALLED BETWEEN PRODUCTION METER AND MAIN SERVICE PANEL.
  - ALL PV SYSTEMS MUST COMPLY WITH THE LATEST REVISION TO CEC ARTICLES 690 AND 726.
  - ALL NECESSARY CLEARANCES SHALL COMPLY WITH CEC ARTICLE 110.26.
  - ALL SIGNS OR IDENTIFIERS SHALL BE ATTACHED TO THE EQUIPMENT OR LOCKED ADJACENT TO THE IDENTIFIED EQUIPMENT (AS APPROVED BY THE AHJ).
  - ALL SIGNS SHALL BE PERMANENTLY ATTACHED BY MEANS OF ENGRAVED LETTERS, MACHINER PRINTED LETTERS, OR ELECTRO-PHOTO PLATING LETTERS IN RED WITH WHITE LETTERING.

SHEET	E23	OF 1 SHEETS	BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS	BRIGHAM CITY ELECTRICAL CONSTRUCTION STANDARDS	BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS
			<b>PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM CENTRAL INVERTER (RESIDENTIAL)</b>		
					
		Brigham City Corporation 200 West 100 South Provo, UT 84601 www.bcpower.com		Brigham City Public Power 200 West 100 South Provo, UT 84601 www.bcpower.com	
DATE	BY	CHECKED	DATE	BY	CHECKED
01/09/2026	N.T.S.	G.S.	01/09/2026	G.S.	G.S.
		TITLE: TD & CS DRAWN: TC			





**THIS DETAIL SHOWS THE REQUIREMENTS FOR A PHOTOVOLTAIC SINGLE-PHASE SYSTEM WITH ENERGY STORAGE (MICRO INVERTER)**



- NOTES:
- A. MAIN SERVICE PANEL MUST COMPLY WITH CEC LATEST REVISION AND OPERATE IN A SAFE MANNER.
  1. BRIGHAM CITY PUBLIC POWER WILL NOT ALLOW INTERCONNECTIONS WITH ANY UNSAFE CONDITIONS.
  - B. PRODUCTION METER TO BE PROVIDED AND INSTALLED BY BRIGHAM CITY PUBLIC POWER AT CUSTOMERS EXPENSE. METER SOCKET TO BE PROVIDED BY INSTALLER. BRIGHAM CITY PUBLIC POWER WILL INITIATE THE PV SYSTEM AFTER IT MEETS ALL REQUIREMENTS AND PASSES ALL INSPECTIONS.
  1. CENTER OF METER MUST BE INSTALLED BETWEEN 4'-0" AND 6'-3" ABOVE FINAL GRADE.
  - C. LOCKABLE KNIFE-BLADE UTILITY A.C. DISCONNECT TO BE LOCATED WITHIN 10'-0" AND LINE OF SIGHT OF SERVICE PANEL AND MUST COMPLY WITH IESRSC DMC 501. INVERTER MUST COMPLY WITH UL1741 REQUIREMENTS. GROUNDING ELECTRODE SYSTEM MUST COMPLY WITH LATEST REVISION OF CEC ARTICLE 690.47.
  - D. SEPARATE D.C. DISCONNECT AT GRADE LEVEL REQUIRED ONLY IF INVERTER DOES NOT HAVE AN INTEGRATED D.C. DISCONNECT
- NOTE: A LEASED SYSTEM MAY INCLUDE A SEPARATE METER PROVIDED AND INSTALLED BY THE LEASING COMPANY.
1. LEASED METER WILL NOT BE INSTALLED BETWEEN PRODUCTION METER AND MAIN SERVICE PANEL.
  - PV SYSTEMS MUST COMPLY WITH THE LATEST REVISION TO CEC ARTICLES 690 AND 705.
  - ALL NECESSARY CLEARANCES SHALL COMPLY WITH THE LATEST REVISION TO CEC ARTICLES 690 AND 705.
  - ALL WIRING OR DIRECTORIES SHALL BE ATTACHED TO THE ELECTRIC EQUIPMENT OR LOCATED ADJACENT TO THE IDENTIFIED EQUIPMENT (AS APPROVED BY THE AHJ).
  - ALL SIGNS SHALL BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT.
  - ALL SIGNS SHALL BE PERMANENTLY ATTACHED BY MEANS OF SCREWS OR BOLTS ARE NOT ALLOWED).
  - ALL SIGNS SHALL BE EITHER METAL OR PLASTIC WITH ENGRAVED LETTERS, MACHINE PRINTED LETTERS, OR ELECTRO-FORMED PLATING LETTERS IN RED WITH WHITE LETTERING.

NO.	DATE	BY	REVISION
01	01/09/2026	TD & CS	IC
02			
03			
04			
05			
06			
07			
08			
09			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			
46			
47			
48			
49			
50			
51			
52			
53			
54			
55			
56			
57			
58			
59			
60			
61			
62			
63			
64			
65			
66			
67			
68			
69			
70			
71			
72			
73			
74			
75			
76			
77			
78			
79			
80			
81			
82			
83			
84			
85			
86			
87			
88			
89			
90			
91			
92			
93			
94			
95			
96			
97			
98			
99			
100			

BRIGHAM CITY PUBLIC POWER  
 ELECTRICAL CONSTRUCTION STANDARDS  
 PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM  
 ENERGY STORAGE - MICRO INVERTER (RESIDENTIAL)


BRIGHAM CITY PUBLIC POWER  
 200 North 200 West  
 Provo, UT 84601  
 Tel: 801.224.1400  
 www.bcpower.com

BRIGHAM CITY  
 CITY

DATE: 01/09/2026  
 DRAWN BY: TD & CS  
 CHECKED BY: IC

PROJECT: E26  
 SHEET: 1 OF 1 SHEETS

**THIS DETAIL SHOWS THE REQUIREMENTS FOR A PHOTOVOLTAIC THREE-PHASE SYSTEM USING MULTIPLE 2-LINE 1-PHASE INVERTERS WITH A NEUTRAL CONNECTION**




**NOTES:**

- A. MAIN SERVICE PANEL MUST COMPLY WITH CEC LATEST REVISION ARTICLES 690.64 AND 705.10 (LABEL).
  - B. UTILITY LOCKABLE A.C. DISCONNECT TO BE LOCATED WITHIN 10'-0" OF SERVICE PANEL. A MINIMUM 10" CLEARANCE IS REQUIRED FROM EDGE OF ANY ENCLOSURE. MUST COMPLY WITH CEC ARTICLES 690.14 (LABEL), 690.17 (LABEL) AND 690.54 (LABEL).
  - C. P.V. GROSS METER TO BE PROVIDED AND INSTALLED BY BRIGHAM CITY PUBLIC POWER AT CUSTOMER'S EXPENSE. METER SOCKET TO BE PROVIDED BY INSTALLER. METER SOCKET SUBMITTAL MUST BE APPROVED BY BRIGHAM CITY PUBLIC POWER. METER MUST BE INSTALLED IN SYSTEM WITH NEUTRAL. SEPARATE METER BETWEEN THE AC DISCONNECT AND P.V. GROSS METER. PROVIDED, INSTALLED BY BRIGHAM CITY PUBLIC POWER. BRIGHAM CITY PUBLIC POWER WILL ACTIVATE THE PV SYSTEM AFTER IT MEETS ALL REQUIREMENTS, AND PASSES ALL INSPECTIONS.
  - D. UTILITY LOCKABLE A.C. DISCONNECT MUST BE LOCATED WITHIN 10'-0" OF B, AND WITHIN LINE OF SIGHT OF MAIN SERVICE PANEL. A MINIMUM CLEARANCE OF 10" IS REQUIRED FROM EDGE OF ANY ENCLOSURE. MUST COMPLY WITH CEC ARTICLES 690.14 (LABEL), 690.17 (LABEL), AND 690.54 (LABEL).
  - E. INVERTER MUST COMPLY WITH CEC ARTICLE 690.47(C)(1), AND UL1741. GROUNDING ELECTRODE SYSTEM MUST COMPLY WITH CEC ARTICLE 690.50. SINGLE-PHASE INVERTERS SHALL NOT BE CONNECTED TO 3-PHASE POWER SYSTEMS UNLESS THE INTERCONNECTED SYSTEM IS DESIGNED SO THAT SIGNIFICANT UNBALANCED VOLTAGES CANNOT RESULT. PER CEC ARTICLE 705.10(B)(4), INVERTER-INTEGRATED PROTECTION MUST INCLUDE THE FOLLOWING MINIMUM PROTECTIVE FUNCTIONS: PHASE OVERCURRENT, OVERVOLTAGE, UNDERVOLTAGE, OVERTEMPERATURE, AND AC ONE PHASE.
  - F. D.C. DISCONNECT MUST COMPLY WITH CEC ARTICLES 690.14(A)-D), 690.53 (LABEL), 690.7 (LABEL), AND 690.8.
- SEPARATE DC DISCONNECT IS REQUIRED ONLY IF INVERTER HAS AN INTEGRATED (BUT NOT SEPARATED) DC DISCONNECT. SIGNS ON DIRECTORIES SHALL BE ATTACHED TO THE ELECTRIC EQUIPMENT OR LOCATED ADJACENT TO THE IDENTIFIED EQUIPMENT. SIGNS SHALL BE 4" X 6" MINIMUM. SIGNS SHALL BE MADE OF ALUMINUM, BRASS, STAINLESS STEEL, OR POLYESTER. SIGNS SHALL BE ENGRAVED OR MACHINE PRINTED. LETTERS OR ELECTRO-PHOTO PLATING, IN A CONTRASTING COLOR TO THE SIGN BACKGROUND. SPACE REQUIREMENTS FOR ELECTRIC EQUIPMENT SHALL COMPLY WITH CEC ARTICLE 110.25.

DATE	01/09/2026
TIME	11:55 AM
SCALE	N.T.S.
DESIGNER	TD & CS
CHECKER	CS
PROJECT NO.	01/09/2026
PROJECT NAME	BRIGHAM CITY PUBLIC POWER
PROJECT ADDRESS	1432 East Dwyer Ave 1000 Provo, UT 84606
PROJECT PHONE	801-734-6600
PROJECT FAX	801-734-6600
PROJECT WEBSITE	www.bcpw.gov
PROJECT DRAWING NO.	E27
PROJECT SHEET NO.	1 OF 1
PROJECT TITLE	PHOTOVOLTAIC THREE-PHASE SYSTEM DIAGRAM USING MULTIPLE TWO-LINE SINGLE-PHASE INVERTERS WITH NEUTRAL CONNECTION

**THIS DETAIL SHOWS THE REQUIREMENTS FOR A PHOTOVOLTAIC THREE-PHASE SYSTEM USING A SINGLE THREE-PHASE INVERTER**



**NOTES:**

- A. MAIN SERVICE PANEL MUST COMPLY WITH CEC LATEST REVISION ARTICLES 680.64 AND 705.10 (LABEL).
  - B. UTILITY LOCKABLE A.C. DISCONNECT TO BE LOCATED WITHIN 10'-0" OF SERVICE PANEL. A MINIMUM 10" CLEARANCE IS REQUIRED FROM EDGE OF ANY ENCLOSURE. MUST COMPLY WITH CEC ARTICLES 690.14 (LABEL), 690.17 (LABEL) AND 680.54 (LABEL).
  - C. P.V. GROSS METER TO BE PROVIDED AND INSTALLED BY BRIGHAM CITY PUBLIC POWER AT CUSTOMER'S EXPENSE. METER SOCKET TO BE PROVIDED BY INSTALLER. METER SOCKET SUBMITTAL MUST BE APPROVED BY BRIGHAM CITY PUBLIC POWER. METER PROVIDED & INSTALLED BY THE LEASING COMPANY. BRIGHAM CITY PUBLIC POWER WILL ACTIVATE THE PV SYSTEM AFTER IT MEETS ALL REQUIREMENTS, AND PASSES ALL INSPECTION.
  - D. UTILITY LOCKABLE A.C. DISCONNECT MUST BE LOCATED WITHIN 10'-0" OF B AND WITHIN LINE OF SIGHT OF MAIN SERVICE PANEL. A MINIMUM CLEARANCE OF 10" IS REQUIRED FROM EDGE OF ANY ENCLOSURE. MUST COMPLY WITH CEC ARTICLES 690.14 (LABEL), 690.17 (LABEL), AND 690.54 (LABEL).
  - E. INVERTER MUST COMPLY WITH CEC ARTICLE 690.47(1) AND UL1741. GROUNDED ELECTRODE SYSTEM MUST COMPLY WITH CEC ARTICLE 690.47. INVERTERS MUST BE INSTALLED IN MULTIPLES OF THREE IN ORDER TO KEEP ALL PHASES BALANCED. SINGLE-PHASE INVERTERS SHALL NOT BE CONNECTED TO 3-PHASE POWER SYSTEMS UNLESS THE INTERCONNECTED PROTECTION MUST INCLUDE THE FOLLOWING MINIMUM PROTECTIVE FUNCTIONS: PHASE OVERCURRENT, OVERVOLTAGE, UNDERVOLTAGE, OVERFREQUENCY, AND AC GND FAULT.
  - F. D.C. DISCONNECT MUST COMPLY WITH CEC ARTICLES 690.14(A)-(D), 690.51 (LABEL), 690.7 (LABEL) AND 690.8.
    - \* SEPARATE DC DISCONNECT IS REQUIRED ONLY IF INVERTER HAS AN INTEGRATED (BUT NOT SEPARATED) DC DISCONNECT
- SEALS OR DISCONNECTS SHALL BE ATTACHED TO THE ELECTRICAL EQUIPMENT OR LOCATED IMMEDIATELY ADJACENT TO THE IDENTIFIED EQUIPMENT. SEALS SHOULD BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT. ALL FORMS SHALL BE REINFORCED WITH METAL OR PLASTIC. SEALS OR ELECTRICAL EQUIPMENT BY MEANS OF EPOXY, SCREWS, OR NAILS. OUTDOOR SEALS SHALL BE EITHER METAL OR PLASTIC WITH ENGRAVED OR MACHINE PRINTED LETTERS. ON ELECTRO-PHOTO PLATING, IN A CONTRASTING COLOR TO THE SIGN BACKGROUND. SPICE REQUIREMENTS FOR ELECTRICAL EQUIPMENT SHALL COMPLY WITH CEC ARTICLE 110.26.

NO.	DATE	BY	REVISION
1	01/09/2028	N.T.S.	
2		TD & CS	
3		DC	
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			
46			
47			
48			
49			
50			
51			
52			
53			
54			
55			
56			
57			
58			
59			
60			
61			
62			
63			
64			
65			
66			
67			
68			
69			
70			
71			
72			
73			
74			
75			
76			
77			
78			
79			
80			
81			
82			
83			
84			
85			
86			
87			
88			
89			
90			
91			
92			
93			
94			
95			
96			
97			
98			
99			
100			

BRIGHAM CITY PUBLIC POWER  
 ELECTRICAL CONSTRUCTION STANDARDS  
 PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM  
 USING A SINGLE THREE-PHASE INVERTER

BRIGHAM CITY PUBLIC POWER  
 100 East Power Court 8000  
 Provo, UT 84601  
 1-800-744-6000  
 www.bcpower.com

BRIGHAM CITY  
 27 North Main Street  
 Provo, UT 84601  
 1-800-744-6000  
 www.bcpower.com

BRIGHAM CITY PUBLIC POWER  
 APPROVED FOR THE USE OF BRIGHAM CITY PUBLIC POWER  
 APPROVED FOR THE USE OF BRIGHAM CITY PUBLIC POWER  
 APPROVED FOR THE USE OF BRIGHAM CITY PUBLIC POWER  
 APPROVED FOR THE USE OF BRIGHAM CITY PUBLIC POWER

DATE: 01/09/2028  
 DRAWN BY: TD & CS  
 CHECKED BY: DC

SCALE: N.T.S.

NO. 1 OF 1 SHEET

**THIS DETAIL SHOWS THE LABELING REQUIREMENTS FOR A PHOTOVOLTAIC SYSTEMS AC AND DC DISCONNECT DEVICES**

**UTILITY INTERACTION POINT  
AC DISCONNECT**


RATED AC OUTPUT CURRENT =  
NOMINAL OPERATING AC VOLTAGE =

**PV POWER SOURCE  
DC DISCONNECT**

RATED MAXIMUM POWER-POINT CURRENT =  
RATED MAXIMUM POWER-POINT VOLTAGE =  
MAXIMUM SYSTEM VOLTAGE =  
SHORT-CIRCUIT CURRENT =

- NOTES:
- REQUIRED PLACARDS SHALL BE ATTACHED TO THE ELECTRIC EQUIPMENT WITHOUT COVERING MANUFACTURER LABELING OR LOCATED ADJACENT TO LABELING OR LOCATED ADJACENT TO THE IDENTIFIED EQUIPMENT (PER ANI APPROVAL)
  - ALL PLACARDS SHALL BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT.
  - ALL PLACARDS SHALL BE PERMANENTLY ATTACHED TO THE SURFACE OF THE ELECTRICAL EQUIPMENT BY MEANS OF EPOXY OR EQUIVALENT (SCREWS OR RIVETS ARE NOT ALLOWED)
  - ALL PLACARDS SHALL BE EITHER METAL OR PLASTIC WITH ENGRAVED OR MACHINE PRINTED LETTERS OR ELECTRO-PHOTO PLATING IN RED
  - ALL PLACARDS SHALL NOT BE SMALLER THAN 2" x 5" AND NO LARGER THAN 3' x 6" (WITH THE EXCEPTION OF THE DIRECTORY PLAQUE)
  - EACH A.C. DISCONNECT SHALL HAVE ITS OWN PLACARD AND MUST COMPLY WITH NEC 690.15(A), 690.13, 690.17, AND 690.54
  - EACH D.C. DISCONNECT SHALL HAVE ITS OWN PLACARD AND MUST COMPLY WITH NEC ARTICLES 690.51 AND 690.7

**THIS DETAIL SHOWS THE WARNING LABEL REQUIREMENTS FOR THE PV SERVICE PANEL**



- NOTES:
- REQUIRED PLACARDS SHALL BE ATTACHED TO THE ELECTRIC EQUIPMENT WITHOUT COVERING MANUFACTURER LABELING OR LOCATED ADJACENT TO THE IDENTIFIED EQUIPMENT (PER ANI APPROVAL)
  - ALL PLACARDS SHALL BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT.
  - ALL PLACARDS SHALL BE PERMANENTLY ATTACHED TO THE SURFACE OF THE ELECTRICAL EQUIPMENT BY MEANS OF EPOXY OR EQUIVALENT (SCREWS OR RIVETS ARE NOT ALLOWED)
  - ALL PLACARDS SHALL BE EITHER METAL OR PLASTIC WITH ENGRAVED OR MACHINE PRINTED LETTERS OR ELECTRO-PHOTO PLATING IN RED WITH WHITE LETTERING.
  - ALL PLACARDS SHALL NOT BE SMALLER THAN 2" x 5" AND NO LARGER THAN 3' x 6" (WITH THE EXCEPTION OF THE DIRECTORY PLAQUE)
  - ALL PLACARDS FONT STYLE SHALL BE ARIAL WITH THE FONT SIZE NO SMALLER THAN SIZE 12 OR NO LARGER THAN SIZE 28.

NO.	DATE	REVISIONS	BY	CHKD.	DATE	DESCRIPTION
1						
2						
3						
4						
5						
6						
7						
8						
9						
10						
11						
12						
13						
14						
15						
16						
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						
28						
29						
30						
31						
32						
33						
34						
35						
36						
37						
38						
39						
40						
41						
42						
43						
44						
45						
46						
47						
48						
49						
50						
51						
52						
53						
54						
55						
56						
57						
58						
59						
60						
61						
62						
63						
64						
65						
66						
67						
68						
69						
70						
71						
72						
73						
74						
75						
76						
77						
78						
79						
80						
81						
82						
83						
84						
85						
86						
87						
88						
89						
90						
91						
92						
93						
94						
95						
96						
97						
98						
99						
100						

BRIGHAM CITY PUBLIC POWER  
ELECTRICAL CONSTRUCTION STANDARDS  
PV DISCONNECT LABELS &  
PV SERVICE PANEL WARNING LABELS

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com


BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com

BRIGHAM CITY  
140 East Power Street  
Provo, UT 84601  
www.bcp.com




EUSERC DWG NO. 501

NOTES:

1. \* CHECK THE ACCEPTABILITY TABLES FOR UTILITY REQUIREMENTS.
2. THE AC DISCONNECT SWITCH MAY BE FUSED OR UNFUSED.
3. THE AC DISCONNECT SWITCH SHALL BE LOCATED WITHIN 10'-0" OF THE MAIN SERVICE PANEL AND WITHIN LINE OF SIGHT.
4. A MINIMUM 10" CLEARANCE IS REQUIRED FROM THE EDGE OF ANY ENCLOSURE.

NO.	DATE	REVISION
1	01/09/2026	TD & CS
2		TC
3		
4		
DRAWING SCALE: N.T.S. DATE: 01/09/2026 DRAWN: TD & CS CHECKED: TC DESIGNER: RCB DESIGNER: TD & CS CHECKED: TC		
BRIGHAM CITY PUBLIC POWER 30 North Main Street Brigham City, UT 84302 Tel: 435-734-8000 www.bcp.com		
BRIGHAM CITY PUBLIC POWER 1400 East Power Plant Road Brigham City, UT 84302 Tel: 435-734-8000 24-Hour Emergency: 1-877-734-8000		
BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS E30 OF 1 SHEET		
EUSERC DWG NO. 501 - AC DISCONNECT GUIDELINES		



DATE	01/09/2028	SCALE	N.T.S.	DATE	05/27	BY	TD & CS	DATE	7/5
DESIGNED BY		CHECKED BY		PROJECT NO.		PROJECT NAME		PROJECT LOCATION	
BRIGHAM CITY PUBLIC POWER ELECTRICAL - VEGETATION MANAGEMENT STANDARDS TREE AND VEGETATION TRIMMING AND CLEARING DETAILS									
BRIGHAM CITY CORPORATION 201 EAST 100 SOUTH PROVO, UT 84601 WWW.BCUT.UTAH.GOV									
BRIGHAM CITY PUBLIC POWER 1500 LAUREL CANYON DRIVE SALT LAKE CITY, UT 84143 (801) 438-5600									



BRIGHAM CITY PUBLIC POWER  
ELECTRICAL REQUIREMENTS  
AND  
STANDARDS MANUAL



FEBRUARY 2026~~AUGUST 2025~~

## TABLE OF CONTENTS

SECTION 1 GENERAL .....	1
1.01 Ordinances Govern .....	1
1.02 Conformance with Federal, State, and Local Laws .....	1
1.03 Definitions .....	1
1.04 Easements .....	2
1.05 Traffic Control .....	2
1.06 Survey .....	2
1.07 Temporary Controls .....	2
SECTION 2 IMPROVEMENT REQUIREMENTS .....	3
2.01 General .....	3
2.02 Variations, Substitutions, Exceptions and Changes .....	3
2.03 Protection of Existing Improvements .....	3
2.04 New Materials .....	3
2.05 City Furnished Products .....	3
2.06 Product Delivery and Handling .....	3
2.07 Product Storage and Protection .....	3
2.08 Other Specifications and Standards .....	4
SECTION 3 SPECIALIZED ENGINEERING .....	4
3.01 General .....	4
SECTION 4 CONSTRUCTION PLANS .....	4
4.01 General .....	4
4.02 Electric Plans .....	4
SECTION 5 POWER UTILITY IMPROVEMENTS .....	5
5.01 General .....	5
5.02 Electric .....	5
SECTION 6 INSPECTION AND TESTING .....	5
6.01 Quality Control .....	5
6.02 Inspection and Testing Notification .....	5
6.03 Work Without Required Inspection and Testing .....	6
6.04 Inspection and Testing Fees .....	6
6.05 Weekly Progress Meetings .....	6
6.06 As-Built Survey .....	6
6.07 Earthwork: Compaction and Moisture Content Tests .....	6
6.08 Inspections .....	6
SECTION 7 PORTLAND CEMENT CONCRETE WORK .....	7
7.01 General .....	7
SECTION 8 EARTHWORK AND TRENCHES .....	7
8.01 Excavation .....	7
8.02 Subsurface Pipe Installation .....	8
8.03 Fill Material .....	8
8.04 Installation and Compaction of Earth Materials .....	9
SECTION 9 GENERAL .....	10
9.01 Standards and Specifications .....	10
9.02 Construction Costs .....	10

9.03	Attaching to Existing City Facilities Prohibited .....	10
9.04	Unusual Service Extensions .....	10
9.05	Permits and Inspections .....	10
9.06	Access to Premises .....	11
9.07	Electrical Plan Drawings .....	11
9.08	Electrical Box Clearance .....	11
9.09	Overhead Electrical Power Line Clearances .....	12
<b>SECTION 10 VOLTAGE AND ENERGY REGULATION .....</b>		<b>13</b>
10.01	Available Voltages .....	13
10.02	Phase Service .....	13
10.03	Power Factor Correction .....	13
10.04	Load Control .....	14
10.05	Voltage Control .....	14
10.06	Fluctuating Load Limitations .....	14
10.07	Penalties .....	14
<b>SECTION 11 MATERIALS .....</b>		<b>14</b>
11.01	Materials .....	14
11.02	Conduit .....	14
11.03	Enclosures .....	15
11.04	Soils & Compaction .....	15
<b>SECTION 12 INSTALLATION .....</b>		<b>15</b>
12.01	General .....	15
12.02	Underground Lines .....	16
12.03	Conduit Depths .....	16
12.04	Pull Strings .....	16
12.05	Identification Tape and Stub Markers .....	16
12.06	Underground Metal Conduit .....	17
12.07	Road Crossings .....	17
12.08	Berms, Slopes, and Hillside Conditions .....	17
12.09	Labels .....	17
<b>SECTION 13 SYSTEM REQUIREMENTS .....</b>		<b>17</b>
13.01	Additional Capacity Requirements .....	17
13.02	Substations .....	18
<b>SECTION 14 SERVICES .....</b>		<b>18</b>
14.01	Point of Service .....	18
14.02	Service Entrance Requirements .....	18
14.03	Underground Residential Service Requirements .....	19
14.04	Overhead Residential Service Requirements .....	21
14.05	Underground Service Requirements for Multi-Family Dwelling Units .....	24
14.06	Underground Service Requirements for Commercial & Industrial Applications ..	24
<b>SECTION 15 METERING .....</b>		<b>27</b>
15.01	General .....	27
15.02	Location .....	27
15.03	Meter Base .....	28
15.04	Commercial Meters .....	28

15.05 Location of Multiple Meters .....	29
15.06 Meter Location Regarding Remodeling .....	29
15.07 Meter Accessibility .....	29
15.08 Outdoor Meters for Non-Residential General Service .....	29
15.09 Instrument Transformer for Metering.....	29
15.10 Current Transformer Cabinet .....	30
15.11 Unacceptable Meter Locations .....	30
SECTION 16 LIGHTING AND SIGNAL POLES .....	31
16.01 General .....	31
16.02 Dark Sky .....	31
16.03 Location .....	31
16.04 Orientation .....	31
16.05 Grounding & Bonding.....	32
16.06 Wiring & Fusing .....	32
SECTION 17 VEGETATION MANAGEMENT .....	33
17.01 Overview .....	33
17.02 Professionalism .....	33
17.03 Safety.....	33
17.04 Fire Protection .....	34
17.05 Species of concerns .....	34
17.06 Bird Protection .....	34
17.07 Tree Removal .....	36
17.08 Debris Disposal.....	37
17.09 Directional Pruning.....	37
17.10 Tree Houses.....	38
17.11 Distribution Cycle Maintenance .....	38
17.12 Transmission procedures.....	41
17.13 Chemical Procedures .....	42
17.14 Approved Herbicides .....	44

<b>ELECTRICAL CONSTRUCTION STANDARD DRAWINGS</b> .....	<b>45</b>
E1 Electric General Information .....	46
E2 Residential Underground Service 200 Amps or Less .....	47
E3 Residential Overhead Service 200 Amps or Less .....	48
E4 Electric Conduit Trench Detail .....	49
E5 Secondary Junction Pedestal .....	50
E6 Single Phase Pad Mount Transformer .....	51
E7 200-Amp 1-Phase Sectionalizer .....	52
E8 200-Amp 1- and 3-Phase Fiberglass Sectionalizer .....	53
E9 600-Amp 3-Phase Fiberglass Sectionalizer .....	54
E10 Electrical Box Backfill & Compaction .....	55
E11 Conduit Routing .....	56
E12 3-Phase Transformer & Concrete Pad .....	57
E13 600 Amp PSE 9/11 Switchgear .....	58
E14 600 Amp PSE 3/5 Switchgear .....	59
E15 Secondary Pedestal, Wire & Connections .....	60
E16 Decorative Street Light Pole Footing Detail .....	61
E17 Street Light Poles and Fixtures .....	62
E18 Temporary Service for Overhead & Underground Lines .....	63
E19 3-Phase Underground Service 201-800 Amps .....	64
E20 Typical Riser Pole .....	65
E21 Overhead Power Line Clearances over 600 Volts to 22,000 Volts .....	66
E22 1-Phase Free Standing Meter Base & 3-Phase Free Standing Meter Base .....	67
E23 Photovoltaic Single-Phase System Diagram Central Inverter (Residential) .....	68
E24 Photovoltaic Single-Phase System Diagram Micro Inverter (Residential) .....	69
E25 Photovoltaic Single-Phase System Diagram Energy Storage – Central Inverter .....	70
E26 Photovoltaic Single-Phase System Diagram Energy Storage – Micro Inverter (Residential) .....	71
E27 Photovoltaic Three-Phase System Diagram Using Multiple Two-Line Single-Phase Inverters with Neutral Connection .....	72
E28 Photovoltaic Single-Phase System Diagram Using a Single Three-Phase Inverter .....	73
E29 PV Disconnect Labels & PV Service Panel Warning Labels .....	74
E30 EUSERC Dwg No. 501 - AC Disconnect Guidelines .....	75
V1 Tree and Vegetation Trimming and Clearing Details .....	76
V2 Tree Planting and Electrical Box Clearance Details .....	77

SECTION 1 GENERAL ..... 1

    1.01 Ordinances Govern ..... 1

    1.02 Conformance with Federal, State, and Local Laws ..... 1

    1.03 Definitions ..... 1

    1.04 Easements ..... 2

    1.05 Traffic Control ..... 2

    1.06 Survey ..... 2

    1.07 Temporary Controls ..... 2

SECTION 2 — IMPROVEMENT REQUIREMENTS ..... 3

    2.01 General ..... 3

    2.02 Variations, Substitutions, Exceptions and Changes ..... 3

    2.03 Protection of Existing Improvements ..... 3

    2.04 New Materials ..... 3

    2.05 City Furnished Products ..... 3

    2.06 Product Delivery and Handling ..... 3

    2.07 Product Storage and Protection ..... 3

    2.08 Other Specifications and Standards ..... 4

SECTION 3 — SPECIALIZED ENGINEERING ..... 4

    3.01 General ..... 4

SECTION 4 CONSTRUCTION PLANS ..... 4

    4.01 General ..... 4

    4.02 Electric Plans ..... 4

SECTION 5 POWER UTILITY IMPROVEMENTS ..... 5

    5.01 General ..... 5

    5.02 Electric ..... 5

SECTION 6 INSPECTION AND TESTING ..... 5

    6.01 Quality Control ..... 5

    6.02 Inspection and Testing Notification ..... 5

    6.03 Work Without Required Inspection and Testing ..... 6

    6.04 Inspection and Testing Fees ..... 6

    6.05 Weekly Progress Meetings ..... 6

    6.06 As-Built Survey ..... 6

    6.07 Earthwork: Compaction and Moisture Content Tests ..... 6

6.08	Inspections.....	6
SECTION 7 PORTLAND CEMENT CONCRETE WORK.....7		
7.01	General.....	7
SECTION 8 EARTHWORK AND TRENCHES.....7		
8.01	Excavation.....	7
8.02	Subsurface Pipe Installation.....	8
8.03	Fill Material.....	8
8.04	Installation and Compaction of Earth Materials.....	9
SECTION 9 GENERAL.....10		
9.01	Standards and Specifications.....	10
9.02	Construction Costs.....	10
9.03	Attaching to Existing City Facilities Prohibited.....	10
9.04	Unusual Service Extensions.....	10
9.05	Permits and Inspections.....	10
9.06	Access to Premises.....	11
9.07	Electrical Plan Drawings.....	11
9.08	Electrical Box Clearance.....	11
9.09	Overhead Electrical Power Line Clearances.....	12
SECTION 10 VOLTAGE AND ENERGY REGULATION.....13		
10.01	Available Voltages.....	13
10.02	Phase Service.....	13
10.03	Power Factor Correction.....	13
10.04	Load Control.....	14
10.05	Voltage Control.....	14
10.06	Fluctuating Load Limitations.....	14
10.07	Penalties.....	14
SECTION 11 MATERIALS.....14		
11.01	Materials.....	14
11.02	Conduit.....	14
11.03	Enclosures.....	15
11.04	Soils & Compaction.....	15
SECTION 12 INSTALLATION.....15		
12.01	General.....	15
12.02	Underground Lines.....	16

12.03	Conduit Depths.....	16
12.04	Pull Strings.....	16
12.05	Identification Tape and Stub Markers .....	16
12.06	Underground Metal Conduit.....	17
12.07	Road Crossings.....	17
12.08	Berms, Slopes, and Hillside Conditions .....	17
12.09	Labels .....	17
SECTION 13	SYSTEM REQUIREMENTS.....	17
13.01	Additional Capacity Requirements .....	17
13.02	Substations .....	17
SECTION 14	SERVICES.....	18
14.01	Point of Service .....	18
14.02	Service Entrance Requirements .....	18
14.03	Underground Residential Service Requirements.....	19
14.04	Overhead Residential Service Requirements.....	21
14.05	Underground Service Requirements for Multi-Family Dwelling Units .....	24
14.06	Underground Service Requirements for Commercial & Industrial App.....	24
SECTION 15	METERING .....	27
15.01	General .....	27
15.02	Location .....	27
15.03	Meter Base .....	28
15.04	Commercial Meters.....	28
15.05	Location of Multiple Meters.....	29
15.06	Meter Location Regarding Remodeling.....	29
15.07	Meter Accessibility .....	29
15.08	Outdoor Meters for Non-Residential General Service .....	29
15.09	Instrument Transformer for Metering.....	29
15.10	Current Transformer Cabinet .....	30
15.11	Unacceptable Meter Locations .....	30
SECTION 16	LIGHTING AND SIGNAL POLES.....	31
16.01	General .....	31
16.02	Dark Sky .....	31
16.03	Location .....	31

16.04 Orientation ..... 31

16.05 Grounding & Bonding..... 32

16.06 Wiring & Fusing ..... 32

SECTION 17 — VEGETATION MANAGEMENT..... 33

17.01 Overview ..... 33

17.02 Professionalism ..... 33

17.03 Safety..... 33

17.04 Fire Protection ..... 34

17.05 Species of concerns ..... 34

17.06 Bird Protection ..... 34

17.07 Tree Removal ..... 36

17.08 Debris Disposal..... 37

17.09 Directional Pruning..... 37

17.10 Tree Houses ..... 38

17.11 Distribution Cycle Maintenance ..... 38

17.12 Transmission procedures..... 41

17.13 Chemical Procedures ..... 42

17.14 Approved Herbicides ..... 44

ELECTRICAL CONSTRUCTION STANDARD DRAWINGS .....	45
E1 — Electric General Information .....	46
E2 — Residential Underground Service 200 Amps or Less .....	47
E3 — Residential Overhead Service 200 Amps or Less .....	48
E4 — Electric Conduit Trench Detail .....	49
E5 — Secondary Junction Pedestal .....	50
E6 — Single Phase Pad Mount Transformer .....	51
E7 — 200-Amp 1-Phase Sectionalizer .....	52
E8 — 200-Amp 1- and 3-Phase Fiberglass Sectionalizer .....	53
E9 — 600-Amp 3-Phase Fiberglass Sectionalizer .....	54
E10 — Electrical Box Backfill & Compaction .....	55
E11 — Conduit Routing .....	56
E12 — 3-Phase Transformer & Concrete Pad .....	57
E13 — 600 Amp PSE 9/11 Switchgear .....	58
E14 — 600 Amp PSE 3/5 Switchgear .....	59
E15 — Secondary Pedestal, Wire & Connections .....	60
E16 — Decorative Street Light Pole Footing Detail .....	61
E17 — Street Light Poles and Fixtures .....	62
E18 — Temporary Service for Overhead & Underground Lines .....	63
E19 — 3-Phase Underground Service 201-800 Amps .....	64
E20 — Typical Riser Pole .....	65
E21 — Overhead Power Line Clearances over 600 Volts to 22,000 Volts .....	66
E22 — 1-Phase Free Standing Meter Base & 3-Phase Free Standing Meter Base .....	67
E23 — Photovoltaic Single-Phase System Diagram Central Inverter (Residential) .....	68
E24 — Photovoltaic Single-Phase System Diagram Micro Inverter (Residential) .....	69
E25 — Photovoltaic Single-Phase System Diagram Energy Storage – Central Inverter .....	70
E26 — Photovoltaic Single-Phase System Diagram Energy Storage – Micro Inverter (Residential) .....	71
E27 — Photovoltaic Three-Phase System Diagram Using Multiple Two-Line Single-Phase Inverters with Neutral Connection .....	72
E28 — Photovoltaic Single-Phase System Diagram Using a Single Three-Phase Inverter .....	73
E29 — PV Disconnect Labels & PV Service Panel Warning Labels .....	74
E30 — EUSERC Dwg No. 501 - AC Disconnect Guidelines .....	75

V1 — Tree and Vegetation Trimming and Clearing Details..... 76

V2 — Tree Planting and Electrical Box Clearance Details..... 77

---

## GENERAL

### SECTION 1 GENERAL

#### 1.01 Ordinances Govern

Nothing in this document shall be construed to be contrary to Brigham City Ordinances. Should a conflict exist between this document and the Ordinances, the Ordinances shall govern.

#### 1.02 Conformance with Federal, State, and Local Laws

Nothing in this document shall relieve the Developer, Engineer, or Contractor from abiding by any and all Federal, State and local laws

#### 1.03 Definitions

- A. APWA. The American Public Works Association
- B. City. The City of Brigham City, Utah.
- C. County. Box Elder County, Utah
- D. Construction Plans. Construction plans include drawings showing all required improvements for a development showing their location, size, grade, and elevations.
- E. Customer. A person or company receiving service from any City utilities
- F. Contractor. A person or company hired by the city or a Developer to perform construction in or for the city, having appropriate state licenses to perform said work.
- G. Council or City Council. The governing body of the city.
- H. Development Review Team. The Review Team (DRT) of Brigham City.
- I. Developer. Person, persons, partnership or corporations developing residential, commercial or industrial property.
- J. Improvements. Includes roads, streets, curbs, gutters, sidewalks, grading, landscaping, water and sanitary sewer systems, irrigation systems, drainage systems, power systems, fences, public facilities, trees or other requirements by this chapter or by the city.
- K. Land Surveyor. A person licensed with the State of Utah to practice as a licensed land surveyor.
- L. Lot. A parcel or tract of land within a subdivision.
- M. MUE. A Municipal Utility Easement acquired by the city for city utilities.
- N. MUTCD. Manual on Uniform Traffic Control Devices.
- O. NEC. The National Electrical Code is a United States standard for the safe installation of electrical wiring and equipment.
- P. NEMA. National Electrical Manufacturers' Association
- Q. NESC. The National Electrical Safety Code
- R. Net billing. A debit and credit metering process in an account.
- S. Offsite Facilities. Facilities outside of the boundaries of the subdivision or development.

- T. Onsite Facilities. Facilities installed within or on the perimeter of the subdivision or development site.
- U. OSHA. The Occupational Safety and Health Administration.
- V. Power Department. The division of City government responsible for the city owned Electric utilities.
- W. Public Power Director. The Public Power Director for Brigham City or authorized representative.
- X. Public Utility Easements. The easements required to place public utilities across any privately owned property.
- Y. ROW. Right of Way

1.04 Easements

Developers shall provide municipal utility easements (MUEs) for all utility extensions through private property and for 10 feet along public right-of-ways. Developments other than single family home developments shall provide 10-foot MUEs along all property lines. If setbacks are less than 10 feet, then MUEs shall be the extent of the setback. Single family lots shall have 10-foot MUEs along public right-of-ways or streets and not necessarily along the other property lines unless a utility is planned there. Developer shall not be allowed to nor shall they include any type of protection easement intended to provide exclusivity to their development.

1.05 Traffic Control

A traffic control plan shall be submitted to the City prior to construction in or along public streets. All traffic control shall comply with APWA 01 55 26 (Traffic Control) and the MUTCD.

1.06 Survey

The alignment of the side property lines for each lot in a subdivision shall be marked in the top back of curb with a lot line witness marker that meets the requirements and specifications of APWA 31 05 10 (Boundary Markers and Survey Monuments). Developers shall provide survey benchmarks and monuments as required by the Public Power Director.

1.07 Temporary Controls

Temporary controls such as noise, dust, mud, surface water, ground water, pollution and erosion controls shall be made. Controls shall meet the requirements and specifications of APWA 01 57 00 (Temporary Controls). Pumping groundwater into the sanitary sewer system is prohibited. Ground water and/or surface water must be kept on the construction site. If either leave the site by any manner, additional temporary controls must be implemented to protect the storm water drain system. A Storm Water Pollution Prevention Plan (SWPPP) and Notice of Intent (NOI) may also be required. See Brigham City's SWPPP Requirements on the public website for more information.

---

**SECTION 2 IMPROVEMENT REQUIREMENTS****2.01 General**

This policy defines the general requirements for improvements to be built by the Developer, sub-divider, owner, or Contractor for all types of construction (including residential, commercial, industrial, institutional, governmental and professional office). All improvements which are in areas that are or will become public rights-of-way and/or easements, or that will be under the responsibility of a homeowner's association, shall meet the requirements of these specifications.

**2.02 Variations, Substitutions, Exceptions and Changes**

Any variation, substitution or exception from the standards in this policy must be authorized in writing by the Public Power Director. Product options and substitutions must meet the requirements of APWA 01 25 00 (Product Options and Substitutions). Any item of construction not covered in these standards must have plans and specifications approved by the Public Power Director. Requests for changes to the Construction Standards shall be made in writing to the Public Power Director. These requests will be reviewed during the revision process conducted in conjunction with the APWA, NESC and NEC revisions. There is no appeal from the decision of the Public Power Director.

**2.03 Protection of Existing Improvements**

The Contractor shall be responsible for the protection of any existing improvements on public or private property at the start of work or placed there during the progress of the work. Existing improvements shall include but are not limited to permanent surfacing, curbs, ditches, driveways, culverts, fences, walls and landscaping. Any surface improvements damaged because of construction shall be restored or replaced to an equal or better condition than before. This shall be accomplished in a timely manner.

**2.04 New Materials**

Only new materials may be used during construction unless otherwise authorized by the Public Power Director.

**2.05 City Furnished Products**

If the City furnishes any products the Contractor shall conform to requirements and specifications of APWA 01 64 00 (Owner-furnished Products), NESC and NEC.

**2.06 Product Delivery and Handling**

The Contractor shall conform to requirements and specifications of APWA 01 65 00 (Product Delivery and Handling), NESC and NEC.

**2.07 Product Storage and Protection**

The Contractor shall conform to requirements and specifications of APWA 01 66 00 (Product Storage and Protection), NESC and NEC.

## 2.08 Other Specifications and Standards

City standards and ordinances shall supersede all other Standards whenever they conflict.

## SECTION 3 SPECIALIZED ENGINEERING

### 3.01 General

Any specialized engineering beyond the expertise of city staff such as, but not limited to, geotechnical, traffic, environmental, hillside, floodplain, bank stabilization and erosion control will require the review of qualified consultants. All review costs shall be paid by the property owner/developer.

Locate utilities within areas of explorations by notifying the appropriate local one-call state utility locate service (Blue Stakes). Independent private utility locates may be required for utilities not identified by the local one-call service. Complete subsurface explorations in accordance with the minimum requirements outlined in this section.

## SECTION 4 CONSTRUCTION PLANS

### 4.01 General

The following instructions are for the purpose of standardizing the preparation of construction plans to obtain uniformity in appearance, clarity, size, and style. Plans and designs shall meet the standards defined in the specifications and drawings hereinafter outlined. All drawings and/or prints shall be clear and legible and conform to good engineering and drafting room practice.

Include the following in construction plans for all developments:

1. A copy of the proposed final plat or site plan.
2. A plan view of the entire project showing all utilities, roads, and appurtenances.
3. Plan and profiles of all storm, land and groundwater drains, sanitary sewer, curb, gutter, and irrigation.
4. Detail drawings of street cross sections according to the standard drawings and other detail drawings only for items not found in the city standard drawings. Detail drawings shall be to scale and completely dimensioned and described. All items shall be designed in accordance with minimum requirements established by the Public Works Standards.
5. Complete plans for all off-site work to be done in conjunction with the project.
6. A stamp and signature of a Civil Engineer licensed in the state of Utah on each plan sheet, detail drawing, and design sheet.

### 4.02 Electric Plans

Construction plans must include the location of all existing poles, transformers, secondary junction boxes, sectionalizers, and overhead electrical wire. After plans

are updated to meet the approval of the DRT, the Developer shall submit a computer aided design (CAD) file of the plans to the Power Department. CAD file must be in a .dwg or .dxf format. Thereafter the Power Department will design and make available plans for the proposed electric lines for the development. City electrical utility design shall supersede any design provided by developer.

## SECTION 5 POWER UTILITY IMPROVEMENTS

### 5.01 General

It shall be the responsibility of the Developer to connect to existing utilities or improvements wherever they are located and extend those improvements to and through the development. This requirement includes hooking up existing homes within the development to all utilities. Existing buildings impacted by development which are currently fed overhead shall be required to be rerouted and metering directly connected to new underground electrical grid at developer's expense. Workmanship and details of construction shall be in accordance with the Public Power Standards and/or other codes adopted by the City. All work shall be done under the supervision of the Public Power Director.

### 5.02 Electric

Electrical lines shall be underground except when the Public Power Director feels that such underground lines are not in the best interest of the City.

## SECTION 6 INSPECTION AND TESTING

### 6.01 Quality Control

The following work shall be subject to the inspection and testing requirements of this chapter:

1. Work on existing or proposed City property.
2. Work on property that will be owned by a property owners association.
3. Work on existing or proposed streets, easements, or right-of-ways.
4. Work on existing or proposed City utilities.

The Contractor is responsible for performing all inspection and testing required to verify installed materials meet these standards and must verify the materials are accepted by the Public Power Director. The Contractor must also ensure that any additional inspection and testing required by the city or a testing company is performed and accepted by the City.

### 6.02 Inspection and Testing Notification

The City may contract with a private company to conduct any inspections or testing specified to be performed by the City. All inspections and tests must be scheduled with the City or company contracted by the City a minimum of 1 full business day

before needed. Requests for inspection on work requiring continuous inspection shall be made 3 full business days prior to commencing the work.

#### 6.03 Work Without Required Inspection and Testing

Failure to provide proper notification or to perform work without inspection will result in rejected material. Rejected material will be subject to additional verification requirements including, but not limited to, post-placement sampling and laboratory testing for material conformance, in-place testing for concrete strength and air content. All post-placement testing for uninspected work will be at no additional cost to the city.

Additionally, any work performed without required inspection or testing will give the city the option to hold the bond covering that portion of the improvements in violation, or require the removal and replacement of the uninspected work. The City shall have the option of retaining part or all the bond for up to 10 years after installation of improvements constructed without required inspection or testing. The Public Power Director may also accept the work at a reduced price.

#### 6.04 Inspection and Testing Fees

Connection fees required shall be paid and permits required shall be obtained prior to the preconstruction meeting.

#### 6.05 Weekly Progress Meetings

The City may require, at their discretion, construction projects in the City to have a weekly progress meeting at the Public Power office. The Public Power Director, City inspectors, the Contractor, and subcontractors shall be in attendance.

#### 6.06 As-Built Survey

The Contractor shall notify the City to survey all underground utilities either installed or uncovered during construction. Contractor shall give the City 24-hour notice to survey utilities.

#### 6.07 Earthwork: Compaction and Moisture Content Tests (Refer to Sheet E10)

The city will test all sub-grade and fill material for compaction and moisture content. Test locations shall be determined by the city.

#### 6.08 Inspections

##### 6.08.1 Conduit Inspections

The Public Power Director must inspect all conduit before backfilled.

##### 6.08.2 Service Stub Inspections

The Public Power Director must inspect all service stubs before backfilled.

### 6.08.3 Street Light Base Inspections

The Public Power Director must inspect all street light bases prior to concrete placement and before they are backfilled around.

### 6.08.4 Bedding Inspections

The Public Power Director must inspect the bedding in all electrical trenches.

### 6.08.5 Final Electrical Inspection

Once all electrical work for a development is completed to City standards, a final electrical inspection must be done by the Public Power Director prior to permanent power installation.

## SECTION 7 PORTLAND CEMENT CONCRETE WORK (Refer to Sheets E5-E9, E12-E14 and E16)

### 7.01 General

All materials and processes involved in concrete work shall be subject to inspection and testing as detailed in general compliance with ASTM E105-54T. For additional information refer to the Public Works Standards manual.

## SECTION 8 EARTHWORK AND TRENCHES (Refer to Sheets E4 and E5)

### 8.01 Excavation

#### 8.01.1 General

Excavation shall meet the requirements and specifications of APWA 31 23 16 (Excavation) unless otherwise indicated.

#### 8.01.2 Safety

All construction shall be done in accordance with the provisions of the Utah State Industrial Commission, OSHA regulations and APWA 31 23 16 (Excavation). No trenches deeper than 4 feet shall be left open at any time unless construction is in process. When construction is in process only 200 feet of trench may be open at one time and must be completely backfilled before proceeding. Any variation will require the approval of the Public Power Director. No trenches shall be left open at any time unless guarded with adequate barricades, warning lamps and signs.

Any injury or damage resulting from lack of adequate bracing and shoring shall be the responsibility of the Developer/Contractor and the Developer/Contractor shall, at his/her own expense, affect all necessary repairs or reconstruction resulting from such damage. No inspections will be done in unsafe trenches and will be the cause for immediate shutdown of the project until the trench is deemed to be safe by the Public Power Director.

## 8.02 Subsurface Pipe Installation

### 8.02.1 General

Pipes, conduits or casings, 4 inches in diameter or less, may be bored, jacked, augured or jetted under sidewalk, curb, gutter if authorized by the Public Power Director. The resulting hole diameter shall not exceed 1 inch plus the outside diameter of the pipe or sleeve installed.

### 8.02.2 Boring or Jacking

Boring or jacking work shall meet the requirements and specifications of APWA 33 05 23 (Trenchless Utility Installation).

### 8.02.3 Tunneling

Where sidewalk, curb, and gutter exist, excavation may be made by tunneling provided the following requirements are met:

1. Excavation shall be vertical and as near to the curb or sidewalk as possible.
2. The length of the tunnel shall not exceed the width of the sidewalk, curb, and gutter.
3. Where a separate sidewalk and curb exist, an excavation shall be made between the sidewalk and the curb.
4. At least three feet of undisturbed earth shall be left under the sidewalk or curb; and
5. Where the sidewalk has been tunneled, the hole shall be filled from each end with flowable fill. Where the excavation cannot meet these requirements, a section of sidewalk, curb, or gutter, from joint to joint shall be removed and replaced.

## 8.03 Fill Material

### 8.03.1 General

All fill material shall be placed on sub-grade prepared according to the specifications of this chapter. All fill material shall be compacted according to the specifications of this chapter.

All fill material under and within a foot of electrical boxes shall be untreated base course. In other areas native excavated material may normally be used unless such material cannot be properly compacted according to specifications in this chapter. All fill material, including native fill material, must be free from debris, organic material, and rocks larger than 6 inches in diameter.

### 8.03.2 Bedding Material

Use sand as a bedding material for electrical conduit. Bedding sand must compact sufficiently to support the pipe and shall meet the following gradation:

#### Sand Gradation

Sieve/Screen Size	% Passing
No. 4	100
No. 200	10 to 20

## 8.04 Installation and Compaction of Earth Materials

### 8.04.1 General

The installation of all fill material shall meet the requirements and specifications of APWA 33 05 20 (Backfilling Trenches), APWA 31 23 23 (Backfilling Structures), APWA 32 05 10 (Backfilling Roadways) and APWA 31 23 26 (Compaction). Fill material outside of pavement areas, as defined by APWA 32 05 10 (Backfilling Roadways), and more than 24 inches from any utility box shall be compacted to not less than 90% of the maximum dry density.

### 8.04.2 Backfill in Trenches

Backfill shall be carefully placed around and over pipes and shall not be permitted to fall directly on a pipe from such a height or in such a manner as to cause damage.

### 8.04.3 Conduit Zone (Refer to Sheet E11)

The conduit zone includes the full width of trench from 3 inches below the conduit to 12 inches above the conduit for all conduit. Electrical conduit may be placed to 3" off the sides of trenches. Trenches shall be wide enough to compact fill material according to the specifications in this chapter.

---

## Electrical Service

### SECTION 9 GENERAL

#### 9.01 Standards and Specifications

All electrical work shall be installed in accordance with these development standards, the most current edition of the National Electrical Code (NEC) and the National Electric Safety Code (NESC), and applicable State, County and OSHA codes and ordinances.

These specifications cover the installation of the electrical system. See Section 2 for improvement and design requirements, Section 6 for inspection and testing requirements, and Section 8 for earthwork and trench requirements. See standard drawings related to electrical system.

#### 9.02 Construction Costs

All costs to install or relocate facilities to provide electrical service shall be paid by the Customer.

If a temporary electrical service is needed the contractor/developer is responsible for providing and installing the required conduit, grounding, transformer pad, and metering equipment as directed by the City. There will be a rental fee for the transformer needed that will be determined based off of the length of time the unit is needed. Brigham City Power will provide and install all primary wiring and transformer at the developers/contractor's expense. Any fees paid to the City for these purposes will not be refundable or be applied to any other electrical fees.

#### 9.03 Attaching to Existing City Facilities Prohibited

Customer shall install no wiring or attachments on poles or other equipment of the City unless specifically authorized, in writing, by the City.

#### 9.04 Unusual Service Extensions

Special and unusual service extension requirements for equipment or structures are treated as separate items and are not included in these standards.

#### 9.05 Permits and Inspections

Service will not be established until all necessary permits have been obtained and not until Customer's wiring installation has been inspected and approved by the Public Power Director. Any variations of this must be preapproved by the Public Power Director. The City reserves the right to inspect wiring and to refuse service to any installation that is, in the opinion

of the Public Power Director, unsafe or if the operation of same may be detrimental to the service furnished to other Customers or the City. All conduits shall be inspected prior to backfilling. All concrete street light bases, concrete transformer pads and other required concrete shall be inspected prior to pouring concrete. A compaction test shall be taken by the City or an approved engineering firm prior to setting any electrical enclosures, cabinets, or other structures. In addition, a test shall be taken on the concrete used for electrical pole bases, and pads.

#### 9.06 Access to Premises

Any properly identified representative of the City shall, at all hours, have free access to and from the premises of the Customer for the purpose of inspecting Customer's installations and electric equipment and for the purpose of reading, repairing, testing, or removing the City's meter or its other property. When, as declared by the Public Power Director, emergency conditions exist with respect to City's service, City's representative shall have immediate and free access to Customer's premises.

#### 9.07 Electrical Plan Drawings

Brigham City Public Power shall design the electrical system and provide approved electrical plan drawings. Requests for any changes to these drawings can be made by contacting Brigham City Public Power with a proposal. Approved electrical drawings must be initialed by an approved electrical division supervisor and signed by Brigham City Public Power to be valid for construction of the electrical system improvements. Photocopies of approved drawings will not be considered valid. Revisions, if needed, must also include the date the revision was approved.

#### 9.08 Electrical Box Clearance

All electrical boxes shall have 12 feet clearance to the front and 3 feet clearance to the back and on either side. Secondary pedestals shall only require 3 feet of clearance on all sides. Switchgears shall have 12 feet clearance in front of the doors and 3 feet of clearance on the sides. Meters, metering cabinets & enclosures, service disconnect cabinets & enclosures, & CT cabinets, shall have a minimum of 8 feet of clearance in front of said cabinets & enclosures. All electrical sectionalizers, transformers, switchgear, etc. shall have a clear and level working space around them. The area shall be backfilled and leveled a minimum of 12 feet in all directions from the respective electrical device.

Meters, meter cabinets, services and related electrical cabinets shall not be enclosed by carports, sheds, out buildings, additions or remodels or other such buildings. Brigham City Public Power shall have ready access to such equipment for safety & maintenance. The City reserves the right to

disconnect the City electrical service to meter bases, services, etc. if in the opinion of the City the service is inaccessible or unsafe until the service & safety issues are resolved to the City's satisfaction. This may include, but is not limited to relocating the service, or upgrading the service to meet current City codes.

9.09 Overhead Electrical Power Line Clearances (Refer to Sheet E21)

As set forth in Section 54-8c-1 through Section 54-8c-7 of the Utah Code, no person or thing may be brought within 15 feet of any high voltage overhead power line unless:

The responsible party has notified Brigham City Public Power of the intended activity; and

The responsible party and Brigham City Public Power have completed mutually satisfactory safety precautions for the activity; and

The responsible party has made prior arrangements to pay Brigham City Public Power for the mutually satisfactory safety precautions (if applicable).

No building, dwelling, sign, bridge, antennae, or structure shall be constructed, or placed underneath any overhead electrical power lines, and shall meet current NESC/NEC and City clearance requirements, both vertically and horizontally, from said power lines. Variances shall only be allowed at the City's discretion.

If existing buildings or structures exist under power lines, those same buildings or structures shall not be modified, remodeled or constructed to further encroach upon the clearances from said power lines.

In general, for overhead high voltage open supply conductors operating from 750 volts to 22,000 volts nominal, the space extending from grade level to the height of the conductor vertically and 15 feet horizontally from the further most outside conductor from the pole shall be kept clear from the power lines. Furthermore, for overhead high voltage open supply conductors operating from 22,001 volts to 138,000 volts nominal, the space extending from grade level to the height of the conductor vertically, and 30 feet horizontally from the further most outside conductor from the pole shall be kept clear from the power lines. Open water, swimming pools, combustible materials or hazardous locations may have additional clearances required.

Additional clearances may be required depending on the installation or application.

## SECTION 10 VOLTAGE AND ENERGY REGULATION (Refer to E19)

## 10.01 Available Voltages

## Standard Electrical Services

Residential	Commercial and Industrial
1 Phase	3 Phase
3 Wire	4 Wire
120/240 Volts	208Y/120 or 480Y/277 Volts

Developers must contact the Public Power Director regarding the availability of other service options.

The Public Power Director reserves the right to deny a customer 3-phase service if the Public Power Director determines that single-phase service will adequately supply Customer's load requirements. The Public Power Director reserves the right to deny a customer single phase service if the Public Power Director determines 3-phase service is in the best interest and beneficial to the City's electrical system.

## 10.02 Phase Service

3 phase service may, at the City's option, be furnished where 3 phase facilities of adequate capacity are already installed immediately adjacent to the point where service is to be delivered to Customer, or where, as determined by the City, it is economically feasible to extend such 3 phase facilities.

The City reserves the right to refuse to extend or install 3 phase facilities to serve motors individually rated at 20 HP or less and to furnish only single-phase service for such motors. In such an event, Customer may elect to install single- phase to 3 phase conversion equipment to operate 3 phase motors.

## 10.03 Power Factor Correction

The City reserves the right to require the Customer to install power factor corrective equipment. This equipment shall maintain the power factor on all of Customers electric power meters to not less than 95% lagging at all times.

#### 10.04 Load Control

The Public Power Director reserves the right to require developers to install equipment to limit load and reduce voltage fluctuations.

#### 10.05 Voltage Control

Where Customer installs power factor corrective equipment, the City reserves the right to require Customer to install controls and equipment to prevent voltage, frequency, and/or harmonics problems that may be detrimental to other Customers or the City.

#### 10.06 Fluctuating Load Limitations

Where large fluctuating single-phase loads, such as spot welders, are involved, the City reserves the right to require such loads to be supplied by means of a 3 phase to a single-phase converter or other similar equipment. All conversion equipment shall be installed, owned, operated and maintained by the Customer.

In the event a separate service or transformer installation or additional transformer capacity is required to adequately serve fluctuating loads (such as X-ray equipment, welders, etc.). Such equipment costs and installations shall be the responsibility of the Customer.

#### 10.07 Penalties

If, such voltage control equipment is not installed by Customer, Customer may be required to pay a power factor penalty and/or all electric service shall be subject to disconnection as provided by Title 50 of the Brigham City Public Power Municipal Code. Customer's wiring used to supply such fluctuating loads shall be installed in a continuous run of rigid conduit and cable as approved by the City.

### SECTION 11 MATERIALS

#### 11.01 Materials

Only electrical grade materials and apparatus shall be used. The materials and apparatus shall be UL Listed and designed for their purpose.

#### 11.02 Conduit

All conduits shall be electrical grade conduit. Conduit shall be Schedule 40 PVC unless otherwise specified by the Public Power Director. Electrical grade Schedule 40 fiberglass and/or PVC conduit shall be used under collector and arterial streets and for all sweeps. Fiberglass conduits shall not be used for riser poles. All conduits extending out of the ground outside of an enclosure shall be rigid metal and the elbows attaching to those risers shall be either rigid metal or fiberglass. All conduits entering any cabinet,

enclosure, vault, or ground sleeve shall have end bells attached to the ends of conduits to protect wire from damage. All buried metal conduit shall be coated with anti-corrosion tape. Tape shall be a minimum of 2 inches wide. Tape shall extend 6 inches above finished grade.

#### 11.03 Enclosures (Refer to Sheets E5-E9 and Sheets E12-E14)

All enclosures, including primary and secondary junction boxes, shall be level. Opening mechanisms and locking devices on all transformer equipment shall be 4 to 6 inches above final grade. Opening mechanisms and locking devices on all primary sectionalizers, switchgear and secondary junction boxes shall be 10 inches above final grade. Only approved enclosures, pads, and vaults shall be used.

#### 11.04 Soils & Compaction (Refer to Sheet E10)

All soils under enclosures shall be approved road base and be compacted to 95% of dry density. The compaction area must extend at least 1 foot past the enclosure in all directions and be a minimum of 1 foot in depth under the enclosure. A compaction test shall be required before any enclosure, box, sleeve, or pad is set into place. The compaction test shall be taken by the City or by the City's approved engineering firm. If ground sleeves or pads settle, Developer shall be required to re-level to the above specifications. If primary enclosures or transformers settle after being energized, the City shall re-level the equipment at the Developer's expense.

### SECTION 12 INSTALLATION (Refer to Sheets E5 – E9 and Sheets E12-E14)

#### 12.01 General

All electrical facilities shall be installed under the supervision of a licensed electrical contractor or journeyman lineman. **A certified journeyman electrician or lineman shall be on site during all conduit installation, cable pulling and connecting of electrical wiring.** All electrical installation & equipment shall be installed in a neat and workmanlike manner.

Curb & gutter shall be installed before excavation of electrical trenches. The curb should have property corners pinned in the top of the curb by approved methods. The curb will give reference for proper conduit depths & locations, and proper placement of electrical and communications boxes. Developer required to notify communication company and give up to 1 week to install communication lines. Open trench will be backfilled up to communication lift during waiting period.

Contractor shall construct all electrical facilities in a development except for the following which shall be completed by the Utility:

1. Pulling high voltage underground cable.
2. Installing high voltage cable terminations.

3. Setting transformers and switch gears (contractor shall furnish & install sectionalizers).
4. Secondary connections shall be connected in transformers (exception: contractors shall connect secondary connectors in 3 phase transformers);

All overhead facilities, including extension of risers as shown in the standard drawings. (Refer to Sheet E20)

12.02 Underground Lines

All new facilities shall be constructed underground unless otherwise authorized by the City. Existing buildings & facilities that have a change of use, or extensive remodeling, may, at the Public Power Director’s discretion, be required to install underground power lines. No overhead power will be allowed unless required or approved by the Utility.

12.03 Conduit Depths

High voltage (12.47kV) primary conduits shall always be installed below secondary (600 volts or less) conduits & communications conduits if installed in a joint trench application. No primary high voltage conduits shall be installed at less than 4 feet in depth to top of conduits unless otherwise approved.

In general, the following table of depths shall be used for electrical conduit: (Note: depths are to the top of conduits)

Table 12.03.A  
Electrical Conduit Depths

Conduit Size	Depth to Top of Conduit
1” Street Light	2 Feet
2” Secondary	2 Feet
3” & 4” Secondary	2 Feet
4” Primary	4 Feet
6” Primary	4 Feet*

\*Depths may increase depending upon application.

12.04 Pull Strings

All primary conduits shall have 1,350 lb. mule tape in the conduit securely tied off in each pad or enclosure.

12.05 Identification Tape and Stub Markers

All conduits shall have a caution tape buried 12 inches below grade directly above conduit. Tape shall meet the requirements and specifications of APWA

23 20. The end of each stubbed conduit, including service laterals, shall be marked to the surface according to the standard drawings.

12.06 Underground Metal Conduit

If underground metal conduit were allowed, all buried metal conduit shall be coated with anti-corrosion protective tape. Tape shall extend 6 inches above finished grade.

12.07 Road Crossings

Conduit shall be schedule 80 gray PVC or rigid fiberglass conduit. Shadow conduit shall be installed at road crossings at Public Power Director's discretion.

12.08 Berms, Slopes, and Hillside Conditions

For installation instructions around berms, slopes, and hillsides contact Brigham City Public Power.

12.09 Labels

A label shall be securely taped to the end of each conduit run where it emerges into any cabinet or enclosure. The label shall indicate whether the conduit run is primary or secondary and the direction & footage of conduit.

SECTION 13 SYSTEM REQUIREMENTS

13.01 Additional Capacity Requirements

In the event a Customer makes application for additional capacity, subject to provisions of the applicable rate schedule, Customer shall install the necessary transformer capacity, service wires and other equipment required to adequately serve Customer's requirements. Customer will be required to submit a Brigham City Load Sheet to be completed by electrical engineer, architect, or master electrician. Report shall include all existing and future load.

Customer shall be required to participate in system load study to ensure needed capacity is available through City's transmission system. Customer shall be responsible for all costs associated with said study.

All applications for service involving the furnishing of additional capacity or equipment by the City may be required of the Customer. The application shall state that any service entrance wiring and main switches required for the utilization of such additional capacity to be furnished by Customer, shall be considered as permanent fixtures belonging to the property being served and property except for replacement or enlargement if necessary.

### 13.02 Substations

Substation may be required of Customer. The City reserves the right, where unusual substation capacity or voltage is involved, to require the Customer to install the necessary complete substation as provided for in City's rate schedule.

Where the Customer furnished the necessary complete substation equipment to take service at primary service voltage, such equipment shall be owned and maintained by the Customer and shall include the necessary transformers, structure, controls, and protective equipment, and shall be of such quality and construction as meets City approval. Customer shall supply main transmission breaker to City for ownership and operation providing interconnection to transmission system. Operation of said breaker will be controlled by the city.

## SECTION 14 SERVICES

### 14.01 Point of Service

The Public Power Director determines the point of delivery for all developments. Public Power Director reserves the right to meter service at either primary or secondary voltage. For large or unusual loads, Public Power Director reserves the right to require Customer to take service at primary voltage and to require Customer to furnish the necessary complete substation equipment. The Public Power Director will decide if multiple buildings, business and residential, or portions of buildings will be metered from one or from multiple metering points. Each building or structure served shall be supplied by only one service. Multiple services are only allowed at the Public Power Director's discretion.

### 14.02 Service Entrance Requirements

The service entrance shall be defined as the facilities that consist of approved service entrance conduit and cable enclosing conductors and apparatuses. Said conductors shall extend from the point of contact with the City's secondary point of service and thence to and include Customer's service entrance safety switch or disconnection means.

Customer shall install all conduit and wire from the building to the pole or transformer according to the City standards.

1. Service Entrance Safety Switch or Main Disconnect for new construction and remodel. A residential service safety switch shall be an exterior service combination meter base and main disconnect device. For commercial & industrial installations a service safety switch shall be an exterior service main disconnect device or devices, which will always

remain accessible. This device shall be a main breaker, but minimum requirement shall be a safety switch, which will disconnect all service power from the premise wiring to the entire facility. The location of the main disconnecting device shall be approved by the City.

2. Identification. (Current NEC) Where a building or structure is supplied by more than one service, or any combination of branch circuits, feeders, and services, a permanent plaque or directory shall be installed at each service disconnect location denoting all other services, feeders, and branch circuits supplying that building or structure and the area served by each.
3. Service Entrance Conductors. All service entrance conductors and any conduit enclosure shall be continuous, unbroken, and completely exposed for external inspection throughout their entire length, extending from said point of contact with City's service wires to the meter socket (or meter cabinet if installed) and thence to Customer's service entry safety switch or main disconnecting means. Service entrance conductor type & size shall meet current NEC, NESC, and City Standards. Brigham City Public Power reserves the right to make an allowance as needed.

Underground service lateral conductors from the City's Secondary service point up to the line side of the main disconnecting means shall be installed, maintained, and owned by the Customer. The City assumes no liability for replacement of secondary service lateral conductors.

14.03 Underground Residential Service Requirements (Refer to Sheets E2 and E15)

14.03.1 Conductor,\* conduit sizes, & conduit depths

Refer to following table:

Service Size	Service Conductor Size (AWG)	Conduit Size	Conduit Depth
100 amp	2/0 alum.	3"	2'
125 amp	2/0 alum.	3"	2'
150 amp	2/0 alum.	3"	2'
200 amp	2/0 alum.	3"	2'
201-400 amps	Contact Brigham City Public Power	Contact Brigham City Public Power	Contact Brigham City Public Power

\*Table 14.03.1.A Note: The current National Electric Code may supersede these conductor sizes based upon service size. Refer to current NEC for service conductor sizes for other types of conductors & installations.

- 14.03.2 Conduit (Refer to Sheet E11)
- Only continuous factory lengths of conduit shall be used. Conduit may be cut or spliced; however the couplers & bends shall not exceed a 360-degree pull on the overall length of the conduit run. Conduit shall be installed in a neat and workman-line manner. All service lateral conduits shall be inspected prior to backfilling.
- 14.03.3 Materials
- Only electrical grade materials shall be used. Rigid metal conduits (RMC), schedule 40 fiberglass and schedule 40 PVC shall be used for any elbows or bends 45 degrees or greater. RMC shall be coated with an anti-corrosion tape below grade and tape shall extend 6 inches above finished grade. RMC shall be used for all above grade service entrance conduits. Customer shall provide and install service wire from house to junction box, transformer or pole according to City standard drawings. Service wire type shall be approved by Brigham City Public Power.
- 14.03.4 Trenching
- Service lateral trenches shall be 24 inches in depth. Trenches shall be as straight as possible from the secondary service point to the Customer disconnect or meter base. The bottom of the trench shall be as level as possible and free from rocks & debris. Backfill placed directly on conduits shall be free from large rocks.
- 14.03.5 Service Entrance Conduits Support and Attachments
- Service Entrance conduits shall be securely attached to the foundation of house or building by means of unistrut, concrete anchors, and unistrut type clamps. Unistrut shall be securely attached to foundation by a minimum 3/8 inches x 3 inches concrete anchors. Unistrut shall typically be 24 inches. Service entrance conduits shall be one continuous, unbroken conduit from the elbow to the point of attachment at the meter base hub.
- 14.03.6 Location(s)
- Note: Refer to 15.02 Metering for additional requirements. Meter/main disconnect shall be located within the front 6 feet of the side of a residential dwelling. Meter/main disconnect shall always be accessible. Meter/main disconnect shall be kept a minimum of 36 inches from any natural gas meters, window wells, windows, doors, stairs and any material deemed

to be combustible or hazardous. For remodels, service upgrades, building additions or other instances or applications affecting the existing electrical service, **CT cabinet**, meter base, meter and disconnect contact the Brigham City Public Power for requirements. Brigham City Public Power will require a meter main disconnect to be installed anytime electrical upgrade work is performed on the residence. The service, meter, meter base, or disconnect may be required to be relocated to meet current Standards and Codes. Meter/main disconnect shall meet all applicable NEC and NESC codes. The Public Power Director reserves the right to accept or reject any locations of meter base/main disconnects.

#### 14.03.7 Temporary Underground Service (Refer to Sheet E18)

For temporary service furnished to individual small single-phase loads, such as house trailers, small construction projects (such as house and small buildings, portable tools, etc.) City will install a standard temporary service drop, at Customer's expense. City's General Service Rate shall apply.

Where the temporary service installation requires additional facilities more than the previously mentioned standard service drop (such as an extension of the City's primary line), such installation will be at the Customers' expense.

#### 14.04 Overhead Residential Service Requirements (Refer to Sheet E3)

##### 14.04.1 General

Overhead services shall also include mast knob and service grips. Wiring shall meet load and installation requirements as indicated in the NESC/NEC.

##### 14.04.2 Service Drop Support and Attachments

For one story buildings, or where conditions will not permit proper ground clearance to be maintained by City's service wires, Customer shall install, at Customer's expense, suitable conduit or service entrance mast pipe or other structure or support that will properly support the City's service drop conductors and to maintain the minimum ground clearance as required by the NESC/NEC. If clearances cannot be met, the service may be required to be relocated or otherwise rerouted underground.

##### 14.04.3 Service Entrance Weather head Clearance

The service entrance weather head shall be located to meet or to exceed NESC/NEC clearance from readily accessible

windows, doors, or porches. The weather head must also be located so that when the service drop conductors are attached to the building structure or other service drop support, adequate clearance will be maintained away from telephone or other wires, windows, awnings, drainpipes, chimneys, or other obstructions.

#### 14.04.4 Service Entrance Mast Pipe

This installation shall be made by Customer, at his/her expense, and shall conform to City's specifications. The service entrance mast pipe shall be of electrical grade galvanized rigid steel of not less than 2 inches inside diameter and shall be attached to the wall of the building by means of an adequate number of approved fastening devices. All service conduits shall be 2 inches in diameter, or larger.

The mast pipe and/or conduit shall be continuous, extending from the service entrance weather head located at the top of the mast pipe to Customer's meter socket base.

The service entrance mast pipe shall extend above the roof surface (through weatherproof roof flashing) so that the point of attachment of City's service wires to the mast pipe will be not less than 18 inches above said roof line, and not to exceed 36 inches without guy support to structural frame plus such additional height as is necessary so that the point of attachment of City's service wires will maintain minimum ground clearance, specified in the NESC/NEC.

#### 14.04.5 Service Drop Attachments to Buildings

The Customer will furnish and the city will install the necessary attachment brackets and apparatuses to attach City's service wires to Customer's service drop termination facilities.

The City further reserves the right to require that the installation of the necessary mast pipe or equivalent facilities required supporting city's service wires, be made by Customer during the course of building construction.

Where the exterior of buildings is finished with brick facing, concrete, plastered metal lathe, sheet iron, stucco, tile or similar material, suitable facilities of adequate strength to hold City's wires and attachments, shall be installed by Customer at Customer's expense.

- 14.04.6      Service Drop Conductor Ground Clearance
- The service drop conductors must be located at such height as will enable adequate clearance to be maintained through the entire service drop length. The minimum ground clearance shall be as specified by the NESC/NEC, but not less than 12 feet over driveways not subject to truck traffic; 16 feet over commercial areas, parking lots and other areas subject to truck traffic; and 22 feet over public streets, alleys and roads. The final height attachment determination shall take into consideration conductor sag due to weather fluctuations & lengths of spans.
- 14.04.7      Service Entrance Conductor Specifications
- The service entrance conductors may be either copper or aluminum, and shall be continuous without any joints, splices or connections, extending from the point of connection with service drop conductors to the termination of same at the meter socket or meter cabinet and thence same shall continue without joints, etc., to Customer's service entrance safety switch.
- The Customer shall have electrical Contractor provide at the service entrance weather head, sufficient excess service entrance conductor length or "tails" (18 inch minimum) so that the City can connect directly to the service drop conductors. The service entrance installation shall conform in every respect to City's specifications, as to conductor connectors, and the method of making connections and all other related matters involved.
- The service entrance conductor size for the ampere load to be carried shall be based on a maximum conductor operating temperature of 75°C (type RH, RHW, XHHW, or equivalent.)  
Note: Refer to Table 14.03.1.A regarding service conduit & conductor sizes.
- 14.04.8      Main Breaker or Disconnect
- The entrance safety switch or main breaker ampacity shall not be less than the rated ampacity of the service conductors. Other specifications, including conductors, shall conform to the latest edition of the NEC.
- Upon special application, City may permit 2 or 3 wire service entrance installations of less than 100 ampere capacity for signs, etc., where the load requirements, as determined by

City, justify the same. In no event will 2 wire service be furnished except at city's option.

14.04.9 Temporary Service Drops (Refer to Sheet E18)

For temporary service furnished to individual small single-phase loads, such as house trailers, small construction projects (such as house and small buildings, portable tools, etc.) City will install a standard temporary service drop, at Customer's expense. City's General Service Rate shall apply.

Where the temporary service installation requires additional facilities more than the previously mentioned standard service drop (such as an extension of the city's primary line), such installation will be at the Customers' expense.

14.04.10 Service to Mobile Homes and Trailer Courts through one meter

For service to trailer courts where more than 1 dwelling unit, mobile home, or trailer exists, the campus shall be supplied through 1 meter and the furnishing of such service shall be provided and installed by the facility owner.

14.04.11 Load to be Balanced on Circuits

The Customer shall use reasonable care in designing electric wiring and circuits; also, the connection of the loads to the circuits, so that the loads on the individual phases and circuits of City's service are properly balanced at all times.

14.04.12 Temporary Service to be Installed on Customer's Pole

All such temporary service drops shall be supported on a pole or post as approved by the Public Power Director and shall be installed by Customer at his/her expense.

14.05 Underground Service Requirements for Multi-Family Dwelling Units

14.05.1 General

Service lateral conduits from the City's point of secondary service shall be 4 inches minimum for multi-family dwelling units. A load calculation study shall be performed for multi-family dwellings units and submitted to Brigham City Public Power. All other residential service requirements apply.

14.06 Underground Service Requirements for Commercial & Industrial Applications

14.06.1 General

Service entrance conductors & conduits shall be sized according to applicable NEC and NESC codes. The City shall

approve all locations & installations of conduits, service disconnection means, and meters.

- a. All commercial & industrial buildings shall have an accessible, exterior main disconnecting means that is capable of disconnecting (opening) all service entrance conductors from the building or structure premises wiring.
- b. All services rated 801 amps or more supplied by a 4-wire three phase 480Y/277 volt connected system shall have a ground fault test performed for protection of equipment.
- c. All services, equipment, cabinets, conduits, etc. shall be grounded & bonded according to applicable NEC & City codes.
- d. The service disconnecting means shall be identified as suitable for use as service equipment.
- e. A building or structure may only be served by one service lateral or service drop, unless otherwise approved by Brigham City Public Power.
- f. There shall not be more than 6 service disconnects for each service. Each service disconnect shall be permanently marked to identify it as part of the service disconnecting means. All service disconnecting means for each service shall be grouped together.
- g. The center of the operating handle of switch or breaker, when in its highest position, shall not be more than 5 feet and not less than 4 feet above finished grade.

#### 14.06.2 Materials

Only electrical grade & UL listed materials shall be used. Rigid metal conduits (RMC), schedule 40 fiberglass and schedule 40 PVC shall be used for any elbows or bends 45 degrees or greater. RMC shall be coated with an anti-corrosion tape below grade and tape shall extend 6 inches above finished grade. RMC shall be used for all above grade service entrance conduits. Customer shall provide service wire from building to utility transformer or pole. All electrical equipment, cabinets, panels, etc. shall be UL listed and approved for the installation.

#### 14.06.3 Trenching

Service lateral trenches shall be 2 feet in depth. Trenches shall be as straight as possible from the secondary service point to the Customer disconnect or meter base. The bottom of the trench shall be as level as possible and free from large rocks & debris

- 14.06.4      Service Entrance Conduits Support and Attachments
- Service Entrance conduits shall be securely attached to the foundation of building by means of unistrut concrete anchors, unistrut type clamps or other approved methods. Unistrut shall be securely attached to the foundation by a minimum 3/8 inches x 3 inches concrete anchors. Service entrance conduits shall be one continuous, unbroken conduit from the elbow to the point of attachment at the meter base, CT cabinet, or main disconnect cabinet. Service lateral conduits shall be installed at a depth of 2 feet to top of conduits. All installations shall be installed in a neat and workman-like manner.
- 14.06.5      Locations
- Locations of service lateral conduits shall be approved by the Public Power Director. Locations of outside main disconnecting equipment shall be approved by the Public Power Director. Meter/main disconnect shall always be accessible. Meter/main disconnect shall be kept a minimum of 36 inches away from any natural gas meters, window wells, windows, doors, stairs and any material deemed to be combustible. Meter/main disconnect shall meet all applicable NEC and NESC codes. The Public Power Director reserves the right to accept or reject any locations of meter base main disconnects. If the Public Power Director determines the service location is inaccessible or otherwise unsafe, the Customer shall relocate or upgrade service to City standards at Customer's expense. The Public Power Director further reserves the right to disconnect electrical power to the Customer's service until the service is brought into compliance.
- 14.06.6      Ownership of Conductors
- For commercial underground installations the secondary service conductors and conduit paths shall be owned & maintained by the Customer from the secondary connections inside the transformer up to the termination point of the service disconnect. For commercial overhead installations the secondary service conductors shall be owned & maintained up to the overhead secondary connection point. City shall own the overhead drop up to the connections at the service mast.
- 14.06.7      Energizing Development
- Developments may be energized when the following is completed and accepted by the city.

1. Curb, gutter and an all-weather road surface.
2. Electric conduit.
3. Electrical boxes and proper access to the boxes.
4. Secondary wiring, except that required for street lighting.

## SECTION 15 METERING (Refer to Sheet E22)

### 15.01 General

The city will furnish and install all electric revenue meters. Normally outdoor socket-mounted meters will be used by the city whenever practical. The meter base will be furnished and installed by Customer's electrical contractor for all normal residential installations. The meter base with test switch shall be provided by the City and installed by Customer's electrical contractor for commercial or industrial applications.

If instrument transformers are required, the City reserves the right to require customers to furnish and install a suitable steel cabinet to house City's instrument transformers and accessories. Said cabinet shall contain only the City's metering equipment and shall be equipped so that it can be sealed and locked by the City. The City shall have sole access to this cabinet.

### 15.02 Location

The City shall approve the location of service entrance and meter. The following conditions must be met for the location of all meters & services:

1. Visibility. All entrance wiring connections shall not be concealed and shall always be in plain view for inspection by the City.
2. Residential properties shall have the point of service externally installed on the primary residence of the property. If a residential property needs multiple services the amount of services must be approved by the City and be contained in one location inside one meter base that is located on the exterior of the primary residence. Any variation of this may be approved by the Public Power Director.
3. Industrial/Commercial businesses are allowed to have up to two points of service with multiple meters at each location. If more than two points of service are required due to the original design of the property or the property is expanded, then the campus will be required to install a primary metering cabinet. Electrical service to the property will be delivered at the City's distribution voltage. The location of the primary metering cabinet will be determined by the city. The City will maintain ownership and control of the metering cabinet but all conductors feeding out of the metering cabinet will be owned and maintained by the property owner.

4. A property that is undergoing renovation and has pulled a building permit or new construction will be required to relocate the electrical meter and main disconnect point (MDP) of the building to the outside of the building. The metering equipment and MDP shall be mounted to the building if under 801 amps. If service is 801 amps or greater than a freestanding MDP switchgear cabinet will be required. The MDP switchgear cabinet will need to be approved by the Public Power Director before equipment order is placed by the contractor.
5. Protection. No meter or service equipment shall be installed in any location where it may be unnecessarily exposed to heat, cold, dampness or other cause of damage, or in any unduly dirty or inaccessible location.
6. Height. The meter socket shall be mounted at a height of not less than 4½ feet, no more than 6 feet above finished grade, as the case may be. Where multiple meters are installed, care shall be taken to ensure the lowest meter is no less than 4 ½ feet and no higher than 6 feet from finished grade.

When a combination 3 phase and single-phase service is supplied to the same premises, all meters and service entrance switches shall be at the same location.

#### 15.03 Meter Base

Residential meter bases shall be furnished and installed by the Contractor according to City standard drawings. No smaller than a 100-amp service entrance will be accepted other than by approval from the Public Power Director. The meter base shall always be kept sealed and under the control of the City.

#### 15.04 Commercial Meters

Single-phase and three-phase self-contained meter bases shall be installed by the Developer and shall have bypass capability in the meter base. For details and specific information regarding this requirement, please contact Brigham City Public Power. For services rated 200 amps up to 800 amps, the Brigham City Public Power will supply the meter base & test switch for contractor to install at Customer's expense. No smaller than a 200-amp 3 phase service entrance will be accepted unless otherwise approved by the Public Power Director. For services rated over 800 amps, a manufacturer's shop drawing of the MDP switchgear cabinet with main disconnect and adequate metering provisions will need to be provided for approval. Contact Brigham City Public Power for specific requirements and submission details.

The Contractor's portion shall be completely installed, inspected, and the electrical hook-up fee paid before the City will complete the final electrical hookup.

#### 15.05 Location of Multiple Meters

Where more than one meter is required for a building, such as an apartment complex, all meter sockets shall be located side by side at an outside location as determined by the Public Power Director.

#### 15.06 Meter Location Regarding Remodeling

When remodeling, where 2 or more houses or dwelling units are combined to form one building, the meter socket shall be moved to a single location. Meter and service locations shall first be approved by Brigham City Public Power. Existing meters and services may require relocation to meet current City standards. In all remodeling where the meter is changed or moved, or wiring changes made, outdoor meter sockets and an approved new service entrance shall be installed by Customer at Customer's expense.

#### 15.07 Meter Accessibility

In the event a structural change is made by the owner that results, in the opinion of the Public Power Director, to be an undesirable meter location, the meter socket, meter cabinet, and/or service entrance installation shall be moved by the Customer at his/her expense to an accessible location as determined by the City.

Whenever the construction of a building on an adjacent lot prevents proper access to any meter, or access to the point of attachment of service drop conductors, or results in inadequate service drop clearance, the Customer shall move, at Customer's expense, the meter socket and service entrance to a location that is acceptable to City. The meter shall not be enclosed by any portion of a building. The meter shall not be placed under carports or enclosed by sheds, garages, outbuildings or other buildings. The meter shall always remain readily accessible to the City.

#### 15.08 Outdoor Meters for Non-Residential General Service

All single-phase meters installed for non-residential use shall be socket type. The meter base shall have bypass links installed. The meter socket shall be furnished and installed by Customer at Customer's expense.

#### 15.09 Instrument Transformer for Metering

In all outdoor installations requiring current transformers, whether single phase or 3 phase, the Customer shall provide an approved meter loop for meter connections. The City shall furnish any instrument transformers, meter bases, or other devices required, to properly meter the Customer's electrical needs at the Customer's expense. Such instrument transformers and devices shall be installed by the City.

#### 15.10 Current Transformer Cabinet (Refer to Sheet E19)

Any cabinets required to house said instrument transformers and accessory equipment shall be furnished and installed by Customer at Customer's expense. This requirement applies to all installations. All cabinets shall be approved by the City.

Such metering or instrument cabinets are for the exclusive use of City, and shall always be under the control of, and kept sealed by City.

#### 15.11 Unacceptable Meter Locations

For reasons of public safety, maintenance of service equipment, and reliability of metering, meters shall not be installed in any of the following locations:

1. Inside any building, unless located within an acceptable meter room.
2. In any location that is not readily accessible.
3. Directly over any stairway, ramp or steps.
4. In any substation or transformer vault.
5. Accessible only by a trap door or in any location which may be hazardous to personnel.
6. On any surface subject to excessive vibration.
7. In or accessed through any rest, bath, shower, powder, or toilet room.
8. In any elevated area.
9. In any location not providing a clear and continuously unobstructed working space extending a minimum of eight (8) feet from the face of the meter panel and having a width to permit ready access to the complete metering installation.
10. In any location where moisture, fumes, or dust may interfere with the operation of the meter or damage it.
11. In any location giving less than three feet clearance to any property line, or with less than three feet clearance to any sidewalk, alley or driveway giving access to non-residential or industrial property.
12. In any basement or depressed area.
13. Within carport or patio areas which are or can become enclosed, when served overhead or underground.
14. Mounted on BCPP poles.
15. In a room containing mechanical equipment.
16. In any elevator shaft or hatchway.
17. Mounted on any trees.
18. In any unsanitary areas in reference to farm animals and products.
19. In a plenum or any portion of a return or supply air ducting system.
20. Areas where entry may be restricted or controlled because of medical, health, environmental or other safety-related issues.

## SECTION 16 LIGHTING AND SIGNAL POLES (Refer to Sheets E16-E17)

## 16.01 General

The City shall provide the street light poles, fixtures & associated parts to install the streetlights. The contractor is responsible for transport of the streetlights from the Public Power Department to their respective developments. Furthermore, the contractor shall be responsible for pouring the concrete bases, assembling and erecting the streetlights.

All local streets, minor & major collectors, and arterial streets shall have the decorative streetlight as shown in the standard drawings or as designed. 25-foot steel galvanized poles with a 6-foot arm, and either a 100-watt or a 250-watt equivalent LED cobra head type fixture may be used or substituted for a decorative type pole & fixture at the City's discretion. All fixture types will be of the Luminaire type with 90-degree cutoff lens.

All traffic signal poles shall be powder coated black.

## 16.02 Dark Sky

All street and parking lot lighting shall meet the IDA (International Dark-Sky Association) recommendation and City ordinance for dark sky compliance. This will require that all lighting, streetlight, parking lot lighting, walkway lighting, etc., cannot broadcast light above 180° from the parallel ground surface. It is advised that all lighting on buildings, such as security lighting, also meets this requirement.

## 16.03 Location

In general, streetlights will be installed at all intersections except where a four-way intersection has an offset of less than 100 feet from another intersection. Streetlights shall be installed on the top of all traffic signal poles. Streetlights for local streets will be installed with a maximum spacing of 400 feet between lights. All mid-block streetlights shall be installed 18 inches from a property line. Collector and arterial streets shall have lights spaced at 175 feet apart on alternating sides of the street. In addition to the typical location design and layout, street light locations may also be designed by Brigham City Public Power. Commercial right-of-way lighting needs to be staggered 125 feet with a maximum of 250 feet of spacing on each side of the ROW.

Each streetlight will be installed so that the street light pole is centered in the planter strip or within 18 inches of the sidewalk if no planter strip exists.

## 16.04 Orientation

Streetlights at intersections of local streets shall aim at the center of the intersection. On collector or arterial streets streetlights shall be set at a 90-degree angle at regular intervals determined by the City.

16.05 Grounding & Bonding

A bonding wire shall be connected from the rebar “Ufer” rings in the concrete pole base to the street light pole grounding/bonding screw or termination point using NEC approved methods and a separate grounding wire will be installed from the pole to the closest secondary pedestal or transformer. The grounding conductor shall be terminated with the neutral conductor.

16.06 Wiring & Fusing

A 10-amp in-line fuse & fuse holder shall be installed in the junction box on the 120/240-volt ungrounded conductors.

---

## VEGETATION MANAGEMENT

### SECTION 17 VEGETATION MANAGEMENT

#### 17.01 Overview

When feasible, BCPP prioritizes the removal of tall-growing trees and vegetation to prevent future conflicts with overhead power lines, while supporting the establishment of low-growing species that will never interfere with the high-voltage lines. Considering the interests of property owners and other land use objectives, it is not always possible to remove incompatible trees.

Tall-growing trees that cannot be removed must be pruned to maintain clearance around power lines through use of arboriculturally sound pruning practices.

#### 17.02 Professionalism

In accordance with ANSI Z133, all personnel working in proximity to overhead conductors at any time are required to hold one of the following designations: Qualified Line Clearance Arborist or Qualified Line Clearance Arborist Trainee.

#### 17.03 Safety

The safety of workers and the public should always be given the highest priority. Federal and state requirements governing vegetation management activities shall always be followed, including all OSHA requirements. ANSI Z133 (2107 or most current) and OSHA 1910.269 are examples of these requirements. Activities shall be conducted to minimize tree crew and public safety risks.

Table 17.03.A Minimum approach distances for Qualified Line Clearance Arborists and Qualified Line Clearance Arborist Trainees.

Voltage (kV) (Phase-to-Phase)	Minimum Approach Distance Sea Level to 5,000 ft.	Minimum Approach Distance 5,000 to 10,000 ft.	Minimum Approach Distance 10,000 to 14,000 ft.	Source*
0.05-0.300	Avoid contact	Avoid contact	Avoid contact	APM/Z133
0.301-0.750	1' - 6"	1' - 7"	1' - 7"	APM/Z133
0.751-15.0	2' - 6"	2' - 7"	2' - 10"	APM/Z133
15.1-46.0	3' - 6"	3' - 7"	3' - 8"	APM/Z133
46.1-72.5	3' - 6"	4' - 0"	4' - 4"	Z133
72.0-121.0	3' - 11"	4' - 6"	4' - 10"	Z133
121.1-145.0	4' - 6"	5' - 2"	5' - 7"	Z133
145.1-169.0	5' - 1"	5' - 9"	6' - 3"	Z133
169.1-242.0	7' - 0"	7' - 11"	8' - 7"	Z133
242.1-362.0	11' - 9"	13' - 6"	14' - 7"	Z133
362.1-420.0	14' - 8"	16' - 9"	18' - 2"	Z133
420.1-550.0	17' - 6"	20' - 0"	21' - 8"	Z133
550.1-800.0	23' - 9"	27' - 2"	29' - 5"	Z133

#### 17.04 Fire Protection

Federal, state, and local fire protection laws and regulations shall be followed, and the Tree Crew Foreman performing the work must obtain necessary work permits. Crews shall have all fire suppression tools and equipment required by the governmental agency responsible. Tree Crew Foreman shall also adhere to fire restrictions concerning work hours, fire watch following work, and other policies of the pertinent jurisdiction. Tree Crew Foreman with crews working in fire-prone rural areas shall provide basic fire prevention and suppression training to their crews annually. Documentation of this training shall be submitted annually to the BCPP Director July 1<sup>st</sup>.

#### 17.05 Species of concerns

Vegetation maintenance shall not disturb or harm any rare, threatened, endangered, or protected plant or animal species. Nesting season work restrictions exemplify important scheduling considerations necessary to accommodate protected species. If there are rare, threatened, endangered, or protected plant or animal species present at a location where work is planned, the Tree Crew Foreman must stop work and immediately inform the BCPP Director.

#### 17.06 Bird Protection

Migratory birds are protected by the Migratory Bird Treaty Act of 1918 (16 USC 703-712) (MBTA). Most bird species are protected under the MBTA; therefore, in an abundance of caution, all bird species should be considered subject to

the law's provisions. The Tree Crew Foreman shall conduct vegetation maintenance consistent with the MBTA.

The MBTA prohibits removal of bird nests that have eggs or chicks and killing any birds which are members of any protected species. Active nests may not be disturbed unless the BCPP Director, after consultation with U.S. Wildlife Services has provided authorization. If tree crews identify a possible immediate risk (e.g., active nest in the vicinity of vegetation listed for work), the Tree Crew Foreman shall contact the BCPP Director. The Director will consult with U.S. Wildlife Services regarding whether work may proceed. If work is postponed until after young have left the nest, the location must be recorded and tracked to ensure completion at the appropriate time.

The nests of eagles threatened and endangered species, and colonial waterbird nests (such as those of herons) may not be disturbed – whether or not they are active. Eagles are subject to additional protection; it is illegal to disturb them near their nests or winter roosting sites. If large stick nests, suspected to be protected nests, are in vegetation identified for removal, the Tree Crew Foreman must contact the BCPP Director who will consult with the U.S. Wildlife Services.

Raptors (birds of prey) and herons require buffers around active nests to prevent them from being disturbed, unless instructed otherwise by U.S. Wildlife Services or applicable regulatory authority.

Table 17.06.A Work buffers around active nests of eagles, hawks, and herons.

Species	Work buffer
Bald Eagles (Jan 1-Aug 31)	660 feet
Bald Eagle roosts (Nov 1-Mar 31)	0.25 mile
Golden Eagles (Jan 1-Aug 31)	0.25 mile
Hawks (exceptions below)	600 feet
Ferruginous hawk	0.5 mile
Northern goshawk (Mar 1-Aug 31)	0.5 mile
Swainsons hawk	0.25 mile
Owls	300 feet
Great Gray Owl	0.25 mile
Northern Spotted Owl	0.25 mile
Osprey	600 feet
Herons/Colonial Nesters	600 feet
Songbirds	50 feet

In general, if a bird leaves a nest and does not return within an hour, it is being disturbed, and the buffer should be increased. In these cases, U.S.

Wildlife Services should be contacted within 24 hours to monitor the nest and respond appropriately if the adults fail to return.

Active bird nests and inactive bird nests should be reported to the BCPP Director and U.S. Wildlife Services.

#### 17.07 Tree Removal

In certain circumstances, it is necessary or appropriate to remove trees (i.e., removed the threat posed to electrical infrastructure or remove the tree from the “inventory” of future work). When a tree is removed, the stump shall be cut to within 6 inches of the ground or as close to it as practical (for example, at the top of a barbed wire fence that has become imbedded in the trunk). Stumps of all deciduous trees, brushes, and vines that are removed shall be treated with an approved herbicide, unless otherwise indicated by landowner or restricted by the land managing agency. Tree removal may be discretionary or necessitated by the presence of Hazard Trees.

##### 17.07.1 Hazard Trees

“Hazard Trees” are defined as a tree in whole or in part, that might fail, and which is identified as a likely source of harm. Trees that are dead, dying, diseased, deformed, or unstable, which have a high likelihood of falling and contacting a specific target (electrical infrastructure) should be assessed for removal. The Tree Crew Foreman shall conduct a visual assessment, consistent with ANSI A300. Hazard Trees pose a safety and reliability risk and must be removed (or pruned to the extent that the tree is no longer a Hazard Tree). BCPP reserves the right to deny chipping of any dead wood and will leave the dead wood on property for customer to clear. Federal and state agencies sometimes request that trees subject to removal be topped to create “wildlife trees.” BCPP may honor such requests, provided the safety of the tree workers or the integrity of facilities are not compromised. Any Hazard Trees removed to accommodate this request should be reduced to a height so that the tree would never contact any BCPP Facilities should it fall.

##### 17.07.2 Discretionary Tree Removal

Discretionary tree removal reduces the total tree inventory and can, therefore, reduce long-term risks to safety and reliability; improve access to facilities, clear lines of sight, and moderate future workloads. In general, removal of trees near power lines are encouraged and are to be pursued by the Tree Crew Foreman.

## 17.08 Debris Disposal

Before leaving a particular worksite, all debris must be brought to ground, with no severed limbs left in the tree canopy (hangers). Work locations shall be left in a safe and orderly condition at the end of the workday. “Debris” is cut vegetation remaining after maintenance operations.

Debris is typically disposed of in multiple ways. First, debris may be chipped using a mechanical chipper and then transported off-site. Second, debris may be chipped using a mechanical chipper and then broadcast on-site. Third, debris may be lopped into maximum lengths of 3 feet and scattered (if necessary to pile debris, piles shall be no more than 18 inches high). The appropriate method of disposal depends on the area where vegetation maintenance is being performed. Additional debris management requirements may be identified by land managing agencies.

### 17.08.1 Inaccessible Areas

In remote off-road areas without reasonable vehicle access, debris can be disposed of on-site. Use the lop and scatter method mentioned above.

## 17.09 Directional Pruning

Directional pruning is a natural target pruning applied to redirect tree growth away from utility lines (Gilman 2012). ANSI A300 and ISA’s best management practices (Kempter 2004) instruct that pruning to clear the utility space involves thinning cuts: removing at natural targets entire branches that are growing toward (or once cut will produce sprouts that will grow toward) the power lines.

While heading cuts produce sprouts that grow quickly back into the power lines, branch removal and reduction promote growth away from conductors. Because one objective of utility pruning is to train trees away from power lines wherever practical, branches growing away from the electric facility should not be pruned. Instead, these stems should be allowed to develop to their natural height or length, provide that growth does not create unreasonable safety risks. This cannot be accomplished with strongly excurrent trees pruned directly beneath conductors.

Topping, round-overs, flush cuts, branch tipping, and rip cuts are improper as they result in damage to the trees. Directional pruning is consistent with natural tree structure. Remaining branches retain their taper, strong attachments, growth regulators, and spacing. They continue to grow and function normally, allowing the tree to reach its natural height.

“V” shapes often result in properly pruned trees growing under power lines, particularly on decurrent, deciduous trees (Gilman 2012; Kempter 2004;

Miller 1998; Shigo 1990). Limbs growing upward and toward the facility should be cut back to the trunk or to limbs growing away from the conductors. Remaining branches should have sufficient clearance, so they do not damage the conductors in inclement weather common for the locality (high wind, freezing rain, snow, or other conditions). Excurrent trees (such as main conifers) are more problematic but should be reduced to appropriate laterals or whorls. “L” or one-sided shapes often result in properly pruned trees to the side of conductors (Shigo 1990; Gilman 2012). Limbs on the wire side of trees located adjacent to facilities should be cut back to the trunk; or to limbs growing vertically, sideways or downward; depending on the distance to the line or available natural target.

#### 17.10 Tree Houses

Tree houses built in trees growing near power lines present electric safety risks. Children or others may contact the line, either directly or indirectly, if a tree house is built too close to conductors. Indirect contact may occur through any conductive object, including a tree or tree parts that are contacting power lines. Minimum tree house distances are set at twice the “Minimum approach distances to energized conductors for arborists not qualified by training and experience to work within 10 feet of electrical conductors” as established in Table 1 of ANSI Z133.

#### 17.11 Distribution Cycle Maintenance

Trees and vegetation are pruned from distribution facilities on scheduled cycles. Facilities are worked systematically, either by circuit or grid. The duration of a cycle is dependent on local conditions, as determined by BCPP. BCPP typically schedules distribution cycle maintenance work on a three-year cycle for most circuits in BCPP service territories.

Refer to Sheet V-1.

In performing distribution cycle maintenance, the Tree Crew Foreman is required to:

- Systematically prune and remove trees and other vegetation at a specified distance from all primary conductors and non-primary conductors, consistent with this section,

- Comply with all other specifications generally applicable to all vegetation maintenance under these SOPs, including without limitation

- Identify and remove (or remediate) Hazard Trees and discretionary tree removals.

- Identify and correct readily climbable trees that are too close to power lines.

Identify and remedy or remove tree houses violating the criteria.

Remove all brush, which include volunteer trees (naturally seeded, non-landscaped trees) and woody plants (including vines).

17.11.1 Distribution Cycle Maintenance - Clearance Distances – Primary (Refer to sheets V-1 and V-2)

Each work cycle, trees and other vegetation are pruned or removed to achieve clearance distances to comply with the NESC, state regulation clearance requirements, and BCPP guidelines.

Specified vegetation clearance distances from primary conductors in the distribution system should allow sufficient space to prevent contact with primary conductors or regulatory mandated clearance distances throughout the cycle.

The Tree Crew Foreman is responsible for identifying all vegetation that would encroach upon conductors, BCPP required distances, or regulatory mandated minimum clearance distances throughout the cycle.

Neutral conductors in a raised position, which includes above or on a crossarm, are treated as primary-conductors for purposes of this section. Low neutral position is treated as a hot conductor.

17.11.2 Distribution Cycle Maintenance – Clearance Distances – Non-Primary

17.11.2.1 A secondary line is a line typically energized to less than 750 volts. Specified distances from secondary conductors in the distribution system are designed to prevent strain (severe deflection) or abrasion. The “Work Threshold,” which is the point at which action must be taken) and Post Work Clearance distances for non-primary are set forth as follows:

Table 17.11.2. A non-primary wire vegetation clearance distances.

Line Type	Work Threshold	Minimum Post-Work Clearance
Non-insulated wire pole-to-pole secondary	N/A	3 feet
Neutral low position	Contact	2 feet
Insulated pole-to-pole secondary	Deflection or abrasion	2 feet
Non-insulated secondary service line/streetlight	N/A	1 foot
Insulated secondary service/streetlight	Deflection or abrasion	1 foot
Guy wire	2-inch or graded diameter limb applying pressure	Relieve pressure

These practices can be changed at any time at the discretion of the BCPP Director.

In addition to the specification clearances (Table 17.11.2.A), the following requirements also apply to distribution cycle maintenance work on distribution non-primary.

**17.11.2.2 Tree Limbs Between Conductors.** Any tree limbs between a primary conductor and any secondary conductor, regardless of type, shall be removed or pruned to Post-Work Clearances for primary.

**17.11.2.3 Customer Work.** If a customer expresses a desire to remove other limbs or trees around any non-primary, in addition to the work to complete under these specifications, vegetation maintenance workers should inform the customer to call BCPP to arrange for a temporary disconnection of the facilities to allow safe completion of the desired tree work, as required by law.

## 17.11.3 Distribution Cycle Maintenance – Other Facility Clearances

In addition to pruning trees to maintain clearances, certain vegetation maintenance is required on utility poles (and supporting guy wires) as part of distribution cycle maintenance work. One-third of the circumference around poles shall be cleared of vegetation to 5 feet from the pole to allow linemen a climbing path. The remaining two-thirds of the pole circumference should be cleared of all vegetation 1 foot from the pole.

Vines growing on poles and guy wires shall be:

Cut at ground level

Treated with an approved herbicide

Removed from the bottom 5 feet of the pole or guy wire

Reported as brush or tree removed

Vines clearly part of a landscape and rooted well away from the pole may be:

Pruned to provide sufficient climbing path and 5 feet of separation (e.g., 5 feet of separation between the top of a fence and facility)

Reported as brush pruned (not to exceed 100 brush ft. pruned)

Where vines remain on facilities after work is completed, the Tree Crew Foreman will document the exception and report it to BCPP Director to clear the remainder of the pole.

## 17.12 Transmission procedures

Transmission facilities are overhead lines energized at a higher voltage. Typical transmission voltages on BCPP's system are 46kV and 138kV. Facility voltage and type determine the amount of transmission clearance needed. Vegetation maintenance performed on transmission lines shall comply with ANSI A300. In addition, vegetation maintenance performed on transmission lines shall conform with the NERC Reliability Standard FAC-003-5. Consistent with requirement R4 of NERC Standard FAC-003-5 and the procedures set forth in BCPP transmission grid operations. BCPP line patrolmen are responsible to complete inspections on certain transmission lines. When doing their inspections, line patrolmen will identify any vegetation that poses a threat of causing a transmission outage. In addition, BCPP vegetation management department completes vegetation inspections of the Right of Way for transmission lines. BCPP vegetation management completes an annual vegetation inspection on main grid transmission lines. All other transmission lines are inspected at least once

every year. Vegetation maintenance on transmission lines is then scheduled according to the results of those inspections.

#### 17.12.1 Transmission Clearances

The objective of systematic transmission work is to safeguard the reliability of BCPP transmission system by preventing outages from contact with vegetation. Clearance work on a transmission line is guided by three concepts: Minimum Vegetation Clearance Distances, Action Thresholds, and Minimum Clearances Following Work.

Minimum Vegetation Clearance Distance (MBVCD) represents radial distances from the conductors inside of which trees shall not encroach.

#### 17.13 Chemical Procedures

Herbicides and tree growth regulators (TGR) are an important part of BCPP Vegetation Management Program. Herbicides are chemicals used to manipulate or control undesirable vegetation. When safely used, herbicides are effective and efficient, minimize soil disturbance, and enhance plant and wildlife diversity. Herbicide applications can benefit wildlife by improving forage as well as escape and nesting cover. In some instances, noxious weed control is a desirable objective in utility ROW that can be accomplished through herbicide treatment. Herbicide use can control individual plants that are prone to resprout or sucker after removal. When trees that resprout or sucker are removed without herbicide treatment, dense thickets develop, impeding access, swelling workloads, increasing costs, blocking lines-of-site, and deteriorating wildlife habitat (Yahner and Hutnik 2004). Treating suckering plants allows early successional, compatible species to dominate the ROW and out-compete incompatible species, reducing work. “Tree growth regulators” refers to chemical treatments that slow the growth of some tree species.

Chemical applications shall always be performed according to federal, state, and local regulations and consistent with all labeling requirements.

##### 17.13.1 Notification to Property Owners

Before chemical use on a property, Tree Crew Foreman shall give notice to the property owner(s). Notice shall be provided at least five days before work but no more than six weeks in advance, whenever chemicals are to be used on their property.

##### 17.13.2 Licensed Applicators

Crew members in Brigham City service territory shall hold a valid Commercial pesticide applicator License. The Tree Crew

Foreman performing work is always responsible to ensure that any application of chemicals is performed by an applicator with a valid applicator's license, as required by state law where the property is located.

17.13.3 Closed Chain of Custody

The Tree Crew Foreman making the application is responsible for chemical purchase, storage, and container disposal. Closed chain of custody is required, including the use of returnable, reusable supply containers.

17.13.4 Chemical Reporting

All chemical applications shall be documented as required by law for a licensed applicator. In addition, chemical applications shall be documented as instructed by BCPP. The Tree Crew Foreman making the application shall be responsible for maintaining reports and shall produce reports for review by the state departments of agriculture upon request.

17.13.5 Herbicide Application Efficiency

Ninety-five percent control shall be assumed on all herbicide applications to be considered effective.

17.13.6 Wetland and Waterbodies

Product label shall be followed and approved for use near wetlands and waterbodies.

17.13.7 Spills

Applicator is responsible for preventing any chemical spills from occurring. Special attention should be made while mixing, loading, and cleaning equipment, which are activities that carry more risk for accidents or spills. Spills can be avoided by using closed chain of custody best management practices. Spill kits are required on every truck when any herbicide is used or being transported.

In the event of a spill:

1. Stop, contain and isolate the spill
2. Report the spill to the BCPP Director, who will notify the environmental services; the following information must be provided to the TREE CREW FOREMAN:
  - a. Caller and manager
  - b. Name
  - c. Date and time of spill

- d. Location (address or longitude and latitude)
  - e. EPA number (product spilled)
  - f. Cause of spill
  - g. Amount of spill
  - h. Types of surfaces contaminated
  - i. Containment and/or clean-up activities performed so far
3. Remediate the spill
  4. Cleanup at or near BCPP generating sites or substations must comply with site-specific spill prevention and remediation plans.

17.14 Approved Herbicides

In all circumstances, the licensed applicator is responsible for following label requirements. In addition, specific chemical products must be approved by the BCPP Director, based on pre-approved chemical products. Any approved chemical products must be based on one or a combination of the following active ingredients:

<p>Stump Application</p> <ul style="list-style-type: none"> <li>2, 4-D</li> <li>Glyphosate</li> <li>Picloram</li> <li>Triclopyr</li> </ul> <p>Foliar Application</p> <ul style="list-style-type: none"> <li>2, 4-D</li> <li>Aminopyralid</li> <li>Fosamine ammonium</li> <li>Glyphosate</li> <li>Imazapyr</li> <li>Metasulfuron methyl</li> <li>Picloram</li> <li>Sulfometuron methyl</li> <li>Triclopyr</li> </ul> <p>Tree Growth Regulators (TGR)</p> <ul style="list-style-type: none"> <li>Fluprimidol</li> <li>Paclobutrazol</li> </ul>	<p>Low Volume Basal Application</p> <ul style="list-style-type: none"> <li>Imazapyr</li> <li>Triclopyr</li> </ul> <p>Soil Application</p> <ul style="list-style-type: none"> <li>Diuron</li> <li>Indaziflam</li> <li>Imazapyr</li> <li>Picloram</li> <li>Sulfentrazone</li> <li>Tebuthiuron</li> </ul>
--	--

17.14.1 Substations Herbicide Treatment

Substations will be sprayed and treated multiple times throughout the year.

# BRIGHAM CITY PUBLIC POWER DEPARTMENT ELECTRICAL CONSTRUCTION STANDARD DRAWINGS

*Index of Drawings (32 Sheets)*

**SUBMITTED & RECOMMENDED**

ENGINEER

**APPROVAL**

TOM COOPER  
PUBLIC POWER DIRECTOR

DATE

TROY DAHLGREN  
PUBLIC POWER SUPERINTENDENT

DATE

CASEY SMITH  
PUBLIC POWER SUPERINTENDENT

DATE

KRISTINA RASMUSSEN  
AITEST, CITY RECORDER

DATE



**BRIGHAM  
CITY**

**SPECIAL STANDARD NOTES:**

- A. AT THE BRIGHAM CITY PUBLIC POWER'S SOLE DISCRETION, ALTERNATE METHODS OF CONSTRUCTION OR DEVIATIONS FROM THESE STANDARDS MAY BE REQUIRED OR APPROVED BY THE CITY PUBLIC POWER DIRECTOR AND PUBLIC POWER SUPERINTENDENT (OR THEIR DESIGNEE), WHEN SUCH ARE NECESSARY TO MEET THE BEST INTERESTS OF THE CITY.
- B. WHEN BRIGHAM CITY PUBLIC POWER APPROVAL IS REQUIRED, IT SHALL MEAN APPROVAL FROM THE CITY PUBLIC POWER DIRECTOR, PUBLIC POWER SUPERINTENDENT, CITY ENGINEER, OR THEIR DESIGNEE.
- C. ANY VARIANCE, DEVIATION, OR WAIVER TO THE CITY ELECTRICAL STANDARDS SHALL BE AS APPROVED BY THE PUBLIC POWER DIRECTOR OR SUPERINTENDENT.

**ELECTRICAL CONSTRUCTION STANDARDS**


- E1.....ELECTRIC FRONT PAGE-INFORMATION
  - E2.....RESIDENTIAL UNDERGROUND SERVICE 200 AMPS OR LESS
  - E3.....RESIDENTIAL OVERHEAD SERVICE 200 AMPS OR LESS
  - E4.....ELECTRIC CONDUIT TRENCH DETAIL
  - E5.....SECONDARY JUNCTION PEDESTAL
  - E6.....SINGLE PHASE PAD MOUNT TRANSFORMER
  - E7.....200-AMP 1-PHASE SECTIONALIZER
  - E8.....200-AMP 1 AND 3-PHASE FIBERGLASS SECTIONALIZER
  - E9.....600-AMP 3-PHASE FIBERGLASS SECTIONALIZER
  - E10.....ELECTRICAL BOX BACKFILL & COMPACTION
  - E11.....CONDUIT ROUTING
  - E12.....3-PHASE TRANSFORMER & CONCRETE PAD
  - E13.....600 AMP PSE 9/11 SWITCHGEAR
  - E14.....600 AMP PSE 3/5 SWITCHGEAR
  - E15.....SECONDARY PEDESTAL, WIRE & CONNECTIONS
  - E16.....DECORATIVE STREET LIGHT POLE FOOTING DETAIL
  - E17.....STREET LIGHT POLES AND FIXTURES
  - E18.....TEMPORARY SERVICE FOR OVERHEAD & UNDERGROUND LINES
  - E19.....3-PHASE UNDERGROUND SERVICE 201-800 AMPS
  - E20.....TYPICAL RISER POLE
  - E21.....OVERHEAD POWER LINE CLEARANCES OVER 600 VOLTS TO 22,000 VOLTS
  - E22.....1-PHASE FREE STANDING METER BASE & 3-PHASE FREE STANDING METER BASE
  - E23.....PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM CENTRAL INVERTER (RESIDENTIAL)
  - E24.....PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM MICRO INVERTER (RESIDENTIAL)
  - E25.....PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM ENERGY STORAGE - CENTRAL INVERTER (RESIDENTIAL)
  - E26.....PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM ENERGY STORAGE - MICRO INVERTER (RESIDENTIAL)
  - E27.....PHOTOVOLTAIC THREE-PHASE SYSTEM DIAGRAM USING MULTIPLE TWO-LINE SINGLE-PHASE INVERTERS WITH NEUTRAL CONNECTION
  - E28.....PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM USING A SINGLE THREE-PHASE INVERTER
  - E29.....PV DISCONNECT LABELS & PV SERVICE PANEL WARNING LABELS
  - E30.....EUSERC DWG NO. 501 - AC DISCONNECT GUIDELINES
- ELECTRICAL - VEGETATION MANAGEMENT STANDARDS**
- V1.....TREE AND VEGETATION TRIMMING AND CLEARING DETAILS
  - V2.....TREE PLANTING AND ELECTRICAL BOX CLEARANCE DETAILS

**FEBRUARY 2026**









TYPE OF CONDUIT	CONDUIT SIZE	MIN. DEPTH TO TOP OF CONDUIT
STREET LIGHT	2" SECONDARY	2'-0"
ELECTRICAL SERVICE	3" SECONDARY	2'-0"
SECONDARY	1"	2'-0"
	2"	2'-0"
	3"	2'-0"
	4"	2'-0"
PRIMARY	4"	4'-0"
	6"	4'-0"

ALL POWER CONDUIT SHALL BE BURIED A MINIMUM OF 4' IN DEPTH TO TOP OF CONDUIT. IF HIGH VOLTAGE (15KV) CONDUITS, LOW VOLTAGE (4KV) CONDUITS AND POWER CONDUITS ARE INSTALLED IN THE SAME TRENCH, THE HIGH VOLTAGE CONDUIT SHALL ALWAYS BE INSTALLED BELOW LOW VOLTAGE POWER CONDUITS. IF THERE ARE MULTIPLE HIGH VOLTAGE CONDUITS (3" PHASE, 6" PHASE) IN THE SAME TRENCH, ALL HIGH VOLTAGE CONDUITS MAY BE INSTALLED AT THE DEPTH OF THE LARGEST CONDUIT (6").

NOTES:

- HIGH VOLTAGE PRIMARY CONDUITS SHALL ALWAYS BE BELOW SECONDARY CONDUITS.
- REBAR SHALL BE CAPPED UNTIL BACKFILLED.
- BACKFILL SHALL MEET THE REQUIREMENTS OF EARTHWORK AND TRENCHES AND OTHER STANDARDS IN THE CONSTRUCTION AND DEVELOPMENT STANDARDS.
- ALL CONDUITS SHALL BE INSPECTED AT EACH "LIFT", AT THE COMPACTION LEVEL, AND FOR A FINAL INSPECTION.
- A CAUTION TAPE SHALL BE PLACED DIRECTLY ON CONDUIT, AND A CAUTION TAPE SHALL BE PLACED 1' BELOW GRADE FOR CITY POWER.
- ONLY CONTINUOUS CONDUIT RUNS ARE PERMITTED. FACTORY JOINTS SHALL BE USED FOR ATTACHING FULL LENGTH CONDUITS TOGETHER UNLESS OTHERWISE APPROVED.



**TYPICAL JOINT TRENCH OF HIGH VOLTAGE, LOW VOLTAGE & COMMUNICATIONS CONDUITS**

DATE: 01/09/2026	SCALE: N.T.S.	DRAWN: BCB	CHECK: TD & CS
PROJECT: 01/09/2026	DESCRIPTION: ELECTRIC CONDUIT TRENCH DETAIL	BRIGHAM CITY PUBLIC POWER	ELECTRICAL CONSTRUCTION STANDARDS
BRIGHAM CITY PUBLIC POWER 1435 East Power Plant Road Brigham City, UT 84302 Tel: (435) 734-9824 Utility Engineering: (435) 734-9848		BRIGHAM CITY CORPORATION 20 North Main Street Brigham City, UT 84302 Tel: (435) 734-6000 www.cityofbr.com	
BRIGHAM CITY PUBLIC POWER ASSUMES NO LIABILITY FOR DESIGN, CONSTRUCTION, OR PERFORMANCE OF CONTRACTORS OR SUBCONTRACTORS. THESE ELECTRICAL STANDARDS ARE SUBJECT TO ANY CHANGES OR MODIFICATIONS MADE BY THE CITY OF BRIGHAM CITY.			











- NOTES:**
- SECTIONALIZER CABINET UNITS FOR 200 AMP 1-PHASE AND 3-PHASE ARE TO BE FABRICATED FROM FIBERGLASS REINFORCED POLYESTER (FRP) UNITS BEING WITHIN THE GROUND SLEEVE WINDOW OF THE SECTIONALIZER. USE MANUFACTURER'S APPROVED GROUND SLEEVE FOR EACH SECTIONALIZER.
  - BLOW IN 1250 LB MULE TAPE IN ALL CONDUITS AND TIE SECURELY TO 4 POINT MOUNTING PLATE.
  - CONTRACTOR TO FURNISH & INSTALL 200-AMP 4-POINT MOUNTING JUNCTION AND PLATES & 4-POINT JUNCTIONS. P/N: COOPER-L215C4U OR HUBBELL-215J4U.
  - 200 AMP 1-PHASE SECTIONALIZER P/N: NORDIC ND-150-MG-101-X-X OR HUBBELL P/N P1342548NDL
  - 200 AMP 3-PHASE SECTIONALIZER P/N: NORDIC ND-350-MG-101-X-X OR HUBBELL P/N P2382548NDM

NO.	DATE	DESCRIPTION	SCALE	BY	CHKD.	DATE	DESCRIPTION
			N.T.S.	BEJ	TD & CS	01/09/2026	TC
BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS 200-AMP 1 AND 3-PHASE FIBERGLASS SECTIONALIZER				BRIGHAM CITY BRIGHAM CITY CORPORATION 20 North Main Street Brigham City, UT 84302 Tel: (435) 734-6000 www.bcp.com			
BRIGHAM CITY PUBLIC POWER 1435 East Power Road Brigham City, UT 84302 Tel: (435) 734-6024 Utility Emergency: (435) 734-6044				BRIGHAM CITY BRIGHAM CITY CORPORATION 20 North Main Street Brigham City, UT 84302 Tel: (435) 734-6000 www.bcp.com			





- NOTES:
1. ALL ELECTRICAL BOXES INCLUDING, BUT NOT LIMITED TO, SECTIONALIZERS, SECONDARY, JUNCTION BOXES, TRANSFORMERS AND TRANSFORMER CONCRETE PADS SHALL BE MINIMUM 12" IN DEPTH. CONDUITS SHALL EXTEND A MINIMUM OF 95% UNDER ALL BOXES. FILL SHALL BE A MINIMUM OF 1" IN DEPTH. ALL SHALL EXTEND A MINIMUM OF 1" PAST ALL SIDES AND BACK AND 1" IN FRONT (6" IF A SIDEWALK IS PRESENT) OF ALL BOXES OR PADS.
  2. ALL COMPACTION TESTS SHALL BE TAKEN BEFORE ELECTRICAL BOXES ARE SET INTO PLACE.
  3. ALL SAND, ROADBASE AND ENGINEERED FILL SHALL MEET BRIGHAM CITY PUBLIC POWER STANDARDS.
  4. REFER TO "EARTHWORK AND TRENCHES" SECTION IN THE CONSTRUCTION STANDARDS FOR ADDITIONAL REQUIREMENTS FOR BACKFILL, TRENCHING AND COMPACTION.
  5. AREA AROUND ELECTRICAL BOXES SHALL BE BACKFILLED & LEVELED A MINIMUM OF 12" IN ALL DIRECTIONS TO PROVIDE A SAFE WORKING AREA FOR THE ELECTRIC DEPARTMENT.

NO.	DATE	BY	CHKD.	SCALE	DESCRIPTION
01				N.T.S.	
02					
03					
04					
05					
06					
07					
08					
09					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					


BRIGHAM CITY PUBLIC POWER  
 ELECTRICAL CONSTRUCTION STANDARDS  
 ELECTRICAL BOX BACKFILL & COMPACTION

BRIGHAM CITY PUBLIC POWER  
 1455 East Power Plaza Road  
 Brigham City, UT 84302  
 Tel: (435) 734-6000  
 Utility Emergency: (435) 724-0866

BRIGHAM CITY  
 20 North Main Street  
 Brigham City, UT 84302  
 Tel: (435) 734-6000  
 www.bcpb.com

BRIGHAM CITY PUBLIC POWER ASSUMES NO LIABILITY FOR DAMAGES TO PROPERTY OR PERSONS ARISING FROM THE USE OF THESE STANDARDS. THE USER OF THESE STANDARDS SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND FOR OBTAINING ALL NECESSARY INFORMATION FROM THE UTILITY COMPANY OR OTHER AGENCIES INVOLVED IN THE PROJECT. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION FROM THE UTILITY COMPANY OR OTHER AGENCIES INVOLVED IN THE PROJECT.

DATE: 01/09/2026  
 DRAWN: TD & CS  
 CHECKED: TC



NOTES:

1. CONTRACTOR TO PERMANENTLY CAP ALL CONDUIT ENDS. ENDS OF CONDUITS TO BE MARKED WITH LOCATION MARKERS. MARK WITH A RADAR ENGINEERS MODEL 600 RED BURIED PIPE MARKER OR APPROVED EQUAL.
2. ~~COMMUNICATION PEDESTALS SHALL BE INSTALLED BY THE SERVICE PROVIDER (ALL TELECOM FACILITIES)~~
3. ALL CONDUIT STUBS SHALL BE INSTALLED BY DEVELOPER.

REV	DATE	DESCRIPTION


DRAWN: <b>BCB</b> CHECKED: <b>TD &amp; CS</b> DATE: <b>01/09/2026</b>	BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS <b>CONDUIT ROUTING</b>
---	--


BRIGHAM CITY CORPORATION 30 North Main Street Brigham City, UT 84302 Tel: (435) 734-6500 www.bcp.com	BRIGHAM CITY PUBLIC POWER 1455 East Power Plant Road Brigham City, UT 84302 Tel: (435) 734-6424 Utility Emergency: (435) 732-6444
--	---


BRIGHAM CITY PUBLIC POWER ASSURES NO LIABILITY FOR DIRECT, INDIRECT, SPECIAL, OR CONSEQUENTIAL DAMAGES, INCLUDING ATTORNEY'S FEES, ARISING FROM ANY CHANGES OR RECONFIGURATIONS WITHOUT PRIOR CONSENT.	BRIGHAM CITY 
--	------------------



**GENERAL TRANSFORMER CLEARANCES**






TRANSFORMER KVA RATING	DIMENSIONS					
	A	B	C	D	E	F
75-500 KVA	114"	78"	36"	15"	18"	9"
750-1500 KVA	118"	105"	52"	16"	20"	11"
2000 KVA	CONTACT POWER DEPT.					



**NOTES:**

- SITE PREPARATION & INSPECTIONS:** AFTER EXCAVATION, ALL EXCAVATED AREA 1' PAST PAD SHALL BE BUILT UP TO ORIGINAL FINISH GRADE AND MUST BE COMPACTED TO 95%. THE GROUND WITHIN THIS LEVEL AN ADDITIONAL 12" PAST THE PAD SHALL BE EXCAVATED AND REBUILT TO FINISH GRADE. ALL PADS SHALL BE INSPECTED PRIOR TO POURING CONCRETE AND THE GROUND SHALL HAVE A COMPACTION TEST DONE PRIOR TO THE FORM BEING CONSTRUCTED.
- CONCRETE:** CONCRETE SHALL BE IN ACCORDANCE WITH BRIGHAM CITY PUBLIC POWER STANDARD SPECIFICATIONS. ALL STEEL REINFORCEMENT SHALL BE #4 BARS PLACED AT 12" CENTERS THROUGHOUT THE PAD. THE PAD SHALL BE REINFORCED WITH #4 BARS PLACED AT 12" CENTERS THROUGHOUT THE FINISHED SURFACE MUST BE COMPLETELY FLAT AND LEVEL. CONCRETE SHALL BE EXCISED BY THE CITY OR THE CITY'S ENGINEERING FIRM PRIOR TO POURING CONCRETE. CONCRETE SHALL CONFORM TO CITY STANDARDS.
- LABORATORY:** THE PAD SHALL BE CONSTRUCTED ON THE SITE ACCORDING TO THE SPECIFICATIONS.
- CONDUIT WINDOW LAYOUT:** LOW VOLTAGE CONDUITS SHALL BE FORMED AS FURTHER AS POSSIBLE AGAINST THE RIGHT SIDE OF THE OPENING AND SHALL IN NO CASE EXTEND FURTHER THAN 20" FROM THE RIGHT SIDE OF THE CONDUIT WINDOW ON THE SMALL PAD OR 30" ON THE LARGE PADS. NO MORE THAN EIGHT CONDUITS WILL BE USED ON THE LOW VOLTAGE SIDE ON 2000 KVA PADS. UNDER THE CONDUIT SECONDARY CONDUITS WILL BE USED. DO NOT PUT ANY CONCRETE IN OR UNDER THE CONDUIT SECONDARY CONDUITS. ALL CONDUITS ENTERING THE PAD SHALL BE SCHEDULE 40 PVC WITH PVC OR FIBERGLASS (FRGC) ELBOWS.
- GROUNDING:** A 5/8" X 8' GROUND ROD SHALL BE USED ON THE SMALL PAD AND A 3/4" X 10' ROD ON THE LARGE PADS. THE GROUND ROD SHALL BE INSTALLED ON THE PRIMARY SIDE OF THE TRANSFORMER.
- CLEARANCES:** THE FRONT OF THE PAD SHOULD ALWAYS FACE AWAY FROM ADJACENT STRUCTURES AND BE FREE OF OBSTRUCTIONS. AT LEAST THREE FEET MUST SEPARATE THE EDGES OF THE PAD FROM ANY ADJACENT STRUCTURE. THE EDGES OF THE PAD MUST BE AT LEAST TEN FEET FROM ANY ADJACENT STRUCTURE. THE ADJACENT STRUCTURE HAS ANY OVERHANG OR EAVE WITHIN 27 VERTICAL FEET OF THE TOP OF THE PAD MUST BE PLACED AWAY FROM THE PAD. THE EDGE OF THE OVERHANG, THE PAD MUST NOT BE PLACED IN AN AREA TEN FEET IN LINE WITH OR THREE FEET TO EITHER SIDE OF ANY WINDOW IN AN ADJACENT STRUCTURE.
- ELBOWS FOR A DOOR:** MUST BE TWENTY FEET IN LINE WITH IT AND TEN FEET ON EITHER SIDE. SLIGHTLY ABOVE THE DOOR. THE DOOR MUST BE TWENTY FEET OR MORE FROM ANY OTHER OBSTRUCTIONS OR STORAGE FACILITY CONTAINING FLAMMABLE MATERIALS. OTHER OBSTRUCTIONS WILL BE PLACED WITHIN THREE FEET OF THE SIDES OR BACK OF THE PAD OR WITHIN TWELVE FEET OF THE FRONT OF THE PAD. THE AREA SURROUNDING THE PAD MUST HAVE TWELVE FEET OF CLEAR LEVEL WORKING AREA FOR MAINTENANCE OF THE TRANSFORMER. THE PAD MUST NOT BE PLACED IN LINE WITH AN AIR INTAKE WITHIN 32 VERTICAL FEET OF THE SURFACE OF THE PAD. ALSO, IT MUST NOT BE PLACED WITHIN 12 FEET VERTICALLY OF A DOOR OR WINDOW.
- BARRIERS:** IF THE TRANSFORMER PAD IS TO BE LOCATED IN AREAS SUBJECT TO VEHICULAR TRAFFIC (PARKING LOTS, DRIVEWAYS, ETC.) CONTACT BRIGHAM CITY PUBLIC POWER FOR PROTECTIVE BARRIER REQUIREMENTS.
- METERING:** IN GENERAL, THE METERING SHALL BE PLACED ON BUILDINGS OR STRUCTURES.
- CONNECTIONS:** ALL SECONDARY (LOW VOLTAGE) CABLES & SECONDARY CONNECTIONS ARE THE CONTRACTOR'S RESPONSIBILITY. BRIGHAM CITY PUBLIC POWER WILL INSTALL & TERMINATE PRIMARY CABLES & CONNECTIONS ONLY.
- ANCHORING:** CONTRACTOR TO ANCHOR TRANSFORMER TO PAD WITH MINIMUM OF TWO ANCHOR POINTS.
- PRECAST TRANSFORMER PADS** MUST BE APPROVED BY THE PUBLIC POWER DEPARTMENT.


DATE:	01/09/2026	SCALE:	N.T.S.	DRWN:	BEP	CHKD:	JD & CS	BY:	TC
REV:	DATE:	DESCRIPTION:							
<p>BRIGHAM CITY PUBLIC POWER ASSUMES NO LIABILITY FOR OVERTIGHT, EXCESSIVE WEIGHT, OR UNUSUAL LOADS ON ANY ELECTRICAL EQUIPMENT OR STRUCTURE. BRIGHAM CITY PUBLIC POWER ASSUMES NO LIABILITY FOR ANY DAMAGE TO EQUIPMENT OR STRUCTURE WITHOUT PROPER CLEARANCES.</p>									
<p>BRIGHAM CITY CORPORATION 20 North Main Street Brigham City, UT 84302 Tel: (435) 734-6600 www.bcpun.gov</p>									
<p>BRIGHAM CITY PUBLIC POWER 1455 East Power Plant Road Brigham City, UT 84302 Tel: (435) 734-6624 Utility Engineering (435) 732-8948</p>									
<p>BRIGHAM CITY ELECTRICAL CONSTRUCTION STANDARDS</p>									
<p>3-PHASE TRANSFORMER &amp; CONCRETE PAD</p>									
<p>BRIGHAM CITY PUBLIC POWER</p>									
<p>E12</p>									
<p>OF 1 SHEET</p>									




- NOTES:
1. SWITCH GEAR GROUND SLEEVES SHALL BE PROVIDED BY BRIGHAM CITY PUBLIC POWER AND INSTALLED BY ELECTRICAL CONTRACTOR AS PER CITY SUPPLIED LAYOUT
  2. 2500 LB MULE TAPE SHALL BE BLOWN INTO CONDUIT AND TIED SECURELY TO EACH (2) GROUND ROD MEETING
  3. CONDUIT LAYOUT DETAIL SHALL BE GIVEN BY BRIGHAM CITY PUBLIC POWER DURING PRE CONSTRUCTION MEETING
  4. TYPICAL FOR SITE DEVELOPMENTS

DATE	01/09/2026	SCALE	N.T.S.	OWNER	BEPP	PROJECT	TD & CS	DESIGNER	TC
REV	DATE	DESCRIPTION							
BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS 600 AMP PSE 9/11 SWITCHGEAR									
BRIGHAM CITY CORPORATION 20 North Main Street Brigham City, UT 84302 Tel: (435) 734-6000 www.bcpub.org									
BRIGHAM CITY PUBLIC POWER 1445 East Power Plant Road Brigham City, UT 84302 Tel: (435) 734-6024 Utility Emergency: (435) 732-6848									





SECONDARY CONNECTIONS



NOTES:

1. INSTALL AN IN-LINE 10 AMP FUSE & FUSE HOLDER ON THE UNGROUNDED 120/240V STREET LIGHT CONDUCTOR(S) IN JUNCTION BOX.
2. CONDUIT ENTERING INTO ANY SECONDARY PEDESTAL MUST HAVE A FABRICATED BELL END.
3. SECONDARY PEDESTAL SHALL BE NORBAC PSP-15-15-30-14G OR PENCELL AG20HDVCL-ML APPROVED EQUIVALENT.
4. GROUND LEVEL INSIDE THE GROUND SLEEVE IS THE BOTTOM OF THE GROUND SLEEVE.
5. ALL SECONDARY CABLE SHALL EXTEND A MINIMUM OF 36" & A MAXIMUM OF 48" FROM TOP OF SECONDARY BOX (WITHOUT LID) AND SHALL BE THE URD TYPE CABLE.
6. ROAD BASE SHALL BE USED UNDER SECONDARY BOXES. ROAD BASE SHALL BE COMPACTED TO 95% AND BE TESTED PRIOR TO BOX BEING SET INTO PLACE.
7. ALL SERVICE STUBS SHALL EXTEND 10' PAST PROPERTY LINE.
8. SECONDARY WATERTIGHT, INSULATED SET SCREW CONNECTORS (BY WHICH CORT-360-60-C100) OR EQUIVALENT) SHALL ACCEPT A MINIMUM OF SIX INDIVIDUAL WIRES, UNLESS OTHERWISE APPROVED BY ELECTRICAL DEPARTMENT.


REV	DESCRIPTION	DATE	BY	CHKD	DATE	DESCRIPTION
01						
02						
03						
04						
05						
DESIGNER		DATE	BY	CHKD	DATE	DESCRIPTION
N.T.S.		01/09/2026				
SCALE		DATE	BY	CHKD	DATE	DESCRIPTION
TD & CS						
TC						
<p>BRIGHAM CITY PUBLIC POWER UTILITIES DEPARTMENT          1435 East Power Plant Road          Brigham City, UT 84302          Tel: (435) 734-6600          Utility Emergency: (435) 734-6884</p>						
<p>BRIGHAM CITY PUBLIC POWER          ELECTRICAL CONSTRUCTION STANDARDS</p>						
<p>SECONDARY PEDESTAL, WIRE &amp; CONNECTIONS</p>						
<p>BRIGHAM CITY PUBLIC POWER          20 North Main Street          Brigham City, UT 84302          Tel: (435) 734-6600          www.bcpou.com</p>						
<p>BRIGHAM CITY PUBLIC POWER UTILITIES DEPARTMENT          1435 East Power Plant Road          Brigham City, UT 84302          Tel: (435) 734-6600          Utility Emergency: (435) 734-6884</p>						
<p>BRIGHAM CITY PUBLIC POWER          ELECTRICAL CONSTRUCTION STANDARDS</p>						
<p>SECONDARY PEDESTAL, WIRE &amp; CONNECTIONS</p>						











NOTES:

1. CONTRACTOR/DEVELOPER SHALL PROVIDE THE RMC (GRC) OR IMC CONDUIT AND ANY ADDITIONAL REQUIRED MATERIALS FOR THE RISER TO BRIGHAM CITY PUBLIC POWER FOR INSTALLATION.
2. FOR RISERS WHERE THE CONTRACTOR IS REQUIRED TO PULL LOW VOLTAGE CABLE (120/240 VOLT, 3 OR 4 WIRE), ENOUGH WIRE SHALL EXTEND FROM THE CONDUIT FOR THE CITY TO ATTACH IT TO THE 2" LOOP AT TOP OF POLE.
3. FIBERGLASS CONDUITS AND FIBERGLASS "ELBOWS" (RMC) ARE NOT PERMITTED ON ANY RISER POLE APPLICATION UNLESS OTHERWISE APPROVED.
4. ALL RIGID METAL CONDUIT INSTALLED BELOW GRADE SHALL BE WRAPPED WITH 10-MIL CORROSION-RESISTANT TAPE. TAPE SHALL EXTEND 6" MIN. ABOVE FINISH GRADE.
5. FIBERGLASS OR GALVANIZED RIGID STEEL CONDUIT (GRC) SHALL BE USED FOR BENDS 45 DEGREES AND GREATER ON ALL CONDUITS EXTENDING OUT OF THE GROUND OUTSIDE OF AN ENCLOSURE.

BY	DATE	SCALE	REVISION	DATE	BY	DATE	SCALE	REVISION	
BRIGHAM CITY PUBLIC POWER			BRIGHAM CITY PUBLIC POWER			BRIGHAM CITY PUBLIC POWER			
1455 East Power Plant Road Brigham City, UT 84302			1455 East Power Plant Road Brigham City, UT 84302			1455 East Power Plant Road Brigham City, UT 84302			
Tel: (435) 734-8624			Tel: (435) 734-8624			Tel: (435) 734-8624			
911 Emergency: (435) 733-0888			911 Emergency: (435) 733-0888			911 Emergency: (435) 733-0888			
BRIGHAM CITY			BRIGHAM CITY			BRIGHAM CITY			
20 North Main Street Brigham City, UT 84302			20 North Main Street Brigham City, UT 84302			20 North Main Street Brigham City, UT 84302			
Tel: (435) 734-6500			Tel: (435) 734-6500			Tel: (435) 734-6500			
www.bcpower.com			www.bcpower.com			www.bcpower.com			
BRIGHAM CITY PUBLIC POWER ASSURES AND ASSUMES LIABILITY FOR THE USE OF ANY OF THE INFORMATION CONTAINED HEREIN. BRIGHAM CITY PUBLIC POWER ASSUMES NO LIABILITY FOR ANY DAMAGES OR INJURIES THAT MAY OCCUR AS A RESULT OF THE USE OF THIS INFORMATION WITHOUT FURTHER CONSULTATION.			BRIGHAM CITY PUBLIC POWER ASSURES AND ASSUMES LIABILITY FOR THE USE OF ANY OF THE INFORMATION CONTAINED HEREIN. BRIGHAM CITY PUBLIC POWER ASSUMES NO LIABILITY FOR ANY DAMAGES OR INJURIES THAT MAY OCCUR AS A RESULT OF THE USE OF THIS INFORMATION WITHOUT FURTHER CONSULTATION.			BRIGHAM CITY PUBLIC POWER ASSURES AND ASSUMES LIABILITY FOR THE USE OF ANY OF THE INFORMATION CONTAINED HEREIN. BRIGHAM CITY PUBLIC POWER ASSUMES NO LIABILITY FOR ANY DAMAGES OR INJURIES THAT MAY OCCUR AS A RESULT OF THE USE OF THIS INFORMATION WITHOUT FURTHER CONSULTATION.			
DATE:	01/09/2026	SCALE:	N.T.S.	REVISION:	REP	DATE:	01/09/2026	BY:	TC
DATE:		SCALE:		REVISION:	ID & CS	DATE:		BY:	










**THIS DETAIL SHOWS THE REQUIREMENTS FOR A PHOTOVOLTAIC SINGLE-PHASE SYSTEM WITH ENERGY STORAGE (CENTRAL INVERTER)**



**NOTES:**

- A. MAIN SERVICE PANEL MUST COMPLY WITH CEC LATEST REVISION AND OPERATE IN A SAFE MANNER.
1. BRIGHAM CITY PUBLIC POWER WILL NOT ALLOW INTERCONNECTIONS WITH ANY UNSAFE CONDITIONS.
- B. PRODUCTION METER TO BE PROVIDED AND INSTALLED BY BRIGHAM CITY PUBLIC POWER AT CUSTOMERS EXPENSE. METER SOCKET TO BE PROVIDED BY INSTALLER. BRIGHAM CITY PUBLIC POWER WILL ACTIVATE THE PV SYSTEM AFTER IT MEETS ALL REQUIREMENTS, AND PASSES ALL INSPECTIONS.
- C. LOCKABLE KNIFE-BLADE UTILITY A.C. DISCONNECT TO BE LOCATED WITHIN 10'-0" AND LINE OF SIGHT OF SERVICE PANEL AND MUST COMPLY WITH ELSERC DMG 501.
- D. INVERTER MUST COMPLY WITH UL1741 REQUIREMENTS. GROUNDING ELECTRODE SYSTEM MUST COMPLY WITH LATEST REVISION OF CEC ARTICLE 690.47.
1. SEPARATE D.C. DISCONNECT AT GRADE LEVEL REQUIRED ONLY IF INVERTER DOES NOT HAVE AN INTEGRATED D.C. DISCONNECT


NOTE: A LEASED SYSTEM MAY INCLUDE A SEPARATE METER PROVIDED AND INSTALLED BY THE LEASING COMPANY.

1. LEASED METER WILL NOT BE INSTALLED BETWEEN PRODUCTION METER AND MAIN SERVICE PANEL.
- ALL PV SYSTEMS MUST COMPLY WITH THE LATEST REVISION TO CEC ARTICLES 690 AND 705.
- ALL NECESSARY CLEARANCES SHALL COMPLY WITH ALL APPLICABLE CODES.
- ALL SIGNS OR DIRECTORIES SHALL BE ATTACHED TO THE ELECTRIC EQUIPMENT OR LOCATED ADJACENT TO THE IDENTIFIED EQUIPMENT (AS APPROVED BY THE AHI).
- ALL SIGNS SHALL BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT.
- ALL SIGNS SHALL BE PERMANENTLY ATTACHED BY MEANS OF EPOXY OR EQUIVALENT SUITABLE FOR THE ENVIRONMENT (SCREWS OR NUTS ARE NOT ALLOWED).
- ALL SIGNS SHALL BE EITHER METAL OR PLASTIC WITH ENGRAVED LETTERS, MACHINE PRINTED LETTERS, OR ELECTRO-PHOTO PLATING LETTERS IN RED WITH WHITE LETTERING.

DATE	01/09/2026	SCALE	N.T.S.	DESIGN	CEP	DATE	01/09/2026	SCALE	N.T.S.	DESIGN	TD & CS	DATE	01/09/2026	SCALE	N.T.S.	DESIGN	TC
REV		DATE		DESCRIPTION													
<p>BRIGHAM CITY PUBLIC POWER ASSUMES NO LIABILITY FOR ANY DAMAGE TO PROPERTY OR PERSONS OR ANY DAMAGE TO PROPERTY OR PERSONS FROM THE USE OF PHOTOVOLTAIC SYSTEMS. PHOTOVOLTAIC SYSTEMS ARE NOT TO BE INSTALLED IN ANY AREA WHERE THEY COULD BE A HAZARD TO PERSONS OR PROPERTY. PHOTOVOLTAIC SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ALL APPLICABLE CODES AND STANDARDS. PHOTOVOLTAIC SYSTEMS SHALL BE PERMANENTLY ATTACHED BY MEANS OF EPOXY OR EQUIVALENT SUITABLE FOR THE ENVIRONMENT (SCREWS OR NUTS ARE NOT ALLOWED).</p>																	
<p>BRIGHAM CITY CORPORATION 20 North Main Street Brigham City, UT 84302 Tel: (435) 734-6500 www.bcpur.gov</p>																	
<p>BRIGHAM CITY PUBLIC POWER 1455 East Power Plant Road Brigham City, UT 84302 Tel: (435) 734-9824 911W Emergency: (435) 732-9888</p>																	
<p>BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM ENERGY STORAGE - CENTRAL INVERTER (RESIDENTIAL)</p>																	
<p>SHEET E25 OF 1 SHEETS 3</p>																	



**THIS DETAIL SHOWS THE REQUIREMENTS FOR A PHOTOVOLTAIC THREE-PHASE SYSTEM USING MULTIPLE 2-LINE 1-PHASE INVERTERS WITH A NEUTRAL CONNECTION**



**NOTES:**


- A. MAIN SERVICE PANEL MUST COMPLY WITH CEC LATEST REVISION ARTICLES 690.64 AND 705.10 (LABEL).
  - B. UTILITY LOCKABLE A.C. DISCONNECT TO BE LOCATED WITHIN 10'-0" OF SERVICE PANEL. A MINIMUM 10" CLEARANCE IS REQUIRED FROM EDGE OF ANY ENCLOSURE. MUST COMPLY WITH CEC ARTICLES 690.14 (LABEL), 690.17 (LABEL) AND 690.54 (LABEL).
  - C. P.V. GROSS METER TO BE PROVIDED AND INSTALLED BY BRIGHAM CITY PUBLIC POWER AT CUSTOMER'S EXPENSE. METER SOCKET TO BE PROVIDED BY INSTALLER. METER SOCKET SUBMITTAL MUST BE APPROVED BY BRIGHAM CITY PUBLIC POWER PRIOR TO INSTALLATION. A LEASED SYSTEM MAY INCLUDE A SEPARATE METER BETWEEN THE AC DISCONNECT AND P.V. GROSS METER, PROVIDED & INSTALLED BY THE LEASING COMPANY. BRIGHAM CITY PUBLIC POWER WILL ACTIVATE THE PV SYSTEM AFTER IT MEETS ALL REQUIREMENTS, AND PASSES ALL INSPECTION.
  - D. UTILITY LOCKABLE A.C. DISCONNECT MUST BE LOCATED WITHIN 10'-0" OF B AND WITHIN LINE OF SIGHT OF MAIN SERVICE PANEL. A MINIMUM CLEARANCE OF 10" IS REQUIRED FROM EDGE OF ANY ENCLOSURE. MUST COMPLY WITH CEC ARTICLES 690.14 (LABEL), 690.17 (LABEL), AND 690.54 (LABEL).
  - E. INVERTER MUST COMPLY WITH CEC ARTICLE 690.47(C)(1) AND UL1741. GROUNDING ELECTRODE SYSTEM MUST COMPLY WITH CEC ARTICLE 690.47(C)(2) AND UL1741. MULTIPLES OF WIRE IN ORDER TO KEEP ALL PHASES BALANCED. SINGLE-PHASE INVERTERS SHALL NOT BE CONNECTED TO PHASES OF A THREE-PHASE SYSTEM UNLESS THE SYSTEM IS DESIGNED SO THAT SIGNIFICANT UNBALANCED VOLTAGES CANNOT RESULT PER CEC ARTICLE 705.10(K). INVERTER-INTERRUPTED PROTECTION MUST INCLUDE THE FOLLOWING MINIMUM PROTECTIVE FUNCTIONS: PHASE OVERCURRENT, OVERVOLTAGE, UNDERVOLTAGE, OVERFREQUENCY, AND AC GND FAULT.
  - F. D.C. DISCONNECT MUST COMPLY WITH CEC ARTICLES 690.14(A-D), 690.53 (LABEL), 690.7 (LABEL) AND 690.8.
- SEPARATE DC DISCONNECT IS REQUIRED ONLY IF INVERTER HAS AN INTEGRATED (BUT NOT SEPARATED) DC DISCONNECT.
- SIGNS OR DIRECTORIES SHALL BE ATTACHED TO THE ELECTRIC EQUIPMENT OR LOCATED ADJACENT TO THE IDENTIFIED EQUIPMENT. SIGNS SHOULD BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT. ALL PLACES SHALL BE PERMANENTLY ATTACHED TO SURFACE MATERIALS. OUTDOOR SIGNS SHALL BE EITHER METAL OR PLASTIC WITH ENGRAVED OR MACHINE PRINTED LETTERS OR PICTURES. ALL SIGNS SHALL BE OF A CONTRASTING COLOR TO THE SIGN BACKGROUND. SPACE REQUIREMENTS FOR ELECTRIC EQUIPMENT SHALL COMPLY WITH CEC ARTICLE 110.26.

NO. 1	DATE	DESCRIPTION	DATE	DESCRIPTION
2	01/09/2026	N.T.S.	DATE	DESCRIPTION
3	TD & CS	DATE	DESCRIPTION	DATE
4	TC	DATE	DESCRIPTION	DATE
5	DATE	DESCRIPTION	DATE	DESCRIPTION

BRIGHAM CITY PUBLIC POWER	
ELECTRICAL CONSTRUCTION STANDARDS	
PHOTOVOLTAIC THREE-PHASE SYSTEM DIAGRAM USING MULTIPLE TWO-LINE SINGLE-PHASE INVERTERS WITH NEUTRAL CONNECTION	
BRIGHAM CITY Public Power 1455 East Power Plant Road Brigham City, UT 84302 Tel: (435) 734-6624 Utility Emergency: (435) 733-1888	BRIGHAM CITY Corporation 20 North Main Street Brigham City, UT 84302 Tel: (435) 734-6600 www.bcpower.com

**THIS DETAIL SHOWS THE REQUIREMENTS FOR A PHOTOVOLTAIC THREE-PHASE SYSTEM USING A SINGLE THREE-PHASE INVERTER**



**NOTES:**



- A. MAIN SERVICE PANEL MUST COMPLY WITH CEC LATEST REVISION ARTICLES 690.64 AND 705.10 (LABEL).
- B. UTILITY LOCKABLE A.C. DISCONNECT TO BE LOCATED WITHIN 10'-0" OF SERVICE PANEL. A MINIMUM 10" CLEARANCE IS REQUIRED FROM EDGE OF ANY ENCLOSURE. MUST COMPLY WITH CEC ARTICLES 690.14 (LABEL), 690.17 (LABEL) AND 690.54 (LABEL).
- C. P.V. GROSS METER TO BE PROVIDED AND INSTALLED BY BRIGHAM CITY PUBLIC POWER AT CUSTOMER'S EXPENSE. METER SOCKET TO BE PROVIDED BY INSTALLER. METER SOCKET SUBMITTAL MUST BE APPROVED BY BRIGHAM CITY PUBLIC POWER PRIOR TO INSTALLATION. A LEASED SYSTEM MAY INCLUDE A SEPARATE METER BETWEEN THE AC DISCONNECT AND PV GROSS METER. THE METER SHALL BE INSTALLED BY BRIGHAM CITY PUBLIC POWER. BRIGHAM CITY PUBLIC POWER WILL ACTIVATE THE PV SYSTEM AFTER IT MEETS ALL REQUIREMENTS, AND PHASES ARE INSPECTED.
- D. UTILITY LOCKABLE A.C. DISCONNECT MUST BE LOCATED WITHIN 10'-0" OF B. AND WITHIN LINE OF SIGHT OF MAIN SERVICE PANEL. A MINIMUM CLEARANCE OF 10" IS REQUIRED FROM EDGE OF ANY ENCLOSURE. MUST COMPLY WITH CEC ARTICLES 690.14 (LABEL), 690.17 (LABEL), AND 690.54 (LABEL).
- E. INVERTER MUST COMPLY WITH CEC ARTICLE 690.47(C)(1) AND 18.1741. GROUNDING ELECTRODE SYSTEM MUST COMPLY WITH CEC ARTICLE 690.47. INVERTERS MUST BE INSTALLED IN UNBLENDED THIRDS TO GROUND. THE PHOTOVOLTAIC SYSTEM IS DESIGNED SO THAT SIGNIFICANT UNBALANCED VOLTAGES CANNOT RESULT. PER CEC ARTICLE 705.100(A), INVERTER-INTEGRATED PROTECTION MUST INCLUDE THE FOLLOWING MINIMUM PROTECTIVE FUNCTIONS: PHASE OVERCURRENT, OVERVOLTAGE, UNDERVOLTAGE, OVERFREQUENCY, AND AC GND FAULT.
- F. D.C. DISCONNECT MUST COMPLY WITH CEC ARTICLES 690.14(A)-(D), 690.53 (LABEL), 690.7 (LABEL), AND 690.8.

SEPARATE DC DISCONNECT IS REQUIRED ONLY IF INVERTER WAS AN INTEGRATED (BUT NOT SEPARATED) DC DISCONNECT. SIGNS OR DIRECTORIES SHALL BE ATTACHED TO THE ELECTRIC EQUIPMENT OR LOCATED ADJACENT TO THE IDENTIFIED EQUIPMENT. SIGNS OR DIRECTORIES SHALL BE PERMANENTLY ATTACHED TO SURFACE OR ELECTRICAL EQUIPMENT BY MEANS OF EPOXY, SCREWS, OR NAILS. OUTDOOR SIGNS SHALL BE ENGRAVED OR MACHINE PRINTED LETTERS, OR ELECTRO-PHOTO PLATING, IN A CONTRASTING COLOR TO THE SIGN BACKGROUND SPACE REQUIREMENTS FOR ELECTRIC EQUIPMENT SHALL COMPLY WITH CEC ARTICLE 110.26.

REV	DATE	DESCRIPTION	DESIGNER	DATE	SCALE	PROJECT	DATE	BY
			CEP	01/09/2026	N.T.S.	BRIGHAM CITY PUBLIC POWER		
			TD & CS					
			TC					
<p>BRIGHAM CITY PUBLIC POWER ELECTRICAL CONSTRUCTION STANDARDS PHOTOVOLTAIC SINGLE-PHASE SYSTEM DIAGRAM USING A SINGLE THREE-PHASE INVERTER</p>							<p>BRIGHAM CITY PUBLIC POWER 1455 East Power Plant Road Brigham City, UT 84302 Tel: (435) 734-6600 Utility Emergency: (435) 733-0888</p>	<p>BRIGHAM CITY CORPORATION 20 North Main Street Brigham City, UT 84302 Tel: (435) 734-6600 www.bcp.com</p>
<p>BRIGHAM CITY PUBLIC POWER ASSUMES NO LIABILITY FOR ANY DAMAGE TO PERSONS OR PROPERTY CAUSED BY THE USE OR MISUSE OF THE INFORMATION CONTAINED IN THESE ELECTRICAL STANDARDS UNLESS THE USER HAS ADVISED BRIGHAM CITY PUBLIC POWER AND HAS BEEN ADVISED OF THE LIMITATIONS OF THE STANDARDS AND ADVISED THAT BRIGHAM CITY PUBLIC POWER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE OR LIABILITY WITHOUT THEIR CONSENT.</p>							<p>BRIGHAM CITY E28 OF 1 SHEETS</p>	







ID NUMBER	WIRE DESCRIPTION	TRIMMING PRIORITY
1	PRIMARY LINES (HIGH VOLTAGE)	PRIORITY 1 (URGENT)
2	SECONDARY LINES	PRIORITY 2
3	STREET LIGHTS	PRIORITY 3
4	POWER SERVICE DROP	PRIORITY 3
5	COMMUNICATION LINES (TELEPHONE, CABLE, FIBER, INTERNET)	NOT MAINTAINED BY PUBLIC POWER

**TRIMMING SCHEDULE**  
 FOR ILLUSTRATIVE PURPOSES, NOT TO SCALE.

DATE	01/09/2026	SCALE	N.T.S.	DRAWN	BEB	CHECKED	TD & CS
BY							
DATE							
BY							
DATE							
BY							
<b>BRIGHAM CITY CORPORATION</b> 20 North Main Street Brigham City, UT 84302 Tel: (435) 734-6000 www.bccorpn.gov							
<b>BRIGHAM CITY PUBLIC POWER</b> 1455 East Tower Point Road Brigham City, UT 84302 Tel: (435) 734-4824 Utility Emergency: (435) 734-8884							
<b>ELECTRICAL - VEGETATION MANAGEMENT STANDARDS</b>							
<b>TREE AND VEGETATION TRIMMING AND CLEARING DETAILS</b>							
SCALE	V1						
OF 1 SHEET							




**BRIGHAM CITY  
AGENDA ITEM FOR CITY COUNCIL MEETING**

- 1. INITIATED BY: Tom Kotter
  
- 2. DEPARTMENT OR DIVISION: Administration
  
- 3. DATE INITIATED: February 03, 2026
  
- 4. BRIEF EXPLANATION OF PROPOSED ACTION (ATTACH OTHER DOCUMENTATION AS NECESSARY):  
Resolution declaring certain two-way radio equipment surplus and authorizing donation to Box Elder County

- 5. ESTIMATED TIME NEEDED: 5 Min
  
- 6. PROPOSED DATE FOR COUNCIL ACTION: February 05, 2026
  
- 7. EXPLANATION OF DEADLINE, IF APPLICABLE:

8. REVIEW

<u>Date</u>	<u>Name</u>	<u>Signature</u>	<u>Attachment</u>
February 03, 2026	Tom Kotter	 <small>*Signed via GovOS.com Key: 323521ea-7128-4d35-668a-a32095a6d47c</small>	✓

9. MAYOR'S SIGNATURE:

  
\*Signed via GovOS.com  
Key: 609a8e0c-e6b3-440c-bd98-27088d4ab2c

**RESOLUTION NO. 26-\_\_\_\_\_**  
**A RESOLUTION DECLARING CERTAIN TWO-WAY RADIO EQUIPMENT  
SURPLUS AND AUTHORIZING DONATION TO BOX ELDER COUNTY**

**WHEREAS**, Brigham City owns certain two-way radio equipment that is no longer needed for City operations; and

**WHEREAS**, the City Council finds that this equipment is surplus to the City's needs; and

**WHEREAS**, donation of the surplus equipment to **Box Elder County** serves a public purpose.

**NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF BRIGHAM CITY, UTAH:**

1. The City Council hereby declares the City's surplus two-way radio equipment to be surplus property.
2. The City Council authorizes the donation of the surplus two-way radio equipment to **Box Elder County**.
3. The equipment is donated **AS-IS, WHERE-IS**, without warranty.
4. The Mayor or City Administrator, or their designee, is authorized to take all actions necessary to complete the transfer.
5. This Resolution shall be effective immediately upon adoption.

PASSED AND ADOPTED this \_\_\_\_\_ day of \_\_\_\_\_, 2026.

BRIGHAM CITY

\_\_\_\_\_  
Dennis J Bott, Mayor

ATTEST:

\_\_\_\_\_  
Kristina Rasmussen, City Recorder