

ADDENDUM #1

2026 Street Maintenance

The following changes are hereby made to the Contract Documents for the above referenced Project:

1. Revised Document, Bid Schedule 1 Bidders shall use the revised Bid Schedule when submitting their bids. Bids received using previous Bid Schedule may be deemed non-responsive. Changes made to the bid schedule include the following:
 - a. 2600 N: Line Items #6 and #7 quantities reduced
 - b. 2925 N: Line Item #7 quantity reduced
 - c. 2550 N: Line Item #7 quantity reduced
 - d. King Hill Drive: Line Item #8 quantity reduced, and Line Item #10 reduced and unit changed from sy to ton.
 - e. 3650 N: Line Item #7 quantity reduced

This Addendum is hereby attached to and made part of the Bidding Documents and each Bidder shall acknowledge receipt of this Addendum on the Bid Form.

MEASUREMENT AND PAYMENT**BID SCHEDULE 1
NORTH OGDEN CITY
2026 Street Maintenance**

CONTRACTOR: _____

2600 N: 450 E – 1050 E

Item #	M&P Reference	Bid Item Description	Estimated Quantity	Unit	Unit Price*	Extended Price
1	3.2.2	Mobilization	1	ls	\$	\$
2	3.2.3	Traffic Control	1	ls	\$	\$
3	3.2.5	Spot Mill Travel Lanes 2" Depth	5500	sy	\$	\$
4	3.2.12	2" Overlay	5500	sy	\$	\$
5	3.2.14	Chip Seal (Class C Chip) & CSS-1 Fog Coat	25,850	sy	\$	\$
6	3.2.15	Adjust Manhole	20	ea	\$	\$
7	3.2.15	Adjust Water Valve Box	25	ea	\$	\$
8	3.2.15	Adjust Survey Monument	1	ea	\$	\$
9	3.2.16	Street Striping	1	ls	\$	\$

Total Base Bid: \$ _____***Unit Price shall contain no more than 2 decimal points (e.g., \$0.00)**

MEASUREMENT AND PAYMENT**2925 N: 1050 E – 3050 N**

Item #	M&P Reference	Bid Item Description	Estimated Quantity	Unit	Unit Price*	Extended Price
1	3.2.2	Mobilization	1	ls	\$	\$
2	3.2.3	Traffic Control	1	ls	\$	\$
3	3.2.7	Remove ±3" Asphalt	4,600	sy	\$	\$
4	3.2.8	Remove Base Course (UTBC) (Estimated 5%)	155	cy	\$	\$
5	3.2.9	Subgrade Stabilization (Estimated 5%)	230	cy	\$	\$
6	3.2.10	Untreated Base Course 8" Depth (UTBC)	155	cy	\$	\$
7	3.2.11	Furnish and Install 3" Bituminous Surface Course	800	ton	\$	\$
8	3.2.14	Chip Seal (Class A Chip) & CSS-1 Fog Coat	4,600	sy	\$	\$
9	3.2.15	Adjust Manhole	15	ea	\$	\$
10	3.2.15	Adjust Water Valve Box	8	ea	\$	\$
11	3.2.15	Adjust Survey Monument	3	ea	\$	\$

Total Base Bid: \$ _____***Unit Price shall contain no more than 2 decimal points (e.g., \$0.00)**

MEASUREMENT AND PAYMENT**1050 E: 2750 N – 2600 N**

Item #	M&P Reference	Bid Item Description	Estimated Quantity	Unit	Unit Price*	Extended Price
1	3.2.2	Mobilization	1	ls	\$	\$
2	3.2.3	Traffic Control	1	ls	\$	\$
3	3.2.4	Asphalt Patching	170	sy	\$	\$
4	3.2.5	Mill Travel Lanes 2" Depth (24' Total Width)	1,000	sy	\$	\$
5	3.2.12	2" Overlay	1,000	sy	\$	\$
6	3.2.14	Chip Seal (Class C Chip) & CSS-1 Fog Coat	7,725	sy	\$	\$
7	3.2.15	Adjust Manhole	6	ea	\$	\$
8	3.2.15	Adjust Water Valve Box	10	ea	\$	\$
9	3.2.15	Adjust Survey Monument	1	ea	\$	\$
10	3.2.16	Street Striping	1	ls	\$	\$

Total Base Bid: \$_____***Unit Price shall contain no more than 2 decimal points (e.g., \$0.00)**

MEASUREMENT AND PAYMENT**2550 N: CITY LIMITS – 160 W**

Item #	M&P Reference	Bid Item Description	Estimated Quantity	Unit	Unit Price*	Extended Price
1	3.2.2	Mobilization	1	ls	\$	\$
2	3.2.3	Traffic Control	1	ls	\$	\$
3	3.2.7	Remove ±3" Asphalt (25.5' Total Width)	1,000	sy	\$	\$
4	3.2.8	Remove Base Course (UTBC) (Estimated 5%)	35	cy	\$	\$
5	3.2.9	Subgrade Stabilization (Estimated 5%)	50	cy	\$	\$
6	3.2.10	Untreated Base Course 8" Depth (UTBC)	35	cy	\$	\$
7	3.2.11	Furnish and Install 3" Bituminous Surface Course	175	ton	\$	\$
8	3.2.15	Adjust Manhole	1	ea	\$	\$
9	3.2.15	Adjust Water Valve Box	1	ea	\$	\$
10	3.2.16	Street Striping	1	ls	\$	\$

Total Base Bid: \$ _____***Unit Price shall contain no more than 2 decimal points (e.g., \$0.00)**

MEASUREMENT AND PAYMENT**3100 N: CITY LIMITS – MOUNTAIN VIEW DRIVE**

Item #	M&P Reference	Bid Item Description	Estimated Quantity	Unit	Unit Price*	Extended Price
1	3.2.2	Mobilization	1	ls	\$	\$
2	3.2.3	Traffic Control	1	ls	\$	\$
3	3.2.4	Asphalt Patching	225	sy	\$	\$
4	3.2.5	Mill Travel Lanes 2" Depth (24'-36' Width)	13,170	sy	\$	\$
5	3.2.12	2" Overlay	13,170	sy	\$	\$
6	3.2.14	Chip Seal (Class C Chip) & CSS-1 Fog Coat	20,120	sy	\$	\$
7	3.2.15	Adjust Manhole	20	ea	\$	\$
8	3.2.15	Adjust Water Valve	10	ea	\$	\$
9	3.2.15	Adjust Storm Drain Box	6	ea	\$	\$
10	3.2.16	Street Striping	1	ls	\$	\$

Total Base Bid: \$_____***Unit Price shall contain no more than 2 decimal points (e.g., \$0.00)**

MEASUREMENT AND PAYMENT

KING HILL DRIVE: 3659 N – 3550 N

Item #	M&P Reference	Bid Item Description	Estimated Quantity	Unit	Unit Price*	Extended Price
1	3.2.2	Mobilization	1	ls	\$	\$
2	3.2.3	Traffic Control	1	ls	\$	\$
3	3.2.6	Edge Mill (7' Width)	760	sy		
4	3.2.7	Remove ±3" Asphalt	1,760	sy	\$	\$
5	3.2.8	Remove Base Course (UTBC) (Estimated 5%)	60	cy	\$	\$
6	3.2.9	Subgrade Stabilization (Estimated 5%)	90	cy	\$	\$
7	3.2.10	Untreated Base Course 8" Depth (UTBC)	60	cy	\$	\$
8	3.2.11	Furnish and Install 3" Bituminous Surface Course	310	ton	\$	\$
9	3.2.12	2" Overlay	2,860	sy	\$	\$
10	3.2.13	Leveling Course	235	ton	\$	\$
11	3.2.14	Chip Seal (Class A Chip) & CSS-1 Fog Coat	4,620	sy	\$	\$
12	3.2.15	Adjust Manhole	7	ea	\$	\$
13	3.2.15	Adjust Water Valve	15	ea	\$	\$

Total Base Bid: \$_____

***Unit Price shall contain no more than 2 decimal points (e.g., \$0.00)**

MEASUREMENT AND PAYMENT**3650 N: 434 E – 472 E**

Item #	M&P Reference	Bid Item Description	Estimated Quantity	Unit	Unit Price*	Extended Price
1	3.2.2	Mobilization	1	ls	\$	\$
2	3.2.3	Traffic Control	1	ls	\$	\$
3	3.2.7	Remove ±3" Asphalt	2,510	sy	\$	\$
4	3.2.8	Remove Base Course (UTBC) (Estimated 5%)	85	cy	\$	\$
5	3.2.9	Subgrade Stabilization (Estimated 5%)	125	cy	\$	\$
6	3.2.10	Untreated Base Course 8" Depth (UTBC)	85	cy	\$	\$
7	3.2.11	Furnish and Install 3" Bituminous Surface Course	440	ton	\$	\$
8	3.2.15	Adjust Manhole	4	ea	\$	\$
9	3.2.15	Adjust Water Valve	3	ea	\$	\$

Total Base Bid: \$_____***Unit Price shall contain no more than 2 decimal points (e.g., \$0.00)**

Bidder acknowledges that (1) each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and (2) estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all unit price Bid items will be based on actual quantities, determined as provided in the Contract Documents.

MEASUREMENT AND PAYMENT**BID SCHEDULE 2
NORTH OGDEN CITY
2026 Street Maintenance**

CONTRACTOR: _____

LEGACY NORTH SUBDIVISION**525 E (2550 N-Legacy Drive), Legacy Drive- (2300 N-End), 2500 N (525 E-Cul-de-Sac), 2450 N (525 E-Cul-de-Sac), 2400 N (525 E-Cul-de-Sac), 2350 N (Legacy Drive- Cul-de-Sac)**

Item #	M&P Reference	Bid Item Description	Estimated Quantity	Unit	Unit Price*	Extended Price
1	3.2.2	Mobilization	1	ls	\$	\$
2	3.2.3	Traffic Control	1	ls	\$	\$
3	3.2.4	Asphalt Patching	110	sy	\$	\$
4	3.2.6	Edge Mill (7' Width)	3,700	sy	\$	\$
5	3.2.12	2" Overlay	11,650	sy	\$	\$
6	3.2.14	Chip Seal (Class A Chip) & CSS-1 Fog Seal	11,650	sy	\$	\$
7	3.2.15	Adjust Manhole	28	ea	\$	\$
8	3.2.15	Adjust Water Valve Box	25	ea	\$	\$
9	3.2.15	Adjust Survey Monument	15	ea	\$	\$
10	3.2.15	Adjust Storm Drain Box	1	ea	\$	\$

Total Base Bid: \$ _____***Unit Price shall contain no more than 2 decimal points (e.g., \$0.00)**

Bidder acknowledges that (1) each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and (2) estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all unit price Bid items will be based on actual quantities, determined as provided in the Contract Documents.