

Meeting Procedures

Outline of Meeting Procedures:

- ❖ The Chair will call the meeting to order, read the opening meeting statement, and then introduce the item.
- ❖ The typical order is for consent items, old business, and then any new business.
- ❖ Please respect the right of other participants to see, hear, and fully participate in the proceedings. In this regard, anyone who becomes disruptive, or refuses to follow the outlined procedures, is subject to removal from the meeting.

Role of Staff:

- ❖ Staff will review the staff report, address the approval criteria, and give a recommendation on the application.
- ❖ The Staff recommendation is based on conformance to the general plan and meeting the ordinance approval criteria.

Role of the Applicant:

- ❖ The applicant will outline the nature of the request and present supporting evidence.
- ❖ The applicant will address any questions the Planning Commission may have.

Role of the Planning Commission:

- ❖ To judge applications based upon the ordinance criteria, not emotions.
- ❖ The Planning Commission's decision is based upon making findings consistent with the ordinance criteria.

Public Comment:

- ❖ The meeting will then be open for either public hearing or comment. Persons in support of and in opposition to the application or item for discussion will provide input and comments.
- ❖ The commission may impose time limits for comment to facilitate the business of the Planning Commission.

Planning Commission Action:

- ❖ The Chair will then close the agenda item from any further public comments. Staff is asked if they have further comments or recommendations.
- ❖ A Planning Commissioner makes a motion and second, then the Planning Commission deliberates the issue. The Planning Commission may ask questions for further clarification.
- ❖ The Chair then calls for a vote and announces the decision.

Commenting at Public Meetings and Public Hearings

Public comment may NOT be heard during Administrative items, the Planning Division Project Manager may be reached at 801-399-8371 before the meeting if you have questions or comments regarding an item.

Address the Decision Makers:

- ❖ When commenting please step to the podium and state your name and address.
- ❖ Please speak into the microphone as the proceedings are being recorded and will be transcribed to written minutes.
- ❖ All comments must be directed toward the matter at hand.
- ❖ All questions must be directed to the Planning Commission.
- ❖ The Planning Commission is grateful and appreciative when comments are pertinent, well organized, and directed specifically to the matter at hand.

Speak to the Point:

- ❖ Do your homework. Obtain the criteria upon which the Planning Commission will base their decision. Know the facts. Don't rely on hearsay and rumor.
- ❖ The application is available for review in the Planning Division office.
- ❖ Speak to the criteria outlined in the ordinances.
- ❖ Don't repeat information that has already been given. If you agree with previous comments, then state that you agree with that comment.
- ❖ Support your arguments with relevant facts and figures.
- ❖ Data should never be distorted to suit your argument; credibility and accuracy are important assets.
- ❖ State your position and your recommendations.

Handouts:

- ❖ Written statements should be accurate and either typed or neatly handwritten with enough copies (10) for the Planning Commission, Staff, and the recorder of the minutes.
- ❖ Handouts and pictures presented as part of the record shall be left with the Planning Commission.

Remember Your Objective:

- ❖ Keep your emotions under control, be polite, and be respectful.
- ❖ It does not do your cause any good to anger, alienate, or antagonize the group you are standing in front of.



WEBER COUNTY PLANNING COMMISSION MEETING

MEETING AGENDA

July 7, 2026

Pre-meeting 4:30 p.m./Regular meeting 5:00 p.m.



- Pledge of Allegiance:
- Roll Call:

1. Legislative

1.1 ZMA2026-04: A request for a public hearing and consideration regarding an application to amend the county's zoning map to rezone approximately 12.3 acres, located at approximately 1940 South, 4700 West, from the A-1 zone to the R1-15 zone.

Applicant: Jordan Holmes, **Staff:** Charlie Ewert

1.2 ZTA 2026-04: A request for a public hearing comment on a proposal to amend the Weber County Code. The amendments pertain to minimum setback and height requirements in the F-1 (formerly the FR-1) Zone, uses in the R-3 (formerly FR-3) Zone, and proposed zoning text amendments relating to minimum fencing requirements. Amending and clarifying provisions, repurposing, simplifying or otherwise amending certain zones, certain development standards and certain processes to better tailor Weber County land use ordinances for optimal efficiency and effectiveness of governance of land use and development in the unincorporated areas.

to amend uses and minimum setbacks in the F-1 Zone, as well as include adjustments to fencing requirements.

Staff Presenter: Tammy Aydelotte

2. Administrative:

2.1 LVL051926: Consideration and action on a request for preliminary approval of the Longhorn East Subdivision, also known as the Meibos Development. The residential single-family development plan includes 211 lots and 7.5 acres of park space built in accordance with the Meibos Zoning Development Agreement. Located at 6700 West 700 South.

Staff Presenter: Felix Lleverino

2.2 LVR061526: Consideration and action on a request for preliminary subdivision approval of the Riverbend Farms Phase 1 Amendment 1 Subdivision, consisting of 10 single family lots within an area previously platted as agricultural open space with additional open space of 3.02 acres being dedicated along the Weber River Corridor. Located at 900 South 3600 West.

Staff Presenter: Felix Lleverino

3. Public Comment for Items not on the Agenda:

4. Remarks from Planning Commissioners:

5. Planning Director Report:

6. Remarks from Legal Counsel:

Adjourn to Work session

WS1: Discussion regarding a proposed rezone on Wagstaff property in West Weber.

The regular meeting will be held in the Weber County Commission Chambers, in the Weber Center, 1st Floor, 2380 Washington Blvd., Ogden, Utah. in the Weber Center, 1st Floor, 2380 Washington Blvd., Ogden, Utah.

Public comment may not be heard during administrative items. Please contact the Planning Division Project Manager at 801-399-8371 before the meeting if you have questions or comments regarding an item.

In compliance with the Americans with Disabilities Act, persons needing auxiliary services for these meetings should call the Weber County Planning Commission at 801-399-8371



Weber County Planning Division

Staff Report to the Weber County Planning Commission

Synopsis

Application Information

Application Request: **ZMA2026-04:** A request for a public hearing and consideration regarding an application to amend the County’s zoning map to rezone approximately 12.3 acres, located at approximately 1940 South, 4700 West, from the A-1 zone to the R1-15 zone.

Agenda Date: July 7, 2026

Applicant: Jordan Holmes

File Number: ZMA2026-04

Frontier Project Link: <https://frontier.co.weber.ut.us/p/Project/Index/26846>

Property Information

Approximate Address: 1940 South, 4700 West, Unincorporated West Weber

Current Zone(s): A-1 Zone

Proposed Zone(s): R1-15 Zone

Adjacent Land Use

North: Agriculture and rural residential (SFD) **South:** Agricultural and rural and medium-lot residential (SFD)

East: High School **West:** Agriculture and rural residential (SFD)

Staff Information

Report Presenter: Charlie Ewert
cewert@webercountyutah.gov
801-399-8763

Report Reviewer: RG

Applicable Ordinances

§Title 102, Chapter 5 Rezone Procedures.
 §Title 104, Chapter 2 Agricultural Zones.
 §Title 104, Chapter 12 Residential Zones.

Legislative Decisions

When the Planning Commission acts as a recommending body to the County Commission on a zoning map amendment, it acts in a legislative capacity. Legislative decisions allow broad discretion. Examples of legislative actions include general plan amendments, zoning map amendments, and land use code amendments.

For this application, the Planning Commission is asked to hold a public hearing and make a recommendation to the County Commission. In making that recommendation, the Planning Commission should review the proposal for compatibility with the General Plan, applicable ordinances, and the broader public health, safety, and welfare.

Summary and Background

This is an application to rezone approximately 12.3 acres from the A-1 Zone to the R1-15 Zone. The Planning Commission has not previously reviewed this proposal. The Applicant requested that the customary Planning Commission work session be waived to expedite consideration of the application. Given the relatively small size and standard nature of the proposal, the Planning Commission may find that a work session is not necessary before forwarding a recommendation to the County Commission.

The application appears generally consistent with recent expectations for similar rezones in the following ways:

- The Applicant proposes expected street and pathway connectivity, including access from 4700 West and a connection through or near the new Single Tree Acres development to the southeast.

Figure 2: Concept Plan



The Weber County Land Use Code includes procedures and criteria for application-driven rezones. The following policy analysis evaluates the requested rezone in the context of the Land Use Code, the Western Weber General Plan, and applicable planning considerations.

Zoning Analysis – Purposes and Intent

The current zone of the subject property is A-1. **Figure 3** displays current zoning of the general area. The purpose and intent of the A-1 zone is to:

1. *Designate low-intensity farm areas, which are anticipated to develop in a rural residential development pattern;*
2. *Set up guidelines to continue agricultural pursuits, including the keeping of farm animals; and*
3. *Direct orderly low-density residential development in a continuing rural environment.*¹

The Applicant proposes rezoning the subject property to the R1-15 Zone. The R1-15 Zone is one of the districts within the County's R1 residential zoning classification. The purpose of the R1 Zone is as follows:

*"... The purpose of the R1 zone is to provide regulated areas for single-family dwelling uses at four different low-to-medium density levels. The R1 zone includes the R1-15, R1-12, R1-10, and R1-5 zones. [...]"*²

The proposed rezone is illustrated in Figure 4, with the yellow border outlining the proposed R1-15 zone polygon.

The R1-15 Zone is designed to support a variety of single-family lot sizes at a density no greater than 2.9 units to the acre, provided no lot is smaller than 6,000 square feet. The R1-15 zone was specifically designed to support the residential directives prescribed by the Western Weber General Plan for this area.


¹ Weber County Code Section 104-2-1.

² Weber County Code Section 104-12-1.

Figure 3: Current Zoning Map and the Subject Property



Figure 4: Proposed Zoning Map and the Subject Property.



Zoning Analysis – Ordinance Criteria

Weber County Code provides six general decision criteria for determining whether a rezone is merited. They are as follows:

- a. *Whether the proposed amendment is consistent with goals, objectives, and policies of the County's general plan.*
- b. *Whether the proposed amendment is compatible with the overall character of existing development in the vicinity of the subject property, and if not, consideration of the specific incompatibilities within the context of the general plan.*
- c. *The extent to which the proposed amendment may adversely affect adjacent property.*
- d. *The adequacy of facilities and services intended to serve the subject property, including, but not limited to, roadways, parks and recreation facilities, police and fire protection, stormwater drainage systems, water supplies, wastewater, and refuse collection.*
- e. *Whether the proposed rezone can be developed in a manner that will not substantially degrade natural/ecological resources or sensitive lands.*
- f. *Whether proposed traffic mitigation plans will prevent transportation corridors from diminishing below an acceptable level of service.*

The following is an analysis of the proposal in the context of each criterion.

(a) Whether the proposed amendment is consistent with goals, objectives, and policies of the County's general plan.

As a legislative decision, a rezone should advance the goals of the General Plan, or, at a minimum, should not be detrimental to them without good cause. The General Plan is a guiding document rather than a mandatory development regulation. However, because it expresses the County's desired future community outcomes, deviations from the General Plan should be approached with caution and supported by appropriate findings.

With the considerations provided in staff's recommendation and the standards typically included in the County's development agreement template, the proposal appears to follow the overall intent of the Western Weber General Plan.

The vision expressed in the General Plan's community character chapter provides an important lens for interpreting the Plan's goals and policies. It reads as follows:

"While the pressure to grow and develop will persist, there is a clear desire for growth to be carefully and deliberately designed in a manner that preserves, complements, and honors the agrarian roots of the community. To do this, Weber County will promote and encourage the community's character through public space and street design standards, open space preservation, and diversity of lot sizes and property uses that address the need for places for living, working, and playing in a growing community."³

To achieve this vision, the General Plan prioritizes implementation of smart growth principles as the area develops. The General Plan encourages the County to use the rezone process as an opportunity to help developers and landowners obtain the benefits of rezoning while also securing community benefits that protect the public health, safety, and welfare.

Because the General Plan is general in nature, its principles are not mandatory unless they have been adopted into the County's development regulations or voluntarily incorporated into a development agreement. Similarly, approval of a rezone is not mandatory. The rezone process therefore provides an opportunity for the County and the Applicant to consider mutually beneficial terms that help implement the General Plan.

General Plan Smart Growth Principles

The Western Weber General Plan identifies basic and exemplary smart growth principles. Among the basic smart growth principles are (1) street connectivity, (2) pathway and trail connectivity, (3) open space and recreation

³ Western Weber General Plan (p. 21)


facilities, (4) dark sky considerations, (5) culinary and secondary water conservation planning, (6) emissions and air quality considerations.

The proposal's relationship to these principles is discussed throughout this report.

The General Plan also identifies exemplary smart growth principles. These principles are aspirational unless otherwise adopted into ordinance or voluntarily included in a development agreement. They are nevertheless relevant to the Planning Commission's legislative review because they help describe the kind of development pattern the General Plan seeks to encourage. The following are most relevant to this application.

- *Provision for a wide variety of housing options and use of tools such as lot-averaging to create smaller lots/housing that responds to the needed moderate-income housing of the area.*
 - The proposal is anticipated to be exclusively single-family residential. However, the flexible lot standards of the R1-15 Zone and the County's connectivity standards allow a variety of lot sizes. Smaller lots may be more affordable than larger lots, which may allow the Applicant to market homes to prospective single-family homeowners at different stages of life.

Figure 5: General Plan's Future Land Use Map



- Lot size variety is not mandatory in the R1-15 zone but enabled by allowing small minimum lot area (6,000sqft in the R1-15 zone) whilst capping density at a smaller number (2.9 units to the acre in the R1-15 zone) than might otherwise be allowed in a development where all lots are as small as the minimum lot area. This allows some lots to be smaller than the average lot size that would otherwise result if every lot were required to match the overall density cap. In turn, that may help provide a larger supply of smaller lots, which may help respond to housing cost pressures in the area.
- If the Planning Commission desires to discuss deed-restricted moderate-income housing, that discussion should be framed as a potential voluntary commitment to be negotiated through the development agreement, rather than as a standard requirement of the R1-15 Zone.
- *Strong trail network with excellent trail connectivity that prioritizes ease of bicycling and pedestrians.*
 - Because the proposal includes approximately 12.3 acres, it can be challenging to determine how trail connectivity should be realized for the immediately surrounding area. For this reason, the connectivity standards recently adopted in County Code apply a pathway-intersection interval of no greater than 400 feet. A pathway connectivity interval occurs where a pathway intersects with another pathway, trail, or sidewalk, including sidewalks that are part of a street right-of-way.
 - The proposal includes two north/south pathway corridors through the project. One appears to parallel or overlap an existing farm ditch. The other parallels 4520 West Street and connects to a pathway in the new Single Tree Acres subdivision. This would extend the 4520 West Street pathway for almost three-quarters of the distance between 2200 South and 1800 South, both of which are planned to have street-adjacent pathways.
 - One item for the Planning Commission and Applicant to consider is whether the 4520 West Street pathway should be moved out of the street right-of-way and behind the lots that abut the high school property. The County has not yet been successful in securing a pedestrian connection through the school property. However, aligning a pathway along the school boundary may improve the possibility of such a connection in the future.
 - Because the property's north/south width is greater than 400 feet, the County can justify requiring up to two east/west pathways through the proposed development. One east/west pathway through the middle of the project may also satisfy the standard, provided the undeveloped land to the north and south eventually provides east/west pathways within a few hundred feet of the project boundary.
 - The Applicant has not proposed an east/west pathway. That omission may be justifiable for the following reasons:
 - Existing development along the east side of 4700 West limits opportunities to create through connections to 4700 West. There may be some space between existing buildings or along property lines where future connections could occur, but those connections are uncertain unless neighboring landowners choose to allow them
 - A future pathway is planned along the east side of 4700 West as part of the County's plan, the Utah Trails Network plan, and the Beehive Bikeways plan. Given the planned facility, a pathway stub toward 4700 West may still be reasonable even if the ultimate connection is not immediately available.
 - The high school campus east of the property has presented pedestrian connectivity challenges in the block between 4700 West and 4300 West. The school district has thus far prohibited pedestrian connections across the campus. This limits the usefulness of an east/west pathway that would otherwise be aligned through the proposed development.
 - There is also an opportunity, though not an ideal one, to provide an east/west pathway along the northern boundary of the subject property or farther north. The Applicant has informed the County that the landowner does not want such a pathway installed at this time because of continued farming on the property to the north. This presents competing considerations:
 - Requiring a pathway along the northern boundary as part of this development would convert a hypothetical future connection into a real community asset.

- Deferring the pathway may preserve a straighter and more direct future alignment across property farther north.
- The property to the north spans multiple ownerships, which reduces the predictability of future development and may make a later connection more difficult to secure.
- Because the northern boundary of the subject property is south of the northern boundary of the neighboring school property, a pathway along the subject property's northern boundary may eventually require a jog around the school property.
- Figure 5 illustrates some of the potential pathway connections.
- *Strong street connectivity and neighborhood connections that avoid the use of cul-de-sacs or deadends.*
 - As shown on the concept plan, the Applicant has configured the project to provide street connections that appear appropriate in the context of existing development and future developable properties in the area. Additional discussion regarding access, roadway adequacy, and traffic is provided later in this report.
- *Large and meaningful open space areas with improved parks, recreation, etc.*

- The County has not adopted local development standards requiring single-family homes in this area to exceed the applicable building code efficiency requirements. If the Planning Commission and Applicant desire to pursue this principle for this project, it should be addressed only as a voluntary development agreement commitment.
- *Homes that have solar-paneled rooftops and watt-smart compliant batteries.*
 - The General Plan also identifies solar-paneled rooftops and watt-smart compliant batteries as an exemplary smart growth principle. This reflects the Plan's support for energy resilience and reduced utility demand.
 - The County has not adopted development standards requiring rooftop solar or battery systems for single-family homes in this area. If pursued for this project, such provisions should be included only as voluntary commitments in the development agreement.
- *Provisions that create attractive communities for the long term and that create a distinctive sense of place.*
 - The General Plan encourages development that creates attractive communities and a distinctive sense of place. Given the relatively small size of this project and its interior block location, significant sense-of-place improvements may be challenging. However, the proposed pathway connections and the volunteered parks and recreation contribution may help advance this principle.
- *Use of transferable development rights from agricultural lands identified for protection.*
 - The General Plan identifies transferable development rights as an exemplary smart growth tool for preserving agricultural lands. The County has not yet implemented a transferable development right program in this area.
 - Separately, House Bill 237 from the 2025 Utah General Session amended the State's rollback tax regulations to require county treasurers to deposit 100 percent of rollback tax funds into a county account or fund set aside for preserving or restoring open land and agricultural land. This information is provided as context for the General Plan's agricultural preservation policies, not as a recommended condition of this application.

(b) Whether the proposed amendment is compatible with the overall character of existing development in the vicinity of the subject property, and if not, consideration of the specific incompatibilities within the context of the general plan.

The Planning Commission should be able to find that the proposal is generally consistent with the pattern of recent development activity in the area, including the neighboring Single Tree Acres subdivision.

There are several large-lot residential properties along 4700 West, 1800 South, and 2200 South that were developed under one-acre-per-lot zoning standards. Residential development at varying lot sizes is generally more compatible with existing residential development than with nonresidential land uses. However, residents who are accustomed to large-acreage lots and nearby agricultural operations may view the proposed density as inconsistent with the existing rural character.

The Western Weber General Plan acknowledges that some incompatibilities may occur as the area develops over time. If the General Plan is followed, the surrounding area is expected to transition toward a pattern that is more similar to the proposed development than to the area's current agricultural and large-lot residential character. For that reason, staff finds that the proposed rezone is compatible with the area's planned future character, even though it may be more intense than some existing nearby development.

(c) The extent to which the proposed amendment may adversely affect adjacent property.

A rezone can affect adjacent properties in several ways. These may include objective impacts, such as traffic, noise, infrastructure demand, drainage, and service levels. They may also include perceived or character-based impacts, such as changes to neighborhood identity, rural atmosphere, and expectations about future development.

Staff recommends that the Planning Commission prioritize fact-based impacts while also recognizing that perceived impacts may be relevant to a legislative decision.

If rezoned, the proposed development and others like it will likely change the immediate area. Existing and future streets may need to be upgraded, new streets will be constructed, and small, medium, and medium-large residential lots should be expected. The proposed development will likely change the visual character of the area, traffic volumes and patterns, and potential noise levels.

That said, the proposed use is single-family residential and is not expected to generate impacts greater than those typically associated with a residential neighborhood. During subdivision review, the Applicant will be responsible for addressing any material degradation in services and infrastructure caused by the development. As a result, most objective impacts are expected to be mitigated through standard development review and improvement requirements.

Staff also recognizes that some neighboring residents may perceive the proposal as inconsistent with the rural character they value. Adjacent property owners do not have a legal right to preserve neighboring zoning classifications indefinitely. However, those concerns may still be considered by the Planning Commission as part of its legislative recommendation, particularly when weighing the proposal against the long-term vision of the General Plan.

(d) The adequacy of facilities and services intended to serve the subject property, including, but not limited to, roadways, parks and recreation facilities, police and fire protection, stormwater drainage systems, water supplies, wastewater, and refuse collection.

The County's adopted development regulations are intended to require each development to address its impact on local service levels and infrastructure. As noted above, the Applicant will be responsible for mitigating material degradation caused by the development.

Roadways/Traffic.

See criterion (f) herein.

Police and Fire Protection

The proposed development is not expected to generate a greater per capita demand for police or fire protection than typical single-family residential development.

Stormwater Drainage Systems

Stormwater drainage is not typically resolved at the time of rezoning unless there are known regional drainage issues affecting the property. In most cases, drainage is more appropriately addressed when specific construction drawings are submitted during subdivision review.

Water Supply

The property is located within the Taylor West Weber Water Improvement District boundaries. The Applicant has provided a letter from the district acknowledging the rezone application and the potential for the district to serve the development. The Applicant has also provided a will-serve letter from Hooper Irrigation.

Wastewater

The project is proposed to be served by sewer that will be routed through County collection lines to the Central Weber Sewer Improvement District gravity trunkline in the area. The Applicant has provided a will-serve letter from Central Weber Sewer.

Refuse Collection

At this time, the development is expected to be served by the County's typical contracted garbage collection service. If a different arrangement is proposed, it can be addressed during subdivision review.

(e) Whether the proposed rezone can be developed in a manner that will not substantially degrade natural/ecological resources or sensitive lands.

Staff is unaware of any natural, ecological, or sensitive lands affecting the property.

(f) Whether proposed traffic mitigation plans will prevent transportation corridors from diminishing below an acceptable level of service.

The concept plan indicates access from 4700 West and to 2200 South through the Single Tree Acres subdivision to the southeast. Additional access opportunities may become available as surrounding properties develop.

Because 4700 West is a state highway, the Applicant will be required to obtain any necessary permits from UDOT and provide any required 4700 West improvements needed to mitigate the development's impacts. 2200 South was

1. *Example: Add a requirement for roadside beautification, water wise vegetation, and street art/décor to the development agreement for the two collector streets in the development. Include decorative night sky friendly street lighting at reasonable intervals. Require the creation of a homeowner's association to operate and maintain.*
2. *Example: Amend staff's consideration item # []. It should instead read: [desired edits here].*
3. *Etc.*

I do so with the following findings:

Example findings:

1. *The proposed changes are supported by the General Plan. [Add specifics explaining how.]*
2. *The proposal serves as an instrument to further implement the vision, goals, and principles of the General Plan*
3. *The changes will enhance the general health, safety, and welfare of residents.*
4. *[Example: allowing short-term rentals runs contrary to providing affordable long-term rental opportunities]*
5. *Etc.*

Motion to recommend denial:

I move we forward a recommendation for **denial** to the County Commission for File #ZMA2026-04, an application to amend the county's zoning map to rezone approximately 12.3 acres, located at approximately 1940 South, 4700 West, from the A-1 zone to the R1-15 zone. **I do so with the following findings:**

Examples findings for denial:

- *Example: The proposal is not adequately supported by the General Plan.*
- *Example: The proposal is not supported by the general public.*
- *Example: The proposal runs contrary to the health, safety, and welfare of the general public.*
- *Example: The area is not yet ready for the proposed changes to be implemented.*
- *[add any other desired findings here].*

Exhibits

Exhibit A: Application Information.

Exhibit B: Template Development Agreement.



Exhibit A: Application
Information

Application

Project Description Single family housing, affordable housing.

Property Address 2057-2087 S 4520 W
Weber County, UT, 84401

Property Owner Jordan Holmes

Representative Jordan Holmes

Accessory Dwelling Unit False

Current Zoning A-1

Subdivision Name

Number of new lots being created 30

Lot Number

Lot Size .25

Frontage

Culinary Water Authority Taylor-West Weber Water District

Secondary Water Provider Hooper Irrigation Company

Sanitary Sewer Authority Central Weber Sewer

Nearest Hydrant Address

Signed By Owner, Jordan Holmes

Parcel Number

150800020

150800018

SITE LAND USE SUMMARY	SF	AC	%
Parcel Area	482152	11.07	100%
ROW	156520	3.59	32.5%
Lots	315621	7.25	65.5%
Retention	8254	0.19	1.7%
Site Total	482152	11.03	100%

SCALE: 1" = 50'
 DATE: 6/29/2026
 DESIGNER: JJS
 DRAWN: JJS
 CHECKED: TIM

DATE	REVISIONS	DESCRIPTION

JUNE 29, 2026
 PROFESSIONAL STRUCTURAL ENGINEER
 No. 4859845
 TYLER M. NIELSON
 LICENSED
 STATE OF UTAH
 DWG:

CONCEPT 4
 MARTIN PROPERTY
 1950 S. 4700 W.
 WEBER COUNTY, UTAH 84404

GARDNER ENGINEERING
 CIVIL • LAND PLANNING
 MUNICIPAL • LAND SURVEYING
 5150 SOUTH 375 EAST OGDEN, UT
 OFFICE: 801.476.0202 FAX: 801.476.0066

C4



RA 0023 - HARD ROCK EXCAVATION-216 MARTIN PROPERTY DESIGN\DWG\MARTIN PROPERTY CONCEPT 4.DWG



Central Weber Sewer Improvement District

June 3, 2026

Felix Llevernio
Weber County Planning Commission
2380 Washington Blvd #240, Ogden, UT 84401

SUBJECT: Martini Farms
Sanitary Sewer Service
Will Serve Letter

Felix:

We have reviewed the request Jordan Holmes to provide sanitary sewer treatment services to the Martini Farms comprising 34 residential lots located at approximate address 4520 South 2057 West, Weber County. We offer the following comments regarding Central Weber providing sanitary sewer service.

1. At this time, Central Weber Sewer Improvement District (District) has the capacity to treat the sanitary sewer flow from this subdivision. Inasmuch as the system demand continuously changes with growth, this assessment is valid for three (3) years from the date issued on this letter.
2. If any connection is made directly into the District's facilities the connection must be constructed in accordance with District standards and must be inspected by the District while the work is being done. **A minimum of 48-hour notice for inspection shall be given to the District prior to any work associated with the connection.**
3. Central Weber Sewer Improvement District is a wholesale wastewater treatment provider to Weber County. Connection to the sewer system must be through a retail provider, which we understand to be Weber County. The District will not take responsibility for the condition, ownership or maintenance of the proposed sanitary sewer lines (gravity or pressure) or system that will be installed to serve this subdivision.
4. The connection of any sump pumps (or similar type pumps) to the sanitary sewer system is prohibited during or after construction. The District's Wastewater Control Rules and Regulations state:



Central Weber Sewer Improvement District

Prohibited Discharge into Sanitary Sewer. No person shall discharge or cause or make a connection which would allow to be discharged any storm water, surface water, groundwater, roof water runoff or subsurface drainage to any sanitary sewer.

5. **The entire parcel of property to be served must be annexed into the Central Weber Sewer Improvement District prior to any sewer service connection or connection to the District's facilities.** This annexation must be complete before the sale of any lots in the subdivision. Annexation into the District is permitted by the District's Board of Trustees. This will serve letter is a statement of available capacity and does not guarantee board approval of annexation.
6. Impact fees must be paid no later than the issuance of any building permits.

If you have any further questions or need additional information, please let us know.

Sincerely,

Clay Marriott

Project Manager

CC: Chad Meyerhoffer, Weber County
Kevin Hall, Central Weber Sewer
Paige Spencer Central Weber Sewer
Jordan Holmes



June 3, 2026

Weber County Planning Commission
2380 Washington Blvd, Ste #240
Ogden, Utah 84401

RE: PRELIMINARY WILL SERVE LETTER – Martini Farms Subdivision

Martini Farms Subdivision is located at approximately 2000 South and 4700 West in Weber County and has proposed a total of 32 lots. The subdivision is in the boundaries of the Hooper Irrigation Company service area.

The subdivision preliminary plat has been reviewed by Hooper Irrigation. The plans have been preliminarily approved for the subdivision. The developer owns sufficient water shares to connect to the secondary pressurized system. The plan review is good only for a period of one year from the date of this letter, if not constructed. A final will serve letter will follow this letter after final fees have been paid and water shares submitted for connection to the secondary system.

Hooper Irrigation's specifications are available at the Company office.

If you have questions, please call 801-985-8429.

Sincerely,

A handwritten signature in black ink that reads "Michelle Pinkston". The signature is written in a cursive style and is placed over a light blue rectangular background.

Michelle Pinkston
Hooper Irrigation
Board Secretary

1. Parks and open space will depend on lot layout and sizing.
2. Red lines show where the proposed trail system will be installed and connect to existing developments.

A red scalloped border surrounds the text.

Exhibit B: Draft
Development
Agreement - From
Template

DEVELOPMENT AGREEMENT

Between

WEBER COUNTY, UTAH

and

[Master Developer Name]

Table of Contents

Table of Contents..... 2

DEVELOPMENT AGREEMENT..... 4

RECITALS..... 4

AGREEMENT TERMS..... 4

1. Incorporation of Recitals and Exhibits..... 4

2. Effective Date, Expiration, Termination..... 5

3. Definitions and Interpretation..... 6

4. Conflicting Provisions..... 9

5. Vested Rights and Reserved Legislative Powers..... 9

6. Project Description..... 11

7. Project Location and Illustration..... 11

8. Development Standards..... 11

9. Amendments, Modifications, and Revisions..... 25

10. Miscellaneous Provisions..... 26

11. General Provisions..... 28

12. Notices..... 31

13. Default and Remedies..... 32

14. Entire Agreement..... 33

15. Covenants Running with the Land..... 33

16. Counterparts..... 33

SIGNATURES..... 35

Exhibit A – Property Legal Description..... 38

Exhibit B – Property Graphic Depiction..... 39

Exhibit C – Concept Plan..... 40

Exhibit D – Associated Rezone Area..... 41

Exhibit E – Street Cross Sections..... 42

Exhibit F – Non-Street-Adjacent Pathway Cross Section..... 45

Exhibit G – Corridor Fence Design Examples..... 46

Exhibit H – Waterwise Yard Landscape Plan Requirements..... 47

Exhibit I – Trailhead Conceptual Design and Improvements **Error! Bookmark not defined.**

Exhibit J – Architectural Design Requirements..... **Error! Bookmark not defined.**

DEVELOPMENT AGREEMENT

Development Name

THIS DEVELOPMENT AGREEMENT ("Agreement") is entered into by and between Weber County, Utah ("County") and *[Master Developer Name]* ("Master Developer"), known together herein as the "Parties."

RECITALS

WHEREAS, The Master Developer desires and intends to develop a *residential* subdivision (the "Project") in the unincorporated area of Weber County known as *West-Central Weber*;

WHEREAS, The Master Developer's objective is to develop in a manner that complements the character of the community and is financially successful;

WHEREAS, The County's objective is to only approve development that supports and advances the health, safety, and welfare of the community, as generally described in the general plan and as otherwise determined appropriate by the Board of County Commissioners;

WHEREAS, Development of the Property pursuant to this Agreement will result in benefits to the County by providing orderly growth, sustainable development practices, street and pathway connectivity, provisions for open space, dark sky lighting, and assurances to the County that the Property will be developed in accordance with this Agreement;

WHEREAS, Entering into this Agreement will result in significant benefits to the Master Developer by providing assurances to Master Developer that it will have the ability to develop the Property in accordance with this Agreement;

WHEREAS, Master Developer and the County have cooperated in the preparation of this Agreement;

WHEREAS, Prior to the execution of this Agreement, the Property's zone is/was *[Prior Zone]* and Master Developer desires to rezone the Property to the *[Proposed Zone]* zone consistent with the terms and provisions contained herein;

WHEREAS, The parties desire to enter into this Agreement as a legislative means to specify the rights and responsibilities of the Master Developer to develop the Property as part of the Project as expressed in this Agreement and the rights and responsibilities of the County to allow and regulate such development pursuant to the requirements of the Agreement; and

WHEREAS, The Project will be located on land referred to herein as the "Property". The Property is as more specifically described in **Exhibit A – Property Legal Description** and illustrated in **Exhibit B – Property Graphic Depiction**. A Concept Plan showing the general location and layout of the Project is contained in **Exhibit C – Concept Plan**.

NOW, THEREFORE, in consideration of the recitals (which are incorporated into the Agreement by this reference), the mutual covenants contained herein, and for other good and valuable consideration, the receipt and sufficiency of which is hereby acknowledged, the Parties agree as follows:

AGREEMENT TERMS

1. Incorporation of Recitals and Exhibits.

The foregoing Recitals and **Exhibits A-[X]** are hereby incorporated into this Agreement.

2. Effective Date, Expiration, Termination.

2.1. Effective Date. The Effective Date of this Agreement is the latter of:

2.1.1. The last date upon which it is signed by any of the Parties hereto;

2.1.2. The recordation of this Agreement; or

2.1.3. The recordation of the rezone ordinance to which this Agreement is associated and inextricably linked.

2.2. Expiration and Zone Reversion.

2.2.1. Expiration of Agreement Related To Development of the Property. The expiration of this Agreement as it relates to the development of the Property or the establishment of new uses on the Property shall be as provided in **Section 2.2.3** of this Agreement, unless earlier terminated or modified by written amendment as set forth herein, or unless the use is abandoned as governed by the Code. In the case of abandonment, this Agreement shall terminate on the date abandonment has been determined. Upon expiration or termination of this Agreement, the portion of the Property that has not been developed as set forth in this Agreement, including any parcel or portion of parcel that could be further developed, shall thereafter be governed as follows:

2.2.1.1. the rights and responsibilities set forth herein related to establishing new development on the Property or establishing new uses on the Property shall terminate; at which time the rights and responsibilities of the Prior Zone shall govern remaining development or the establishment of new uses on the Property; and

2.2.1.2. the portion of the Property that has not been developed as set forth in this Agreement shall automatically revert to the Prior Zone without further Notice, unless the legislative body decides to keep the existing zone or rezone the Property in any other manner. The Parties agree that should zone reversion occur, the process due and provided for the adoption of this Agreement and related rezone accomplishes the process due for the zone map to be reverted to the Prior Zone, and any future owners of any portion of the Property are hereby on notice accordingly. Existing development and uses lawfully established under this Agreement prior to expiration or termination shall be deemed nonconforming rights, as governed by the Code and the Act.

2.2.1.3. After the expiration or termination of this agreement, the legislative body may make changes to the zoning provisions established in **Section 2.2.1.1** and **Section 2.2.1.2** pursuant to their typical legislative authority.

2.2.2. Expiration of Agreement Related to Ongoing Performance Responsibilities. Notwithstanding the expiration or termination of this Agreement, all ongoing operations, performance, and maintenance responsibilities such as, but not limited to, compliance with requirements pertaining to outdoor lighting, landscaping, noise, berming, buffering, screening, parks, pathways, or building or architectural designs shall remain in effect as legislatively adopted land use provisions that govern any development that has occurred on the Property pursuant to this Agreement. After the expiration or termination of this Agreement, typical legislative action shall be required to make changes thereto. This provision shall not be interpreted to be a restriction on the County's legislative

power to act otherwise if deemed appropriate at that time by the legislative body.

2.2.3. Term. This agreement expires five years after the Effective Date.

2.2.3.1. Automatic Renewal. If prior to the expiration of this agreement Master Developer has not been notified of any Default, or if any Default has been satisfactorily cured or is in the process of being satisfactorily cured as provided herein, then this Agreement shall be automatically extended for an additional five years.

2.2.3.2. Reserved.

2.3. Termination. This Agreement may be terminated by mutual written agreement of the Parties to this Agreement. This Agreement automatically terminates, without notice, in the following circumstances:

2.3.1. The term of this Agreement expires and is not extended as provided above;

2.3.2. The Project is abandoned or the use is discontinued, as provided for by Weber County Code **Chapter 108-12**.

2.3.3. The Master Developer defaults on any provision of this Agreement and the default is not resolved as specified in **Section 13** of this Agreement; or

2.3.4. The provisions of **Section 5.4** of this agreement take effect.

3. Definitions and Interpretation.

For purposes of this Agreement, the following terms, phrases, words, and their derivations shall have the meaning given herein where capitalized; words not defined herein shall have the same meaning as provided by the Code, if applicable. When consistent with the context, words used in the present tense include the future, words in the plural number include the singular number, words in the singular number include the plural number, and the use of any gender shall apply to all genders whenever the context requires. The words "shall" and "will" are mandatory and the word "may" is permissive. References to governmental officials or entities refer to those officials or entities and their Successors. If specific provisions of law referred to herein are renumbered, then the reference shall be read to refer to the renumbered provision.

3.1. Act means the County Land Use, Development, and Management Act, Utah Code Ann. **§§17-27a-101**, et seq.

3.2. Approval Date. "Approval Date" means the date the Board of County Commissioners approved this Agreement.

3.3. Agreement means this Development Agreement between the County and Master Developer, approved by the Board of County Commissioners, and executed by the undersigned, including all of this Agreement's exhibits.

3.4. Applicant means a person or entity submitting a Development Application, a Modification Application or a request for an Administrative Decision.

3.5. Assignee means a person or entity that assumes the rights and responsibilities of Master Developer pursuant to a valid assignment, as provided in **Section 11.4** of this Agreement.

3.6. Board of County Commissioners means the elected County Commission of Weber County.

3.7. Building Permit means the County's building permit or building permit review process, as specified in the Code of Ordinances of Weber County.

- 3.8. **Buildout** means the completion of all of the development on all of the Property for all of the Project.
- 3.9. **Code** means the County's Code containing its land use regulations adopted pursuant to the Act.
- 3.10. **Concept Plan** means **Exhibit C – Concept Plan**, a conceptual plan for the Project which is hereby approved by the County as part of this Agreement. The Concept Plan sets forth general guidelines for the proposed future development of the Property.
- 3.11. **County** means Weber County, a political subdivision of the State of Utah.
- 3.12. **County Consultants** means those outside consultants employed by the County in various specialized disciplines such as traffic, hydrology, legal, or drainage for reviewing certain aspects of the development of the Project.
- 3.13. **Default** means a material breach of this Agreement.
- 3.14. **Design Review** means the County's design review process, as specified in the Code.
- 3.15. **Development Application** means an application to the County for development of a portion of the Project including a Subdivision, a Design Review, a Building Permit, or any other permit, certificate, or other authorization from the County required for development of the Project.
- 3.16. **Development Standards** means a set of standards approved by the County as a part of the approval of the Concept Plan and this Agreement controlling certain aspects of the design and construction of the development of the Property including setbacks, building sizes, height limitations, parking and signage; and, the design and construction standards for buildings, roadways, and other Improvements.
- 3.17. **Effective Date.** "Effective Date" has the meaning set forth in **Section 2** of this Agreement.
- 3.18. **Force Majeure Event** means any event beyond the reasonable control of the affected Party that directly prevents or delays the performance by such Party of any obligation arising under this Agreement, including an event that is within one or more of the following categories: condemnation; expropriation; invasion; plague; drought; landslide; tornado; hurricane; tsunami; flood; lightning; earthquake; fire; explosion; epidemic; pandemic; quarantine; war (declared or undeclared), terrorism or other armed conflict; material physical damage to the Project caused by third parties; riot or similar civil disturbance or commotion; material or supply delay; other acts of God; acts of the public enemy; blockade; insurrection, riot or revolution; sabotage or vandalism; embargoes; and, actions of governmental or judicial authority.
- 3.19. **Impact Fees** means those fees, assessments, or payments of money imposed by the County as a condition on development activity as specified in Utah Code Ann., §§ 11-36a-101, et seq.
- 3.20. **Improvements** means those improvements of public or private infrastructure which are specified in this Agreement, by the Code, or as a condition of the approval of a Development Application because they are necessary for development of the Property, such as local roads or utilities.
- 3.21. **Master Developer** means *[name of Master Developer]* or its Assignees as provided in **Section 11.4** of this Agreement.
- 3.22. **Modification Application** means an application to amend this Agreement.
- 3.23. **Non-County Agency** means a governmental entity, quasi-governmental entity, or water or sanitary sewer authority, other than those of the County, which has jurisdiction over the approval of any aspect of the Project.
- 3.24. **Notice** means any notice to or from any Party to this Agreement that is either required or

permitted to be given to another Party.

- 3.25. **Outsourc[e][ing]** means the process of the County contracting with County Consultants to provide technical support in the review and approval of the various aspects of a Development Application as is more fully set out in this Agreement.
- 3.26. **Owner** means *the same as Master Developer*.
- 3.27. **Parcel** means any parcel of land within the Property created by any means other than a Subdivision plat, upon which development is not approved.
- 3.28. **Parties** means the Master Developer and the County, including their Successors.
- 3.29. **Pathway** means a 10-foot wide multi-use paved pathway that complies with **Exhibit E – Street Cross Sections** or **Exhibit F – Non-Street-Adjacent Pathway Cross Section** of this Agreement and any other requirements of the County Engineer.
- 3.30. **Phase or Phasing** means the development of a portion of the Project at a point in a logical sequence as determined by Master Developer but in compliance with the Code and this Agreement.
- 3.31. **Planning Commission** means the Planning Commission for the area in which the Property is located.
- 3.32. **Prior Zone** means the zone in effect prior to the rezone to which this Agreement is linked.
- 3.33. **Project** means the development to be constructed on the Property pursuant to this Agreement with the associated public and private facilities and all of the other aspects approved as part of this Agreement including its exhibits.
- 3.34. **Property** means the land area on which the Project will be sited, as more specifically described in **Exhibit A – Property Legal Description** and **Exhibit B – Property Graphic Depiction**.
- 3.35. **Proposed Taxing Entity or Proposed Tax** means the proposed inclusion of the Property within a taxing entity's area, or within the area of a specific tax, when the Property was not subject to the taxing entity or tax at the time this Agreement was executed, and when the taxing entity or tax is proposed to compensate for the provision of at least one public service or Improvement resulting from the growth and development of the Property or the general area. A Proposed Taxing Entity or Proposed Tax includes but is not limited to the proposed inclusion of the Property into a municipality, special service district, special district, assessment area, or any similar entity or tax.
- 3.36. **Public Landscaping** means landscaping Improvements within street rights-of-way, in required Public Park Open Space, and on other properties owned by a public entity or required to be open to the public.
- 3.37. **Public Park Open Space** means the area intended to meet the minimum 10 acres per 1,000 residents of public open space, whether improved or unimproved as may be specified in this Agreement.
- 3.38. **Routine and Uncontested** means simple and germane to the Project or Property, having very little chance of affecting the general character of the area, and not anticipated to generate meaningful concern from the public.
- 3.39. **Smart Watering Controller** is an automatic landscape watering controller that can connect to the internet to automatically adjust watering schedules or amounts based on local weather and environmental conditions, such as an Orbit B-Hyve smart controller or a Rainbird ESP smart controller.

- 3.40. **Subdeveloper** means an entity not “related” (as determined by Internal Revenue Service regulations) to Master Developer which purchases a Parcel for Subdivision platting prior to development thereon.
- 3.41. **Subdivision** means the division of any portion of the Project into a subdivision pursuant to the Act and/or the Code.
- 3.42. **Subdivision Application** means the application to create a Subdivision.
- 3.43. **Successor** means a person or entity that succeeds to a Party’s rights and responsibilities under this Agreement by any means, whether in whole or in part, and whether directly or indirectly. It does not include a purchaser or other transferee to whom Master Developer or its Successor conveys a lot within an approved subdivision.

4. **Conflicting Provisions**

The Code shall apply to each Development Application except as the County’s Vested Laws are expressly modified by this Agreement (including any written provision in exhibits thereto). For any conflict between the exhibits and this Agreement, this Agreement shall prevail. For any conflict between exhibits and each other, the most restrictive for Master Developer shall apply. The Parties agree that the graphic depiction of the Project provided in **Exhibit C – Concept Plan** is conceptual in nature and designed to illustrate the general layout and configuration of the Project’s streets, clusters of lots, trails, open spaces, and other amenities to which Master Developer shall be entitled. By nature of being conceptual, these exhibits may not show all specifics necessary for the Project to comply with all County’s Vested Laws, which shall not be interpreted to be an exception to County’s Vested Laws.

5. **Vested Rights and Reserved Legislative Powers.**

- 5.1. **Vested Rights.** Master Developer shall have the Vested Right to develop and construct the Project on the Property in accordance with the *R1-15 zone* and in accordance with **Section 8** of this Agreement (the Vested Rights), subject to compliance with the terms and conditions of this Agreement and other applicable Code provisions in effect as of the Approval Date. The Parties intend that the rights granted to the Master Developer under this Agreement are contractual and also those rights that exist under statute, common law, and at equity.
- 5.2. **Existing Laws.** Except as otherwise specified in this Agreement, the Parties hereby mutually volunteer to the application of the Code, except **Title 102**, in effect at the time of the Approval Date herein, to the Project until this Agreement is terminated or expires. The Code is incorporated into this Agreement by reference.
- 5.3. **Exceptions to Vested Rights.** The Parties understand and agree that the Project may be required to comply with future changes to the Code that do not limit or interfere with the vested rights granted pursuant to the terms of this Agreement. The following are examples for illustrative purposes of a non-exhaustive list of the type of future laws that may be enacted by the County that would be applicable to the Project:
 - 5.3.1. **County Discretion to Apply Future Laws.** County has full discretion to either apply or not apply any future law or adopted standard provided it does not explicitly conflict with any specific provision of this Agreement, except as may be allowed by **Section 5.5** of this agreement.
 - 5.3.2. **Written Agreement.** The Parties may mutually agree, in writing, to the application of future laws to the Project.

- 5.3.3. Compliance with State and Federal Laws.** Future laws which are generally applicable to all properties in the County and which are required to comply with State and Federal laws and regulations affecting the Project.
- 5.3.4. Safety Code Updates.** Future laws that are updates or amendments to existing building, plumbing, mechanical, electrical, dangerous buildings, drainage, or similar construction or safety related codes, such as the International Building Code (IBC), International Residential Code (IRC), the American Public Works Association (APWA) Specifications, American Association of State Highway and Transportation Officials (AASHTO) Standards, the Manual of Uniform Traffic Control Devices (MUTCD), the National Association of City Transportation Officials (NACTO) or similar standards that are generated by a nationally or statewide recognized construction/safety organization, or by the State or Federal governments and are required to meet legitimate concerns related to public health, safety, or welfare;
- 5.3.5. Taxes.** Taxes, or modifications thereto, so long as such taxes are lawfully imposed and charged uniformly by the County to all properties, applications, persons and entities similarly situated;
- 5.3.6. Fees.** Changes to the amounts of fees for the processing of Development Applications that are generally applicable to all development within the County, or a portion of the County as specified in the lawfully adopted fee schedule, and which are adopted pursuant to State law; and
- 5.3.7. Impact Fees.** Impact Fees or modifications thereto which are lawfully adopted, imposed, and collected.
- 5.4. Future Laws and Preservation of Material Obligations.** The Parties acknowledge and agree that the County's approval of this Agreement and the associated rezone is based, in material part, on Master Developer's obligations under this Agreement and on the requirements, limitations, standards, and conditions applicable under the County Code in effect on the Effective Date. Master Developer's performance of those obligations is a material inducement for the County's approval of this Agreement and the associated rezone, and is an essential part of the consideration received by the County.

 - 5.4.1. Future Laws.** For purposes of this Section, "Future Law" means any statute, regulation, ordinance, binding judicial decision, binding administrative order, or other legally binding governmental action that becomes effective after the Effective Date and that creates, recognizes, expands, or applies a right, defense, exemption, limitation, or other legal basis by which Master Developer could avoid, reduce, delay, invalidate, or materially impair any obligation imposed on Master Developer under this Agreement or under the County Code in effect on the Effective Date.
 - 5.4.2. Waiver by Master Developer.** To the maximum extent permitted by law, Master Developer knowingly, voluntarily, and irrevocably waives any right, defense, exemption, limitation, claim, or other legal benefit arising from a Future Law to the extent the Future Law would allow Master Developer to avoid, reduce, delay, invalidate, or materially impair any material obligation imposed on Master Developer under this Agreement or under the County Code in effect on the Effective Date. Master Developer agrees that the obligations described in this Section shall continue to apply as contractual obligations, independent of whether the County could impose the same obligations on similarly situated property under laws enacted after the Effective Date.
 - 5.4.3. Non-Waivable Change in Law.** If a Future Law is not legally waivable, or if Master Developer's waiver under **Subsection 5.4.2** is ineffective to preserve the County's

material benefit of the bargain, the Parties shall confer in good faith to determine whether this Agreement may be amended in a manner that is lawful and that preserves, to the greatest extent practicable, the material obligations, benefits, and burdens originally agreed upon by the Parties.

5.4.4. County Determination. If the County determines, in its reasonable discretion, that a Future Law has materially impaired the County's benefit of the bargain and that the impairment cannot be cured by waiver, performance, or amendment, the County may terminate this Agreement as provided in **Section 2**. The County may instead determine, in writing, to continue this Agreement in effect notwithstanding the Future Law. Any such written determination applies only to the specific Future Law identified in the determination and does not waive the County's rights with respect to any other Future Law or later impairment.

5.5. Reserved Legislative Powers. Master Developer acknowledges that the County is restricted in its authority to limit its police powers by contract and that the limitations, reservations, and exceptions set forth herein are intended to reserve to the County all of its police power that cannot be so limited. Notwithstanding the retained power of the County to enact such legislation under its police powers, any such legislation shall only be applied to modify the Vested Rights of Master Developer based upon policies, facts, and circumstances meeting the compelling, countervailing public interest exception to the Vested Rights doctrine in the State of Utah as codified in Utah Code §17-27a-508, and case law interpreting the same. Any such proposed change affecting the Vested Rights of the Project shall be of general application to all development activity in similarly situated unincorporated areas of the County; and unless in good faith the County declares an emergency, Master Developer shall be entitled to prior written notice and an opportunity to be heard with respect to the proposed change and its applicability to the Project under the compelling, countervailing public interest exception to the Vested Rights doctrine.

6. Project Description.

A residential subdivision within the R1-15 zone that complies with the connectivity requirements of Code **Section 106-2-1.020**.

7. Project Location and Illustration.

The Project is located on the Property as described in **Exhibit A – Property Legal Description**, and illustrated in **Exhibit B – Property Graphic Depiction**.

8. Development Standards.

8.1. Project Density. In exchange for the benefits offered by the Master Developer in this Agreement, County agrees to allow Master Developer to create a residential subdivision at the density allowed by the Code for the R1-15 zone.

8.2. Phasing. The County acknowledges that Master Developer, Assignees of Master Developer, and/or Subdevelopers who have purchased Parcels of the Property may submit multiple applications from time-to-time to develop and/or construct portions of the Concept Plan for the Project in Phases. Allowance for Phasing is subject to the following and any other Phasing provision in this Agreement:

- 8.2.1. **Construction Drawings Required.** Phasing is only allowed if each Phase is based on an approved final plat that succeeds an approved preliminary plat/plan. A final plat for a Phase shall not be submitted or accepted until after a complete set of construction drawings for the entire preliminary plat has been approved by the County Engineer. The construction drawings shall include all required Improvements of this Agreement and the Code.
- 8.2.2. **Streets and Pathways.** Each Phase shall provide for the logical extension of Improvements of the public road and pathways system as conceptually represented in the Concept Plan;
- 8.2.3. **Project Improvements.** Each Phase shall provide logical extension of Improvements through and throughout the Project as approved by the County in compliance with the terms of this Agreement and other applicable provisions of the Code.
- 8.2.4. **Public Park Open Space.** Each Phase shall include its proportionate share of Public Park Open Space area and Improvements including, if applicable, pathways and trailheads. Each Phase shall provide for the platting and installing of a proportionate share of Public Park Open Space area and Improvements, even if such area or Improvements are not within or immediately adjacent to the subject Phase. Developer may propose which Public Park Open Space area and Improvements are provided for each Phase; however, the County has full discretion to require other Public Park Open Space area and Improvements if the County determines it is in the best interest of the community.
- 8.3. **Street Connectivity.** Master Developer hereby volunteers and agrees to follow the minimum street and pathway connectivity standards as provided in **Section 106-2-1.020** of the Code. The County also agrees that the conceptual street layout illustrated in **Exhibit C – Concept Plan** satisfactorily complies with that code section.
- 8.4. **Street Right-of-Way Dedication.** Master Developer agrees to dedicate or, if allowed by the County, otherwise reserve the Project’s street rights-of-way, as illustrated and labeled in **Exhibit C – Concept Plan**, as public thoroughfares at no cost to the County.
 - 8.4.1. **Minimum Requirements.** Each street right-of-way shall meet the minimum applicable width specifications illustrated in **Exhibit E – Street Cross Sections**.
 - 8.4.2. **Project-Specific Right-of-Way Dedication.**
 - 8.4.2.1. **Reserved.**
 - 8.4.2.2. **Reserved.**
- 8.5. **Street Improvements.** Streets in or immediately adjacent to the Project shall be designed and installed by the Master Developer in accordance with their corresponding street cross sections depicted in **Exhibit E – Street Cross Sections** and as more specifically provided as follows.
 - 8.5.1. **Reserved.**
 - 8.5.2. **Project-Specific Street Improvements.** Project-specific street Improvements include Improvements required to street rights-of-way that are adjacent to the Project, and to offsite streets as follows.
 - 8.5.2.1. **Reserved.**
 - 8.5.2.2. **Reserved.**
 - 8.5.3. **Sidewalks.** Master Developer agrees that all public sidewalks in the project or along

adjacent public rights-of-way shall be no less than five-feet wide.

- 8.5.4. Driveway Accesses along Collector or Arterial Streets.** Master Developer agrees that no lot will be platted to provide driveway access to any collector or arterial street. County agrees to allow these lots to front these streets if they are provided access by means other than these streets.
- 8.5.5. Corridor Fencing along Collector or Arterial Streets.** Master Developer agrees to install a fence or wall ("Corridor Fence") that is at least six-feet high where the rear or side of a lot abuts or is otherwise adjacent to and visible from a collector or arterial street. The height of the Corridor Fence shall be reduced where necessary to not inhibit the clear-view triangle of an intersection.
- 8.5.5.1. Corridor Fence Design.** Corridor Fences of these streets shall be designed to provide visual breaks in the horizontal and vertical fence planes at least every 20 feet, such as a column or similar, and the Corridor Fence shall have a base and a cap distinctly different from the body. Examples of Corridor Fences is provided in **Exhibit G – Corridor Fence Design Examples**.
- 8.5.5.2. Corridor Fence to Match Others in Area.** If in compliance with this part or unless allowed otherwise by the Planning Director, the Corridor Fence material, color, and general design shall match other Corridor Fences installed or previously approved along the same street corridor.
- 8.5.5.3. Corridor Fence Alternative Design.** Alternative fencing along these streets may be approved by the Planning Director if it provides similar or better visual qualities and materials.
- 8.5.5.4. Prohibited Corridor Fence Material.** A Corridor Fence shall not be made of vinyl.
- 8.5.5.5. Corridor Fence Maintenance.** Unless delegated to a community association, the immediately adjoining landowner is responsible for the maintenance and repair of their lot or parcel's portion of the Corridor Fence.
- 8.5.5.6. Reserved.**
- 8.5.6. Street Trees.** All streets shall be lined with shade trees in the parkstrip. Trees lining an adjacent and parallel sidewalk or pathway shall suffice for the street's trees.
- 8.5.6.1. Tree Canopy.** Except as otherwise provided herein, the trees shall be planted in intervals and of a species such that the expected tree crown will converge with the expected tree crown of the trees adjacent. The expected tree crown shall be the average crown of the tree species at maturity. County shall allow for reasonable gaps between expected tree crowns to accommodate driveways, streets, intersection clear-view triangles, and other right-of-way accommodations as determined appropriate by County. A reasonable gap is the width or expected width of the accommodation(s).
- 8.5.6.2. Tree Selection.** At least two different tree varieties selected from County's adopted tree list shall be used and dispersed in a manner that avoids transmission of pests/disease, or as may otherwise be specified by an arborist certified by the International Society of Arborists, such that the trees have optimal chance of long-term survival.
- 8.5.6.3. Tree Size.** No tree with a caliper less than two inches, as measured at the

top of the root collar, shall be planted.

8.5.6.4. Certificate of Occupancy. No final certificate of occupancy for a dwelling unit shall be granted or effective until after the installation of all proposed trees, which shall clearly be in good health, in the parkstrip to which the lot is abutting.

8.5.7. Street Tree Installation and Maintenance Alternatives. Developer has the following two installation and maintenance alternatives options for street trees, or some combination if mutually agreeable by the Developer and Planning Director:

8.5.7.1. Master Developer Controlled:

8.5.7.1.1. Planting. Tree planting shall be in accordance with best practices. Care shall be taken when planting a tree or when placing anything at the base of the tree so that the root's soils are not compacted.

8.5.7.1.2. Tree Watering. Master Developer agrees to provide each street tree with a watering mechanism tied either to a homeowner's association master meter, or tied directly to the meter providing secondary water to the lot fronting the street Improvements. County may allow alternative tree watering methods if Master Developer:

8.5.7.1.2.1. can provide a watering plan that the County determines sufficient and appropriate for the health of the tree; and

8.5.7.1.2.2. volunteers to be responsible for tree care, pursuant to **Section 8.5.6.1.6**, for an additional two years after the end of the warranty period.

8.5.7.1.3. Tree Care. Master Developer agrees to be responsible for tree health throughout the duration of the warranty period, after which the owner of the lot fronting the Improvements is responsible for the tree's health.

8.5.7.2. County Controlled:

8.5.7.2.1. At Master Developer's expense, County shall employ or contract with an arborist certified by the International Society of Arborists to install the trees. Master Developer shall provide a cash escrow for the full estimated cost of the installation as is typically required, including reasonable contingency costs, reasonable costs for tree replacements, and reasonable costs required for the County to operate such tree planting program. Cost for tree replacement shall be based on the average rate of establishment failure of the tree species within the first year. If requested by the County, Master Developer agrees to periodically increase the escrow or reimburse the County to cover reasonable costs resulting from increases in labor and materials and/or inflation. Master Developer further agrees that County has full authority to draw from this escrow at any time to pay for the installation of street

trees.

8.5.7.2.2. For this alternative, County agrees to waive the required warranty period for the trees.

8.5.7.2.3. Master Developer agrees on behalf of itself and future lot owners that no final certificate of occupancy shall be issued for any building until after the required trees and appropriate and operating irrigation mechanisms for the trees are installed. County shall have full authority, based on recommendations from its tree professional, to determine what constitutes an appropriate and operating irrigation mechanism.

8.5.7.2.4. If no appropriate and operating irrigation mechanism is provided, Master Developer agrees to compensate County for reasonable costs to routinely irrigate installed trees by whatever reasonable means necessary. County may recoup this cost from the adjoining lot owner if unable to recoup from Master Developer.

8.5.7.2.5. Master Developer shall provide each lot owner notice upon each lot sale of the tree installation program, including the owner's responsibility for long-term irrigation and tree maintenance pursuant to the Code.

8.5.7.2.6. Master Developer agrees that regardless of the escrowed amount and regardless of the submitted or approved tree or landscaping plan, that the County has sole discretion over the number and type of trees planted within the development provided that the funds shall be used for reasonable costs associated with the installation of trees within the development.

8.5.8. Public Landscaping. The following are required for required landscaping within public rights-of-way and along public pathways:

8.5.8.1. Other Landscaping. Except around the base of a tree (root area), Master Developer shall place six-inch-plus angular rock, 10-inches deep, in each parkstrip, with a weed barrier beneath. Plantings in addition to street and pathway trees may be placed within parkstrips and along pathways by the Master Developer or homeowners, to be operated and maintained either by the adjoining owner or a homeowners association.

8.5.8.2. Construction Drawings to Include Landscaping. Each Development Application submitted shall provide a detailed Public Landscape plan that, at a minimum, shows landscaping materials proposed to be used, the proposed location, species, including the measurements of each tree's mature crown, and the method of vegetation irrigation.

8.5.8.3. Quality Control. For best practices quality control, planting shall be conducted based on the recommendations from, and under the supervision of, an arborist certified by the International Society of Arborists. Written confirmation that best practices and provisions of this Agreement pertaining to Public Landscaping were followed for each planting or installation shall be provided to the County from the arborist, along with the certification

number of the arborist, prior to the release of any financial guarantee for the Public Landscaping.

8.5.9. Offsite or Project-Specific Street Improvements. Master Developer agrees to construct, or cause to be constructed, the following.

8.5.9.1. Reserved.

8.5.9.2. Reserved.

8.5.9.3. Reserved.

8.5.9.4. Reserved.

8.5.10. Secondary Egress.

8.5.10.1. Master Developer agrees that as the project is platted and constructed, street improvements shall be installed such that at no time shall there be more than 15 lots or dwelling units on a single access street or route of streets before a second egress is installed. The second egress shall not loop back on any part of the single access street or route of streets.

8.5.10.2. Project-Specific Egress Requirements.

8.5.10.2.1. Reserved.

8.5.10.2.2. Reserved.

8.6. Non-Public Landscaping to be Water-Wise. Except within a publicly accessible park, if applicable, all lots within the development will implement water-wise landscaping measures as follows.

8.6.1. Water-wise landscaping. All lots within the development will implement water wise landscaping measures as follows:

8.6.1.1. Landscaping Pursuant to a Yard Landscape Plan. A yard landscape plan shall be submitted with each building permit application for a primary structure and be in compliance with **Exhibit H – Waterwise Yard Landscape Plan Requirements**.

8.6.1.2. Reserved.

8.6.2. Project-Specific Water-Wise Requirements.

8.6.2.1. The requirements of this Section 8.6 shall not apply to a lot or area that is xeriscaped and no sprinkler or flood watering is used.

8.6.2.2. Reserved.

8.6.2.3. Reserved.

8.7. Utilities.

8.7.1. Burying Utilities. Master Developer agrees to underground all utilities, both existing and proposed, within the Property and within any right-of-way adjacent to the Property in a manner that complies with adopted standards. This shall include but is not limited to canals, ditches, stormwater infrastructure, and existing overhead utilities. Long distance high voltage power transmission lines are exempt from this requirement.

8.7.2. Sanitary Sewer. Prior to issuance of the first Building Permit for the Project, Master Developer shall have the right and the obligation to construct or cause to be constructed a sewer collection and conveyance system.

- 8.7.2.1. Reserved.**
- 8.7.2.2. Sewer Collection Service from County.** County agrees to allow the Project to be connected to County's sewer collection system, provided compliance with this Agreement and the Code; and provided compliance with County standards, which may be updated from time-to-time.
- 8.7.2.3. Sewer Treatment.** Master Developer recognizes that County is not a provider for sewer treatment services. Master Developer shall arrange sewer treatment services for the Project with a provider prior to submittal of a Development Application. If within an existing sewer district's adopted future annexation area, Master Developer agrees to annex the Property into the sewer district boundaries, if the sewer district allows it, prior to submittal of a Development Application. If the sewer district does not allow the annexation, County agrees that Master Developer may pursue other sewer treatment options that do not involve the County.
- 8.7.2.1. Gravity Sewer Collection Lines.** Master Developer agrees to install, or cause to be installed, a gravity sanitary sewer collection system to, throughout, and across the Property. The system shall stub to all lots or parcels within the Project that needs or will in the future need a sewer connection, and to adjacent properties in locations approved by the County Engineer, including, if applicable, offsite parcels to which **Section 36-1-1** of the Code applies. It shall be of sufficient size and at sufficient depth necessary to gravity-flow the anticipated future buildout volume of sewage of the general area intended to be served by it, as shown on the sewer master plan or as required by the County Engineer.
 - 8.7.2.1.1. Reserved. [See note].**
 - 8.7.2.1.2. Reserved. [See note].**
- 8.7.2.2. Reserved. [see note.]**
- 8.7.2.3. Reserved. [see note.]**
- 8.7.2.4. Project-Specific Sanitary Sewer Requirements.**
 - 8.7.2.4.1. Reserved.**
 - 8.7.2.4.2. Reserved.**
- 8.7.3. Culinary and Secondary Water.** Master Developer recognizes that the County does not provide culinary or secondary water to the area and has no obligation to help Master Developer gain access to water services. Prior to issuance of the first Building Permit for the Project, Master Developer shall have the right and the obligation to construct or cause to be constructed culinary water and pressurized secondary water Improvements to and across the Property. Master Developer agrees to secure both culinary and secondary water from an existing culinary and secondary water provider in the area.
- 8.7.4. Stormwater.** Master Developer shall have the right and obligation to install a storm water drainage and detention system sufficient to support the storm water and drainage needs of the Project and adjacent public streets. The system shall be sized to support the anticipated storm water and drainage needs of the Project at full build-out such that multiple new drainage or detention facilities are avoided if possible in the future. The County Engineer has discretion to require the storm water facilities to be sized to accommodate the general area's anticipated storm water and drainage needs at the

area's buildout or as otherwise recommended by the stormwater master plan. Unless otherwise allowed by the County Engineer, the storm water from the Project shall be sufficiently treated, as approved by County Engineer, before discharging into the Weber River or other water body.

8.7.4.1. Stormwater Storage Ownership and Maintenance. The County reserves the right to require the maintenance of a stormwater storage facility to be the responsibility of a homeowner's or landowner's association in the event the County Engineer determines that the proposed facility presents an inordinate demand for services.

8.7.4.2. Reserved.

8.7.4.3. Project-Specific Stormwater Requirements.

8.7.4.3.1. Reserved.

8.7.4.3.2. Reserved.

8.7.5. Project-Specific Utility Requirements.

8.7.5.1. Reserved.

8.7.5.2. Reserved.

8.8. Parks and Open Space. Master Developer agrees to help the County reach its goal of providing at least ten acres of Public Park Open Space per 1,000 persons. Master Developer understands that the creation and/or preservation of parks and open space is a critical part of the County's consideration for this Agreement, the associated rezone, and the additional density given. Further, the Parties agree that the per-dwelling unit cost to build parks to this standard in 2024 dollars equals approximately \$7,500.00. Given this, Master Developer agrees to provide, at no cost to the County, for the following parks, open space, and trails amenities:

8.8.1. Parks Financial Donation. *Master Developer agrees to donate \$7,500, adjusted by the annual rate of inflation, per residential lot to the County or, if required by the County, the [Park District] ("Park District"). The inflation-adjusted amount will be calculated using the "Consumer Price Index for All Urban Consumers: All Items," using \$7,500.00 in 2024 dollars as the baseline. Master Developer agrees that this is a donation offered of the Master Developer's own free will as part of the consideration for this Agreement and associated rezone, which is a voluntary development choice made by Master Developer in lieu of developing using the Prior Zone. As such, this donation is not a fee or exaction imposed by the County or Park District. Master Developer agrees to remit these funds prior to recordation of a subdivision plat. Master Developer hereby relinquishes control over how the County spends the donated funds, provided that the funds shall be used for reasonable costs associated with providing Public Park Open Space or recreational trails in an unincorporated area of the County. No building division or planning division application will be accepted or approved, and any that are approved shall be void, until the County receives this donation or a written confirmation of receipt of it from the Park District, if applicable.*

8.8.2. Park Dedication. *Master Developer agrees to dedicate a minimum of one acre per every 34 residential lots as Public Park Open Space, with the open space rounded up to the nearest whole acre, if applicable. Open space provided by Master Developer in excess of the minimum required Public Park Open Space is not governed by this Section 8.8.2. unless more specifically provided in this Agreement. The minimum required Public Park Open Space shall comply with the following.*

- 8.8.2.1. Dedication Method.** Unless specified otherwise in this Agreement, the minimum acreage per lot shall be dedicated to the County by means of subdivision plat dedication. County may require it be dedicated to the [Park District] (“Park District”) instead. County may allow the acreage to be transferred in fee or easement if County determines it appropriate.
- 8.8.2.2. Deferred Conveyance.** County may defer dedication or conveyance, including any required Improvements, for any of the minimum required Public Park Open Space only if deferral is in the best interest of the public. This deferral shall be by means of a separate mutually acceptable agreement, recorded to the property to run with the land, and shall specify the terms of the deferral.
- 8.8.2.3. Publicly Accessible Private Parks.** When allowed, the acreage of a private park that is continuously open for public use may be counted toward the minimum required Public Park Open Space, provided compliance with the following.

 - 8.8.2.3.1.** Master Developer shall provide County with a written recommendation on this matter from the Park District.
 - 8.8.2.3.2.** The private park shall be open for use by the general public from sunrise until dusk or 9:00 PM daily, whichever is earlier, excluding reasonable closures for emergencies, maintenance, replacement, or repair; and
 - 8.8.2.3.3.** The private park shall be operated and maintained by a professional management company that is funded by the owners in the Project.
- 8.8.2.4. Follow Concept Plan.** The configuration of Public Park Open Space shall be as generally represented in the Concept Plan. Open space shown on the Concept Plan shall be interpreted as Public Park Open Space unless clearly labeled otherwise, or unless rejected by the County and Park District.
- 8.8.2.5. Phasing Public Park Open Space Dedication.** Each subdivision plat within the Property shall plat and dedicate no less than its pro-rata share of Public Park Open Space acreage per lot, but never less than one acre until all proposed Public Park Open Space is platted.
- 8.8.2.6. Reserved,**
- 8.8.2.7. Other Waterways.** County may require open space corridors along creeks, sloughs, canals, or other waterways or former waterways specified in the general plan or others that can provide valuable public open space or pathway connectivity to be dedicated.
- 8.8.2.8. Project-Specific Parks or Open Space Dedication.**

 - 8.8.2.8.1. Reserved.**
 - 8.8.2.8.2. Reserved.**
- 8.8.3. Public Park Open Space Improvements.** Master Developer agrees, unless specified in this Agreement otherwise, that the Public Park Open Space acreage shall be developed as an improved park.

- 8.8.3.1. Minimum Park Improvements Required.** Unless agreed otherwise by the Parties and, if applicable, the Park District, Master Developer shall provide the following minimum Improvements for the Public Park Open Space.
- 8.8.3.1.1. Parking.** Eight off-street parking spaces per acre of improved park area.
 - 8.8.3.1.2. ADA Access.** ADA accessibility from parking areas to all restrooms, ramps, benches, and along the paved pathway.
 - 8.8.3.1.3. Restroom.** One restroom building with no less than two private toilet rooms.
 - 8.8.3.1.4. Pavilion.** 325 square feet of covered pavilion area per acre of developed park. There shall be no less than two picnic tables with attached benches for every 325 square feet of pavilion area (fractions may be rounded down to the nearest whole number). Restrooms and storage/mechanical area may be connected to the pavilion structure, but are not counted as pavilion area.
 - 8.8.3.1.5. Playground.** 600 square feet of playground area per each acre of developed park with typical playground ground cover. At least 10 percent of the playground area shall be playground equipment. Playground equipment area shall be measured from the outside boundary of the footprint of the playground equipment when viewed from above.
 - 8.8.3.1.6. Park Perimeter Pathway.** The perimeter of the park shall be encircled with a Pathway, the standards for which are depicted in **Exhibit F – Non-Street-Adjacent Pathway Cross Section**, or if adjacent to a street, **Exhibit E – Street Cross Sections**.
 - 8.8.3.1.6.1. Benches.** At least one pathway-adjacent bench shall be installed every 500 feet along the pathway.
 - 8.8.3.1.6.2. Bench Shade Trees.** At least one shade tree shall be installed per bench, planted adjacent to the bench in a manner that will cast the most shade onto the bench throughout the summer.
 - 8.8.3.1.7. Park District Standards.** If the improved park is to be dedicated to the Park District, then all improvements must conform to the Park District's established standards.
 - 8.8.3.1.8. Additional Project Specific Improvements.** Master Developer shall additionally provide the project specific improvements established in **Section 8.8.4** below, if any.
- 8.8.3.2. Park Detail Submittal.** With each subdivision plat or improvement drawings, provide site specific detail of the Park(s). The detail shall provide:
- 8.8.3.2.1.** The location, configuration, and construction detail of required Improvements; and

- 8.8.3.2.2. *Tree location, species, average mature crown-width, and required planting and irrigation methods.*
- 8.8.3.2.3. *Other proposed landscaping and other Improvements.*
- 8.8.3.2.4. *Tabulations that demonstrate compliance with required Improvements and associated acreage.*
- 8.8.3.3. **Public Park Open Space Financial Guarantee.** *Public Park Open Space Improvements shall be included in the subdivision's financial guarantee regardless of ownership. Prior to the release of any financial guarantee for Public Park Open Space Improvements, Master Developer shall provide County with a letter of acceptance from the Park District or other allowed park owner, if applicable.*
- 8.8.3.4. **Public Park Open Space Water.** *Master Developer shall provide sufficient water (rights/shares, quantities, and pressure) to provide for the Public Park Open Space's culinary and secondary water needs. Unless allowed by the County otherwise, prior to recordation of the first plat in the Project, all of the right/shares needed to serve the entire Public Park Open Space needs shall be transferred to the Park District or other allowed park owner at the time the Public Park Open Space acreage is dedicated or otherwise transferred to the Park District or other allowed park owner. If the Park District or other allowed Park owner requires the rights/shares to be transferred to another entity instead, such as the applicable water service provider for the Park, the Master Developer shall do so.*
- 8.8.3.5. **Weber River Corridor and/or Other Natural Park Areas.** *The County reserves the right to waive any of the requirements in Section 8.8.3.1 for a Public Park Open Space area that has a location or features that make it desirable to preserve in a relatively natural state, as generally guided by the general plan.*
 - 8.8.3.5.1. **Weber River Corridor.** *As a supplement to the provisions of Section 8.8.2.6, Master Developer shall provide a pathway within the Weber River Corridor Park in a manner acceptable to the County and Parks District.*
 - 8.8.3.5.2. **Other Waterways.** *As a supplement to the provisions of Section 8.8.2.7, County may require open space pathways and other Improvements that support the health of the open space corridor.*
 - 8.8.3.5.3. **Improvements and Expense.** *For this acreage, County may require any restoration, reclamation, revegetation or other similar Improvements or efforts it deems necessary, provided those Improvements or efforts have the same or lower estimated expenses of what would otherwise be required if the Public Park Open Space acreage was improved to the required minimum standards of this Agreement.*
 - 8.8.3.5.4. **Removal of Vegetation and Hydroseeding.** *At a minimum, all invasive plant species shall be removed from the Public Park Open Space acreage and, unless required otherwise, any ground not already fully vegetated shall be hydro-seeded with*

a native seed mix and erosion control methods shall be implemented in accordance with best practices.

8.8.3.5.5. Quality Control. *For best practices quality control, all efforts shall be conducted based on the recommendations from, and under the general supervision of, a landscape architect, arborist, or a similarly qualified professional. Written confirmation that best practices were followed shall be provided to the County from the professional prior to the release of any financial guarantee for the work.*

8.8.3.6. Phasing of Public Park Open Space Improvements. *Unless provided otherwise in this Agreement, Public Park Open Space Improvements may be Phased with the rest of the Project's Phasing plan as long as:*

8.8.3.6.1. Approved Construction Drawings. *All required final construction drawings for the entire Project, including all Public Park Open Space Improvements, have been approved by the County Engineer;*

8.8.3.6.2. Successive Improvements. *All Phases provide sufficient Improvements necessary for the successive construction of Improvements proposed in other Phases; and*

8.8.3.6.3. Completed prior to C/O. *A Phase's minimum required per-acre park Improvements specified in Section 8.8.3.1 are installed, accepted, and open for public use prior to issuance of the first certificate of occupancy in the Phase.*

8.8.3.7. Public Park Open Space Maintenance. *Master Developer agrees to operate and maintain or cause to be operated and maintained the Public Park Open Space acreage until _____.*

8.8.4. Project-Specific Public Park Open Space Improvements and Considerations. Master Developer agrees to provide the following Project-specific Public Park Open Space Improvements and considerations.

8.8.4.1. Reserved. *[see note.]*

8.8.4.2. Reserved. *[see note.]*

8.8.4.3. Reserved.

8.9. Pathways and Trailheads. Master Developer agrees to help the County's reach its goal of providing a walkable community wherein neighborhoods are interlinked to each other and to community destinations. Master Developer understands that the creation and interconnection of trails/pathways is a critical part of the County's consideration for this Agreement, the associated rezone, and the additional density given. As such, Master Developer agrees to install or cause to be installed the pathways as generally configured on the attached Concept Plan (**Exhibit C – Concept Plan**) and as otherwise specified as follows.

8.9.1. Pathway and Trailhead Dedication.

8.9.1.1. Pathway dedication. Master Developer agrees to dedicate the minimum area required for proposed pathways. The minimum required pathway right-of-way shall comply with the configuration in the attached **Concept Plan (Exhibit C – Concept Plan)**, and **Pathway Cross Section (Exhibit**

F – Non-Street-Adjacent Pathway Cross Section, or if adjacent to a street, **Exhibit E – Street Cross Sections**). Pathway rights-of-way shall count toward the minimum required Public Park Open Space area specified in **Section 8.8.2** of this Agreement; this does not apply to Pathways within a street right-of-way. Dedication of a Pathway right-of-way shall comply with that section, with the term “Park” being supplanted with the term “pathway” or “trailhead” as may be contextually applicable, except that the per-lot pro-rata share of pathway right-of-way shall be based on the amount of linear feet of pathway that can be constructed within such right-of-way and not solely on acreage.

8.9.1.2. Trailhead dedication. *The minimum required trailhead dedication shall comply with **Exhibit I – Trailhead Conceptual Design and Improvements**. Trailhead area shall count toward the minimum required Public Park Open Space area specified in **Section 8.8.2** of this Agreement. Dedication of a trailhead area shall comply with that section, with the term “Park” being supplanted with the term “trailhead.”*

8.9.2. Pathway Improvements. Unless specified in this Agreement otherwise, Master Developer agrees that each proposed pathway right-of-way, pursuant to **Exhibit C – Concept Plan**, or required pathway right-of-way shall be developed as an improved pathway.

8.9.2.1. Required Pathways. Regardless of what is displayed in **Exhibit C – Concept Plan**, a street-adjacent pathway shall be installed along each major residential, collector, and arterial street within or immediately adjacent to the Property.

8.9.2.2. Pathway Trees. Each pathway and sidewalk within the Project or along adjoining pathway rights-of-way shall be lined with shade trees. Pathway trees shall follow the same standards as set forth in **Section 8.5.6.1**. However, County agrees that if the Park District desires to have ownership, operation, or maintenance responsibility for a pathway right-of-way in or adjacent to the Project, Master Developer’s responsibility for tree health ends after County has been notified, in writing, by the Park District that the Park District will assume said ownership, operation, or maintenance responsibility.

8.9.2.3. Non-Street Adjacent Pathway Landscaping. For a pathway that is not adjacent to a street, Master Developer shall place three-inch plus rock, six-inches deep, on the shoulders of each pathway, with a permeable weed barrier beneath. Alternatively, County agrees that Master Developer may install alternative planting and landscaping as long as it is operated and maintained by a homeowner’s association. Refer to **Exhibit F – Non-Street-Adjacent Pathway Cross Section** for a depiction of these pathways.

8.9.2.4. Construction Drawings to Include Landscaping. Each subdivision’s improvement plans shall provide a detailed Public Landscape plan that, at a minimum, shows landscaping materials proposed to be used, the proposed location, species, including the measurements of each tree’s mature crown, and the method of vegetation irrigation.

8.9.2.5. Pathway Crossing of Residential Street. Wherever a pathway intersects

with a residential street, Master Developer agrees to install or cause to be installed the following in accordance with NACTO and other applicable best practice standards:

8.9.2.5.1. Raised Crosswalk. A raised crossing with a zebra-style crosswalk. The raised crossing shall be constructed of concrete and be designed as a six-inch high ramped speed table with six-foot ramps or greater if required by the County Engineer. The top (horizontal) of the speed table shall be at least ten-feet wide. Notification signage shall be posted in advance of the speed table.

8.9.2.5.2. Curb Extensions. Curb extensions (bulb-outs) shall be installed for pathway street crossings on both sides of the applicable street. A curb extension (bulb-out) shall be constructed to constrict a residential street width to no greater than 24 feet, or 36 feet if the street has or is planned to have an on-street bike lane. The County Engineer has discretion to modify this width if the street's design is different than the County's standard. Each curb extension shall be marked with a traffic delineator as prescribed by the County Engineer or County Roads Supervisor. If Master Developer is not responsible for other street Improvements on the opposite side of a street, the following minimum curb extension requirements shall be installed on that side.

8.9.2.5.2.1. Each end of the curb extension shall at least provide a temporary means of directing drainage to the intended or expected drainage collection system or swale;

8.9.2.5.2.2. The curb extension shall provide pedestrians a convenient and safe transition from the crossing to whatever historic pedestrian facility exists there. If no formal NACTO-standard pedestrian facility exists on that side, Master Developer shall post a "Crossing Temporarily Closed" sign at the entrance of the crosswalk, or as otherwise required by the County Engineer or Roads Supervisor.

8.9.2.5.2.3. The County Engineer or Roads Supervisor may require other Improvements that minimize potential safety risks of the curb-extension, such as but not limited to, additional curbing, guardrail, signage, drainage and street shoulder Improvements. If required, Master Developer hereby agrees to install such Improvements.

8.9.2.6. Pathway Crossing of Collector or Arterial Street. On a collector or minor arterial street, the raised crosswalk (speed table) and curb extensions pursuant to **Section 8.9.2.5** shall be installed in a manner as approved by the County or UDOT unless required otherwise by the

County Engineer, UDOT, or the local fire authority. Regardless of whether a speed table or curb extension (bulb-out) is required, zebra style crosswalk is required, as is a double-sided battery powered user-activated rapid flashing beacon on both sides of the crossing in accordance with installation best practices, and crosswalk notification signage in advance of the crosswalk on both sides of the street. The rapid flashing beacons shall be hardwired to each other through underground conduit.

8.9.2.7. Project Specific Pathway Improvements.

8.9.2.7.1. Reserved.

8.9.2.7.2. Reserved.

8.9.3. Reserved.

8.10. Environmental and Air Quality Standards. The Parties agree to implement the community's overall goal of minimizing development impacts on the environment to a reasonable degree practicable. As such, Master Developer agrees, on behalf of itself and all successive owners of the Project or of lots within the Project, to exceed minimum requirements of applicable building and construction codes and conventions by ensuring each dwelling unit is equipped with the following prior to receiving a final certificate of occupancy.

8.10.1. Energy Efficiency. All buildings will be designed to an energy efficiency rating that is one climate zone colder than the area's designated climate zone. Gas-heated furnaces and water heaters shall have an efficiency rating of 95 percent or greater.

8.10.2. Reserved.

8.11. Outdoor Lighting. Master Developer agrees that all outdoor lighting within the Project will be dark-sky friendly and as such will be governed by the County's Outdoor Lighting Ordinance, Chapter 108-16 of the Code.

8.12. Reserved.

9. Amendments, Modifications, and Revisions.

This Agreement may be amended by mutual agreement of the Parties only if the amendment is in writing and approved and signed by Master Developer and County (an "Amendment"). The following sections specify what Project changes can be undertaken without the need for amendment of the Development Agreement, and what changes require Amendment to this Agreement.

9.1. Who may Submit Modification Applications. Only the County and Master Developer or an Assignee that succeeds to all of the rights and obligations of Master Developer under this Agreement (and not including a Subdeveloper) may submit a Modification Application.

9.2. Modification Application Contents and Process.

9.2.1. Contents. Modification Applications shall:

9.2.1.1. Identification of Property. Identify the property or properties affected by the Modification Application.

9.2.1.2. Description of Effect. Describe the effect of the Modification Application on the affected portions of the Project.

9.2.1.3. Identification of Non-County Agencies. Identify any Non-County

agencies potentially having jurisdiction over the Modification Application.

9.2.1.4. Map. Provide a map of any affected property and all property within one thousand feet (1000') showing the present or intended uses and density of all such properties.

9.2.1.5. Fee. Modification Applications shall be accompanied by a fee in an amount reasonably estimated by the County to cover the costs of processing the Modification Application.

9.2.2. County Cooperation in Processing Modification Applications. The County shall cooperate reasonably in promptly and fairly processing Modification Applications.

9.2.3. Planning Commission Review of Modification Applications.

9.2.3.1. Review. All aspects of a Modification Application required by law to be reviewed by the Planning Commission shall be considered by the Planning Commission as soon as reasonably possible in light of the nature and/or complexity of the Modification Application.

9.2.3.2. Recommendation. The Planning Commission's vote on the Modification Application shall be only a recommendation and shall not have any binding effect on the consideration of the Modification Application by the Board of County Commissioners.

9.2.4. Board of County Commissioners' Review of Modification Application. After the Planning Commission, if required by law, has made or been deemed to have made its recommendation of the Modification Application the Board of County Commissioners shall consider the Modification Application.

9.3. Project Facility Repair, Maintenance, and Replacement. Master Developer shall be permitted to repair, maintain and replace the Project and its components consistent with the terms of this Agreement without amending the Agreement.

9.4. Authorized Changes, Enlargements, or Alterations. As set forth below, County staff may review and approve certain minor changes, enlargements or adjustments ("Changes") to the Project in their respective administrative capacities. The following types of Changes are considered minor, provided that no such Changes shall directly or indirectly result in significantly greater impacts than those contemplated in the approval of this Agreement.

9.4.1. Changes Necessary to Comply with Other Laws. Any resulting changes as a consequence of obtaining or complying with a federal, state, or local permit or approval; provided that the changes are Routine and Uncontested and the application thereof does not materially affect the County's original intent, findings, or conditions on the Project in a manner that would have likely resulted in a different decision on this Agreement, as determined by the Planning Division Director.

9.4.2. Landscaping Changes. Any changes to this Agreement's landscaping designs, guidelines, standards, plantings, materials and installation of the same anywhere in the project.

9.4.3. De Minimis Changes. Other de Minimis changes requested by the Master Developer, which are reasonably consistent with the intent of this agreement and the R1-15 Zone, and are Routine and Uncontested.

10. Miscellaneous Provisions.

- 10.1. Certificate of Occupancy Requirements.** The following are required prior to issuance of a certificate of occupancy.
 - 10.1.1.** Installation of street trees, as specified in **Section 8.5.6.4** of this Agreement.
 - 10.1.2. Reserved.**
 - 10.1.3. Reserved.**
 - 10.1.4.** Installation of a furnace that is at least 95% efficient, and installation of a smart thermostat, as specified in **Section 8.10.1** of this Agreement.
 - 10.1.5.** Installation of dark-sky friendly outdoor lighting, as specified in **Section 8.11** of this Agreement.
- 10.2. Financial Guarantee Requirements.** Master Developer agrees to be governed by the financial guarantee provisions in **Section 106-4-3** of the Code in effect at the time of the Approval Date. In addition to required Improvements listed in the Code, Master Developer further agrees that the financial guarantee shall include all required Improvements specified in this Agreement. Prior to the release or partial release of certain financial guarantee funds, the following are required.
 - 10.2.1.** Written confirmation of implementation of landscape best practices from a qualified professional, as specified in **Section 8.8.3.5.5**.
 - 10.2.2.** Written confirmation of implementation of landscape best practices from a qualified professional, as specified in **Section 8.5.8.3**.
 - 10.2.3.** Written letter of acceptance for Public Park Open Space Improvements, as specified in **Section 8.8.3.3**.
- 10.3. Financial Guarantee for Public Landscaping, Public Park Open Space, and Trailheads.** Master Developer agrees to provide a financial guarantee to the County for required landscaping on public property, for required Public Park Open Space Improvements, and for required trailhead improvements. The financial guarantee shall follow the same standards and processes as provided in **Section 10.2** of this Agreement.
- 10.4. Reserved.**
- 10.5. Reserved.**
- 10.6. Future Taxes, Services, and Districts.**
 - 10.6.1. District(s).** Master Developer agrees to annex the Property into any local taxing district if the purpose of that district is to provide any service necessary for the development of the property pursuant to this Agreement and the Code. Annexation shall occur prior to final plat recordation. If the project will be Phased, the entire preliminary plat/plan shall be annexed into said district(s) prior to recordation of the first plat.
 - 10.6.2. Municipal Services Tax.** Master Developer agrees that the County may impose additional tax to the Property to better accommodate for the municipal services demand of the Project, provided that the tax is reasonably necessary to provide the service(s).
 - 10.6.3. Restriction on Right to Protest Future Tax or Taxing Entity.** If the Property is ever within the boundaries of a Proposed Taxing Entity or Proposed Tax, and the process for applying the Proposed Taxing Entity or Proposed Tax to the Property includes the right for affected landowners to file a protest in a manner that could hinder the application of the Proposed Taxing Entity or Proposed Tax to the Property, Master Developer hereby waives the right to file the protest, and agrees that any protest filed

is void. Master Developer does so on behalf of itself and all future owners who may obtain any interest in the Property. Future owners are hereby on notice that the right is waived. This provision applies unless the County Commission agrees, in writing, with and to the protest.

- 10.7. Expert Review for Development Applications.** If the County subjects the Development Application to a review by County Consultants then payment of the reasonable and actual costs of the County Consultants' review shall be the responsibility of Applicant.
- 10.8. Parcel Sales.** Master Developer may obtain approval of a Subdivision that does not create any individually developable lots in the Parcel without being subject to any requirement in the Code to complete or provide security for the Improvements at the time of the Subdivision except that the County may require as a part of the Subdivision of the Parcel the construction of perimeter Improvements such as curb and gutter, sidewalks and fire hydrants if reasonably necessary given the location of the Parcel Sale in relation to other development and the respective timing of the completion of such developments. The responsibility for completing and providing security for completion of any Improvements in the Parcel shall be that of the Master Developer or a Subdeveloper upon a further Subdivision of the Parcel that creates individually developable lots. The provisions of the foregoing notwithstanding, no division shall be made that disproportionately splits the public spaces or public Improvements anticipated by this Agreement or the Code without first providing adequate security in a manner satisfactory to County to ensure those public improvements or spaces are provided.
- 10.9. Provision of Services.** The County agrees to provide all County services to the Project that it provides from time-to-time to other residents and properties within the County including, but not limited to, police and other emergency services. Such services shall be provided to the Project at the same levels of services, on the same terms and at the same rates as provided to other residents and properties in the County.

11. General Provisions.

- 11.1. Entire Agreement.** This Agreement, and all exhibits thereto, is the entire agreement between the Parties and may not be amended or modified except either as provided herein or by a subsequent written amendment signed by all parties.
- 11.2. Headings.** The captions used in this Agreement are for convenience only and are not intended to be substantive provisions or evidences of intent.
- 11.3. No Third Party Rights/No Joint Venture.** This Agreement does not create a joint venture relationship, partnership or agency relationship between the County and Master Developer. Further, the parties do not intend this Agreement to create any third-party beneficiary rights. The parties acknowledge that this Agreement refers to a private development and that the County has no interest in, responsibility for or duty to any third parties concerning any Improvements to the Property unless the County has accepted the dedication of such Improvements at which time all rights and responsibilities for the dedicated public improvement shall be the County's.
- 11.4. Assignability.** The rights and responsibilities of Master Developer under this Agreement may be assigned as provided below by Master Developer with the consent of the County as provided herein.
 - 11.4.1. Partial Assignment.** *Assignment is only allowed if in whole. No partial assignment of the Project or Property is allowed.*
 - 11.4.2. Sales not an Assignment.** Master Developer's selling or conveying a lot in any

approved Subdivision or Parcels or any other real estate interest within the Project, to builders, users, or Subdevelopers, shall not be deemed to be an "assignment" subject to the above-referenced approval by the County. Despite the selling or conveyance, Master Developer still maintains all rights, responsibilities, and obligations of this Agreement relative to development on the sold or conveyed property.

11.4.3. Related Party Transfer. Master Developer's transfer of all or any part of the Property to any entity "related" to Master Developer (as defined by regulations of the Internal Revenue Service), Master Developer's entry into a joint venture for the development of the Project or Master Developer's pledging of part or all of the Project as security for financing shall also not be deemed to be an "assignment" subject to the above-referenced approval by the County unless specifically designated as such an assignment by the Master Developer. Master Developer shall give the County Notice of any event specified in this subsection within ten (10) days after the event has occurred. Such Notice shall include providing the County with all necessary contact information for the newly responsible Party.

11.4.4. Notice. Master Developer shall give Notice to the County of any proposed assignment and provide such information regarding the proposed Assignee that the County may reasonably request in making the evaluation permitted under this Section. Such Notice shall include the following.

11.4.4.1. All necessary contact information for the proposed Assignee.

11.4.4.2. The entry number of this Agreement on file in the Office of the Weber County Recorder, and entry number to any successive amendments thereto or other agreements that may affect this Agreement or amendments thereto.

11.4.4.3. A verbatim transcription of this **Section 11.4.** "Assignability," or future amendment thereof, if applicable.

11.4.5. Grounds for Denying Assignment. The County may only withhold its consent for the reasons listed herein.

11.4.5.1. If the County is not reasonably satisfied of the proposed Assignee's ability to perform the obligations of Master Developer proposed to be assigned;

11.4.5.2. If the County has reasonable concern that the assignment will separate the Project in a manner that creates unreasonable additional demand for any type of governmental service, including additional demand for coordination amongst Assignees or other administrative review services not otherwise anticipated at the time of the execution of this Agreement; or

11.4.5.3. If the County has reasonable concern that the assignment will separate the Project in a manner that negates the purpose of master planning the Project area as one complete development.

11.4.6. Assignee Bound by this Agreement. An Assignee shall be bound by the assigned terms and conditions of this Agreement.

11.5. Binding Effect. Except as otherwise specified in this Agreement, this Agreement shall be binding upon the Parties and their respective Successors, as well as all other persons or entities acquiring all or any portion of the Project, any lot, parcel or any portion thereof within the Property, or any interest therein, whether by sale, operation of law, devise, or in any manner whatsoever.

- 11.6. No Waiver.** Failure of any Party hereto to exercise any right hereunder shall not be deemed a waiver of any such right and shall not affect the right of such Party to exercise at some future date any such right or any other right it may have unless the Party has waived the right in writing.
- 11.7. Severability.** If any provision of this Agreement is held by a court of competent jurisdiction to be invalid for any reason, the parties consider and intend that this Agreement shall be deemed amended to the extent necessary to make it consistent with such decision and the balance of this Agreement shall remain in full force and affect.
- 11.8. Appointment of Representatives.** To further the commitment of the parties to cooperate in the implementation of this Agreement, the County and Master Developer each shall designate and appoint a representative to act as a liaison between the County and its various departments and the Master Developer. The initial representative for the County shall be the Planning Division Director and the initial representative for Master Developer shall be the presiding member of **[name of entity]**. The parties may change their designated representatives by Notice.
- 11.9. Mutual Drafting.** Each Party has participated in negotiating and drafting this Agreement and therefore no provision of this Agreement shall be construed for or against either Party based on which Party drafted any particular portion of this Agreement.
- 11.10. Utah Law.** This Agreement is entered into under the laws of the State of Utah, and the Parties hereto intend that Utah law shall apply to the interpretation hereof.
- 11.11. Authority.** Each Party represents and warrants that it has the respective power and authority, and is duly authorized, to enter into this Agreement on the terms and conditions herein stated, and to execute, deliver and perform its obligations under this Agreement.
- 11.12. Duty to Act Reasonably and in Good Faith.** Unless otherwise expressly provided, each Party shall act reasonably in giving consent, approval, or taking any other action under this Agreement. The Parties agree that each of them shall at all times act in good faith in order to carry out the terms of this Agreement and each of them covenants that it will not at any time voluntarily engage in any actions which frustrate the purpose and intent of the Parties to develop the Project in conformity with the terms and conditions specified in this Agreement.
- 11.13. Communication and Coordination.** The Parties understand and agree that the process described in this Agreement depends upon timely and open communication and cooperation between the Parties. The Parties agree to use best efforts to communicate regarding issues, changes, or problems that arise in the performance of the rights, duties and obligations hereunder as early as possible in the process, and not wait for explicit due dates or deadlines. Each Party agrees to work cooperatively and in good faith toward resolution of any such issues.
- 11.14. Force Majeure.** Any prevention, delay or stoppage of the performance of any obligation under this Agreement which is due to strikes, labor disputes, inability to obtain labor, materials, equipment or reasonable substitutes therefor; acts of nature, governmental restrictions, regulations or controls, judicial orders, enemy or hostile government actions, wars, civil commotions, fires or other casualties or other causes beyond the reasonable control of the Party obligated to perform hereunder shall excuse performance of the obligation by that Party for a period equal to the duration of that prevention, delay or stoppage.
- 11.15. Incorporation of Recitals and Introductory Paragraph.** The Recitals contained in this Agreement, and the introductory paragraph preceding the Recitals, are hereby incorporated into this Agreement as if fully set forth herein.
- 11.16. Subjection and Subordination.** Each person or entity that holds any beneficial, equitable, or other interest or encumbrances in all or any portion of Project at any time hereby automatically, and without the need for any further documentation or consent, subjects and subordinates such

interests and encumbrances to this Agreement and all amendments hereof. Each such person or entity agrees to provide written evidence of that subjection and subordination within 15 days following a written request for the same from, and in a form reasonably satisfactory to Master Developer or the County

- 11.17. Severability.** If any term or provision of this Agreement, or the application of any term or provision of this Agreement to a particular situation, is held by a court of competent jurisdiction to be invalid, void or unenforceable, the remaining terms and provisions of this Agreement, or the application of this Agreement to other situations, shall continue in full force and effect unless amended or modified by mutual consent of the Parties.
- 11.18. Other Necessary Acts.** Each of the Parties shall execute and deliver to the other any further instruments and documents as may be reasonably necessary to carry out the objectives and intent of this Agreement.
- 11.19. Agreement Recordation Deadline.** This agreement and its associated rezone shall be considered abandoned and become null and void if not presented to the County for recordation within one year of the Approval Date.

12. Notices.

- 12.1. Written Notice.** Any notice, demand, or other communication ("Notice") given under this Agreement shall be in writing and given personally or by registered or certified mail (return receipt requested). A courtesy copy of the Notice may be sent by facsimile transmission or email.
- 12.2. Addresses.** Notices shall be given to the Parties at their addresses set forth as follows in this Section.

If to the County:

Weber County Commission
2380 Washington Blvd, Ste #360
Ogden, UT 84401

With copies to:

Weber County Attorney
2380 Washington BLVD, Ste. #230
Ogden, UT 84401

Weber County Planning Director
2380 Washington BLVD, Ste. #240
Ogden, UT 84401

If to Master Developer:



-
- 12.3. Effectiveness Of Notice.** Except as otherwise provided in this Agreement, each Notice shall be effective and shall be deemed delivered on the earlier of:

- 12.3.1. Physical Delivery.** Its actual receipt, if delivered personally, by courier service, or by facsimile provided that a copy of the facsimile Notice is mailed or personally delivered as set forth herein on the same day and the sending Party has confirmation of transmission receipt of the Notice).
- 12.3.2. Electronic Delivery.** Its actual receipt if delivered electronically by email provided that a copy of the email is printed out in physical form and mailed or personally delivered as set forth herein on the same day and the sending Party has an electronic receipt of the delivery of the Notice
- 12.3.3. Mail Delivery.** On the day the Notice is postmarked for mailing, postage prepaid, by First Class or Certified United States Mail and actually deposited in or delivered to the United States Mail. Any Party may change its address for Notice under this Agreement by giving written Notice to the other Party in accordance with the provisions of this Section.

13. Default and Remedies.

- 13.1. Notice of Default.** If Master Developer or a Subdeveloper or the County fails to perform their respective obligations hereunder or to comply with the terms hereof, the Party believing that a Default has occurred shall provide Notice to the other Party.
 - 13.1.1. Contents of the Notice of Default.** The Notice of Default shall:
 - 13.1.1.1. Claim of Default.** Specify the claimed event of Default, including the approximate date of when the event is determined to have begun;
 - 13.1.1.2. Identification of Provisions.** Identify with particularity the provisions of any applicable law, rule, regulation or provision of this Agreement that is claimed to be in Default;
 - 13.1.1.3. Specify Materiality.** Identify why the Default is claimed to be material; and
 - 13.1.1.4. Optional Proposed Cure.** If the County chooses, in its discretion, propose a method and time for curing the Default which shall be of no less than sixty (60) days duration.
- 13.2. Dispute Resolution Process.**
 - 13.2.1. Conference.** In the event of any dispute relating to this Agreement, the Parties, upon the request of either Party, shall meet within fourteen (14) calendar days to confer and seek to resolve the dispute ("Conference"). The Conference shall be attended by the following parties: (a) the County shall send department director(s) and County employees and contractors with information relating to the dispute, and (b) Master Developer shall send Master Developer's representative and any consultant(s) with technical information or expertise related to the dispute. The Parties shall, in good faith, endeavor to resolve their disputes through the Conference.
 - 13.2.2. Mediation.** If this Conference process does not resolve the dispute within the 7-day Conference period, the Parties shall in good faith submit the matter to mediation. The Parties shall send the same types of representatives to mediation as specified for the "Conference" process. The mediation shall take place within forty-five (45) days of the Parties submitting the dispute to mediation. If the dispute is not able to be resolved through the mediation process in the 45-day period, the Parties may pursue their legal remedies in accordance with Utah and local law.
- 13.3. Remedies.** If the parties are not able to resolve the Default by "Meet and Confer" then the

parties may have the following remedies:

- 13.3.1. Code Enforcement.** The Master Developer's failure to comply with this agreement constitutes a violation of the Land Use Code of Weber County, and is subject to the enforcement provisions and remedies thereof.
 - 13.3.2. Legal Remedies.** The rights and remedies available at law and in equity, including injunctive relief and specific performance, but not damages.
 - 13.3.3. Enforcement of Security.** The right to draw on any security posted or provided in connection with the Project and relating to remedying of the particular Default.
 - 13.3.4. Withholding Further Development Approvals.** The right to withhold all further reviews, approvals, licenses, Building Permits and/or other permits for development of the Project in the case of a Default by Master Developer until the Default has been cured.
 - 13.3.5. Extended Cure Period.** If any Default cannot be reasonably cured within sixty days, then such cure period shall be extended so long as the defaulting Party can provide evidence that it is pursuing a cure with reasonable diligence.
 - 13.3.6. Cumulative Rights.** The rights and remedies set forth herein shall be cumulative.
- 13.4. Venue.** Any action to enforce this Agreement shall be brought only in the Second Judicial District Court for the State of Utah, Weber County.

14. Entire Agreement.

This Agreement, together with all exhibits hereto, constitutes the entire Agreement between the Parties with respect to the subject matter of this Agreement. This Agreement is specifically intended by the Parties to supersede all prior agreements between them or recorded to the property, whether written or oral.

15. Covenants Running with the Land

The provisions of this Agreement shall constitute real covenants, contract and property rights, and equitable servitudes, which shall run with all of the land subject to this Agreement. Notwithstanding anything in this Agreement to the contrary, the owners of individual units or lots, as opposed to Subdivided plats or Parcels, in the Project shall (1) only be subject to the burdens of this Agreement to the extent applicable to their particular unit or lot; and (2) have no right to bring any action under this Agreement as a third-party beneficiary or otherwise.

16. Counterparts.

This Agreement may be executed in several counterparts and all so executed shall constitute one agreement binding on all the Parties, notwithstanding that each of the Parties are not signatory to the original or the same counterpart. Further, executed copies of this Agreement delivered by facsimile or by e-mail shall be deemed originally signed copies of this Agreement.

IN WITNESS HEREOF, the Parties hereto, having been duly authorized, have executed this Agreement.

(Signatures on following pages)

SIGNATURES

“County”

Weber County, a body corporate and politic of the State of Utah

Signed by: _____ on: _____
Commission Chair *Signature Date*

Commission Approval Date: _____
Approval Date
(as defined in this Agreement)

ATTEST: _____

Ricky D. Hatch, CPA
Weber County Clerk/Auditor

“Owner”

By: _____

Print Name: _____

Title: _____

DATE: _____

Owner Acknowledgment

State of Utah)
)ss.

County of Davis)

On the _____ day of _____, 20__, personally appeared before me _____, who being by me duly sworn, did say that he is the _____ of _____, a limited liability company, and that the foregoing instrument was signed in behalf of said limited liability company by authority of its members or its articles of organization; and said person acknowledged to me that said limited liability company executed the same.

My Commission Expires:

Notary Public, residing in

Exhibit A – Property Legal Description

(Need from Applicant – Verify with GIS)

Exhibit B – Property Graphic Depiction

Insert aerial imagery with border around Property.

Exhibit C – Concept Plan

The following illustration represents the conceptual configuration of the project. The Parties understand that de minimis deviations from this configuration may be allowed to better consider actual site conditions, pursuant to **Section 9.4** of this Agreement. Any conflict contained within this agreement shall be interpreted to apply the stricter requirement. Master Developer agrees that any omission of required information shall be interpreted in a manner best suited to benefit the general public, as determined by the County, regardless of how it may affect the Project.

Requirements of a concept plan. A concept plan shall comply with the following. The final agreement should replace this text box with the concept plan.

- **Survey.** The surveyed boundary lines of the Property and, if multiple zones, the boundaries of the zones, showing measured and/or recorded bearings, distances, and other controlling data with ties to section corners. Survey boundaries shall match the legal description(s) of **Exhibit A – Property Legal Description.**
- **Street and Pathway Layout and Configuration.**
 - **Connectivity Plan.** Conceptually illustrate the Project streets and how they align or connect to each other and to other streets on the perimeter of the Project. Also include in dashed lines a concept for how streets *might* align or connect with other streets outside of the Property.
 - **Street Labels.** All streets shall be labeled accordingly.
 - Minor Residential Streets shall be labeled with an “A.”
 - Major Residential Streets shall be labeled with a “B.”
 - Minor Collector Streets shall be labeled with a “C.”
 - Major Collector Streets shall be labeled with an “D.”
 - Minor Arterial Streets shall be labeled with an “E.”
 - Major Arterial Streets shall be labeled with an “F.”
- **Public Park Open Space.** Conceptually illustrate the Public Park Open Space acreage.
 - Label and shade, in a unique hue of green, the acreage intended to be improved park.
 - Label and shade, in a unique hue of green, the acreage intended to be natural park.
 - Label and shade, in a unique hue of green, the acreage intended to be pathway right-of-way.
 - Provide an open space table that shows:
 - Total Public Park Open Space acreage;
 - Improved park acreage;
 - Natural park acreage;
 - Pathway right-of-way acreage (except that acreage already counted within improved or natural park area); and
 - Linear feet of pathway that is not street-adjacent.
- **Lots.** Conceptually illustrate the general configuration of lot area. Unless otherwise required by the county, each lot or unit need not be illustrated, but rather each area that will contain lots and the configuration thereof.
- **Other.** Conceptually illustrate areas that are likely to be used for other purposes not specified above, such as area for utilities, water reservoirs, lift stations, pump houses, etc.

Exhibit D – Associated Rezone Area

Insert depiction of the rezone.


Exhibit E – Street Cross Sections

Notes:


Each street may need ½ width Project boundary variant.

Specified materials and thicknesses are typical and may be varied by County Engineer to improve longevity due to atypical or unique site-specific characteristics.

Minor Residential Streets shall be labeled with an “A” on the Master Plan.



Major Residential Streets shall be labeled with a “B” on the Master Plan.



Minor Collector Streets shall be labeled with a “C” on the Master Plan.

[Select the applicable cross section that fits the context of the development. If multiples of the same type will be used, be sure each have a corresponding identification on the Master Plan]

Minor Arterial Streets shall be labeled with an “E” on the Master Plan and shall be designed per the department of transportation specifications.

[Select the applicable cross section that fits the context of the development. If multiples of the same type will be used, be sure each have a corresponding identification on the Master Plan]

MINOR ARTERIAL 3HS
 VEHICLE LANES: 3
 INTENDED SPEED: 45+ MPH
 SHOULDER: BIKE LANE, NO PARKING
 BICYCLE FACILITIES: BUFFERED BIKE LANE

CONTEXT: BETWEEN EXISTING OR PLANNED POPULATION CENTERS. HIGHEST EXPECTED VEHICLE SPEED, MODERATE VOLUME. CURRENT AND EXPECTED FUTURE DEMAND FOR ON-STREET PARKING IS LOW (I.E. ACCESS TO EXISTING AND PLANNED ABUTTING LOTS IS RESTRICTED, SUFFICIENT OFF-STREET PARKING EXISTS, ETCO). PRIVATE ACCESS GENERALLY LIMITED TO INTERSECTIONS.

NOTE: ROW AND PARKSTRIP WIDTHS SHALL BE INCREASED WHEN NECESSARY TO SUPPORT THE SELECTED TREE SPECIES.




Exhibit F – Non-Street-Adjacent Pathway Cross Section

Notes:

County Engineer may require concrete instead of asphalt. If concrete, pathway joints shall be saw-cut. If asphalt, both edges of the pathway shall be bounded by a concrete ribbon that is at least six inches wide and 12 inches deep.

See County Code **Section 106-2-1.020** for alternative right of way width standards.



Exhibit G – Corridor Fence Design Examples




Exhibit H – Waterwise Yard Landscape Plan Requirements

The yard landscape plan shall be created by a landscape architect licensed in the State of Utah. The architect shall certify that the plan is designed, using a combination of planting and watering methods, to use 50 percent less outdoor water than expected for a typical residential lot in Weber County.

Weber Basin Water Conservancy District estimates the typical quarter-acre (10,890 square-foot) residential lot has an expected outdoor water use of 0.38 acre feet (119,385 gallons) annually. This equates to approximately 11.37 gallons per square foot of the total lot area (both landscaped area and non-landscaped area). 50 percent less is 5.68 gallons per square-foot annually.

Thus, the yard landscape plan's landscaping and watering methods shall be certified by the landscape architect to allow no more than 5.68 gallons of water per square-foot of total lot area for each lot up to 10,890 square feet (up to 59,693 gallons). For lots greater than 10,890 square feet, the applicant's architect shall certify that the plan allows for no more than 59,693 total gallons of water per year. Care shall be taken to reduce use of sprinklers where possible.



Staff Report to the Western Weber Planning Commission

Weber County Planning Division

Synopsis

Application Information

Application Request: ZTA2026-04, A public hearing and consideration regarding an application to amend the Weber County Code pertaining to minimum setbacks in the F-1 (formerly the FR-1) Zone, uses in the R3-A and R3-S (formerly FR-3) Zone, and proposed zoning text amendments relating to minimum fencing requirements.

Applicant: Weber County

Agenda Date: Tuesday, July 7, 2026

File Number: ZTA2026-04

Staff Information

Report Presenter: Tammy Aydelotte, Planner
taydelotte@webercountyutah.gov
(801) 399-8794

Report Reviewer: CE

Applicable Ordinances

[See attached]

Legislative Decisions

Decision on this item is a legislative action. When the Planning Commission is acting on a legislative item it is acting as a recommending body to the County Commission. Legislative decisions have wide discretion. Examples of legislative actions are general plan, zoning map, and land use code amendments. Typically, the criterion for providing a recommendation on a legislative matter suggests a review for compatibility with the general plan and existing ordinances.

Summary and Background

In examining needed changes to ordinance, based upon existing and previous development applications, and addressing direction from the County Commission, it has been determined that some adjustments to Weber County Land Use Ordinance are needed.

With recent changes to the FR-3 Zone (now known as the R3-A Zone) as it pertains to areas around Powder Mountain, a few of the uses previously permitted in the FR-3 Zone were inadvertently omitted with the last batch of text changes. Staff is seeking to correct the omission and include these uses once again, making them specific to the resort area.

In looking at the many legal, non-conforming parcels/structures in Ogden Canyon, and to better allow development in Ogden Canyon, staff is seeking to adjust minimum setback requirements in the F-1 Zone, at specific direction from the County Commission. In making these adjustments, property owners can more easily adjust existing structures, and become less non-conforming, without having to go through the variance process.

Fencing requirements are being looked at as more developments are being built-out with smaller corner lots. Weber County will still require a clear site triangle with the proposed changes; corner lot owners will be able to maximize the side and rear yard area allowed to be behind a six-foot tall fence with the proposed changes, among other fencing provisions intended to support use of paralleling sidewalks and pathways. A developer has identified a challenge with compliance to the existing fencing requirements. Staff is proposing to clarify fencing standards to more easily enforce them

The attached Exhibit A contains the amendments created through this effort.

Policy Analysis

Policy Considerations:

Ordinance Amendments (See Exhibit A):

General Revisions:

Adjustments to setbacks and height requirements for those parcels in the F-1 Zone, located in Ogden Canyon. Previously permitted residential uses are proposed to be added back into the FR-3 Zone (now the R-3A Zone). Fencing requirements proposed include allowance for 6' fencing anywhere on a corner lot, as long as a clear-view site triangle is preserved and to require a minimum 2' strip between proposed fencing and sidewalk, where fencing is proposed along a right-of-way.

This proposal is provided in Exhibit A.

Setbacks and height requirements in the F-1 (formerly FR-1) Zone.

There are several draws to living in the Ogden Canyon area. Some of these include the existing natural and recreational resources located in Ogden Canyon. Ogden Canyon Goal 1 addresses existing residential uses and protection of natural and recreational uses in the Canyon. As ownership has changed and these residences have become full-time homes, property owners are looking to renovate and expand the footprints of these small structures. There are several dwellings in the canyon that are 100+ years old, and in need of rehabilitation.

With expanding buildable areas on these non-conforming lots, it could be argued that open space through the Canyon will become less, development may become crowded, and the character and intent of the Ogden Canyon Scenic Byway may be compromised, as newer development occurs.

With these applications for new land use permits, the implied limits with setbacks for a one-acre minimum lot size, on a legal lot that does not conform to minimum lot area or width for the F-1 Zone (1 acre and 150 feet in width) can be prohibitive in some cases, where the request to build is on a lot as small as 0.10 acre. As such, Approximately 16% of land use permit applications are submitted after requesting a variance from the Board of Adjustment. Of the approximate 160 non-conforming parcels in Ogden Canyon owned by private property owners, 130 of these do not access directly off Highway 39 (Ogden Canyon Road), and the majority of these lots do not conform to minimum lot development standards for the F-1 Zone. To allow for continued revitalization of existing structures and encourage new development (not additional density in the Canyon), a reduction in setbacks could more easily allow for fewer delays of many of these applications to meet the setbacks, without the additional step of requesting a variance.

Ogden Canyon Goal 1: A goal of Weber County is to, in harmony with existing residential uses, protect the historical, natural, and recreational resources in Ogden Canyon.

Ogden Canyon Principle 1.1: in harmony with existing residential uses, support the development and improvement of recreational amenities in Ogden Canyon, such as trails, hiking and climbing routes, access to the Ogden River, and public facilities like restrooms and picnic areas.

Ogden Canyon Implementation 1.1.1: Support creation of the Ogden Canyon Trail.

Ogden Canyon Principle 1.2: Protect the unique historical, geological, and recreational features of Ogden Canyon. Protect the free flowing nature of the Ogden River and its channel and riparian areas.

Ogden Canyon Implementation 1.2.1: Work with UDOT and local landowners during the Ogden Canyon Transportation Use Study to protect the historical, geologic, natural and recreational resources of Ogden Canyon to the extent possible.

Ogden Canyon Implementation 1.2.2: Ensure that projects proposed for Ogden Canyon recognize its importance as a historical, recreational visitor destination, and Ogden River Scenic Byway, and protect the historic, cultural, recreational and natural resources of the Canyon.

Where Ogden Canyon is considered a gateway to the Ogden Valley, the need to update and allow for development that will only enhance this scenic byway is becoming increasingly significant as development continues in Ogden Valley, in preparation for the Winter Olympics in 2034.

A reduction in setbacks will maximize the buildable area for the property owners, allowing for more appealing opportunities for property owners in the renovation of existing structures. This revitalization will contribute to the visual enhancement of the Ogden River Scenic Byway. This proposal allows for reduced setbacks only for those lots whose direct access is not from Ogden Canyon Road. This proposal assists with Ogden Canyon Implementation 1.2.1 in keeping development from further encroaching within areas where UDOT may seek to expand Highway 39 in the future.

Gateways and Viewsheds Goal 2 states: "A goal of Weber County is to protect the Valley's sense of openness and rural character." The principles and implementation strategies of Goal 2 include protection of agricultural activities and lands as integral to the rural character of Ogden Valley.

Historically, the Ogden Canyon was developed as a summer home area, with smaller houses that were occupied only seasonally. Some of the residential structures are older than 100 years old. As ownership of these lots change, new owners are looking for more than a seasonal residence and are seeking to update, expand, and in some cases, rebuild homes to better suit their needs. While the historic character may be as maintained through not allowing for additional density, merely improving upon the current development rights already present, the current layout of the Ogden Canyon area would be minimally changed or disturbed. While the Ogden Valley General Plan seems to lean away from reduced setbacks in this area, because of the increased visual, spatial, and environmental impact in this narrow, scenic area, the existing residential uses and the allowance of limited development (setback) flexibility may be appropriate where it helps existing legal lots function reasonably without increasing density or compromising the Canyon's scenic, historic, natural, recreational, or transportation-related resources. The Planning Commission should use their own policy judgement to decide whether you think the plan supports or opposes the idea.

Uses in the R3 (formerly FR-3) Zone.

The R3 Zone allows for attached residential dwellings (specifically, R3-A). These dwelling types primarily consist of townhomes and can be a popular type of dwelling unit near resort development. . It would make sense to allow for these uses, when not more than 1,000 feet from the DRR-1 Zone, as this would provide additional commercial and recreating opportunities. The short-term rental uses (transient lodging, short-term rental, recreation lodge) that were previously in the FR-3 Zone made sense as this zone was located adjacent to the DRR-1 Zone at the Powder Mountain resort. With previous changes to ordinance, these uses were inadvertently left out as the FR-3 Zone became the R3 Zone. As growth of residential units is trending towards more second homes, and short-term rentals, the need to meet goals for recreational development opportunities includes allowance for short-term rentals in the areas that are located in and around the existing resorts. The R3 (formerly FR-3) Zones in Ogden Valley are located in two areas adjacent to the DRR-1 Zone that is the Powder Mountain resort. Resort development is supported by the addition of Short-Term Rental, Recreation Lodge, and Transient Lodging uses in this zone that is surrounded by the resort (DRR-1 Zone).

Parks and Recreation Goal 2: A goal of Weber County is to pursue Valley recreation expansion by working with resort developers.

Parks and Recreation Principle 2.1: Weber County will continue to pursue recreational development opportunities with existing and future recreation resorts in the Ogden Valley planning area, subject to the provision of Land Use Principle 1.1. Future resort development should broaden the array of outdoor recreation opportunities available to both residents and visitors.

Ensuring these uses are inserted back into the zone when in proximity to resort areas will allow continued support of the recreational opportunities that are vital to the character of the Ogden Valley.

Clarification and change to Fencing Ordinance.

With the number of zoning map amendments out in the Western Weber County area, come more specialized developments with smaller lots, more trails and sidewalks (pedestrian connectivity). The desire by homeowners for clearer fencing standards, and to allow for maximization of usable yard space has created a need to look at some small adjustments/clarifications to fencing standards. As Weber County continues to work towards meeting residential development goals as outlined in their General Plan, for a variety of housing types, there is a domino-effect related to how these smaller lots are developed for residential use. One of these elements affected is location and height of fencing permitted on residential lots. Proposed changes to these fencing standards are found in Exhibit A.

Staff Recommendation

Staff recommends that the Planning Commission consider the text included as Exhibit A and offer staff feedback for additional consideration, if any. Alternatively, when/if the Planning Commission is comfortable with the proposal, a positive recommendation should be passed to the County Commission.

Model Motion

The model motions herein are only intended to help the planning commissioners provide clear and decisive motions for the record. Any specifics provided here are completely optional and voluntary. Some specifics, the inclusion of which may or may not be desired by the motioner, are listed to help the planning commission recall previous points of discussion that may help formulate a clear motion. Their inclusion here, or any omission of other previous points of discussion, are not intended to be interpreted as steering the final decision.

Motion for positive recommendation as-is:

I move we forward a positive recommendation to the County Commission for File #ZTA2026-04, an application to amend the Weber County Code to _____, as provided in Exhibit A.

I do so with the following findings:

Example findings:

1. *The changes are supported by the Western Weber General Plan.*
2. *The proposal serves as an instrument to further implement the vision, goals, and principles of the Western Weber General Plan*
3. *The changes will enhance the general health and welfare of Western Weber residents.*
4. *[_____ add any other desired findings here _____].*

Motion for positive recommendation with changes:

I move we forward a positive recommendation to the County Commission for File #ZTA2026-04, an application to amend the Weber County Code to _____, as provided in Exhibit A, **but with the following additional edits and corrections:**

Example of ways to format a motion with changes:

1. *Example: In Section 104-12-3(f), remove short-term rentals as a permitted use.*
2. *Example: On line number [____], it should read: [_____ desired edits here _____].*
3. *Etc.*

I do so with the following findings:

Example findings:

1. *The changes are supported by the Western Weber General Plan.*
2. *The proposal serves as an instrument to further implement the vision, goals, and principles of the Western Weber General Plan*

3. *The changes will enhance the general health, safety, and welfare of Western Weber residents.*
4. *[Example: allowing short-term rentals runs contrary to providing affordable long-term rental opportunities]*
5. *Etc.*

Motion to table:

I move we **table** action on File #ZTA2026-04, an application to amend the Weber County Code to _____, as provided in Exhibit A, to [provide a date certain], so that:

Examples of reasons to table:

- *Example: We have more time to review the proposal.*
- *Example: Staff can get us more information on [_____ specify what is needed from staff _____].*
- *Example: The applicant can get us more information on [_____ specify what is needed from the applicant _____].*
- *Example: More public noticing or outreach has occurred.*
- *[_____ add any other desired reason here _____].*

Motion to recommend denial:

I move we forward a recommendation for **denial** to the County Commission for File #ZTA2026-04, an application to amend the Weber County Code to _____, as provided in Exhibit A. I do so with the following findings:

Examples findings for denial:

- *Example: The proposal is not adequately supported by the General Plan.*
- *Example: The proposal is not supported by the general public.*
- *Example: The proposal runs contrary to the health, safety, and welfare of the general public.*
- *Example: The area is not yet ready for the proposed changes to be implemented.*
- *[_____ add any other desired findings here _____].*

Exhibits

- A. Proposed Amendments to _____ (Redlined Copy).

1 **SECTION 4 EXHIBIT A: AMENDMENT.** The Weber County Code is hereby *amended* as follows:

2 **Part II Land Use Code**

3 ...

4 **TITLE 104 Zones**

5 ...

6 **Chapter 104-9 Forest Zones**

7 ...

8 **Sec 104-9-5.040 Front Setbacks**

STANDARD	F-1	F-3	F-5	F-10	F-40	SPECIAL REGULATIONS
Minimum for all buildings:	<u>30-15</u> feet ^{1,2}	<u>30 feet</u> ^{1,2}		50 feet ^{1,2}	75 feet ^{1,2}	

9 ¹See Section 108-7-10 if lot abuts an arterial street or collector street.

10 ²If a lot approved under a repealed cluster subdivision code, the minimum front setback shall be 20 feet.

11 **Sec 104-9-5.050 Side Setbacks**

STANDARD	F-1	F-3	F-5	F-10	F-40	SPECIAL REGULATIONS
Minimum for all buildings:	<u>20-10</u> feet ^{1,2}		<u>20 feet</u> ^{1,2}		40 feet ^{1,2}	

12 ¹See Section 108-7-10 if lot abuts an arterial street or collector street.

13 ²If a lot approved under a repealed cluster subdivision code, the minimum side setback shall be 5 feet, except one foot for an accessory building that is at least 6 feet in the rear of the main building.

14 **Sec 104-9-5.060 Rear Setbacks**

STANDARD	F-1	F-3	F-5	F-10	F-40	SPECIAL REGULATIONS
Minimum for all buildings:	<u>30-15</u> feet ^{1,2}		<u>30 feet</u> ^{1,2}			
Minimum for accessory building			10 feet ^{1,2}			

16 ¹See Section 108-7-10 if lot abuts an arterial street or collector street.

17 ²If a lot approved under a repealed cluster subdivision code, the minimum rear setback shall be 20 feet, except one foot for an accessory building that is at least 6 feet in the rear of the main building.

18

19

20

21

22

Sec 104-9-5.070 Rear Setbacks

STANDARD	F-1	F-3	F-5	F-10	F-40	SPECIAL REGULATIONS
Minimum main building height:	1 story					
Maximum main building height:	35 feet					
Maximum accessory building height:	25-30 feet ¹					

23 ¹Except when governed otherwise by Section 108-7-16 large accessory buildings.

24 ...

25 Chapter 104-12 Residential Zones R1, R2, and R3

26 ...

27

28 (a) Residential uses.

RESIDENTIAL USES	R1				R2	R3		SPECIAL REGULATIONS
	R1-15	R1-12	R1-10	R1-5		R3-A	R3-S	
<i>Dwelling, group. A group dwelling, as defined by Title 101, Chapter 2.</i>	N	N	N	N	P	P	P	See Section 108-7-11. No more than 24 dwelling units allowed per lot.
<i>Dwelling, single-family. A single-family dwelling, as defined by Title 101, Chapter 2.</i>	P	P	P	P	P	P	N	
<i>Dwelling, single-family attached. A single-family attached dwelling, as defined by Title 101, Chapter 2.</i>	N	N	N	N	P	P	P	In the R2 zone, no more than two dwelling units allowed per lot.
<i>Dwelling, two-family. A two-family dwelling, as defined by Title 101, Chapter 2.</i>	N	N	N	N	P	P	P	See Section 104-12-4
<i>Dwelling, three-family. A three-family dwelling, as defined by Title 101, Chapter 2.</i>	N	N	N	N	N	P	P	See Section 104-12-4

Dwelling, four-family. A four-family dwelling, as defined by Title 101, Chapter 2.	N	N	N	N	N	P	P	See Section 104-12-4
Dwelling, multi-family. A multi-family dwelling, as defined by Title 101, Chapter 2.	N	N	N	N	N	P	P	See Section 104-12-4
Residential facility for elderly persons.	P	P	P	P	P	P	P	See Section 108-7-15.
Residential facility for handicapped persons.	P	P	P	P	P	P	P	See Section 108-7-13.
Residential facility for troubled youth.	P	P	P	P	P	P	P	See Section 108-7-14.
Short-term rental. A short-term rental.	N	N	N	N	N	<u>NP</u>	<u>PN</u>	See Title 108 Chapter 11
<u>Recreation Lodge. A recreation lodge as defined in Title 101, Chapter 2.</u>	<u>N</u>	<u>N</u>	<u>N</u>	<u>N</u>	<u>N</u>	<u>C</u>	<u>N</u>	<u>Must be located no further than 1,000 feet from the DRR-1 Zone.</u>
<u>Transient Lodging. A hotel, motel, lodging house, condominium rental apartment (condotel), or timeshare condominium</u>	<u>N</u>	<u>N</u>	<u>N</u>	<u>N</u>	<u>N</u>	<u>P</u>	<u>N</u>	<u>This may include lockout sleeping rooms, as defined by Title 101, Chapter 2, as an accessory use.</u>

Commented [CE1]: What if you rewrite this whole section to make it more defensible? Here is what AI spat out for me (which I do think resolves some challenges – and note that it does not say anything about perimeter development fencing, relying instead on the general height principles):

(a) **Applicability.** Except as provided in Subsection (e), a wall, fence, or hedge shall comply with this section, Section 108-7-7, and all other applicable provisions of this Land Use Code. Except as expressly provided in this section, the most restrictive applicable provision shall control.

(b) **Walls, Fences, and Hedges Generally.**

(1) **Pedestrian-facility separation.** A wall, fence, or hedge greater than three feet in height shall not be located within two feet of a sidewalk, pathway, trail, pedestrian walkway, or similar facility intended for public or common pedestrian travel. The separation shall be measured horizontally from the nearest above-grade portion of the wall, fence, or hedge to the nearest edge of the pedestrian facility. A hedge shall be maintained so that its outer edge does not encroach into the required separation.

(2) **Height.** A wall, fence, or hedge shall not exceed four feet in height within the minimum required front setback area for the lot, and shall not exceed six feet in height outside the minimum required front setback area for the lot, unless a greater height is expressly allowed by this section or another provision of this Land Use Code.

(c) **Wall, Fence, or Hedge atop Retaining Walls.**

(1) A fence, wall, or hedge on top of a retaining wall protecting a cut below natural grade shall not exceed the height allowed at that location if the retaining wall did not exist.

(2) The height of a retaining wall containing fill shall count toward the maximum height allowed for a fence, wall, or hedge at that location, except that a protective fence or wall not exceeding four feet in height may be located on top of the retaining wall.

(d) **Sport Court Fences.** A fence for a tennis court, sport court, or similar recreational use shall not exceed 12 feet in height, shall comply with the accessory-building setbacks of the zone in which it is located, and requires a land use permit and building permit. Any portion of the fence that exceeds six feet in height shall be constructed of open-mesh fencing or sport netting that is at least 80 percent open when viewed perpendicular to the fence. Slats, panels, fabric screening, privacy mesh, or other materials that create a solid or substantially solid fence are prohibited above six feet in height.

(e) **State-Required Fences.** This section does not apply to a fence required by state law to surround or enclose a public utility substation or public school.

(f) **Ogden Canyon.** In the Ogden Canyon, a fence greater than four feet in height shall not be located within 50 feet of the centerline of Highway 39.

29 ...

30 **Chapter 108-7-3 Fencing Requirements**

31 ~~1. A wall, fence or hedge not exceeding four feet in height may be located and maintained~~
32 ~~anywhere on a lot except as required by Section 108-7-7. A wall, fence, or hedge not more~~
33 ~~than six feet in height may be located anywhere on an interior lot except within the area~~
34 ~~comprising the required front setback. A wall, fence, or hedge not more than six feet in height~~
35 ~~may be located anywhere on a corner lot except within the areas comprising the required~~
36 ~~front setback and the required side setback which faces the street. A wall, fence, or hedge on~~
37 ~~a corner lot shall comply with the requirements of Section 108-7-7.~~

38 ~~2. Notwithstanding the requirements of subsection (a) of this section, residential subdivisions and~~
39 ~~projects may be encompassed in whole or in part by a perimeter fence of not more than six feet in~~
40 ~~height, subject to design review and provided that access to lots is allowed only from approved~~
41 ~~interior public or private streets that are part of the approved subdivision or project. In addition, a~~
42 ~~permanent means of landscaping and maintaining the parking strip between the fence and the~~
43 ~~street curb shall be provided.~~

44 ~~3. Where a retaining wall protects a cut below the natural grade, such retaining wall may be topped~~
45 ~~by a fence, wall or hedge of the same height that would otherwise be permitted at the location if~~

46 no retaining wall existed. Where a retaining wall contains a fill, the height of the retaining wall built
47 to retain the fill shall be considered as contributing to the permissible height of a fence, solid wall,
48 or hedge, provided that in any event a protective fence or wall not more than four feet in height
49 may be erected at the top of the retaining wall. These provisions shall comply with the
50 requirements of Section 108-7-7.

51 4. Fences for uses such as tennis or sport courts may be a maximum of 12 feet high, provided the
52 fence meets all of the required setbacks for an accessory building in the zone in which it is
53 located and a land use and building permit are obtained.

54 5. The provisions of this section shall not apply to fences required by state law to surround and
55 enclose public utility subdivisions and public schools.

56 6. In the Ogden Canyon, a fence that is greater than four feet in height shall not be located within 50
57 feet of the centerline of Highway 39.

58 (a) **Applicability.** Except as provided in Subsection (e), a wall, fence, or hedge shall comply with this section,
59 Section 108-7-7, and all other applicable provisions of this Land Use Code. Except as expressly provided in this
60 section, the most restrictive applicable provision shall control.

61 **(b) Walls, Fences, and Hedges Generally.**

62 (1) **Pedestrian-facility separation.** A wall, fence, or hedge greater than three feet in height shall not be
63 located within two feet of a sidewalk, pathway, trail, pedestrian walkway, or similar facility intended for public
64 or common pedestrian travel. The separation shall be measured horizontally from the nearest above-grade
65 portion of the wall, fence, or hedge to the nearest edge of the pedestrian facility. A hedge shall be
66 maintained so that its outer edge does not encroach into the required separation.

67 (2) **Height.** A wall, fence, or hedge shall not exceed four feet in height within the minimum required front
68 setback area for the lot, and shall not exceed six feet in height in all other areas not within the front setback
69 area for the lot, unless a greater height is expressly allowed by this section or another provision of this Land
70 Use Code.

71 **(c) Wall, Fence, or Hedge atop Retaining Walls.**

72 (1) A fence, wall, or hedge on top of a retaining wall protecting a cut below natural grade shall not exceed
73 the height allowed at that location if the retaining wall did not exist.

74 (2) The height of a retaining wall containing fill shall count toward the maximum height allowed for a fence,
75 wall, or hedge at that location, except that a protective fence or wall not exceeding four feet in height may
76 be located on top of the retaining wall.

77 (d) **Sport Court Fences.** A fence for a tennis court, sport court, or similar recreational use shall not exceed 12 feet
78 in height, shall comply with the accessory-building setbacks of the zone in which it is located. Any portion of the
79 fence that exceeds six feet in height shall be constructed of open-mesh fencing or sport netting that is at least 80
80 percent open when viewed perpendicular to the fence. Slats, panels, fabric screening, privacy mesh, or other
81 materials that create a solid or substantially solid fence are prohibited above six feet in height.

82 (e) **State-Required Fences.** This section does not apply to a fence required by state law to surround or enclose a
83 public utility substation or public school.

84 (f) **Ogden Canyon.** In the Ogden Canyon, a fence greater than four feet in height shall not be located within 50
85 feet of the centerline of Highway 39.

86



Staff Report to the Weber County Planning Commission

Weber County Planning Division

Synopsis

Application Information

Application Request: A request for preliminary approval of the Longhorn East Subdivision. A residential development consisting of 208 lots.

Type of Decision: Administrative

Agenda Date: Tuesday, July 07, 2026

Applicant: Pat Burns

File Number: LVL051926

Approximate Address: 7100 W 700 S

Project Area: 64.2 acres

Zoning: Residential (R1-15)

Existing Land Use: Vacant

Proposed Land Use: Residential

Parcel ID: 10-036-0068

Township, Range, Section: T6N, R3W, Section 14

Adjacent Land Use

North: Vacant	South: Agricultural
East: Residential/Agricultural	West: Residential

Staff Information

Report Presenter: Felix Lleverino
 flleverino@co.weber.ut.us
 801-399-8767

Report Reviewer: TA

Applicable Ordinances

- Title 104, Chapter 12 Residential (R1-15)
- Title 106, Subdivisions
- Rezone Ordinance #2026-07
- Meibos Zoning Development Agreement, Longhorn East

Development History

The Meibos Zoning Development Agreement was approved for a zoning map amendment by the County Commission on March 17, 2026.

A development agreement between Weber County and the developer is recorded on title under entry number 3413670.

A request for preliminary subdivision approval was considered by the Western Weber Planning Commission on July 7, 2026.

Background and Summary

The developer, Mr. Pat Burns, is requesting preliminary approval to subdivide a 64.2-acre parcel into 208 single-family residential lots. The residential lots range in size from 6,000 to 24,000 square feet. This residential development includes storm-water detention, pressurized irrigation water delivery, public pathways, and a 7.5-acre public park. The streets and pathways throughout the development are designed to satisfy the connectivity requirements of the development agreement concept plan and Section 106-2-1.020, which will result in efficient pedestrian and cycling mobility. This plan was designed around the Future Streets and Transit Plan of the Weber County General Plan shown in Exhibit E.

Following preliminary approval from the planning commission, this development proposal will need to satisfy the preliminary conditions and the standards from the development agreement before being presented to the planning director for final approval. The developer is also aware that before the recordation of any phase within the Longhorn Estates development is recorded, the planning division requires the satisfactory completion of infrastructure, as specified in the Longhorn Estates Development Agreement, for the Vaquero Village Cluster Subdivision.

Analysis

General Plan: This proposal conforms to the Weber County General Plan by preserving open spaces and rural qualities (see page 1-7).

Zoning: The property is located in the R1-15 Zone. The purpose of this zone is stated in the LUC §104-12.

The purpose of the R1 zone is to provide regulated areas for single-family dwelling uses at four different low-to-medium density levels. The R1 zone includes the R1-15, R1-12, R1-10, and R1-5 zones. Any R-1-12 and R-1-10 zones shown on the zoning map or elsewhere in the Land Use Code are references to the R1-12 and R1-10 zones, respectively.

Each lot meets the zoning requirement of 6,000 square feet minimum and 60 feet of lot width.

Open Space: Public pathway corridors and the dedication of 7.5 acres of public park are designed to complement the existing West Warren Park. A 10-foot pathway on 7100 West Street will tie with the improvements within the Longhorn development. The development agreement specifies that one acre of park space is dedicated to Weber County or the park district for every 35 lots. This Longhorn East plan satisfies the acreage and parking requirements.

Natural Hazards: A Geotechnical Investigation by Christensen Geotechnical, dated September 19 2024, with Project Number 145-026, provides valuable information regarding soil types, site grading, soil removal, structural fill, compaction, and types and severity of hazards present on the property. Pages 7 through 11 address earthwork, foundations, estimated settlement, lateral earth pressures, concrete slab on grade construction, moisture protection and surface drainage, and pavement design. The developer shall provide a design verification letter indicating that the subdivision improvements are done in accordance with the geotechnical study.

Secondary Egress: The Developer of the Longhorn East Subdivision shall provide for secondary egress with the development of Phase 1 so as not to exceed the maximum of 30 lots from a temporary terminal street. As more phases commence development, the Developer shall install an additional secondary egress in order to abide by Section 106-2-2.040 Terminal Streets.

The through street connecting 7100 West to 6700 West will be completed with Phase 1; the additional 4 phases will be looped back to this through street in a fashion to avoid secondary egress issues. The developer agrees to this requirement and will make the needed improvements in concert with the Phase 1 development.

Traffic Study: At the rezone stage, the developer was required to provide a traffic impact study. The study prepared by Reeve and Associates is complete to address the roadways, intersections, traffic generation, and existing road conditions that will be impacted by the Longhorn development and the public park. The Introduction and Executive Summary list the following:

1. A deceleration lane is recommended for the right-turn movements onto 7100 West from the westbound traffic on 900 South.
2. Restriping of the two-way left-turn lane for eastbound traffic on 900 South for a dedicated left-turn lane onto 7100 West.
3. The widening of 6700 West to accommodate future growth.

Offsite Improvements: Improvements to 6700 West Street to the intersection of 900 South Street are included with the construction plan. See pages 11, 33, and 34 of Exhibit F.

Section 8.9.2.7 requires a pathway parallel to the Warren Canal. A conversation with Mr Jeff Hale from the Warren Irrigation Company indicates that the board would entertain the placement of a public pathway on top of the canal levee. The developer would be responsible for the construction of the pathway in the location specified by the Irrigation Company. If the Warren Irrigation Company does not allow a pathway on top of the levee, the pathway shall be built along the north edge of the subdivision boundary.

Flood Zone: This parcel is within a Zone X flood area and determined to be outside the 500-year flood risk.

Culinary Water: West Warren-Warren Water Improvement District has provided a letter stating that water is available for the Longhorn East upon meeting their conditions:

- The land must be annexed into the District boundaries.
- A letter from the Fire District for a fire flow test
- Proof of access to secondary water with the appropriate acre-feet for the development
- Proof of a functioning secondary water system

- Impact fees paid to Weber Basin Water
- All remaining fees paid to the District

The items above are stated in the preliminary will-serve; the District will require additional work including fees and inspections following preliminary approval and before final approval is granted.

Secondary Water: The developer has provided an acknowledgement letter confirming that Pineview Water District may serve this property through the Weber Box Elder Conservation District. The property is not currently within the secondary water district; however, after approval from the Board of Directors, payment of all required fees, and the provision of sufficient water shares are complete, the District will take ownership and responsibility for the maintenance and operation of the irrigation pond and system, thereby becoming the water provider for Vaquero Village, Longhorn Estates, and Longhorn East Subdivisions.

The developer possesses 20 Class A shares of Warren Irrigation water shares. 15 of those shares are used to provide irrigation water to Phase 1 of Vaquero Village, Longhorn Estates, and Longhorn East. The planning staff requires that the developer enter into a covenant that will require sufficient irrigation water for the entire development, that the water rights will not be disposed of except to lots within the subdivision, and that the rights will be transferred at no cost.

Sewer: A will-serve letter from the Central Weber Sewer Improvement District (CWSID) states that the District has the capacity to treat sanitary sewer flow from this subdivision. The letter attached in Exhibit C contains conditions that must be satisfied. The entire parcel of property to be served must be annexed into the Central Weber Sewer Improvement District prior to any sewer connections. The developer is responsible for coordinating directly with the Promontory Commerce Center Public Infrastructure District regarding the construction schedule and available capacity. The Little Mountain Sewer District and the Central Weber Sewer District require annexation because LMSA will service the conveyance, and the CWSID will provide the treatment.

Review Agencies: The Planning Division has several review comments that will be addressed with plan amendments and will be addressed before final approval is granted. The primary concern from the Weber County Fire District relates to turn-arounds, cul-de-sac diameter, and fire hydrant location. Weber County Surveying is recommending preliminary approval with further comments expected upon final subdivision review. Weber County Engineering has posted preliminary application review comments regarding an updated sewer will-serve letter and off-site sewer plans. The planning staff is expecting more preliminary review comments that will be addressed before considering final subdivision plat approval.

Staff Recommendation

Staff recommends preliminary approval of the Longhorn East Subdivision, consisting of 208 lots. This recommendation is based on the following conditions:

1. Requirements from the water and sewer districts are satisfied.
2. Annexation into the service provider districts is complete before the subdivision plat is recorded.
3. Pineview Water Systems or Weber-Box Elder Conservation District accepts ownership and maintenance of the secondary water system before final subdivision is granted.
4. The developer will coordinate with the Promontory Commerce Center Public Infrastructure District regarding the construction schedule and available capacity.
5. Update all construction plans and cost estimate to include canal pathway and park.
6. All county agency preliminary review comments are satisfied.
7. Standards from the development agreement are satisfied.
8. The Vaquero Village Cluster Subdivision plat is amended before the first phase of Longhorn East is recorded.
9. All improvements in Vaquero Village Subdivision are complete or escrowed before the first phase of Longhorn East is recorded.

This recommendation is based on the following findings:

1. The proposed subdivision complies with Weber County General Plan.
2. The proposed subdivision complies with the applicable County codes.

Exhibits

- A. Longhorn East phasing plan
- B. Letter from West Warren Water (Culinary)
- C. Letter from Weber Box-Elder Conservation District (Secondary)
- D. Little Mountain Sewer District and Central Weber Sewer District will-serve letter
- E. Connectivity plan
- F. Construction plan

Area Map





Exhibit A




PROVIDE 4" THICKNESS OF 3/4" OR 1" GRAVEL BASE COURSE UNDER SIDEWALK, DRIVEWAY APPROACHES AND CURB & GUTTER WHEN SUBGRADE IS CLAY OR C.B.R. IS LESS THAN 10 OR AS DIRECTED BY COUNTY ENGINEER

Street Section (60' R.O.W.)

SCALE: NONE

*VERIFY LOCATION WITH PHONE, GAS AND POWER COMPANIES.



PROVIDE 4" THICKNESS OF 3/4" OR 1" GRAVEL BASE COURSE UNDER SIDEWALK, DRIVEWAY APPROACHES AND CURB & GUTTER WHEN SUBGRADE IS CLAY OR C.B.R. IS LESS THAN 10 OR AS DIRECTED BY COUNTY ENGINEER


Street Section (66' R.O.W.)

SCALE: NONE

*VERIFY LOCATION WITH PHONE, GAS AND POWER COMPANIES.


NOTES

- STREETS HEADING IN A EAST/WEST DIRECTION WILL HAVE A 10' PATH ON THE NORTH SIDE OF THE STREET.
- STREETS HEADING IN A NORTH/SOUTH DIRECTION WILL HAVE A 10' PATH ON THE EAST SIDE OF THE STREET.



30' Trail Easement Detail

SCALE: NONE



VICINITY MAP


SCALE: NONE

BOUNDARY DESCRIPTION

PART OF THE SOUTHEAST QUARTER OF SECTION 14, TOWNSHIP 6 NORTH, RANGE 3 WEST, SALT LAKE BASE AND MERIDIAN, U.S. SURVEY. MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT BEING 1335.30 FEET NORTH 00°38'39" EAST FROM THE SOUTH QUARTER CORNER OF SAID SECTION 14; THENCE NORTH 00°38'39" EAST 1335.30 FEET; THENCE SOUTH 89°31'02" EAST 1814.20 FEET; THENCE SOUTH 01°07'35" WEST 549.07 FEET; THENCE SOUTH 89°24'27" EAST 402.07 FEET; THENCE SOUTH 00°47'57" WEST 205.71 FEET; THENCE NORTH 89°12'03" WEST 33.71 FEET; THENCE SOUTH 00°47'42" WEST 150.12 FEET; THENCE SOUTH 89°24'27" EAST 436.30 FEET; THENCE SOUTH 00°47'57" WEST 60.00 FEET; THENCE NORTH 89°24'27" WEST 291.00 FEET; THENCE SOUTH 00°47'57" WEST 375.16 FEET; THENCE NORTH 89°22'46" WEST 2321.11 FEET TO THE POINT OF BEGINNING.

CONTAINING 2,799,569 SQUARE FEET OR 64.269 ACRES.



6 PACK LOT DETAIL

SCALE: 1"=60'

LINE TABLE

#	BEARING	DISTANCE
L1	S00°28'56" W	100.00'
L2	S00°28'56" W	113.00'
L3	S00°28'56" W	113.00'
L4	S00°28'56" W	113.00'
L5	S00°28'56" W	113.00'
L6	S00°28'56" W	113.00'
L7	S00°28'56" W	113.00'
L8	S00°28'56" W	113.00'
L9	S00°28'56" W	113.00'
L10	S00°28'56" W	113.00'
L11	N00°28'56" E	100.00'
L12	N00°28'56" E	100.00'
L13	S89°31'04" E	60.00'
L14	S89°31'04" E	60.00'
L15	S89°31'04" E	70.00'
L16	N00°28'56" E	113.00'
L17	N00°28'56" E	113.00'
L18	N00°28'56" E	113.00'
L19	N00°28'56" E	113.00'
L20	N00°28'56" E	113.00'
L21	N00°28'56" E	113.00'
L22	N00°28'56" E	113.00'
L23	N00°28'56" E	113.00'
L24	N00°28'56" E	113.00'
L28	N00°28'56" E	113.00'
L29	N00°28'56" E	113.00'
L30	N89°31'04" W	70.00'
L31	N89°31'04" W	60.00'
L32	N89°31'04" W	60.00'
L33	N00°28'56" E	113.00'
L34	N00°28'56" E	113.00'
L38	N00°28'56" E	113.00'
L39	N00°28'56" E	113.00'
L40	N89°31'04" W	70.00'
L41	N89°31'04" W	60.00'
L42	N89°31'04" W	60.00'
L43	N00°28'56" E	100.00'
L44	N00°28'56" E	100.00'
L45	S00°28'56" W	100.00'
L46	S00°28'56" W	100.00'
L47	N89°31'04" W	60.00'
L48	N89°31'04" W	60.00'
L49	N89°31'04" W	70.00'
L50	S00°28'56" W	113.00'
L51	S00°28'56" W	113.00'
L54	N89°31'04" W	70.00'
L55	S00°28'56" W	113.00'
L56	S00°28'56" W	113.00'
L57	N89°31'04" W	60.00'
L58	N89°31'04" W	60.00'
L59	N89°31'04" W	70.00'
L60	N00°28'56" E	113.00'
L61	N00°28'56" E	113.00'
L62	N89°31'04" W	60.00'
L64	N89°31'04" W	70.00'
L65	S00°28'56" W	113.00'
L66	S89°31'04" E	190.00'
L69	S00°28'56" W	113.00'
L70	S00°28'56" W	113.00'
L73	S89°31'04" E	60.00'
L74	S00°28'56" W	113.00'
L76	N89°31'04" W	60.00'
L77	S89°31'04" E	70.00'
L78	S89°31'04" E	60.00'
L79	S00°28'56" W	100.00'
L80	N00°28'56" E	100.00'
L81	N00°28'56" E	100.00'
L82	N00°28'56" E	100.00'
L83	N89°31'04" W	70.00'
L84	N89°31'04" W	60.00'
L85	N89°31'04" W	60.00'
L86	N00°28'56" E	113.00'
L87	N00°28'56" E	113.00'
L91	N00°28'56" E	113.00'
L92	N00°28'56" E	113.00'
L93	N89°31'04" W	190.00'
L95	N00°28'56" E	113.00'
L96	N00°28'56" E	113.00'
L98	N89°31'04" W	60.00'
L100	N00°28'56" E	113.00'
L101	N00°28'56" E	113.00'
L102	N89°31'04" W	70.00'
L103	N89°31'04" W	60.00'
L104	N89°31'04" W	60.00'
L105	N00°28'56" E	113.00'
L106	N00°28'56" E	113.00'
L110	N00°28'56" E	113.00'
L111	N00°28'56" E	113.00'
L112	N89°31'04" W	70.00'
L113	N89°31'04" W	60.00'
L114	N89°31'04" W	60.00'
L115	N00°28'56" E	100.00'
L116	N00°28'56" E	100.00'
L117	S00°28'56" W	100.00'
L118	S00°28'56" W	100.00'
L119	S00°28'56" W	100.00'
L120	N89°31'04" W	60.00'
L121	N89°31'04" W	60.00'
L122	N89°31'04" W	70.00'

SHEET INDEX

- Sheet 1 - Cover/Details Plan
- Sheet 2 - Dimension Plan
- Sheet 3 - Buildable Area Plan

CURVE TABLE

CURVE	RADIUS	ARC	LTH	CHD	LTH	CHD	BEARING	DELTA
C1	120.00'	70.18'	69.19'	S15°57'16" E	33°30'39"			
C2	150.00'	87.73'	86.49'	S15°57'16" E	33°30'39"			
C3	360.00'	0.47'	0.47'	S00°46'56" W	0°04'30"			
C4	180.02'	76.02'	75.46'	S11°26'57" E	24°11'48"			
C5	170.00'	68.63'	68.19'	S79°01'24" W	23°08'17"			
C6	200.00'	115.25'	114.62'	N2°56'28" E	33°18'05"			
C7	230.00'	103.09'	102.23'	S77°45'08" W	25°40'49"			
C8	120.00'	59.15'	58.55'	N13°19'20" W	28°14'33"			
C9	150.00'	87.73'	86.48'	N15°57'20" W	33°30'32"			
C10	180.00'	49.33'	49.17'	N21°18'55" W	15°42'05"			
C11	230.00'	59.57'	59.41'	S42°27'41" W	14°50'27"			
C12	200.00'	114.80'	113.04'	N40°52'27" E	32°49'54"			
C13	170.00'	67.28'	66.82'	N35°47'31" E	22°40'03"			
C14	230.00'	49.51'	49.42'	S30°37'31" W	12°20'03"			
C15	200.00'	230.47'	217.93'	N67°28'13" E	66°01'26"			
C16	170.00'	150.00'	145.18'	N49°44'10" E	50°33'21"			
C17	170.00'	45.90'	45.76'	N82°44'54" E	15°28'06"			
C18	30.00'	17.08'	16.85'	S17°06'45" W	32°37'36"			
C19	65.00'	11.59'	11.58'	N28°19'34" E	10°13'10"			
C20	65.00'	56.31'	54.56'	S01°37'37" E	49°38'06"			
C21	65.00'	48.95'	47.80'	S48°01'09" E	43°08'58"			
C22	65.03'	60.14'	58.02'	N63°54'16" E	52°59'34"			
C23	30.11'	16.57'	16.57'	S74°40'59" W	31°32'05"			
C24	20.03'	31.53'	28.37'	N44°23'20" W	90°10'46"			
C25	55.00'	44.41'	43.22'	N67°20'55" E	46°16'06"			
C26	55.00'	45.29'	44.02'	N20°37'19" E	47°11'05"			
C27	55.00'	41.72'	40.33'	N24°42'11" W	43°27'55"			
C28	55.00'	20.11'	20.00'	S56°54'41" E	20°57'05"			
C29	55.00'	60.77'	57.90'	S80°51'21" W	63°30'51"			
C30	55.00'	23.33'	23.15'	S36°56'54" W	24°18'03"			
C31	30.00'	34.39'	32.54'	N57°38'25" E	65°41'03"			
C32	180.00'	124.44'	121.97'	N69°24'59" W	39°36'33"			
C33	120.00'	63.58'	61.90'	N69°33'53" W	39°54'22"			
C34	150.00'	104.43'	102.37'	N69°33'53" W	39°54'21"			
C35	150.00'	103.70'	101.64'	S69°24'59" E	39°36'33"			
C36	120.00'	17.95'	17.93'	N84°56'07" W	8°34'16"			
C37	120.00'	65.01'	64.21'	N65°07'51" W	31°02'17"			
C38	180.00'	16.15'	16.14'	S32°10'55" E	50°28'25"			
C39	180.00'	77.74'	77.14'	N67°07'28" W	24°44'43"			
C40	180.00'	31.48'	31.44'	N84°30'27" W	10°01'14"			
C41	230.00'	35.48'	35.45'	S86°03'47" W	8°50'19"			
C42	230.00'	79.60'	79.21'	S71°43'44" W	19°49'47"			
C43	230.00'	100.44'	99.65'	S49°18'12" W	25°01'18"			
C44	230.00'	49.51'	49.42'	S30°37'31" W	12°20'03"			
C45	180.00'	42.48'	42.42'	N29°44'59" E	10°34'58"			
C46	180.00'	44.81'	44.69'	S06°19'58" E	14°15'48"			
C47	180.00'	28.78'	28.75'	N28°07'45" W	9°09'42"			
C48	230.00'	42.48'	42.42'	N29°44'59" E	10°34'58"			

Reeve & Associates, Inc.
 5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
 TEL: (801) 621-3100 FAX: (801) 621-2666 www.reeveco.com
 LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
 TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

DATE	DESCRIPTION
9-9-25	4 LOTS ADDED P6
9-9-25	4 LOTS ADDED P8
4/1/26	PARK ADDED
5/18/26	LOTS ADDED PHS 6

Longhorn East
 PART OF THE SE 1/4 OF SECTION 14, T.6N., R.3W., S.L.B. & M., U.S. SURVEY
 WEBER COUNTY, UTAH


Cover/Details Plan

Project Info.
 Engineer: N. Reeve
 Planner: C. Cove
 Designer: S. Simrayh
 Date: 9-9-2025
 Name: LONGHORN EAST
 Number: 6298-32

Sheet **3**
 1 Sheets

Longhorn East

Weber County, Utah



S89°13'19"E (BASIS OF BEARINGS) 2643.28'

SOUTHWEST CORNER OF SECTION 14, TOWNSHIP 6 NORTH, RANGE 3 WEST, SALT LAKE BASE AND MERIDIAN, U.S. SURVEY. FOUND WEBER COUNTY SURVEY BRASS CAP MONUMENT

SOUTH QUARTER CORNER OF SECTION 14, TOWNSHIP 6 NORTH, RANGE 3 WEST, SALT LAKE BASE AND MERIDIAN, U.S. SURVEY. FOUND WEBER COUNTY SURVEY BRASS CAP MONUMENT


LOT TABLE

- PHASE 6 - 51 Lots
- PHASE 7 - 47 Lots
- PHASE 8 - 36 Lots
- PHASE 9 - 46 Lots
- PHASE 10 - 31 Lots

Total Lots : 211

LEGEND

- = SECTION CORNER
- = BOUNDARY LINE
- = LOT LINE
- = ADJOINING PROPERTY
- = EASEMENTS
- = SECTION TIE LINE
- = PUBLIC UTILITY EASEMENT



Longhorn East

Weber County, Utah



REVISIONS

DATE	DESCRIPTION
7-23-2025	Lot Table Added
9-9-25	LOTS ADDED P6
4/1/26	PARK ADDED
5/18/26	LOTS ADDED PHS 6

Longhorn East
 PART OF THE SE 1/4 OF SECTION 14, T.6N., R.3W., S.L.B. & M., U.S. SURVEY
 WEBER COUNTY, UTAH

Dimension Plan

Project Info.
 Engineer: N. Reeve
 Planner: C. Cove
 Designer: S. Simrayh
 Date: 9-9-2025
 Name: LONGHORN EAST
 Number: 6298-32

LOT #	BUILDABLE AREA S.F.
601	3820
602	3596
603	3596
604	3596
605	3624
606	4132
607	3840
608	8242
609	8315
610	5956
611	5225
612	5195
613	5161
614	5142
615	4694
616	4854
617	4844
618	4833
619	4823
620	4812
621	4798
622	4788
623	4778
624	5019
625	5415
626	4280
627	4979
628	7089
629	7831
630	2251
631	2250
632	2250
633	2250
634	2500
635	2250
636	2250
637	2250
638	2250
639	2250
640	2500
641	2250
642	2250
643	2400
644	4901
645	4901
646	6974
647	5847
648	4934
701	2829
702	7012
703	4184
704	4498
705	4506
706	4513
707	2225
708	2980
709	3016
710	3067
711	3119
712	2902
713	4927
714	4800
715	4800
716	4800
717	4800
718	4639
719	4400
720	2250
721	2500
722	2250
723	2250
724	2600
725	2250
726	2250
727	2250
728	2250
729	2250
730	2250
731	2250
732	2250
733	2900
734	2250
735	2250
736	2250
737	3150
738	2835
739	2835
740	2835
741	2835
742	3150
743	2250
744	2250
745	2250
746	2250
747	2869
801	2835
802	2835
803	3150
804	3150
805	2835
806	2835
807	2835
808	2835
809	3150
810	3150
811	2835
812	2835
813	2835
814	2835
815	3150
816	3150
817	2835
818	2835
819	2835
820	2835
821	2835
822	2835
823	2835
824	2835
825	2835
826	2835
827	2835
828	2835
829	2835
830	2835


LOT #	BUILDABLE AREA S.F.
831	2835
832	2835
833	2835
834	2835
835	2835
836	2835
901	2835
902	2835
903	3150
904	3150
905	2835
906	2835
907	2835
908	2835
909	3150
910	3150
911	2835
912	2835
913	2835
914	2835
915	3150
916	3150
917	2835
918	2835
919	2835
920	2835
921	2835
922	2835
923	2835
924	2835
925	2835
926	2835
927	2835
928	2835
929	2835
930	2835
931	2835
932	2835
933	2835
934	2835
935	2835
936	2835
937	3024
938	3024
939	3024
940	3024
941	3024
942	3024
943	2811
944	2811
945	2811
946	2811
1001	4560
1002	4560
1003	4560
1004	4560
1005	4560
1006	4560
1007	4560
1008	4560
1009	4800
1010	4800
1011	4800
1012	4800
1013	4800
1014	8825
1015	4429
1016	6440
1017	6067
1018	6996
1019	3900
1020	5063
1021	5437
1022	3024
1023	2744
1024	2250
1025	2250
1026	2250
1027	2250
1028	2250
1029	2250
1030	2250
1031	2250
1032	2250



SETBACK NOTE
 ZONE R1-15
 FRONT SETBACK: 20'
 SIDE SETBACK: 5' ON ONE SIDE & 10' ON THE OTHER/15' CORNER LOTS
 REAR SETBACK: 30'

Longhorn East

Weber County, Utah



REVISIONS	DATE	DESCRIPTION
1	9-9-25	4 LOTS ADDED P6
2	9-9-25	6 LOTS ADDED P8
3	4/1/26	PARK ADDED
4	5/18/26	LOTS ADDED PHS 6

Longhorn East
 PART OF THE SE 1/4 OF SECTION 14, T.6N., R.3W., S.L.B. & M., U.S. SURVEY
 WEBER COUNTY, UTAH

Buildable Area Plan

Project Info.
 Engineer: N. Reeve
 Planner: C. Cove
 Designer: S. Simrayh
 Date: 9-9-2025
 Name: LONGHORN EAST
 Number: 6298-32

Exhibit B

West Warren-Warren Water Improvement District
1561 S. 7500 W.
Ogden, UT 84404
801-259-7614
westwarrentwtr@gmail.com

November 6, 2025

To Whom it May Concern:

RE: UPDATED WATER AVAILABILITY LETTER FOR Longhorn East c/o Lyn Construction

This proposed development is located at North-East of 7100 W 900 S. in West Warren, Weber County, Utah. It is proposed to have 208 residences. The West Warren-Warren Water Improvement District (hereafter the District) does have culinary water available for this proposed development. Secondary water for this development will be provided with shares from Warren Irrigation.


This letter is only to state that the above-mentioned project is in the boundaries of the District and water may only be made available if the following conditions are met. This letter is the first of two letters that will be issued for this development. When these and any necessary additional conditions are met, the District may issue the Will-Serve Letter.

Conditions for a Will-Serve Letter to be issued:

- The land must be annexed into the District's taxable boundaries, if not done already.
- A letter from the Fire District stating that a flow test is not required, will need to be provided to the District as soon as possible.
- Proof of access to secondary water and engineered calculations to prove sufficient shares, time, etc, to produce sufficient acre feet for the development.
- A plan for installation of a functioning, pressurized, secondary water delivery system, including an engineered pond, for any subdivision over 2 lots, to be inspected and approved by the WWWID board chairman, prior to the delivery of any culinary water, including water for construction use. Pressure requirements are a minimum of 50 to a maximum of 80 lbsp.
- The owner or contractor will need to furnish all materials and labor to run the service line. The District will furnish and place the water meter. All materials and workmanship must be in compliance with and approved by the District.
- The Weber Basin Water Rights Impact Fee of \$10,082.00 per proposed unit of service, must be paid prior to receiving a Will-Serve Letter and prior to the commencement of any development or construction as well as \$100.00 fee for water for construction.
- All remaining fees according to the most current District fee schedule at the time a will-serve letter is approved, must be paid to the District before culinary water services may be made available. Be advised that all fees are subject to change with future public hearings.

Should you have clerical questions or comments, please contact the district clerk. Please direct questions regarding water systems, materials, etc., to (801-791-7368) Randy Giordano, Chairman of the WWWID Board. This letter expires 1 year from the day it is issued.

Sincerely,


Melissa Murray, Clerk



Water Service Availability Letter

June 1, 2026

West Weber City Planning
Re: Longhorn East Subdivision
Parcel #'s 10-036-0068

To Whom It May Concern:

This letter is to confirm that secondary (non-potable) irrigation water service may be available to the property located at Approx 6100 W 700 S, West Weber, Utah through the Weber Box Elder Conservation District. This determination will be made once we have reviewed the subdivision improvement plans and completed the modeling process.

This property is not currently part of the secondary water district. Water service will be made available upon completion of the inclusion process. This process includes approval of our Board of Directors, payment of all required fees, and the provision of sufficient water shares to bring the property into the water district.

Availability of water service is contingent upon meeting all applicable requirements and standards.

This water availability letter shall remain valid for one (1) year from the date issued. The District reserves the right to require an updated letter if significant development occurs, system conditions change, or the District otherwise determines that an update is necessary.

Please contact me with any questions or concerns.

Sincerely,
Jacee Bingham
jbingham@pineviewwater.com
Assessment Clerk
Pineview Water Systems
801-622-4352

471 West 2nd Street
Ogden, UT 84404
801-621-6555



LITTLE MOUNTAIN SERVICE AREA DISTRICT (LMSA) WASTEWATER WILL-SERVE LETTER

Dear Mr. Burns,

May 14, 2026

The Little Mountain Service Area (LMSA) is pleased to inform you that, based on your application and supporting documentation, LMSA has the potential future capacity, capability, and authority to provide sewer conveyance services for the proposed project area located on parcels #100360043, #100360066, #101770017, and #100350072.

This Will-Serve Letter confirms that the project area may obtain future access to the proposed LMSA regional wastewater transmission system, including the future sewer transmission line and lift station located at or near 5900 West, subject to the following conditions and requirements:

1. Availability of Services:

- Service availability is also contingent upon LMSA acquiring ownership and operational control of the constructed wastewater infrastructure upon completion.
- Conveyance service availability shall remain subject to system capacity, operational capability, and LMSA authority at the time of final connection application.

2. Engineering Plan and System Approval Requirements:

- Any proposed sewer conveyance design plans associated with this project area must be reviewed by LMSA's engineering firm and approved by the Central Weber Sewer Improvement District Board prior to construction authorization or connection approval.
- **Issuance of this Will-Serve Letter does not constitute authorization for construction, physical connection, or system tie-in approval.**

3. Petitioner Responsibilities:

- The petitioner is responsible for all associated user, impact, and connection fees.
- Costs for design, construction, maintenance, permitting, and installation of all lateral lines and associated infrastructure necessary to connect to the future LMSA wastewater conveyance system shall be the petitioner's responsibility unless otherwise agreed to in writing by LMSA.
- All wastewater conveyance activities, design, and construction must comply with applicable federal, state, and local regulations, as well as LMSA policies, standards, and engineering requirements.

4. Request for Connection Application and Fees:

- Prior to any physical connection to the LMSA system, a formal Request for Connection application must be submitted and approved.
- All applicable connection fees and related charges must be paid in full prior to construction or tie-in to the system.

5. Service Agreement and Fee Structure:

- Prior to connecting to the LMSA system, an approved service agreement must be executed.
- A fee structure outlining all applicable costs, including connection fees, user rates, and other related charges, shall be established and agreed upon prior to service activation.

6. Connection Application Review Process:

- Applications are reviewed monthly during LMSA Board Meetings.

7. Connection Application Fee:

- A non-refundable application fee of \$300.00 is due upon submission.
- Please make checks payable to Little Mountain Service Area.



LITTLE MOUNTAIN SERVICE AREA DISTRICT (LMSA) WASTEWATER WILL-SERVE LETTER

This Will-Serve Letter is valid for a period of twelve (12) months from the date of issuance and is contingent upon compliance with all applicable requirements, approvals, and regulations. Failure to adhere to these conditions may result in revocation of future service availability.

If you have any questions or require further information, please do not hesitate to contact me at 404.343.6746 or srussell@sagedevelopmentgroup.com.

Stephanie Russell
LMSA Board and Project Manager



Central Weber Sewer Improvement District

March 4, 2026

Felix Llevernio
Weber County Planning Commission
2380 Washington Blvd #240, Ogden, UT 84401

SUBJECT: Meibos
Sanitary Sewer Service
Will Serve Letter

Felix:

We have reviewed the request of Pat Burns to provide sanitary sewer treatment services to the subdivision called Meibos comprising 208 residential lots located at approximate address 6700 West 691 South, Weber County. We offer the following comments regarding Central Weber providing sanitary sewer service.

1. At this time, Central Weber Sewer Improvement District (District) has the capacity to treat the sanitary sewer flow from this subdivision. Inasmuch as the system demand continuously changes with growth, this assessment is valid for three (3) years from the date issued on this letter.
2. If any connection is made directly into the District's facilities the connection must be constructed in accordance with District standards and must be inspected by the District while the work is being done. A minimum of 48-hour notice for inspection shall be given to the District prior to any work associated with the connection.
3. Central Weber Sewer Improvement District is a wholesale wastewater treatment provider to Weber County. Connection to the sewer system must be through a retail provider, which we understand to be Weber County. The District will not take responsibility for the condition, ownership or maintenance of the proposed sanitary sewer lines (gravity or pressure) or system that will be installed to serve this subdivision.
4. We understand the intent of the developer is to connect to facilities currently planned by the Promontory Commerce Center Public Infrastructure Districts. Central Weber Sewer Improvement District is not responsible for the construction of these facilities and you are advised to coordinate directly with the Promontory Commerce Center Public Infrastructure Districts regarding the construction schedule and available capacity.



Central Weber Sewer Improvement District

5. The connection of any sump pumps (or similar type pumps) to the sanitary sewer system is prohibited during or after construction. The District's Wastewater Control Rules and Regulations state:

Prohibited Discharge into Sanitary Sewer. No person shall discharge or cause or make a connection which would allow to be discharged any storm water, surface water, groundwater, roof water runoff or subsurface drainage to any sanitary sewer. Maximum of 500 gallons per day discharge per unit.

6. **The entire parcel of property to be served must be annexed into the Central Weber Sewer Improvement District prior to any sewer service connection or connection to the District's facilities.** This annexation must be complete before the sale of any lots in the subdivision. Annexation into the District is permitted by the District's Board of Trustees. This will serve letter is a statement of available capacity and does not guarantee board approval of annexation.
7. Impact fees must be paid no later than the issuance of any building permits.

If you have any further questions or need additional information, please let us know.

Sincerely,


Digitally signed by Clayton Marriott
DN: cn=US, e=Clayton@centralweberut.gov, ou=Central Weber Sewer Improvement District, cn=Clayton Marriott
Reason: I am the author of this document
Date: 2025.03.05 08:53:19-07:00

Clay Marriott


Project Manager

CC: Chad Meyerhoffer, Weber County
Kevin Hall, Central Weber Sewer
Paige Spencer Central Weber Sewer
Pat Burns

Exhibit E



VICINITY MAP
(NOT TO SCALE)




LEGEND

- = PARKING/PARK ACCESS
TOTAL ACREAGE: 0.74
- = IMPROVED PARK
TOTAL ACREAGE: 6.73
- = DETENTION
- = LOTS
- = PROPOSED TRAIL
TOTAL LINEAR FEET: 2,512.75
(EXCLUDES ROAD TRAILS)

BOUNDARY DESCRIPTION

PART OF THE SOUTHEAST QUARTER OF SECTION 14, TOWNSHIP 6 NORTH, RANGE 3 WEST, SALT LAKE BASE AND MERIDIAN, U.S. SURVEY. MORE PARTICULARLY DESCRIBED AS FOLLOWS:
 BEGINNING AT A POINT BEING 1335.30 FEET NORTH 00°38'39" EAST FROM THE SOUTH QUARTER CORNER OF SAID SECTION 14; THENCE NORTH 00°38'39" EAST 1335.30 FEET; THENCE SOUTH 89°31'02" EAST 1814.20 FEET; THENCE SOUTH 01°07'35" WEST 549.07 FEET; THENCE SOUTH 89°24'27" EAST 402.07 FEET; THENCE SOUTH 00°47'57" WEST 205.71 FEET; THENCE NORTH 89°12'03" WEST 33.71 FEET; THENCE SOUTH 00°47'42" WEST 150.12 FEET; THENCE SOUTH 89°24'27" EAST 436.30 FEET; THENCE SOUTH 00°47'57" WEST 60.00 FEET; THENCE NORTH 89°24'27" WEST 291.00 FEET; THENCE SOUTH 00°47'57" WEST 375.16 FEET; THENCE NORTH 89°22'46" WEST 2321.11 FEET TO THE POINT OF BEGINNING.
 CONTAINING 2,799,569 SQUARE FEET OR 64.269 ACRES.



STREET TYPE KEY:
 STREET TYPE 'A' - MAJOR RESIDENTIAL (66' R.O.W.)
 STREET TYPE 'B' - MINOR RESIDENTIAL (60' R.O.W.)
 STREET TYPE 'C' - MINOR COLLECTOR (80' R.O.W.)

Longhorn East

Weber County, Utah

Reeve & Associates, Inc.
 910 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
 TEL: 435.338.1100 FAX: 435.338.1101
 WWW.REEVE-ASSOCIATES.COM

REVISIONS	DESCRIPTION
DATE	

Longhorn East
 PART OF THE SE 1/4 OF SECTION 14, T.6N, R.3W, S.14B & M., U.S. SURVEY
 WEBER COUNTY, UTAH

Connectivity Plan

Project Info.

Engineer:	N. Reeve
Planner:	C. Cave
Designer:	S. Simrayh
Date:	4-1-26
Name:	LONGHORN EAST
Number:	6298-32

Sheet	1
1	Sheets


Exhibit F

Longhorn Subdivision Phases 6-10 Improvement Plans



WEBER COUNTY, UTAH
APRIL 2026

Project Narrative/Notes/Revisions

- 05/15/2026 CK - COMPLETED DESIGN FOR CLIENT & CITY REVIEW.
- 06/15/2026 CK - UPDATED SEWER OUTFALL PIPE LOCATION.
- 06/25/2026 CK - FIRE COMMENTS.
- 06/29/2026 CK - MOVED FIRE HYDRANTS.



VICINITY MAP
SCALE: NONE



Reeve & Associates, Inc.
5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
TEL: (801) 621-3100 www.ra-inc.com


RA

LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS	DATE	DESCRIPTION
06-15-26	CK	SS Outfall
06-25-26	CK	Fire Comments
06-29-26	CK	Fire Hydrants

**Longhorn Subdivision
Phases 6-10**
WEBER COUNTY, UTAH

Cover Sheet



Project Info.
Designer: KENNETH H. HUNTER, P.E.
Drafter: C. KINGSLEY
Begin Date: APRIL 2026
Name: LONGHORN SUBDIVISION PHASES 6-10
Number: 6298-35

Elevation Datum:
SITE BENCHMARK:
TOP OF BRASS CAP FOR
WEBER COUNTY BENCHMARK
223. NAVD88 PER WEBER
COUNTY SURVEY STATIC GPS



Project Contact:
Jeremy Draper
Reeve & Associates, Inc.
5160 South 1500 West
Riverdale, Utah, 84405
PH:(801) 621-3100

Surveyor:
Jason Felt
Reeve & Associates, Inc.
5160 South 1500 West
Riverdale, Utah, 84405
PH:(801) 621-3100

Landscape Architect:
Nathan Peterson
Reeve & Associates, Inc.
5160 South 1500 West
Riverdale, Utah, 84405
PH: (801) 621-3100

Engineer's Notice To Contractors:
THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITY PIPES OR STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED FROM AVAILABLE INFORMATION PROVIDED BY OTHERS. THE LOCATIONS SHOWN ARE APPROXIMATE AND SHALL BE CONFIRMED IN THE FIELD BY THE CONTRACTOR, SO THAT ANY NECESSARY ADJUSTMENT CAN BE MADE IN ALIGNMENT AND/OR GRADE OF THE PROPOSED IMPROVEMENT. THE CONTRACTOR IS REQUIRED TO CONTACT THE UTILITY COMPANIES AND TAKE DUE PRECAUTIONARY MEASURE TO PROTECT ANY UTILITY LINES SHOWN, AND ANY OTHER LINES OBTAINED BY THE CONTRACTOR'S RESEARCH, AND OTHERS NOT OF RECORD OR NOT SHOWN ON THESE PLANS.





Construction Notes:

- 1) ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
- 2) CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS. TRUNCATED DOMES TO BE GRAY IN COLOR.
- 3) ALL WATER & SEWER MAINS & LATERALS TO MAINTAIN 10' MINIMUM HORIZONTAL CLEARANCE & MAINTAIN 18" VERTICAL CLEARANCE. SLEEVE SEWER WHEN 18" EDGE-EDGE VERTICAL CLEARANCE UNDER WATER CANNOT BE MAINTAINED.
- 4) CULINARY WATER SYSTEM TO BE CONSTRUCTED TO WEST WARREN-WARREN WID STANDARDS. ITEMS NOT COVERED BY WID STANDARDS TO BE COUNTERSTRUCTED TO APWA STANDARDS.
- 5) SECONDARY WATER METERS REQUIRED AT EACH LOT.
- 6) PRESERVE ALL EXISTING CURB AND GUTTER AND OTHER EXISTING IMPROVEMENTS.
- 7) FIELD VERIFY ALL EXISTING STORM DRAIN DEPTHS AND ROUTING

CULINARY WATER
 NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
 W/8 - 8" DR18 C900 PVC WATER LINE
 W - 1" CTS SDR9 HDPE SERVICE LATERAL



SANITARY SEWER
 SS/4 - 4" PVC SDR-35 SERVICE LATERAL
 SS/8 - 8" PVC SDR-35 SEWER LINE
 SS/10 - 10" PVC SDR-35 SEWER LINE
 SS/12 - 12" PVC SDR-35 SEWER LINE

STORM DRAIN
 SD/15 - 15" RCP CLASS III STORM DRAIN
 SD/18 - 18" RCP CLASS III STORM DRAIN
 SD/24 - 24" RCP CLASS III STORM DRAIN
 SD/36 - 36" RCP CLASS III STORM DRAIN

SECONDARY WATER
 SW/8 - 8" DR-14 PVC C-900 SECONDARY WATER LINE
 SW LAT- (SINGLE SERVICE) 1.0" CTS HDPE PIPE SERVICE LATERAL
 SW LAT- (MULTIPLE METER BANK) 2.0" CTS HDPE PIPE SERVICE LATERAL

MINIMUM SLEEVE SIZE REQUIREMENT:
 CASING 4" SEWER LATERAL = 8"x20" CENTERED AT CROSSING
 CASING 8" SEWER MAIN = 12"x20" CENTERED AT CROSSING
 CASING 10" SEWER MAIN = 15"x20" CENTERED AT CROSSING
 CASING 12" SEWER MAIN = 16"x20" CENTERED AT CROSSING

Holstein Drive 26+30.00 - 30+10.00



Reeve & Associates, Inc.
 5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
 TEL: (801) 621-3100 www.reeve.co

PA
 LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
 TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS	DATE	DESCRIPTION
06-15-26 CK	SS	Outfall
06-25-26 CK	Fire	Comments
06-29-26 CK	Fire	Hydrants


Longhorn Subdivision
Phases 6-10
 WEBER COUNTY, UTAH

Holstein Drive 26+30.00 - 30+10.00




Project Info.

Designer: KENNETH H. HUNTER, P.E.
 Drafter: C. KINGSLEY
 Begin Date: APRIL 2026
 Name: LONGHORN SUBDIVISION PHASES 6-10
 Number: 6298-35



Key Map

NOT TO SCALE



Construction Notes:

- 1) ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
- 2) CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS. TRUNCATED DOMES TO BE GRAY IN COLOR.
- 3) ALL WATER & SEWER MAINS & LATERALS TO MAINTAIN 10' MINIMUM HORIZONTAL CLEARANCE & MAINTAIN 18" VERTICAL CLEARANCE. SLEEVE SEWER WHEN 18" EDGE-EDGE VERTICAL CLEARANCE UNDER WATER CANNOT BE MAINTAINED.
- 4) CULINARY WATER SYSTEM TO BE CONSTRUCTED TO WEST WARREN-WARREN WID STANDARDS. ITEMS NOT COVERED BY WID STANDARDS TO BE CONSTRUCTED TO APWA STANDARDS.
- 5) SECONDARY WATER METERS REQUIRED AT EACH LOT.
- 6) PRESERVE ALL EXISTING CURB AND GUTTER AND OTHER EXISTING IMPROVEMENTS.
- 7) FIELD VERIFY ALL EXISTING STORM DRAIN DEPTHS AND ROUTING

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
 W/8 - 8" DR18 C900 PVC WATER LINE
 W - 1" CTS SDR9 HDPE SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
 SS/8 - 8" PVC SDR-35 SEWER LINE
 SS/10 - 10" PVC SDR-35 SEWER LINE
 SS/12 - 12" PVC SDR-35 SEWER LINE

STORM DRAIN


SD/15 - 15" RCP CLASS III STORM DRAIN
 SD/18 - 18" RCP CLASS III STORM DRAIN
 SD/24 - 24" RCP CLASS III STORM DRAIN
 SD/36 - 36" RCP CLASS III STORM DRAIN

SECONDARY WATER



SW/8 - 8" DR-14 PVC C-900 SECONDARY WATER LINE
 SW LAT- (SINGLE SERVICE) 1.0" CTS HDPE PIPE SERVICE LATERAL
 SW LAT- (MULTIPLE METER BANK) 2.0" CTS HDPE PIPE SERVICE LATERAL

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL = 8"x20" CENTERED AT CROSSING
 CASING 8" SEWER MAIN = 12"x20" CENTERED AT CROSSING
 CASING 10" SEWER MAIN = 15"x20" CENTERED AT CROSSING
 CASING 12" SEWER MAIN = 16"x20" CENTERED AT CROSSING



6700 West 13+00.00 - 22+25.76




Reeve & Associates, Inc.
 5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
 LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
 TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS	DATE	DESCRIPTION
06-15-26	CK	SS Outfall
06-25-26	CK	Fire Comments
06-29-26	CK	Fire Hydrants


Longhorn Subdivision
Phases 6-10
 WEBER COUNTY, UTAH


6700 West 13+00.00 - 22+25.76





Project Info.

Designer: KENNETH H. HUNTER, P.E.
 Drafter: C. KINGSLEY
 Begin Date: APRIL 2026
 Name: LONGHORN SUBDIVISION PHASES 6-10
 Number: 6298-35






6700 West 22+25.76 - 31+49.80



Key Map



Construction Notes:

- 1) ALL CONSTRUCTION IS TO CONFORM TO THE COUNTY STANDARD DRAWINGS AND SPECIFICATIONS.
- 2) CONSTRUCT HANDICAP RAMP PER ADA AND COUNTY REQUIREMENTS. TRUNCATED DOMES TO BE GRAY IN COLOR.
- 3) ALL WATER & SEWER MAINS & LATERALS TO MAINTAIN 10' MINIMUM HORIZONTAL CLEARANCE & MAINTAIN 18" VERTICAL CLEARANCE. SLEEVE SEWER WHEN 18" EDGE-EDGE VERTICAL CLEARANCE UNDER WATER CANNOT BE MAINTAINED.
- 4) CULINARY WATER SYSTEM TO BE CONSTRUCTED TO WEST WARREN-WARREN WID STANDARDS. ITEMS NOT COVERED BY WID STANDARDS TO BE CONSTRUCTED TO APWA STANDARDS.
- 5) SECONDARY WATER METERS REQUIRED AT EACH LOT.
- 6) PRESERVE ALL EXISTING CURB AND GUTTER AND OTHER EXISTING IMPROVEMENTS.
- 7) FIELD VERIFY ALL EXISTING STORM DRAIN DEPTHS AND ROUTING

CULINARY WATER

NOTE: 4' MIN. COVER REQUIRED OVER CW LINES
 W/8 - 8" DR18 C900 PVC WATER LINE
 W - 1" CTS SDR9 HDPE SERVICE LATERAL

SANITARY SEWER

SS/4 - 4" PVC SDR-35 SERVICE LATERAL
 SS/8 - 8" PVC SDR-35 SEWER LINE
 SS/10 - 10" PVC SDR-35 SEWER LINE
 SS/12 - 12" PVC SDR-35 SEWER LINE

STORM DRAIN

SD/15 - 15" RCP CLASS III STORM DRAIN
 SD/18 - 18" RCP CLASS III STORM DRAIN
 SD/24 - 24" RCP CLASS III STORM DRAIN
 SD/36 - 36" RCP CLASS III STORM DRAIN

SECONDARY WATER

SW/8 - 8" DR-14 PVC C-900 SECONDARY WATER LINE
 SW LAT- (SINGLE SERVICE) 1.0" CTS HDPE PIPE SERVICE LATERAL
 SW LAT- (MULTIPLE METER BANK) 2.0" CTS HDPE PIPE SERVICE LATERAL

MINIMUM SLEEVE SIZE REQUIREMENT:

CASING 4" SEWER LATERAL = 8"x20" CENTERED AT CROSSING
 CASING 8" SEWER MAIN = 12"x20" CENTERED AT CROSSING
 CASING 10" SEWER MAIN = 15"x20" CENTERED AT CROSSING
 CASING 12" SEWER MAIN = 16"x20" CENTERED AT CROSSING

Reeve & Associates, Inc.
 5160 SOUTH 1500 WEST, RIVERDALE, UTAH 84405
 TEL: (801) 621-3100 www.reeve.co

LAND PLANNERS • CIVIL ENGINEERS • LAND SURVEYORS
TRAFFIC ENGINEERS • STRUCTURAL ENGINEERS • LANDSCAPE ARCHITECTS

REVISIONS	DATE	DESCRIPTION
06-15-26	CK	SS Outfall
06-25-26	CK	Fire Comments
06-29-26	CK	Fire Hydrants


Longhorn Subdivision
Phases 6-10
 WEBER COUNTY, UTAH

6700 West 22+25.76 - 31+49.80



Project Info.

Designer: KENNETH H. HUNTER, P.E.
 Drafter: C. KINGSLEY
 Begin Date: APRIL 2026
 Name: LONGHORN SUBDIVISION PHASES 6-10
 Number: 6298-35





Synopsis

Application Information

Application Request: Consideration and action on a request for preliminary approval of the Riverbend Farms Cluster Subdivision Phase 1 First Amendment, to relocate open space and plat a ten lot subdivision over a 3.7 acre parcel located on the corner of 900 South Street and 3600 West Street.

Agenda Date: Tuesday, July 07, 2026

Applicant: Joseph Herring

File Number: LVR061626

Property Information

Approximate Address: 900 S 3600 W

Project Area: 6.7 acres

Zoning: Agricultural A-1 and A-2

Existing Land Use: Vacant/Cluster Open Space

Proposed Land Use: Residential/ Agricultural

Parcel ID: 15-823-0049, 15-043-0097

Township, Range, Section: T2N, R2W, Sections 15 and 16

Adjacent Land Use

North: Residential/Agricultural	South: Residential/Agricultural
East: Residential	West: Hooper Irrigation Co.

Staff Information

Report Presenter: Felix Lleverino
 flleverino@webercountyutah.gov
 801-399-8767

Report Reviewer: TA

Applicable Ordinances

- Title 101, Chapter 1 General Provisions, Section 7, Definitions
- Title 104, Chapter 2 Agricultural Zones
- Title 108, Chapter 3 Cluster Subdivisions

Development History

The Riverbend Farms Cluster Subdivision Phase 1 was recorded on July 26, 2023.

Summary

This is a request for preliminary subdivision approval of an amendment to Riverbend Farms Cluster Subdivision Phase 1. The original cluster subdivision plan was approved with 72.2 acres gross acres. After deducting for roads, the net developable area is 62.13 acres. The cluster code was written to preserve at least 30% of the net developable open space in the Agricultural A-1 and A-2 zones. This plan preserved 64 percent open space.

The process for a cluster subdivision proposal begins with a sketch plan endorsement from the planning commission before review of a preliminary subdivision application. The cluster subdivision ordinance is now repealed, as May 26, 2026, under Ordinance Number 2026-06. So the planning division, under the direction of the county attorney, recommends that the planning commission remain the approval body for this cluster subdivision amendment. The County Commission will be the approval body for the relocation of the open space since the original cluster subdivision dedicated an open easement over all of the common area and agricultural parcels. The planning division will create a resolution to be approved by the County Commission, which will allow for the relocation of the open space, while the amended subdivision plat will serve as the legal document memorializing the amendment. The Planning Director will remain the land use authority for final Subdivision approval.

Analysis

General Plan: With conditions stated in the Staff Recommendation. This proposal does not conflict with the Weber County General Plan as it relates to residential development and open space preservation along the Weber River Corridor.

Zoning: The property is located within the A-1 and A-2 Zones. The purpose of these zones is stated in the LUC §104-2.

- a) The A-1 Zone is an agricultural zone and a low-density rural residential zone. The purpose of the A-1 Zone is to:
 1. Designate low-intensity farm areas, which are anticipated to develop in a rural residential development pattern;
 2. Set up guidelines to continue agricultural pursuits, including the keeping of farm animals; and
 3. Direct orderly low-density residential development in a continuing rural environment.
- b) The A-2 Zone is both an agricultural zone and a low-density rural residential zone. The purpose of the A-2 Zone is to designate moderate-intensity farming areas where agricultural pursuits and the rural environment should be promoted and preserved where possible.

Site Development Standards: The minimum lot size for lots within a cluster subdivision in the A-1 and A-2 Zones is 60 wide and 9000 sq. ft. in area. All lots within this development meet or exceed the minimum requirement.

Bonus Density: The following table provides area calculations for the entire development, including the land area of the proposed amendment:

Gross Acreage	Area deducted for roads	Net developable Area	Open Space	Percentage of Open Space
78.944	10.415	68.529	43.047	62%

The Riverbend Farms Cluster Subdivision Phase 1 contains a total of 48 lots; with the inclusion of more land, Phase 1 will have a total of 58 lots.

Weber County Code requires that each phase preserve the appropriate amount of open space. With the inclusion of the 3.02 acres, Phase 1 is preserving 54% open space. Since this development was granted a 50% bonus density, the following criteria must be met:

1. Provide a minimum 50 percent open space of the net developable acreage, as defined in section 101-1-7.
2. Provide one street tree of at least two-inch caliper, from a species list as determined by county policy, every 50 feet on both sides of each street within the subdivision boundaries. In the event infrastructure or a driveway approach makes a tree's placement impossible, that tree shall be located as close to the 50-foot spacing as otherwise reasonably possible, provided compliance with the clear view triangle as defined in section 108-7-7.
3. Comply with all provisions of title 108, chapter 16: Ogden Valley Outdoor Lighting Ordinance, which is incorporated by reference herein as applicable to a cluster subdivision in the Western Weber Planning Area that receives bonus density. A note shall be placed on the final subdivision plat indicating this requirement.

Pathways: A ten-foot pathway along 900 South Street, 3600 West Street, and through the open space river corridor is required

Open Space: The open space parcel that will be dedicated as a common area with an open easement dedicated to Weber County has the potential to be held by the HOA with the option of being deeded to the park district for open space along the river corridor, with a ten-foot pathway as intended by the Weber County General Plan. The planned ten lot subdivision will be developed on land which is individually owned by Riverbend Farms LLC, a subsidiary of Nilson Land Development.

Flood Zone: This lot development parcel is within the 500-year floodplain area of the Weber River according to the April 12, 2021 Flood Insurance Rate Map FIRM.

Culinary Water: The preliminary will-serve letter from Taylor West Weber Water District is included. The District will provide only culinary water to the Riverbend Amended 10-lot subdivision with the condition that a pressurized secondary water system must be functional before final approval from the District is granted. The subdivision plan must include a signature block for the Taylor West Weber Water District.

3600 West Street: The Street Master Plan for this area shows that 3600 West Street is planning Future Major Collector (100' ROW). For this propose the planning division is recommending elements:

1. The appropriate ROW dedication is made to 3600 West and 900 South

2. Driveway access from 3600 West is limited. The use of shared accesses is permitted under Section 106-2-2.050 (b) and designed in accordance with 108-7-29.
3. Section 106-2-1.020 (d) (2) requires a ten foot pathway along all collector streets.

Sewer Services: Central Weber Sewer District has provided a will-serve letter stating that the District can serve this development. The District will need to approve the connection plans and inspect the connection. The area proposed for lot development is annexed into the district.

Review Agencies: The Weber County Planning and Engineering have submitted comments that will be addressed by a revised subdivision plat and revised civil drawings. The County Surveyor's office will submit comments regarding final subdivision plat revisions. The Weber Fire District has posted its approval, further requirements will become necessary at the final stage of the review process and at the time of building permits.

Staff Recommendations

Staff recommends preliminary approval of the Riverbend Farms Cluster Subdivision Phase 1 First Amendment. This recommendation is based on all review agency requirements and upon the following conditions:

1. Developer shall provide a cost estimate for all subdivision improvements, including a 10' open space common area pathway along the river, a 10' pathway on the north side of 900 South Street, a 10' pathway on the west side of 3600 West Street, and street trees.
2. Developer shall provide final will-serve letters from the Hooper Irrigation Company and the Taylor West Weber Water District before final subdivision approval.
3. The final subdivision plat shall include a signature block for Taylor West Weber Water District.
4. The final plan will show open space pathway dedication and shared access from properties fronting 3600 West Street.


This recommendation is based on the following findings:

1. The proposed subdivision conforms to the Weber County General Plan.
2. The proposed subdivision complies with the applicable County codes.
3. The subdivision conforms to zoning and subdivision ordinances.

Exhibits

- A. Riverbend Farms Cluster Subdivision Phase 1 First Amendment plat
- B. Riverbend Farms Phase 1 plat (2023)
- C. Civil Drawings (select pages)
- D. Will serve letters

Area Map







Exhibit A



- GENERAL NOTES**
1. ALL WORK TO COMPLY WITH THE GOVERNING AGENCY'S STANDARDS AND SPECIFICATIONS.
 2. ALL IMPROVEMENTS MUST COMPLY WITH ADA STANDARDS AND RECOMMENDATIONS.
 3. ALL PAVEMENT MARKINGS SHALL CONFORM TO THE LATEST EDITION OF THE M.U.T.C.D. (MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES).
 4. ALL SURFACE IMPROVEMENTS DISTURBED BY CONSTRUCTION SHALL BE RESTORED OR REPLACED, INCLUDING TREES AND DECORATIVE SHRUBS, SOIL, FENCES, WALLS AND STRUCTURES, WHETHER OR NOT THEY ARE SPECIFICALLY SHOWN ON THE CONTRACT DOCUMENTS.
 5. NOTIFY ENGINEER OF ANY DISCREPANCIES IN DESIGN OR STAKING BEFORE PLACING CONCRETE OR ASPHALT.
 6. THE CONTRACTOR IS TO PROTECT AND PRESERVE ALL EXISTING IMPROVEMENTS, UTILITIES, AND SIGNS, ETC. UNLESS OTHERWISE NOTED ON THESE PLANS.

ENSIGN
THE STANDARD IN ENGINEERING

LAYTON
919 North 400 West
Layton, UT 84041
Phone: 801.547.1100

SANDY
Phone: 801.255.0529

TOOELE
Phone: 435.843.3590

CEDAR CITY
Phone: 435.865.1453

RICHFIELD
Phone: 435.896.2983

WWW.ENSIGNENG.COM


FOR:
NILSON HOMES
1740 COMBE ROAD, SUITE 2
SOUTH OGDEN, UTAH 84403

CONTACT:
STEVE ANDERSON
PHONE: 801-392-8100

**RIVERBEND FARMS WEST
SUBDIVISION**
850 SOUTH 3600 WEST
WEBER COUNTY, UTAH



LAND USE TABLE		
LOT AREA	140,111 sq. ft.	46.3%
ROADWAY DEDICATION	31,043 sq. ft.	10.2%
OPEN SPACE	131,860 sq. ft.	43.5%
TOTAL PROJECT AREA	303,014 sq. ft.	100%
ACREAGE	6.956 acres	
TOTAL LOTS	10	
DENSITY	1.43 UNITS/ACRE	
AVERAGE LOT AREA	14,011 sq. ft.	



**PRELIMINARY OVERALL
SITE PLAN**

PROJECT NUMBER: 14027
PROJECT MANAGER: C. PRESTON

PRINT DATE: 2026-05-01
DESIGNED BY: M. ELMER


C-100

Riverbend Farms Phase 1

A part of Section 15 and Section 16, T6N, R2W, SLB&M, U.S. Survey,
Weber County, Utah
May 2023



Scale: 1" = 60'



Legend

- ▲ Set Nail & Washer
- Set Rebar & Cap w/ fencepost
- Set Hub & Tack Monument to be set
- (Rad.) Radial Line
- (N/R) Non-Radial Line
- - - Fence
- P.U.E. Public Utility Easement






Exhibit C

RIVERBEND FARMS WEST SUBDIVISION PRELIMINARY PLAT

PRELIMINARY
FOR REVIEW
NOT FOR CONSTRUCTION

DATE PRINTED
May 1, 2026

850 SOUTH 3600 WEST
WEBER COUNTY, UTAH

INDEX OF DRAWINGS

C-001	GENERAL NOTES
C-100	PRELIMINARY OVERALL SITE PLAN
C-101	PRELIMINARY SITE PLAN
C-200	PRELIMINARY GRADING AND DRAINAGE PLAN
C-300	PRELIMINARY UTILITY PLAN

NOTICE TO CONTRACTOR

ALL CONTRACTORS AND SUBCONTRACTORS PERFORMING WORK SHOWN ON OR RELATED TO THESE PLANS SHALL CONDUCT THEIR OPERATIONS SO THAT ALL EMPLOYEES ARE PROVIDED A SAFE PLACE TO WORK AND THE PUBLIC IS PROTECTED. ALL CONTRACTORS AND SUBCONTRACTORS SHALL COMPLY WITH THE OCCUPATIONAL SAFETY AND HEALTH REGULATIONS OF THE U.S. DEPARTMENT OF LABOR AND THE STATE OF UTAH DEPARTMENT OF INDUSTRIAL RELATIONS CONSTRUCTION SAFETY ORDERS. THE CIVIL ENGINEER SHALL NOT BE RESPONSIBLE IN ANY WAY FOR THE CONTRACTORS AND SUBCONTRACTORS COMPLIANCE WITH SAID REGULATIONS AND ORDERS.


CONTRACTOR FURTHER AGREES TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB-SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY, THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNER AND THE CIVIL ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

NOTICE TO DEVELOPER/ CONTRACTOR

UNAPPROVED DRAWINGS REPRESENT WORK IN PROGRESS, ARE SUBJECT TO CHANGE, AND DO NOT CONSTITUTE A FINISHED ENGINEERING PRODUCT. ANY WORK UNDERTAKEN BY DEVELOPER OR CONTRACTOR BEFORE PLANS ARE APPROVED IS UNDERTAKEN AT THE SOLE RISK OF THE DEVELOPER, INCLUDING BUT NOT LIMITED TO BIDS, ESTIMATION, FINANCING, BONDING, SITE CLEARING, GRADING, INFRASTRUCTURE CONSTRUCTION, ETC.

UTILITY DISCLAIMER

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND / OR ELEVATIONS OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE LOCAL UTILITY LOCATION CENTER AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.



GENERAL NOTES

1. ALL WORK SHALL CONFORM TO WEBER COUNTY STANDARDS & SPECIFICATIONS.
2. CALL BLUE STAKES AT LEAST 48 HOURS PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION ACTIVITIES.



LAYTON
919 North 400 West
Layton, UT 84041
Phone: 801.547.1100

SANDY
Phone: 801.255.0529

TOOELE
Phone: 435.843.3590

CEDAR CITY
Phone: 435.865.1453

RICHFIELD
Phone: 435.896.2983

WWW.ENSGNENG.COM

FOR:
NILSON HOMES
1740 COMBE ROAD, SUITE 2
SOUTH OGDEN, UTAH 84403

CONTACT:
STEVE ANDERSON
PHONE: 801-392-8100

RIVERBEND FARMS WEST
SUBDIVISION
850 SOUTH 3600 WEST
WEBER COUNTY, UTAH



NO. DATE REVISION FOR REVIEW

COVER SHEET

PROJECT NUMBER 14027
PRINT DATE 2026-05-01
PROJECT MANAGER C.PRESTON
DESIGNED BY M.ELMER

GENERAL NOTES

- ALL CONSTRUCTION MUST STRICTLY FOLLOW THE STANDARDS AND SPECIFICATIONS SET FORTH BY: THE DESIGN ENGINEER, LOCAL AGENCY JURISDICTION, APWA (CURRENT EDITION), AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (M.U.T.C.D.). THE ORDER LISTED ABOVE IS ARRANGED BY SENIORITY. THE LATEST EDITION OF ALL STANDARDS AND SPECIFICATIONS MUST BE ADHERED TO. IF A CONSTRUCTION PRACTICE IS NOT SPECIFIED BY ANY OF THE LISTED SOURCES, CONTRACTOR MUST CONTACT DESIGN ENGINEER FOR DIRECTION.
- CONTRACTOR TO STRICTLY FOLLOW THE MOST CURRENT COPY OF THE SOILS REPORT FOR THIS PROJECT. ALL GRADING INCLUDING BUT NOT LIMITED TO CUT, FILL, COMPACTION, ASPHALT SECTION, SUBBASE, TRENCH EXCAVATION/BACKFILL, SITE GRUBBING, AND FOOTINGS MUST BE COORDINATED DIRECTLY WITH SOILS REPORT.
- CONTRACTOR MUST VERIFY ALL EXISTING CONDITIONS BEFORE BIDDING, AND BRING UP ANY QUESTIONS BEFORE SUBMITTING BID.
- CONTRACTOR SHALL PROVIDE A CONSTRUCTION SCHEDULE IN ACCORDANCE WITH THE CITY, STATE, OR COUNTY REGULATIONS FOR WORKING IN THE PUBLIC WAY.
- CONTRACTOR SHALL BE RESPONSIBLE FOR DUST CONTROL ACCORDING TO GOVERNING AGENCY STANDARDS. WET DOWN DRY MATERIALS AND RUBBISH TO PREVENT BLOWING.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO ADJACENT SURFACE IMPROVEMENTS.
- CONTRACTOR SHALL BE RESPONSIBLE FOR CORRECTING ANY SETTLEMENT OF OR DAMAGE TO EXISTING UTILITIES.
- THE CONTRACTOR IS RESPONSIBLE TO FURNISH ALL MATERIALS TO COMPLETE THE PROJECT.
- ALL EXPOSED SURFACES WILL HAVE A TEXTURED FINISH, RUBBED, OR BROOMED. ANY "PLASTERING" OF NEW CONCRETE WILL BE DONE WHILE IT IS STILL "GREEN".
- PRIOR TO STARTING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OR FABRICATION SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED AND THOROUGHLY REVIEWED ALL PLANS AND OTHER DOCUMENTS APPROVED BY ALL OF THE PERMITTING AUTHORITIES.
- THE LOCATIONS OF UNDERGROUND FACILITIES SHOWN ON THESE PLANS ARE BASED ON FIELD SURVEYS AND LOCAL UTILITY COMPANY RECORDS. IT SHALL BE THE CONTRACTOR'S FULL RESPONSIBILITY TO CONTACT THE VARIOUS UTILITY COMPANIES TO LOCATE THEIR FACILITIES PRIOR TO PROCEEDING WITH CONSTRUCTION. NO ADDITIONAL COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR DAMAGE AND REPAIR TO THESE FACILITIES CAUSED BY HIS WORK FORCE. CONTRACTOR SHALL START INSTALLATION AT LOW POINT OF ALL NEW GRAVITY UTILITY LINES.
- ALL DIMENSIONS, GRADES, AND UTILITY DESIGN SHOWN ON THE PLANS SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. CONTRACTOR SHALL NOTIFY THE ENGINEER IF ANY DISCREPANCIES EXIST. PRIOR TO PROCEEDING WITH CONSTRUCTION FOR NECESSARY PLAN OR GRADE CHANGES, NO EXTRA COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR WORK HAVING TO BE REDONE DUE TO THE DIMENSIONS OR GRADES SHOWN INCORRECTLY ON THESE PLANS, IF SUCH NOTIFICATION HAS NOT BEEN GIVEN.
- NO CHANGE IN DESIGN LOCATION OR GRADE WILL BE MADE BY THE CONTRACTOR WITHOUT THE WRITTEN APPROVAL OF THE PROJECT ENGINEER.
- NATURAL VEGETATION AND SOIL COVER SHALL NOT BE DISTURBED PRIOR TO ACTUAL CONSTRUCTION OF A REQUIRED FACILITY OR IMPROVEMENT. MASS CLEARING OF THE SITE IN ANTICIPATION OF CONSTRUCTION SHALL BE AVOIDED.
- CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING, MAINTAINING, OR RESTORING ALL MONUMENTS AND MONUMENT REFERENCE MARKS WITHIN THE PROJECT SITE. CONTACT THE CITY OR COUNTY SURVEYOR FOR MONUMENT LOCATIONS AND CONSTRUCTION DETAILS.
- EXISTING UTILITY INFORMATION SHOWN IS FOR INFORMATIONAL PURPOSES ONLY. IT IS DERIVED FROM ON-SITE SURVEY AND/OR UTILITY MAPPING PROVIDED TO THE ENGINEER, AND THEREFORE UTILITIES MAY NOT BE LOCATED CORRECTLY, EITHER HORIZONTALLY OR VERTICALLY, AND MAY NOT BE ALL INCLUSIVE. CONTRACTOR IS REQUIRED TO FOLLOW THE PROCEDURE OUTLINED BELOW.
 - CONTRACTOR IS REQUIRED TO LOCATE AND POTHOLE ALL EXISTING UTILITY LINES (BOTH HORIZONTALLY AND VERTICALLY) THAT AFFECT THE PROJECT CONSTRUCTION, EITHER ON-SITE OR OFF-SITE, AND DETERMINE IF THERE ARE ANY CONFLICTS WITH THE DESIGN OF THE SITE AS SHOWN ON THE APPROVED PLANS PRIOR TO ANY CONSTRUCTION. IF IT IS DETERMINED THAT CONFLICTS EXIST BETWEEN EXISTING UTILITIES AND DESIGN UTILITIES (OR ANOTHER ASPECT OF PROPOSED CONSTRUCTION) THE ENGINEER MUST BE NOTIFIED IMMEDIATELY TO CORRECT THE CONFLICTS BEFORE ANY WORK CAN BEGIN. IF THE CONTRACTOR FAILS TO FOLLOW THIS ABSOLUTE REQUIREMENT AND CONFLICTS ARISE DURING CONSTRUCTION THE CONTRACTOR WILL BEAR THE SOLE RESPONSIBILITY TO FIX THE CONFLICTS.
 - CONTRACTOR IS REQUIRED TO VERIFY THAT PROPER COVER AND PROTECTION OF EXISTING UTILITY LINES IS MAINTAINED OR ATTAINED WITHIN THE DESIGN ONCE VERIFICATION OF THE EXISTING UTILITIES IS COMPLETED AS OUTLINED IN 16.1 ABOVE.
 - IN ADDITION TO 16.1 AND 16.2 ABOVE, THE CONTRACTOR WILL VERIFY DEPTHS OF UTILITIES IN THE FIELD BY "POTHOLING" TO A MINIMUM OF 300 FEET AHEAD OF PROPOSED PIPELINE CONSTRUCTION TO AVOID POTENTIAL CONFLICTS WITH DESIGNED PIPELINE ALIGNMENT AND GRADE AND EXISTING UTILITIES.
 - IF A CONFLICT ARISES BETWEEN EXISTING UTILITIES AND DESIGN UTILITIES (OR ANOTHER ASPECT OF PROPOSED CONSTRUCTION) AS DETERMINED UNDER 16.1, 16.2 OR 16.3 THE CONTRACTOR WILL NOTIFY THE ENGINEER IMMEDIATELY TO RESOLVE THE CONFLICT.
 - IF A CONFLICT ARISES BETWEEN EXISTING UTILITIES AND DESIGN UTILITIES (OR ANOTHER ASPECT OF PROPOSED CONSTRUCTION) RESULTING FROM THE CONTRACTOR'S NEGLIGENCE TO IDENTIFY AND/OR "POTHOLE" EXISTING UTILITIES AS REQUIRED IN 16.1, 16.2 AND 16.3 ABOVE, THE CONTRACTOR WILL BE REQUIRED TO RESOLVE THE CONFLICT WITHOUT ADDITIONAL COST OR CLAIM TO THE OWNER OR ENGINEER.
- ANY AREA OUTSIDE THE LIMIT OF WORK THAT IS DISTURBED SHALL BE RESTORED TO ITS ORIGINAL CONDITION AT NO COST TO OWNER.
- CONSULT ALL OF THE DRAWINGS AND SPECIFICATIONS FOR COORDINATION REQUIREMENTS BEFORE COMMENCING CONSTRUCTION.
- AT ALL LOCATIONS WHERE EXISTING PAVEMENT ABUTS NEW CONSTRUCTION, THE EDGE OF THE EXISTING PAVEMENT SHALL BE SAWCUT TO A CLEAN, SMOOTH EDGE.
- ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THE MOST RECENT, ADOPTED EDITION OF ADA ACCESSIBILITY GUIDELINES.
- CONTRACTOR SHALL, AT THE TIME OF BIDDING AND THROUGHOUT THE PERIOD OF THE CONTRACT, BE LICENSED IN THE STATE OF UTAH AND SHALL BE BONDABLE FOR AN AMOUNT REQUIRED BY THE OWNER.
- CONTRACTOR SHALL BE RESPONSIBLE TO PROVIDE ALL WATER, POWER, SANITARY FACILITIES AND TELEPHONE SERVICES AS REQUIRED FOR THE CONTRACTOR'S USE DURING CONSTRUCTION.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ADEQUATELY SCHEDULING INSPECTION AND TESTING OF ALL FACILITIES CONSTRUCTED UNDER THIS CONTRACT. ALL TESTING SHALL CONFORM TO THE REGULATORY AGENCY'S STANDARD SPECIFICATIONS. ALL RE-TESTING AND/OR RE-INSPECTION SHALL BE PAID FOR BY THE CONTRACTOR.
- IF EXISTING IMPROVEMENTS NEED TO BE DISTURBED AND/OR REMOVED FOR THE PROPER PLACEMENT OF IMPROVEMENTS TO BE CONSTRUCTED BY THESE PLANS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING EXISTING IMPROVEMENTS FROM DAMAGE. COST OF REPLACING OR REPAIRING EXISTING IMPROVEMENTS SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEMS REQUIRING REMOVAL AND/OR REPLACEMENT. THERE WILL BE NO EXTRA COST DUE TO THE CONTRACTOR FOR REPLACING OR REPAIRING EXISTING IMPROVEMENTS.
- WHENEVER EXISTING FACILITIES ARE REMOVED, DAMAGED, BROKEN, OR CUT IN THE INSTALLATION OF THE WORK COVERED BY THESE PLANS OR SPECIFICATIONS, SAID FACILITIES SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE WITH MATERIALS EQUAL TO OR BETTER THAN THE MATERIALS USED IN THE ORIGINAL EXISTING FACILITIES. THE FINISHED PRODUCT SHALL BE SUBJECT TO THE APPROVAL OF THE OWNER, THE ENGINEER, AND THE RESPECTIVE REGULATORY AGENCY.
- CONTRACTOR SHALL MAINTAIN A NEATLY MARKED SET OF FULL-SIZE RECORD DRAWINGS SHOWING THE FINAL LOCATION AND LAYOUT OF ALL STRUCTURES AND OTHER FACILITIES. RECORD DRAWINGS SHALL REFLECT CHANGE ORDERS, ACCOMMODATIONS, AND ADJUSTMENTS TO ALL IMPROVEMENTS CONSTRUCTED. WHERE NECESSARY, SUPPLEMENTAL DRAWINGS SHALL BE PREPARED AND SUBMITTED BY THE CONTRACTOR. PRIOR TO ACCEPTANCE OF THE PROJECT, THE CONTRACTOR SHALL DELIVER TO THE ENGINEER ONE SET OF NEATLY MARKED RECORD DRAWINGS SHOWING THE INFORMATION REQUIRED ABOVE. RECORD DRAWINGS SHALL BE REVIEWED AND THE COMPLETE RECORD DRAWING SET SHALL BE CURRENT WITH ALL CHANGES AND DEVIATIONS REDLINED AS A PRECONDITION TO THE FINAL PROGRESS PAYMENT APPROVAL AND/OR FINAL ACCEPTANCE.
- WHERE THE PLANS OR SPECIFICATIONS DESCRIBE PORTIONS OF THE WORK IN GENERAL TERMS BUT NOT IN COMPLETE DETAIL, IT IS UNDERSTOOD THAT ONLY THE BEST GENERAL PRACTICE IS TO PREVAIL AND THAT ONLY MATERIALS AND WORKMANSHIP OF THE FIRST QUALITY ARE TO BE USED.
- ALL EXISTING GATES AND FENCES TO REMAIN UNLESS OTHERWISE NOTED ON PLANS. PROTECT ALL GATES AND FENCES FROM DAMAGE.
- ALL EXISTING TREES ARE TO REMAIN UNLESS OTHERWISE NOTED ON PLANS. PROTECT ALL TREES FROM DAMAGE.
- ASPHALT MIX DESIGN MUST BE SUBMITTED AND APPROVED BY THE GOVERNING AGENCY PRIOR TO THE PLACEMENT.
- CONTRACTORS ARE RESPONSIBLE FOR ALL OSHA REQUIREMENTS ON THE PROJECT SITE.
- A UPDES (UTAH POLLUTANT DISCHARGE ELIMINATION SYSTEM) PERMIT IS REQUIRED FOR ALL CONSTRUCTION ACTIVITIES 1 ACRE OR MORE AS WELL AS A STORM WATER POLLUTION PREVENTION PLAN.

UTILITY NOTES

- ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THESE CONTRACT DOCUMENTS, CITY AND STATE REQUIREMENTS AND THE MOST RECENT EDITIONS OF THE FOLLOWING: THE INTERNATIONAL PLUMBING CODE, UTAH DRINKING WATER REGULATIONS, APWA MANUAL OF STANDARD PLANS AND SPECIFICATIONS. THE CONTRACTOR IS REQUIRED TO ADHERE TO ALL OF THE ABOVE-MENTIONED DOCUMENTS UNLESS OTHERWISE NOTED AND APPROVED BY THE ENGINEER.
- CONTRACTOR SHALL COORDINATE LOCATION OF NEW "DRY UTILITIES" WITH THE APPROPRIATE UTILITY COMPANY, INCLUDING BUT NOT LIMITED TO, TELEPHONE & INTERNET SERVICE, GAS SERVICE, CABLE, AND POWER.
- EXISTING UTILITIES HAVE BEEN SHOWN ON THE PLANS BASED ON ON-SITE SURVEY. PRIOR TO COMMENCING ANY WORK, IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO HAVE EACH UTILITY COMPANY LOCATE IN THE FIELD, THEIR MAIN AND SERVICE LINES. THE CONTRACTOR SHALL NOTIFY BLUE STAKES AT 1-800-662-4111 48 HOURS IN ADVANCE OF PERFORMING ANY EXCAVATION WORK. THE CONTRACTOR SHALL RECORD THE BLUE STAKES ORDER NUMBER AND FURNISH ORDER NUMBER TO OWNER AND ENGINEER PRIOR TO ANY EXCAVATION. IT WILL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO DIRECTLY CONTACT ANY OTHER UTILITY COMPANIES THAT ARE NOT MEMBERS OF BLUE STAKES. IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO PROTECT ALL EXISTING UTILITIES SO THAT NO DAMAGE RESULTS TO THEM DURING THE PERFORMANCE OF THIS CONTRACT. ANY REPAIRS NECESSARY TO DAMAGED UTILITIES SHALL BE PAID FOR BY THE CONTRACTOR. THE CONTRACTOR SHALL BE REQUIRED TO COOPERATE WITH OTHER CONTRACTORS AND UTILITY COMPANIES INSTALLING NEW STRUCTURES, UTILITIES AND SERVICE TO THE PROJECT.
- CARE SHOULD BE TAKEN IN ALL EXCAVATIONS DUE TO POSSIBLE EXISTENCE OF UNRECORDED UTILITY LINES. EXCAVATION REQUIRED WITHIN PROXIMITY OF EXISTING UTILITY LINES SHALL BE DONE BY HAND. CONTRACTOR SHALL REPAIR ANY DAMAGE TO EXISTING UTILITY LINES OR STRUCTURES INCURRED DURING CONSTRUCTION OPERATIONS AT CONTRACTOR'S EXPENSE.
- TRENCH BACKFILL MATERIAL AND COMPACTION TESTS ARE TO BE TAKEN PER APWA STANDARD SPECIFICATIONS (CURRENT EDITION), SECTION 33 05 20 - BACKFILLING TRENCHES, OR AS REQUIRED BY THE GEOTECHNICAL REPORT IF NATIVE MATERIALS ARE USED. NO NATIVE MATERIALS ARE ALLOWED IN THE PIPE ZONE. THE MAXIMUM LIFT FOR BACKFILLING EXCAVATIONS IS DETERMINED BY THE GEOTECHNICAL RECOMMENDATIONS.
- THE CONTRACTOR IS SOLELY RESPONSIBLE FOR CONFORMING TO LOCAL AND FEDERAL CODES GOVERNING SHORING AND BRACING OF EXCAVATIONS AND TRENCHES AND FOR THE PROTECTION OF WORKERS.
- THE CONTRACTOR IS REQUIRED TO KEEP ALL CONSTRUCTION ACTIVITIES WITHIN THE APPROVED PROJECT LIMITS. THIS INCLUDES, BUT IS NOT LIMITED TO VEHICLE AND EQUIPMENT STAGING, MATERIAL STORAGE AND LIMITS OF TRENCH EXCAVATION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN PERMISSION AND/OR EASEMENTS FROM THE APPROPRIATE GOVERNING ENTITY (AND/OR INDIVIDUAL PROPERTY OWNER(S) FOR WORK OR STAGING OUTSIDE OF THE PROJECT LIMITS.
- THE CONTRACTOR IS RESPONSIBLE FOR REPAIRING ANY DAMAGE, CAUSED BY ANY CONDITION INCLUDING SETTLEMENT, TO EXISTING UTILITIES FROM WORK PERFORMED AT OR NEAR EXISTING UTILITIES. THE CONTRACTOR SHALL TAKE ALL MEASURES NECESSARY TO PROTECT ALL EXISTING PUBLIC AND PRIVATE ROADWAY AND UTILITY FACILITIES. DAMAGE TO EXISTING FACILITIES CAUSED BY THE CONTRACTOR MUST BE REPAIRED BY THE CONTRACTOR AT HIS/HER EXPENSE TO THE SATISFACTION OF THE OWNER OF SAID FACILITIES.
- ALL WATER LINE AND SEWER LINE INSTALLATION AND TESTING TO BE IN ACCORDANCE WITH LOCAL GOVERNING AGENCY'S STANDARDS AND SPECIFICATIONS.
- ALL MANHOLES, HYDRANTS, VALVES, CLEANOUT BOXES, CATCH BASINS, METERS, ETC. MUST BE RAISED OR LOWERED TO FINAL GRADE PER APWA (CURRENT EDITION) STANDARDS AND INSPECTOR REQUIREMENTS. CONCRETE COLLARS MUST BE CONSTRUCTED ON ALL MANHOLES, CLEANOUT BOXES, CATCH BASINS, AND VALVES PER APWA STANDARDS. ALL MANHOLE, CATCH BASIN, OR CLEANOUT BOX CONNECTIONS MUST BE MADE WITH THE PIPE CUT FLUSH WITH THE INSIDE OF THE BOX AND GROUTED OR SEALED.
- CONTRACTOR SHALL NOT ALLOW ANY GROUNDWATER OR DEBRIS TO ENTER THE NEW OR EXISTING PIPE DURING CONSTRUCTION.
- SILT AND DEBRIS ARE TO BE CLEANED OUT OF ALL STORM DRAIN BOXES. CATCH BASINS ARE TO BE MAINTAINED IN A CLEANED CONDITION AS NEEDED UNTIL AFTER THE FINAL BOND RELEASE INSPECTION.
- CONTRACTOR SHALL CLEAN ASPHALT, TAR OR OTHER ADHESIVES OFF OF ALL MANHOLE LIDS AND INLET GRATES TO ALLOW ACCESS.
- EACH TRENCH SHALL BE EXCAVATED SO THAT THE PIPE CAN BE LAID TO THE ALIGNMENT AND GRADE AS REQUIRED. THE TRENCH WALL SHALL BE SO BRACED THAT THE WORKMEN MAY WORK SAFELY AND EFFICIENTLY. ALL TRENCHES SHALL BE DRAINED SO THE PIPE LAYING MAY TAKE PLACE IN DEWATERED CONDITIONS.
- CONTRACTOR SHALL PROVIDE AND MAINTAIN AT ALL TIMES AMPLE MEANS AND DEVICES WITH WHICH TO REMOVE PROMPTLY AND TO PROPERLY DISPOSE OF ALL WATER ENTERING THE TRENCH EXCAVATION.
- ALL SEWER LINES AND SEWER SERVICES SHALL HAVE A MINIMUM SEPARATION OF 10 FEET. EDGE TO EDGE, FROM THE WATER LINES. IF A 10 FOOT SEPARATION CAN NOT BE MAINTAINED, CONSTRUCT PER GOVERNING AGENCY'S MINIMUM SEPARATION STANDARDS.
- CONTRACTOR SHALL INSTALL THRUST BLOCKING AT ALL WATERLINE ANGLE POINTS AND TEES.
- ALL UNDERGROUND UTILITIES SHALL BE IN PLACE PRIOR TO INSTALLATION OF CURB, GUTTER, SIDEWALK AND STREET PAVING.
- CONTRACTOR SHALL INSTALL MAGNETIC LOCATING TAPE CONTINUOUSLY OVER ALL NONMETALLIC PIPE.

TRAFFIC CONTROL AND SAFETY NOTES

- TRAFFIC CONTROL AND STRIPING TO CONFORM TO THE CURRENT MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (M.U.T.C.D.).
- BARRICADING AND DETOURING SHALL BE IN CONFORMANCE WITH THE REQUIREMENTS OF THE CURRENT M.U.T.C.D.
- NO STREET SHALL BE CLOSED TO TRAFFIC WITHOUT WRITTEN PERMISSION FROM THE APPROPRIATE AGENCY, EXCEPT WHEN DIRECTED BY LAW ENFORCEMENT OR FIRE OFFICIALS.
- THE CONTRACTOR SHALL MAKE EVERY EFFORT TO PROVIDE FOR SMOOTH TRAFFIC FLOW AND SAFETY. ACCESS SHALL BE MAINTAINED FOR ALL PROPERTIES ADJACENT TO THE WORK.
- DETOURING OPERATIONS FOR A PERIOD OF SIX CONSECUTIVE CALENDAR DAYS, OR MORE, REQUIRE THE INSTALLATION OF TEMPORARY STREET STRIPING AND REMOVAL OF INTERFERING STRIPING BY SANDBLASTING. THE DETOURING STRIPING PLAN OR CONSTRUCTION TRAFFIC CONTROL PLAN MUST BE SUBMITTED TO THE GOVERNING AGENCY FOR REVIEW AND APPROVAL.
- ALL TRAFFIC CONTROL DEVICES SHALL BE RESTORED TO THEIR ORIGINAL CONDITION AT THE END OF THE WORK TO THE SATISFACTION OF THE GOVERNING AGENCY.
- TRAFFIC CONTROL DEVICES (TCDs) SHALL REMAIN VISIBLE AND OPERATIONAL AT ALL TIMES.
- ALL PERMANENT TRAFFIC CONTROL DEVICES CALLED FOR HEREON SHALL BE IN PLACE AND IN FINAL POSITION PRIOR TO ALLOWING ANY PUBLIC TRAFFIC ONTO THE PORTIONS OF THE ROAD(S) BEING IMPROVED HEREUNDER, REGARDLESS OF THE STATUS OF COMPLETION OF PAVING OR OTHER OFF-SITE IMPROVEMENTS CALLED FOR BY THESE PLANS.
- THE CONTRACTOR SHALL PROVIDE BARRICADES, SIGNS, FLASHERS, OTHER EQUIPMENT AND FLAG PERSONS NECESSARY TO INSURE THE SAFETY OF WORKERS AND VISITORS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING UTAH TRANSIT AUTHORITY (UTA) IF THE CONSTRUCTION INTERRUPTS OR RELOCATES A BUS STOP OR HAS AN ADVERSE EFFECT ON BUS SERVICE ON THAT STREET TO ARRANGE FOR TEMPORARY RELOCATION OF STOP.

DEMOLITION NOTES

- EXISTING UTILITY INFORMATION SHOWN IS FOR INFORMATIONAL PURPOSES ONLY. IT IS DERIVED FROM ON-SITE SURVEY AND MAY NOT BE LOCATED CORRECTLY AND IS NOT ALL INCLUSIVE. CONTRACTOR SHALL FIELD LOCATE ALL UTILITIES WITHIN THE PROJECT LIMITS BEFORE BEGINNING DEMOLITION/CONSTRUCTION.
- THERE MAY BE BURIED UTILITIES WITHIN THE LIMITS OF DISTURBANCE THAT ARE NOT SHOWN ON THE PLANS DUE TO LACK OF MAPPING OR RECORD INFORMATION. CONTRACTOR SHALL NOTIFY THE ENGINEER WHEN UNEXPECTED UTILITIES ARE DISCOVERED.
- THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR LOCATING AND PROTECTING FROM DAMAGE ALL EXISTING UTILITIES AND IMPROVEMENTS WHETHER OR NOT SHOWN ON THESE PLANS. THE FACILITIES AND IMPROVEMENTS ARE BELIEVED TO BE CORRECTLY SHOWN BUT THE CONTRACTOR IS REQUIRED TO SATISFY HIMSELF AS TO THE COMPLETENESS AND ACCURACY OF THE LOCATIONS. ANY CONTRACTOR PERFORMING WORK ON THIS PROJECT SHALL FAMILIARIZE HIMSELF WITH THE SITE AND SHALL BE HELD SOLELY RESPONSIBLE FOR ANY DAMAGE TO EXISTING FACILITIES RESULTING DIRECTLY, OR INDIRECTLY, FROM HIS OPERATIONS, WHETHER OR NOT SAID FACILITIES ARE SHOWN ON THESE PLANS.

GRADING AND DRAINAGE NOTES

- SITE GRADING SHALL BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE RECOMMENDATIONS SET FORTH IN THE GEOTECHNICAL REPORT AND ALL RELATED ADDENDUMS.
- THE CONTRACTOR SHALL STRIP AND CLEAR THE TOPSOIL, MAJOR ROOTS AND ORGANIC MATERIAL FROM ALL PROPOSED BUILDING AND PAVEMENT AREAS PRIOR TO SITE GRADING. (THE TOPSOIL MAY BE STOCKPILED FOR LATER USE IN LANDSCAPED AREAS.)
- THE CONTRACTOR SHALL REMOVE ALL ORGANIC MATERIAL AND OTHER DELETERIOUS MATERIALS PRIOR TO PLACING GRADING FILL OR BASE COURSE. THE AREA SHOULD BE PROOF-ROLLED TO IDENTIFY ANY SOFT AREAS. WHERE SOFT AREAS ARE ENCOUNTERED, THE CONTRACTOR SHALL REMOVE THE SOIL AND REPLACE WITH COMPACTED FILL.
- ALL DEBRIS PILES AND BERMS SHOULD BE REMOVED AND HAULED AWAY FROM SITE OR USED AS GENERAL FILL IN LANDSCAPED AREAS.
- THE CONTRACTOR SHALL CONSTRUCT THE BUILDING PAD TO THESE DESIGN PLANS AS PART OF THE SITE GRADING CONTRACT, AND STRICTLY ADHERE TO THE SITE PREPARATION AND GRADING REQUIREMENTS OUTLINED IN THE GEOTECHNICAL REPORT.
- THE CONTRACTOR SHALL GRADE THE PROJECT SITE TO PROVIDE A SMOOTH TRANSITION BETWEEN NEW AND EXISTING ASPHALT, CURB AND GUTTER, AND ADJOINING SITE IMPROVEMENTS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR DAMAGE AND DEBRIS ON ADJACENT STREETS WHEN EQUIPMENT IS TRAVELING THOSE STREETS.
- THE CONTRACTOR SHALL BE FAMILIAR WITH ALL CONDITIONS AND RECOMMENDATIONS OUTLINED IN THE GEOTECHNICAL REPORT AND TAKE ALL NECESSARY PRECAUTIONS AND RECOMMENDED PROCEDURES TO ASSURE SOUND GRADING PRACTICES.
- THE CONTRACTOR SHALL TAKE APPROPRIATE GRADING MEASURES TO DIRECT STORM SURFACE RUNOFF TOWARDS CATCH BASINS.
- THE LOCATIONS OF UNDERGROUND FACILITIES SHOWN ON THESE PLANS ARE BASED ON ON-SITE SURVEY. IT SHALL BE THE CONTRACTOR'S FULL RESPONSIBILITY TO CONTACT THE VARIOUS UTILITY COMPANIES TO LOCATE THEIR FACILITIES PRIOR TO PROCEEDING WITH CONSTRUCTION. NO ADDITIONAL COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR DAMAGE AND REPAIR TO THESE FACILITIES CAUSED BY HIS WORK FORCE.
- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO PERFORM ALL NECESSARY CUTS AND FILLS WITHIN THE LIMITS OF THIS PROJECT AND THE RELATED OFF-SITE WORK, SO AS TO GENERATE THE DESIRED SUBGRADE, FINISH GRADES, AND SLOPES SHOWN.
- THE CONTRACTOR IS WARNED THAT AN EARTHWORK BALANCE WAS NOT NECESSARILY THE INTENT OF THIS PROJECT. ANY ADDITIONAL MATERIAL REQUIRED OR LEFTOVER MATERIAL FOLLOWING EARTHWORK OPERATIONS BECOMES THE RESPONSIBILITY OF THE CONTRACTOR.
- THE GRADING CONTRACTOR IS RESPONSIBLE TO COORDINATE WITH THE OWNER TO PROVIDE FOR THE REQUIREMENTS OF THE PROJECT STORM WATER POLLUTION PREVENTION PLAN (SWPPP) AND ASSOCIATED PERMIT. ALL CONTRACTOR ACTIVITIES 1 ACRE OR MORE IN SIZE ARE REQUIRED TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN.
- ALL CUT AND FILL SLOPES SHALL BE PROTECTED UNTIL EFFECTIVE EROSION CONTROL HAS BEEN ESTABLISHED.
- THE USE OF POTABLE WATER WITHOUT A SPECIAL PERMIT FOR BUILDING OR CONSTRUCTION PURPOSES INCLUDING CONSOLIDATION OF BACKFILL OR DUST CONTROL IS PROHIBITED. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS FOR CONSTRUCTION WATER FROM GOVERNING AGENCY.
- THE CONTRACTOR SHALL MAINTAIN THE STREETS, SIDEWALKS, AND ALL OTHER PUBLIC RIGHT-OF-WAYS IN A CLEAN, SAFE, AND USABLE CONDITION. ALL SPILLS OF SOIL, ROCK OR CONSTRUCTION DEBRIS SHALL BE PROMPTLY REMOVED FROM THE PUBLICLY-OWNED PROPERTY DURING CONSTRUCTION AND UPON COMPLETION OF THE PROJECT. ALL ADJACENT PROPERTY, PRIVATE OR PUBLIC, SHALL BE MAINTAINED IN A CLEAN, SAFE, AND USABLE CONDITION.

ABBREVIATIONS

APWA	AMERICAN PUBLIC WORKS ASSOCIATION
AR	ACCESSIBLE ROUTE
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS
AWWA	AMERICAN WATER WORKS ASSOCIATION
BOS	BOTTOM OF STEP
BVC	BEGIN VERTICAL CURVE
CB	CATCH BASIN
CF	CURB FACE OR CUBIC FEET
CL	CENTER LINE
CO	CLEAN OUT
COMM	COMMUNICATION
CONC	CONCRETE
CONT	CONTINUOUS
DIA	DIAMETER
DIP	DUCTILE IRON PIPE
ELEC	ELECTRICAL
ELEV	ELEVATION
EOA	EDGE OF ASPHALT
EVC	END OF VERTICAL CURVE
EW	EACH WAY
EXIST	EXISTING
FF	FINISH FLOOR
FG	FINISH GRADE
FH	FIRE HYDRANT
FL	FLOW LINE OR FLANGE
GB	GRADE BREAK
GF	GARAGE FLOOR
GV	GATE VALVE
HC	HANDICAP
HP	HIGH POINT
IRR	IRRIGATION
K	RATE OF VERTICAL CURVATURE
LD	LAND DRAIN
LF	LINEAR FEET
LP	LOW POINT
MEX	MATCH EXISTING
MH	MANHOLE
MJ	MECHANICAL JOINT
NG	NATURAL GROUND
NIC	NOT IN CONTRACT
NO	NUMBER
OC	ON CENTER
OCW	ON CENTER EACH WAY
OHP	OVERHEAD POWER
PC	POINT OF CURVATURE OR PRESSURE CLASS
PCC	POINT OF COMPOUND CURVATURE
PI	POINT OF INTERSECTION
PV	POST INDICATOR VALVE
PL	PROPERTY LINE
PRC	POINT OF REVERSE CURVATURE
PRO	PROPOSED
PT	POINT OF TANGENCY
PVC	POINT OF VERTICAL CURVATURE
PVI	POINT OF VERTICAL INTERSECTION
PVT	POINT OF VERTICAL TANGENCY
R	RADIUS
RD	ROOF DRAIN
ROW	RIGHT OF WAY
S	SLOPE
SAN SWR	SANITARY SEWER
SD	STORM DRAIN
SEC	SECONDARY
SS	SANITARY SEWER
STA	STATION
SW	SECONDARY WATER LINE
TBC	TOP BACK OF CURB
TOG	TOP OF GRATE
TOA	TOP OF ASPHALT
TOC	TOP OF CONCRETE
TOF	TOP OF FOUNDATION
TOW	TOP OF WALL
TOS	TOP OF STEP
TYP	TYPICAL
VC	VERTICAL CURVE
VW	WALL INDICATOR VALVE
W	WATER LINE

NOTE: MAY CONTAIN ABBREVIATIONS THAT ARE NOT USED IN THIS PLAN SET.

LEGEND

	SECTION CORNER		EXISTING EDGE OF ASPHALT
	EXISTING MONUMENT		PROPOSED EDGE OF ASPHALT
	PROPOSED MONUMENT		EXISTING STRIPING
	EXISTING REBAR AND CAP		PROPOSED STRIPING
	SET ENSIGN REBAR AND CAP		EXISTING FENCE
	EXISTING WATER METER		PROPOSED FENCE
	PROPOSED WATER METER		EXISTING FLOW LINE
	EXISTING WATER MANHOLE		PROPOSED FLOW LINE
	PROPOSED WATER MANHOLE		GRADE BREAK
	EXISTING WATER BOX		EXISTING STORM DRAIN LINE
	EXISTING WATER VALVE		PROPOSED STORM DRAIN LINE
	PROPOSED WATER VALVE		ROOF DRAIN LINE
	EXISTING FIRE HYDRANT		CATCHMENTS
	PROPOSED FIRE HYDRANT		HIGHWATER LINE
	PROPOSED FIRE DEPARTMENT CONNECTION		EXISTING SANITARY SEWER
	EXISTING SECONDARY WATER VALVE		PROPOSED SANITARY SEWER LINE
	PROPOSED SECONDARY WATER VALVE		PROPOSED SAN. SWR. SERVICE LINE
	EXISTING IRRIGATION BOX		EXISTING LAND DRAIN LINE
	EXISTING IRRIGATION VALVE		PROPOSED LAND DRAIN LINE
	PROPOSED IRRIGATION VALVE		PROPOSED LAND DRAIN SERVICE LINE
	EXISTING SANITARY SEWER MANHOLE		EXISTING CULINARY WATER LINE
	PROPOSED SANITARY SEWER MANHOLE		PROPOSED CULINARY WATER LINE
	EXISTING SANITARY CLEAN OUT		PROPOSED CULINARY WATER SERVICE LINE
	EXISTING STORM DRAIN CLEAN OUT BOX		EXISTING SECONDARY WATER LINE
	PROPOSED STORM DRAIN CLEAN OUT BOX		PROPOSED SEC. WATER SERVICE LINE
	EXISTING STORM DRAIN INLET BOX		EXISTING IRRIGATION LINE
	EXISTING STORM DRAIN CATCH BASIN		PROPOSED IRRIGATION LINE
	PROPOSED STORM DRAIN CATCH BASIN		EXISTING OVERHEAD POWER LINE
	EXISTING STORM DRAIN COMBO BOX		EXISTING ELECTRICAL LINE
	PROPOSED STORM DRAIN COMBO BOX		EXISTING GAS LINE
	EXISTING STORM DRAIN CLEAN OUT		EXISTING TELEPHONE LINE
	EXISTING STORM DRAIN CULVERT		ACCESSIBLE ROUTE
	PROPOSED STORM DRAIN CULVERT		SAW CUT LINE
	TEMPORARY SAG INLET PROTECTION		STRAW WATTLE
	TEMPORARY IN-LINE INLET PROTECTION		TEMPORARY BERM
	ROOF DRAIN		TEMPORARY SILT FENCE
	EXISTING ELECTRICAL MANHOLE		LIMITS OF DISTURBANCE
	EXISTING ELECTRICAL BOX		EXISTING WALL
	EXISTING TRANSFORMER		PROPOSED WALL
	EXISTING UTILITY POLE		EXISTING CONTOURS
	EXISTING LIGHT		PROPOSED CONTOURS
	EXISTING GAS METER		BUILDABLE AREA WITHIN SETBACKS
	EXISTING GAS MANHOLE		PUBLIC DRAINAGE EASEMENT
	EXISTING GAS VALVE		EXISTING ASPHALT TO BE REMOVED
	EXISTING TELEPHONE MANHOLE		EXISTING ASPHALT
	EXISTING TELEPHONE BOX		EXISTING CURB AND GUTTER
	EXISTING TRAFFIC SIGNAL BOX		PROPOSED CURB AND GUTTER
	EXISTING CABLE BOX		PROPOSED REVERSE PAN CURB AND GUTTER
	EXISTING BOLLARD		TRANSITION TO REVERSE PAN CURB
	PROPOSED BOLLARD		CONCRETE TO BE REMOVED
	EXISTING SIGN		EXISTING CONCRETE
	PROPOSED SIGN		PROPOSED CONCRETE
	EXISTING SPOT ELEVATION		BUILDING TO BE REMOVED
	PROPOSED SPOT ELEVATION		EXISTING BUILDING
	EXISTING FLOW DIRECTION		PROPOSED BUILDING
	EXISTING TREE		
	DENSE VEGETATION		

NOTE: MAY CONTAIN SYMBOLS THAT ARE NOT USED IN THIS PLAN SET.



LAYTON
919 North 400 West
Layton, UT 84041
Phone: 801.547.1100

SANDY
Phone: 801.255.0529

TOEELE
Phone: 435.843.3590

CEDAR CITY
Phone: 435.865.1453


RICHFIELD
Phone: 435.896.2983

WWW.ENSIGNENG.COM

FOR:
NILSON HOMES
1740 COMBE ROAD, SUITE 2
SOUTH OGDEN, UTAH 84403

CONTACT:
STEVE ANDERSON
PHONE: 801-392-8100

**RIVERBEND FARMS WEST
SUBDIVISION**
850 SOUTH 3600 WEST
WEBER COUNTY, UTAH



- GENERAL NOTES**
1. ALL WORK TO COMPLY WITH THE GOVERNING AGENCY'S STANDARDS AND SPECIFICATIONS.
 2. ALL IMPROVEMENTS MUST COMPLY WITH ADA STANDARDS AND RECOMMENDATIONS.
 3. ALL PAVEMENT MARKINGS SHALL CONFORM TO THE LATEST EDITION OF THE M.U.T.C.D. (MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES).
 4. ALL SURFACE IMPROVEMENTS DISTURBED BY CONSTRUCTION SHALL BE RESTORED OR REPLACED, INCLUDING TREES AND DECORATIVE SHRUBS, SOIL, FENCES, WALLS AND STRUCTURES, WHETHER OR NOT THEY ARE SPECIFICALLY SHOWN ON THE CONTRACT DOCUMENTS.
 5. NOTIFY ENGINEER OF ANY DISCREPANCIES IN DESIGN OR STAKING BEFORE PLACING CONCRETE OR ASPHALT.
 6. THE CONTRACTOR IS TO PROTECT AND PRESERVE ALL EXISTING IMPROVEMENTS, UTILITIES, AND SIGNS, ETC. UNLESS OTHERWISE NOTED ON THESE PLANS.

ENSIGN
THE STANDARD IN ENGINEERING

LAYTON
919 North 400 West
Layton, UT 84041
Phone: 801.547.1100

SANDY
Phone: 801.255.0529

TOOELE
Phone: 435.843.3590

CEDAR CITY
Phone: 435.865.1453

RICHFIELD
Phone: 435.896.2983

WWW.ENSIGNENG.COM

FOR:
NILSON HOMES
1740 COMBE ROAD, SUITE 2
SOUTH OGDEN, UTAH 84403


CONTACT:
STEVE ANDERSON
PHONE: 801-392-8100

**RIVERBEND FARMS WEST
SUBDIVISION**
850 SOUTH 3600 WEST
WEBER COUNTY, UTAH



NO. DATE REVISION FOR REVIEW

LAND USE TABLE		
LOT AREA	140,111 sq. ft.	46.3%
ROADWAY DEDICATION	31,043 sq. ft.	10.2%
OPEN SPACE	131,860 sq. ft.	43.5%
TOTAL PROJECT AREA	303,014 sq. ft.	100%
ACREAGE	6.956 acres	
TOTAL LOTS	10	
DENSITY	1.43 UNITS/ACRE	
AVERAGE LOT AREA	14,011 sq. ft.	





**PRELIMINARY OVERALL
SITE PLAN**

PROJECT NUMBER: 14027
PROJECT MANAGER: C. PRESTON

PRINT DATE: 2026-05-01
DESIGNED BY: M. ELMER

C-100



- GENERAL NOTES**
- PROPERTY IS ZONED A-1 CLUSTER SUBDIVISION.
 - FRONT YARD SETBACK IS 20'
 - REAR YARD SETBACK IS 20'
 - SIDE YARD SETBACK IS 8'
 - CORNER LOT SIDE YARD SETBACK IS 20' ARTERIAL STREET MINIMUM SIDE YARD AND (STREET) 20'.
 - 9,000 SQUARE FOOT MINIMUM LOT AREA
 - 60-FOOT MINIMUM LOT WIDTH
 - ALL WORK TO COMPLY WITH THE GOVERNING AGENCY'S STANDARDS AND SPECIFICATIONS.
 - ALL IMPROVEMENTS MUST COMPLY WITH ADA STANDARDS AND RECOMMENDATIONS.
 - ALL PAVEMENT MARKINGS SHALL CONFORM TO THE LATEST EDITION OF THE M.U.T.C.D. (MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES).
 - ALL SURFACE IMPROVEMENTS DISTURBED BY CONSTRUCTION SHALL BE RESTORED OR REPLACED, INCLUDING TREES AND DECORATIVE SHRUBS, SOD, FENCES, WALLS AND STRUCTURES, WHETHER OR NOT THEY ARE SPECIFICALLY SHOWN ON THE CONTRACT DOCUMENTS.
 - NOTIFY ENGINEER OF ANY DISCREPANCIES IN DESIGN OR STAKING BEFORE PLACING CONCRETE OR ASPHALT.
 - THE CONTRACTOR IS TO PROTECT AND PRESERVE ALL EXISTING IMPROVEMENTS, UTILITIES, AND SIGNS, ETC. UNLESS OTHERWISE NOTED ON THESE PLANS.

- SCOPE OF WORK:**
 PROVIDE, INSTALL AND/OR CONSTRUCT THE FOLLOWING PER THE SPECIFICATIONS GIVEN OR REFERENCED, THE DETAILS NOTED, AND/OR AS SHOWN ON THE CONSTRUCTION DRAWINGS:
- INSTALL FIRE HYDRANT AND VALVE PER TAYLOR-WEST WEBER WATER IMPROVEMENTS DISTRICT STANDARDS AND SPECIFICATIONS
 - INSTALL HANDICAP ACCESSIBLE RAMP PER APWA PLAN 235.2
 - INSTALL 30" TYPE 'A' CURB AND GUTTER
 - INSTALL CONCRETE SIDEWALK PER APWA PLAN 231. WIDTH PER PLAN
 - INSTALL STREET LIGHT PER WEBER COUNTY STANDARDS AND SPECIFICATIONS. COORDINATE ALL PROPOSED STREET LIGHT LOCATIONS WITH WEBER COUNTY AND THE STREET LIGHT INSTALLATION WITH ROCKY MOUNTAIN POWER
 - EXIST FIRE HYDRANT TO BE RELOCATED
 - EXIST UTILITY POLE TO REMAIN
 - EXIST UTILITY POLE TO BE REMOVED
 - EXIST OVERHEAD POWER TO BE BURIED
 - RELOCATE EXIST OVERHEAD POWER
 - INSTALL UTILITY POLE

ENSIGN
 THE STANDARD IN ENGINEERING

LAYTON
 919 North 400 West
 Layton, UT 84041
 Phone: 801.547.1100

SANDY
 Phone: 801.255.0529

TOOLEE
 Phone: 435.843.3590

CEDAR CITY
 Phone: 435.865.1453

RICHFIELD
 Phone: 435.896.2983

WWW.ENSIGNENG.COM

FOR:
 NILSON HOMES
 1740 COMBE ROAD, SUITE 2
 SOUTH OGDEN, UTAH 84403

CONTACT:
 STEVE ANDERSON
 PHONE: 801-392-8100

**RIVERBEND FARMS WEST
 SUBDIVISION
 850 SOUTH 3600 WEST
 WEBER COUNTY, UTAH**




NO. DATE REVISION FOR REVIEW

**PRELIMINARY
 SITE PLAN**


PROJECT NUMBER: 14027
 PRINT DATE: 2026-05-01
 PROJECT MANAGER: C. PRESTON
 DESIGNED BY: M. ELMER

C-101



811
Know what's below.
Call before you dig.

CALL BLUESTAKES @ 811
AT LEAST 48 HOURS PRIOR
TO THE COMMENCEMENT
OF ANY CONSTRUCTION



Catchment Calculations (10-year storm)

Time of Concentration: 15 min
Rainfall Intensity I: 2.04 in/hr
Mannings N: 0.013

Catchment	Area (SF)	C	Flow (CFS)	Destination
1	64,634	0.350	1,068	OFF
2	16,170	0.700	0.535	SD3
3	13,370	0.700	0.442	SD2
4	13,394	0.700	0.443	SD1
5	30,414	0.700	1,005	SD4
6	52,635	0.350	0.870	OFF

Pipe Design (10-year storm)

Mannings N (ADS): 0.011
Mannings N (RCP): 0.013

Pipe	Tributary	Surface	Upstream	Pipe Flow	Total	Pipe	Diameter	Pipe Type	Full Flow	% of Full
SD1	4	0.443		0.443	0.443	0.30%	15 RCP	3.548	12.5%	
SD2	3	0.442	SD1	0.885	0.885	0.30%	15 RCP	3.548	24.9%	
SD3	2	0.535		0.535	0.535	0.25%	15 RCP	3.239	16.5%	
SD4	5	1.005		1.005	1.005	0.30%	15 RCP	3.548	28.3%	
SD5			SD2,3,4	2.425	2.425	0.30%	15 RCP	3.548	68.3%	

- GENERAL NOTES**
- ALL WORK TO COMPLY WITH THE GOVERNING AGENCY'S STANDARDS AND SPECIFICATIONS.
 - ALL IMPROVEMENTS MUST COMPLY WITH ADA STANDARDS AND RECOMMENDATIONS.
 - ALL WORK SHALL COMPLY WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL ENGINEER POSSIBLY INCLUDING, BUT NOT LIMITED TO, REMOVAL OF UNCONSOLIDATED FILL, ORGANICS, AND DEBRIS. PLACEMENT OF SUBSURFACE DRAIN LINES AND GEOTEXTILE, AND OVEREXCAVATION OF UNSUITABLE BEARING MATERIALS AND PLACEMENT OF ACCEPTABLE FILL MATERIAL.
 - THE CONTRACTOR SHALL BECOME FAMILIAR WITH THE EXISTING SOIL CONDITIONS.
 - LANDSCAPED AREAS REQUIRE SUBGRADE TO BE MAINTAINED AT A SPECIFIC ELEVATION BELOW FINISHED GRADE AND REQUIRE SUBGRADE TO BE PROPERLY PREPARED AND SCARIFIED. SEE LANDSCAPE PLANS FOR ADDITIONAL INFORMATION.
 - SLOPE ALL LANDSCAPED AREAS AWAY FROM BUILDING FOUNDATIONS TOWARD CURB AND GUTTER OR STORM DRAIN INLETS.
 - EXISTING UNDERGROUND UTILITIES AND IMPROVEMENTS ARE SHOWN IN THEIR APPROXIMATE LOCATIONS BASED UPON RECORD INFORMATION AVAILABLE AT THE TIME OF PREPARATION OF THESE PLANS. LOCATIONS MAY NOT HAVE BEEN VERIFIED IN THE FIELD AND NO GUARANTEE IS MADE AS TO THE ACCURACY OR COMPLETENESS OF THE INFORMATION SHOWN. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE EXISTENCE AND LOCATION OF THE UTILITIES SHOWN ON THESE PLANS OR INDICATED IN THE FIELD BY LOCATING SERVICES. ANY ADDITIONAL COSTS INCURRED AS A RESULT OF THE CONTRACTOR'S FAILURE TO VERIFY THE LOCATIONS OF EXISTING UTILITIES PRIOR TO THE BEGINNING OF CONSTRUCTION IN THEIR VICINITY SHALL BE BORNE BY THE CONTRACTOR AND ASSUMED INCLUDED IN THE CONTRACT. THE CONTRACTOR IS TO VERIFY ALL CONNECTION POINTS WITH THE EXISTING UTILITIES. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE CAUSED TO THE EXISTING UTILITIES AND UTILITY STRUCTURES THAT ARE TO REMAIN. IF CONFLICTS WITH EXISTING UTILITIES OCCUR, THE CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO CONSTRUCTION TO DETERMINE IF ANY FIELD ADJUSTMENTS SHOULD BE MADE.
 - ALL STORM DRAIN INFRASTRUCTURE TO BE INSTALLED PER GOVERNING AGENCY OR APWA STANDARD PLANS AND SPECIFICATIONS.
 - ENSURE MINIMUM COVER OVER ALL STORM DRAIN PIPES PER MANUFACTURER'S RECOMMENDATIONS. NOTIFY ENGINEER IF MINIMUM COVER CANNOT BE ATTAINED.
 - THE CONTRACTOR SHALL ADJUST TO GRADE ALL EXISTING UTILITIES AS NEEDED PER LOCAL GOVERNING AGENCY'S STANDARDS AND SPECIFICATIONS.
 - NOTIFY ENGINEER OF ANY DISCREPANCIES IN DESIGN OR STAKING BEFORE PLACING CONCRETE, ASPHALT, OR STORM DRAIN STRUCTURES OR PIPES.
 - THE CONTRACTOR IS TO PROTECT AND PRESERVE ALL EXISTING IMPROVEMENTS, UTILITIES, AND SIGNS, ETC. UNLESS OTHERWISE NOTED ON THESE PLANS.

ENSIGN
THE STANDARD IN ENGINEERING

LAYTON
919 North 400 West
Layton, UT 84041
Phone: 801.547.1100

SANDY
Phone: 801.255.0529

TOOELE
Phone: 435.843.3590

CEDAR CITY
Phone: 435.865.1453

RICHFIELD
Phone: 435.896.2983

WWW.ENSIGNENG.COM

FOR:
NILSON HOMES
1740 COMBE ROAD, SUITE 2
SOUTH OGDEN, UTAH 84403

CONTACT:
STEVE ANDERSON
PHONE: 801-392-9100

**RIVERBEND FARMS WEST
SUBDIVISION**
850 SOUTH 3600 WEST
WEBER COUNTY, UTAH




NO. DATE REVISION FOR REVIEW

**PRELIMINARY
GRADING AND
DRAINAGE PLAN**


PROJECT NUMBER: 14027
PROJECT MANAGER: C. PRESTON
PRINT DATE: 2026-05-01
DESIGNED BY: M. ELMER

C-200



811
Know what's below.
Call before you dig.

CALL BLUESTAKES @ 811
AT LEAST 48 HOURS PRIOR
TO THE COMMENCEMENT
OF ANY CONSTRUCTION



- GENERAL NOTES**
1. ALL WORK TO COMPLY WITH THE GOVERNING AGENCY'S STANDARDS AND SPECIFICATIONS.
 2. EXISTING UNDERGROUND UTILITIES AND IMPROVEMENTS ARE SHOWN IN THEIR APPROXIMATE LOCATIONS BASED UPON RECORD INFORMATION AVAILABLE AT THE TIME OF PREPARATION OF THESE PLANS. LOCATIONS MAY NOT HAVE BEEN VERIFIED IN THE FIELD AND NO GUARANTEE IS MADE AS TO THE ACCURACY OR COMPLETENESS OF THE INFORMATION SHOWN. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE EXISTENCE AND LOCATION OF THE UTILITIES SHOWN ON THESE PLANS OR INDICATED IN THE FIELD BY LOCATING SERVICES. ANY ADDITIONAL COSTS INCURRED AS A RESULT OF THE CONTRACTOR'S FAILURE TO VERIFY THE LOCATIONS OF EXISTING UTILITIES PRIOR TO THE BEGINNING OF CONSTRUCTION IN THEIR VICINITY SHALL BE BORNE BY THE CONTRACTOR AND ASSUMED INCLUDED IN THE CONTRACT. THE CONTRACTOR IS TO VERIFY ALL CONNECTION POINTS WITH THE EXISTING UTILITIES. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE CAUSED TO THE EXISTING UTILITIES AND UTILITY STRUCTURES THAT ARE TO REMAIN. IF CONFLICTS WITH EXISTING UTILITIES OCCUR, THE CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO CONSTRUCTION TO DETERMINE IF ANY FIELD ADJUSTMENTS SHOULD BE MADE.
 3. ALL SANITARY SEWER INFRASTRUCTURE TO BE INSTALLED PER CENTRAL WEBER SEWER DISTRICT STANDARD PLANS AND SPECIFICATIONS.
 4. ALL CULINARY WATER FACILITIES SHALL MEET THE REQUIREMENTS OF THE TAYLOR-WEST WEBER WATER IMPROVEMENT DISTRICT. STANDARD DETAILS AND CONSTRUCTIONS SPECIFICATIONS ARE AVAILABLE UPON REQUEST TO TAYLORWESTWEBERWATER@MSM.COM OR 801-731-1668. THE DISTRICT SHALL BE NOTIFIED AT LEAST 24 HOURS PRIOR TO ANY PRECONSTRUCTION MEETING OR CONSTRUCTION ACTIVITY.
 5. ALL CONSTRUCTION OF THE SECONDARY WATER SYSTEM WILL CONFORM TO HOOPER IRRIGATION COMPANY STANDARDS AND SPECIFICATIONS.
 6. DEFLECT OR LOOP ALL WATERLINES TO AVOID CONFLICTS WITH OTHER UTILITIES PER GOVERNING AGENCY'S STANDARDS AND SPECIFICATIONS.
 7. PROJECT SHALL COMPLY WITH ALL UTAH DIVISION OF DRINKING WATER RULES AND REGULATIONS INCLUDING, BUT NOT LIMITED TO, THOSE PERTAINING TO BACKFLOW PROTECTION AND CROSS CONNECTION PREVENTION.
 8. THE CONTRACTOR IS TO COORDINATE ALL UTILITIES WITH MECHANICAL/PLUMBING PLANS.
 9. NOTIFY ENGINEER OF ANY DISCREPANCIES IN DESIGN OR STAKING BEFORE PLACING UTILITY STRUCTURES OR PIPES.
 10. THE CONTRACTOR SHALL ADJUST TO GRADE ALL EXISTING UTILITIES AS NEEDED PER LOCAL GOVERNING AGENCY'S STANDARDS AND SPECIFICATIONS.
 11. THE CONTRACTOR IS TO PROTECT AND PRESERVE ALL EXISTING IMPROVEMENTS, UTILITIES, AND SIGNS, ETC. UNLESS OTHERWISE NOTED ON THESE PLANS.

- SCOPE OF WORK:**
PROVIDE, INSTALL AND/OR CONSTRUCT THE FOLLOWING PER THE SPECIFICATIONS GIVEN OR REFERENCED, THE DETAILS NOTED, AND/OR AS SHOWN ON THE CONSTRUCTION DRAWINGS:
1. INSTALL 1" POLY PIPE (200 PSI CTS POLY PIPE AWWA STANDARD C901) TO BE CENTERED ON THE FRONTAGE AND EXTENDED 10' BEYOND THE RIGHT-OF-WAY LINE. PER TAYLOR-WEST WEBER WATER IMPROVEMENT DISTRICT STANDARDS AND SPECIFICATIONS
 2. INSTALL 4" SANITARY SEWER SERVICE LATERAL @ 2.00% MINIMUM SLOPE PER CENTRAL WEBER SEWER DISTRICT STANDARDS AND SPECIFICATIONS
 3. INSTALL 1-1/2" PVC DUAL TURNOUT SECONDARY WATER SERVICE LINE PER HOOPER IRRIGATION COMPANY STANDARDS AND SPECIFICATIONS
 4. INSTALL 2" SECONDARY WATER BLOWOFF PER HOOPER IRRIGATION COMPANY STANDARDS AND SPECIFICATIONS
 5. INSTALL 8" C900 DR18 PVC CULINARY WATERLINE PER TAYLOR-WEST WEBER WATER IMPROVEMENT DISTRICT STANDARDS AND SPECIFICATIONS
 6. INSTALL 8" C900 DR18 PVC "PURPLE" SECONDARY WATERLINE PER HOOPER IRRIGATION COMPANY STANDARDS AND SPECIFICATIONS
 7. FIELD LOCATE AND CONNECT TO EXISTING CULINARY WATERLINE PER TAYLOR-WEST WEBER WATER IMPROVEMENT DISTRICT STANDARDS AND SPECIFICATIONS
 8. FIELD LOCATE AND CONNECT TO EXISTING SECONDARY WATERLINE PER HOOPER IRRIGATION COMPANY STANDARDS AND SPECIFICATIONS
 9. INSTALL FIRE HYDRANT AND VALVE PER TAYLOR-WEST WEBER WATER IMPROVEMENT DISTRICT STANDARDS AND SPECIFICATIONS
 10. INSTALL STREET LIGHT PER WEBER COUNTY STANDARDS AND SPECIFICATIONS. COORDINATE ALL PROPOSED STREET LIGHT LOCATIONS WITH WEBER COUNTY AND THE STREET LIGHT INSTALLATION WITH ROCKY MOUNTAIN POWER.
 11. INSTALL 8" CULINARY WATER VALVE PER TAYLOR-WEST WEBER WATER IMPROVEMENT DISTRICT STANDARDS AND SPECIFICATIONS
 12. INSTALL 8" SECONDARY WATER VALVE PER HOOPER IRRIGATION COMPANY STANDARDS AND SPECIFICATIONS
 13. EXISTING FIRE HYDRANT TO BE RELOCATED
 14. EXISTING CULINARY WATERLINE. FIELD VERIFY SIZE & LOCATION
 15. EXISTING SECONDARY WATERLINE. FIELD VERIFY SIZE & LOCATION
 16. EXISTING WATER VALVE
 17. INSTALL 12" C900 DR18 "PURPLE" SECONDARY WATERLINE PER HOOPER IRRIGATION COMPANY STANDARDS AND SPECIFICATIONS

ENSIGN
THE STANDARD IN ENGINEERING

LAYTON
919 North 400 West
Layton, UT 84041
Phone: 801.547.1100

SANDY
Phone: 801.255.0529

TOOELE
Phone: 435.843.3590

CEDAR CITY
Phone: 435.865.1453

RICHFIELD
Phone: 435.896.2983

WWW.ENSIGNENG.COM

FOR:
NILSON HOMES
1740 COMBE ROAD, SUITE 2
SOUTH OGDEN, UTAH 84003

CONTACT:
STEVE ANDERSON
PHONE: 801-392-8100

**RIVERBEND FARMS WEST
SUBDIVISION**
850 SOUTH 3600 WEST
WEBER COUNTY, UTAH




NO. DATE REVISION FOR REVIEW

**PRELIMINARY
UTILITY PLAN**

PROJECT NUMBER 14027 PRINT DATE 2026-05-01
PROJECT MANAGER C.PRESTON DESIGNED BY M.ELMER

C-300





Central Weber Sewer Improvement District

November 5, 2025

Steve Burton
Weber County Planning Commission
2380 Washington Blvd #240, Ogden, UT 84401

SUBJECT: Riverbend Subdivision
Sanitary Sewer Service
Will Serve Letter

Steve:

We have reviewed the request of Joseph Herring, we have reviewed a subdivision plan for Riverbend Subdivision with 10 additional proposed residences located at approximate address. 900 S 3600 W West Weber. We offer the following comments regarding Central Weber Sewer Improvement District ('the District') providing sanitary sewer service.

1. At this time, the district has the capacity to treat the sanitary sewer flow from this subdivision. Inasmuch as the system demand continuously changes with growth, this assessment is valid for three (3) years from the date issued on this letter.
2. If any connection is made directly into the district's facilities the connection must be constructed in accordance with District standards and must be inspected by the District while the work is being done. A minimum of 48-hour notice for inspection shall be given to the district prior to any work associated with the connection.
3. Central Weber Sewer Improvement District is a wholesale wastewater treatment provider to Weber County. Connection to the sewer system must be through a retail provider, which we understand to be Weber County. The district will not take responsibility for the condition, ownership or maintenance of the proposed sanitary sewer lines (gravity or pressure) or system that will be installed to serve this subdivision.
4. The connection of any sump pumps (or similar type pumps) to the sanitary sewer system is prohibited during or after construction. The District's Wastewater Control Rules and Regulations state:



Central Weber Sewer Improvement District

Prohibited Discharge into Sanitary Sewer. No person shall discharge or cause or make a connection which would allow to be discharged any storm water, surface water, groundwater, roof water runoff or subsurface drainage to any sanitary sewer.

5. The entire parcel of property to be served must be annexed into the Central Weber Sewer Improvement District prior to any sewer service connection or connection to the district's facilities. This annexation must be complete before the sale of any lots in the subdivision. Annexation into the District is permitted by the District's Board of Trustees. This will serve letter is a statement of available capacity and does not guarantee board approval of annexation.
6. Impact fees must be paid no later than the issuance of any building permits.

If you have any further questions or need additional information, please let us know.

Sincerely,

Clay Marriott

Project Manager

CC: Chad Meyerhoffer, Weber County
Kevin Hall, Central Weber Sewer



November 24, 2025

Weber County Planning Commission
2380 Washington Blvd, Suite 240
Ogden, Utah 84401

RE: PRELIMINARY WILL SERVE LETTER – Riverbend Farms Amended Subdivision, West Lots

The Riverbend Farms Amended Subdivision, West Lots is located at approximately 850 South and 3600 West, and a total of 10 lots are proposed. The subdivision is in the boundaries of the Hooper Irrigation Company service area. A formal application has been made to our office and an escrow for application has been paid.

The subdivision plat plan has been reviewed by Hooper Irrigation. The preliminary plans have been conditionally approved for the above subdivision phase. There are sufficient shares affiliated with the property to connect to the secondary pressurized system for the building lots, and the shares are in good standing.

This subdivision only is in consideration and guaranteed service, and the plan review is good only for a period of one year from the date of this letter, if not constructed. A final will serve letter will follow this letter after all plans have received final approval, fees have been paid, and water shares have been surrendered to Hooper Irrigation.


Hooper Irrigation's specifications are available at the Company office.

If you have questions, please call 801-985-8429.

Sincerely,

A handwritten signature in black ink that reads "Michelle Pinkston". The signature is written in a cursive style and is positioned above the typed name.

Michelle Pinkston
Office Manager
Board Secretary



**2815 WEST 3300 SOUTH
WEST HAVEN, UTAH 84401
801-731-1668**

11/4/2025

Weber County Planning Commission
2380 Washington Boulevard
Ogden, Utah 84401

To Whom It May Concern:

This is to inform you that **Preliminary Will Serve** approval has been given and Taylor West Weber Water District ("the District") has the capacity to provide **only** culinary water for **River Bend Amended Subdivision a 10-lot** subdivision. The address is approx. 3600 W. 850 S. West Weber UT. This subdivision must have a pressurized secondary water system for outdoor use. Plan review fees and water right impact fees must be paid to the District clerk before subdivision approval is granted. A pressurized secondary water system must be functional before final approval will be granted.

Requirements:

- Plan review fee=**\$200 per lot total= \$2,000.00**
- Water Right Impact fee= **\$7,842 x 10 ERU's total = \$78,420.00**
- Complete plan reviews.
- Will serve letter from Hooper Irrigation.
- Impact fees=\$6,856.00 per lot. This fee includes the cost of the meter. This fee will be collected at the time building permits are requested. Fees are subject to change.
- Installation of the water line and services. The District will need to be notified prior to working on the water lines. Taylor West Weber standards must be followed in all installation procedures.
- The construction of the pipelines must pass all inspections.
- Taylor West Weber Water reserves the right to make or revise changes as needed or as advised by the district engineer or the district attorney.

FINAL SUBDIVISION APPROVAL MUST NOT BE ISSUED UNTIL APPROVAL IS GIVEN BY TAYLOR WEST WEBER WATER. A SIGNATURE BLOCK FOR TAYLOR WEST WEBER WATER MUST BE ON THE FINAL RECORDED MYLAR AND SIGNED BY A REPRESENTATIVE OF THE DISTRICT.

Sincerely,

A handwritten signature in blue ink, appearing to read "Ryan Rogers".

Ryan Rogers-Manager

Taylor West Weber Water District

Expires 5/4/2026



- GENERAL NOTES:**
1. PROPERTY OWNER'S UTILITY REQUIREMENTS.
 2. PROPERTY OWNER'S UTILITY REQUIREMENTS.
 3. PROPERTY OWNER'S UTILITY REQUIREMENTS.
 4. PROPERTY OWNER'S UTILITY REQUIREMENTS.
 5. PROPERTY OWNER'S UTILITY REQUIREMENTS.
 6. PROPERTY OWNER'S UTILITY REQUIREMENTS.
 7. PROPERTY OWNER'S UTILITY REQUIREMENTS.
 8. PROPERTY OWNER'S UTILITY REQUIREMENTS.
 9. PROPERTY OWNER'S UTILITY REQUIREMENTS.
 10. PROPERTY OWNER'S UTILITY REQUIREMENTS.



ENSIGN
 THE ENGINEERS OF UTAH
 LAYTON
 515 NORTH 400 West
 Layton, UT 84041
 Phone: 801.541.1100
 SANDY
 Phone: 801.255.8329
 TORRILE
 Phone: 435.843.3388
 CEDAR CITY
 Phone: 435.855.1453
 RICHFIELD
 Phone: 435.846.2883
 WWW.ENSIGNENGINEERS.COM

DATE: 01/15/2014
 DRAWN BY: J. J. JENSEN
 CHECKED BY: J. J. JENSEN
 SCALE: AS SHOWN
 PROJECT: 14-001

**RIVERBEND FARMS SUBDIVISION
 WEST LOTS**
 775 SOUTH 3500 WEST
 WEBER COUNTY, UTAH

CONCEPT PLAN

DATE: 01/15/2014
 TIME: 10:00 AM
 PROJECT: 14-001
 SHEET: 1 OF 1

