AMERICAN FORK CITY PLANNING COMMISSION
NOVEMBER 17, 2021
REGULAR SESSION

Notice is hereby given that the American Fork City Planning Commission will meet in regular session on November 17, 2021, at the American Fork City Hall, 31 North Church Street, commencing at 7:00 p.m.

The agenda shall be as follows:

1. Hearing, review and action on amendments to Section 17.5.133 of the American Fork City Municipal Code entitled "Off-Street Parking Standards"

2. Hearing, review and action on a land use map amendment from the Residential Low Density and Design Commercial designation to the Institutional Lands and Schools designation, located in the area of 970 East 1750 North

3. Hearing, review and action on a zone map amendment from the RA-1 Residential Agricultural zone to the PF Public Facilities zone, located in the area of 970 East 1750 North

4. Hearing, review and action on a zone map amendment from the R2-7,500 Residential zone to the R2-7,500 (O) Residential zone, located in the area of 162 West 400 South

5. Hearing, review and action on the preliminary plan and final plat for Auble Office Condominiums, located at 1134 East 300 North in the PO-1 Professional Office zone

6. Hearing, review and action on a preliminary plan and final plat for Stonecreek Plat G, located at approximately 350 West 900 South in the PR-3.0 Residential zone

7. Hearing, review and action on a preliminary plan and final plat for Auto Mall Drive Business Center Plat B, located at approximately 450 East Auto Mall Drive in the PI-1 Planned Industrial zone

8. Hearing, review and action on a preliminary plan, final plat and site plan for Deer Park Subdivision consisting of two lots, located in the area of 9 West 1100 South in the PI-1 Planned Industrial zone

9. Other Business
10. Site Plan Committee Report

11. Review and action on the minutes of the November 3, 2021 Planning Commission Regular Session

12. Adjournment

John H. Woffinden, P.G.
Planning Commission Chairman

The order of agenda items may change to accommodate the needs of the commission, city staff and the public

Hearing, review and action on amendments to Section 17.5.133 of the American Fork City Municipal Code entitled "Off-Street Parking Standards"

The American Fork City Council and Planning Commission discussed varying approaches to parking for multiple family residential projects during their September 7th, 2021, joint work session and requested of staff to propose alternative ways to handle this situation.

UPDATE: Planning Commission recommended approval of both options on October 6, 2021. However, to more clearly identify that the proposed parking standards only apply in the CC-1 zone, it is recommended the planning commission adopt amended language set for in the proposed amendment to Section 17.5.133.

Potential Motions

APPROVAL
Mr. Chairman, I move that we recommend approval of the proposed amendment to Section 17.5.133:

DENIAL
Mr. Chairman, I move that we recommend denial of the proposed amendments.

TABLE
Mr. Chairman, I move that we table action on the proposed amendment and instruct staff to _____.

AN ORDINANCE AMENDING SUBSECTION 17.5.133(D) AND ADOPTING SUBSECTION 17.5.133(F) OF THE AMERICAN FORK CITY CODE RELATED TO OFF STREET PARKING STANDARDS AND PROVIDING FOR THE ADOPTION AND ENFORCEMENT OF THE AMENDMENT.

WHEREAS the City is authorized to enact ordinances as are necessary and proper to promote the health, safety, morals, convenience, order, prosperity, and general welfare of American Fork;

WHEREAS the City is authorized by law to enact ordinances establishing regulations for development within the City;

WHEREAS, it is in the best interest and general welfare of residents of American Fork to amend the city code relating to the off-street parking standards.

BE IT ORDAINED BY THE CITY COUNCIL OF AMERICAN FORK CITY, UTAH, AS FOLLOWS:

PART I
TEXT OF ORDINANCE

Section 1. Section 17.5.133(D) shall be amended as follows:

D. Adjustments permitted.

1. The planning commission may recommend to the city council an increase or decrease to the number of off-street parking spaces herein specified upon a finding, made following a study on the matter, that the use characteristics of the proposed use warrant adjustment. Provided, however, no reduction in the parking requirement shall be permitted based on the projected demand of the initial occupant of a new retail, office or similar use for which a subsequent change in tenancy to another user is probable.

2. After receiving a recommendation (positive or negative) from planning commission regarding the number of off-street parking spaces, the city council shall have the authority to increase or decrease the number of off-street parking spaces herein specified upon a finding, made following a study on the matter, that the use characteristics of the proposed use warrant adjustment. Provided, however, no reduction in the parking requirement shall be permitted based on the projected demand of the initial occupant of a new retail, office or similar use for which a subsequent change in tenancy to another user is probable.

Section 2. Section 17.5.133(F) shall read as follows:

F. Exception to off-street parking standard in the CC-1 Zone, excluding the Downtown Area. Notwithstanding the provisions of subsections C and E of this section, additional off-street parking spaces will be required as a condition of approval for any new construction, reconstruction of an existing building, or incidental expansion of any building in the CC-1 zone subject to either one of the following criteria:

1. Residential uses: Either of the following off-street parking calculations may be requested by the applicant and may be approved by the city council.
    a. Two spaces per dwelling unit, plus 0.25 spaces per dwelling unit for visitor parking. Visitor parking shall be evenly distributed throughout the project. However, if any of the conditions found in Table A of this subsection apply, the City Council may, after review and recommendation (positive or negative) from the Planning Commission, decrease the required number of off-street parking spaces as shown. The visitor parking requirement shall not be affected by this reduction and remains at 0.25 spaces per dwelling unit. Under no circumstance shall the per-unit parking requirement drop below 1.75 spaces per dwelling unit.

Table A

Condition	**Parking Reduction Per Dwelling Unit**
Bike Room[1]	0.05
Grocery Store[2]	0.10
Off-Site Parking[3]	0.15
Transit[4]	0.15
Public[5] Agency/HUD	Up to 0.15

Definitions:

[1] - Bike Room: A secured bike room of sufficient size to accommodate a minimum of one bicycle per dwelling unit shall be located within the structure. In the event of a multi-structure project each building shall have a secured bike room of sufficient size to accommodate a minimum of one bicycle per dwelling unit in the building. The applicant can opt to either (1) show how the required number of bicycles is accommodated in the room or (2) provide a minimum of 40 square feet per bicycle in the room.

[2] – Grocery Store: The location of the grocery store shall be less than 1320 feet walking distance from the main entrance of the most distant dwelling unit in the project.

[3] – Off-Site Parking: Additional public or shared parking shall be located less than 1320 feet walking distance from the main entrance of the most distant dwelling unit in the project. Parking equivalent to the 0.15 space per dwelling unit reduction shall be secured via agreement with the property owner and recorded. A parking study shall accommodate the agreement so that it can be ensured that the parking facility will not be overallocated.

[4] – Transit: The location of the high-capacity transit line (light rail, "Trax", heavy rail, "FrontRunner", streetcar, high-capacity Bus Rapid Transit, "BRT") shall be less than 1320 feet walking distance from the main entrance of the most distant dwelling unit in the project.

[5]- Public Agency/HUD: Projects that are owned and operated by a public agency or have received a subsidy by HUD or other public agency may be eligible for a reduction of up to 0.15 stalls per unit upon a study that a reduction is warranted.

b. Parking shall be required per unit size as depicted in Table B of this subsection, plus 0.25 spaces per dwelling unit for visitor parking. Visitor parking shall be evenly distributed throughout the project. The visitor parking requirement shall not be affected by this reduction and remains at 0.25 spaces per dwelling unit. Under no circumstance shall the per-unit parking requirement including visitor parking drop below 1.75 spaces per dwelling unit.

Table B

Unit Size	**Parking Requirement Per Unit** (Add 0.25 for visitor parking per unit to derive the aggregated requirement.)
0-350 square feet	1.50
351-600 square feet	1.75
Above 600 square feet	2.00

PART II

SECTION 1 – Conflicting Provisions. Whenever the provisions of this Ordinance conflict with the provisions of any other ordinance, resolution or part thereof, the more stringent shall prevail.

SECTION 2 – Provisions Severable. This Ordinance and the various sections, clauses and paragraphs are hereby declared to be severable. If any part, sentence, clause or phrase is adjudged to be unconstitutional or invalid it is hereby declared that the remainder of the ordinance shall not be affected thereby.

SECTION 3 – Effective Date. This Ordinance shall take effect upon its passage and publication as required by law.

PASSED, by the American Fork City Council this day of _____, 2021.

MAYOR:

_____
BRADLEY J. FROST

ATTEST:

_____
TERILYN LURKER, CITY RECORDER

AMERICAN FORK CITY
PLANNING COMMISSION

MEETING DATE: 11/17/2021
STAFF: Ben Hunter

AGENDA TOPICS:

Hearing, review, and action on a land use map amendment for property located at 970 East 1750 North from the Residential Low Density and Design Commercial designation to the Institutional Lands, Schools and Public Facilities designation.

Hearing, review, and action on a zone map amendment for property located at 970 East 1750 North from the RA-1 Residential Agricultural zone to the PF Public Facilities zone.

ACTION REQUESTED: Recommendations of approval for land use and zone map amendments.

BACKGROUND INFORMATION		
Location:		970 East 1750 North
Applicants:		American Fork City
Existing Land Use:		Residential Low Density and Design Commercial
Proposed Land Use:		Institutional Lands, Schools and Public Facilities
Surrounding Land Use:	North	Residential Low Density and Design Commercial
	South	Design Commercial and Cedar Hills
	East	Cedar Hills
	West	Institutional Lands, Schools and Public Facilities
Existing Zoning:		RA-1 Residential Agricultural
Proposed Zoning:		PF Public Facilities
Surrounding Zoning:	North	R1-9,000
	South	GC-2 and Cedar Hills (R-1 11,000)
	East	Cedar Hills (R-1 11,000)
	West	Unincorporated

Background

The applicant proposes to amend the land use and zone map designations of the parcel located at 970 East 1750 North. The existing land use for the property is divided into two classifications: Design Commercial on the west and Residential Low Density on the east. The existing zone designation for the entire parcel is RA-1 Residential Agricultural.

The applicant is asking to change the land use designation to Institutional Lands, Schools and Public Facilities over the entire property. Applicant is also asking to change the existing zone to Public Facilities over the entire parcel.

POTENTIAL MOTIONS:

LAND USE MAP AMENDMENT

APPROVAL

Mr. Chairman, I move that we recommend approval of the land use map amendment.

DENIAL

Mr. Chairman, I move that we recommend denial of the land use map amendment.

TABLE

Mr. Chairman, I move that we table action on the land use map amendment.

ZONE MAP AMENDMENT

APPROVAL

Mr. Chairman, I move that we recommend approval of the zone map amendment.

DENIAL


Mr. Chairman, I move that we recommend denial of the zone map amendment.

TABLE

Mr. Chairman, I move that we table action on the zone map amendment.


Land Use Map


Area proposed to be changed from Residential Low Density and Design Commercial designations to Institutional Lands, Schools and Public Facilities designation



Zoning Map

Area proposed to be changed from the RA-1 Residential Agricultural zone to the PF Public Facilities zone.





Utah County Parcel Map

This cadastral map is generated from Utah County Recorder data. It is for reference only and no liability is assumed for any inaccuracies, incorrect data or variations with an actual survey

Date: 11/10/2021

N

AMERICAN FORK CITY
PLANNING COMMISSION

MEETING DATE: 11/17/2021
STAFF: Ben Hunter

AGENDA TOPICS:

Hearing, review, and action on a zone map amendment for property located at 162 West 400 South from the R2-7,500 Residential zone to the R2-7,500 (O) Residential Overlay zone.

ACTION REQUESTED: Recommendation of approval for zone map amendment.

BACKGROUND INFORMATION		
Location:		162 West 400 South
Applicants:		Kaskade Homes
Existing Land Use:		Residential Low Density
Proposed Land Use:		Residential Low Density
Surrounding Land Use:	North	Design Industrial
	South	Residential Low Density
	East	Residential Low Density
	West	Residential Low Density
Existing Zoning:		R2-7,500 Residential
Proposed Zoning:		R2-7,500 (O) Residential Overlay
Surrounding Zoning:	North	PI-1 Planned Industrial
	South	R2-7,500 Residential
	East	R2-7,500 Residential
	West	R2-7,500 Residential

Background

The applicant proposes to amend the zone map designation of the parcels located at 162 West 400 South. The existing zone designation for the parcels is R2-7,500 Residential.

The applicant is asking to change the existing zone to R2-7,500 (O) Residential Overlay. The overlay zone provides additional options for those desiring to live on separate smaller lots, with densities as permitted under the “two-family dwelling” option without a common wall between the residences.

POTENTIAL MOTIONS:

ZONE MAP AMENDMENT

APPROVAL


Mr. Chairman, I move that we recommend approval of the zone map amendment.

DENIAL

Mr. Chairman, I move that we recommend denial of the zone map amendment.

TABLE

Mr. Chairman, I move that we table action on the zone map amendment.


Zoning proposed to be changed from R2-7500 to R2-7500 (O).
Zone Map
PI-1
R2-7500
350 SOUTH ST
380 SOUTH ST
400 SOUTH ST
400 SOUTH ST
190 WEST ST
170 WEST ST
STORRS AVE
STORRS AVE

Kaskade Homes

Kaskade Homes
13775 S. 78 W.
Draper, UT 84020
10/22/2021

American Fork City
Planning and Zoning
30 N Center St.
American Fork, UT 84003

To whom it may concern:

This letter is written as an explanation to the application for a zone change regarding 2.11 acres located at 162 W. 400 S. in American Fork City, 84003. We would like to change the current R2-7500 zoning to R2-7500 (O). This zone change would allow 6000 SF minimum lots of which we intend to place (9) single family residences. (See attached concept plan.)

It is our understanding that the property immediately West of this proposed subdivision was constructed using the same R2-7500 (O) zoning. A majority, if not all the homes at this location appear to have been built on the minimum requirement of 6000 SF per lot.

We feel that this change from R2-7500 to R2-7500 (O) is consistent with bordering properties and would be a great addition to the neighborhoods of the surrounding area.

If you have any questions or would like any additional information, please feel free to contact me at any time using the contact info below.


Sincerely,

Tod Kirton
Project Manager
358-277-5870
tod@kaskadehomes.com

Attached: Concept plan for subdivision

STORRS PROPERTY

CONCEPT



Scale 1" = #### ft

WILDING
ENGINEERING
14721 South Heritage Crest Way
Bluffdale, Utah 84065
801.553.8112
www.wildingengineering.com

DRAWING NOTES:

G:\DATA\21308 Storrs Boundary Survey\dwg\21308 Concept.dwg
PLOT DATE: Oct 13, 2021

NO.	REVISION	DATE

PROJECT INFORMATION

STORRS PROPERTY

CONCEPT

AMERICAN FORK, UTAH

DRAWN	CHECKED	PROJECT #
KMD	---	21308

DATE: 10/12/2021

SCALE: 1" = 30'

SHEET: CONCEPT

ENGINEER'S STAMP

AMERICAN FORK CITY
PLANNING COMMISSION

MEETING DATE: 11/17/2021
STAFF: Ben Hunter

AGENDA TOPIC: Hearing, review and action on the preliminary plan and final plat for Auble Office Condominiums, located at 1134 East 300 North in the PO-1 Professional Office zone.

BACKGROUND INFORMATION					
Location:		1134 East 300 North			
Applicants:		Davies Design Build/Steve Davies			
Existing Land Use:		Professional Office			
Proposed Land Use:		N/A			
Surrounding Land Use:	North	Residential Low Density			
	South	Professional Office			
	East	Professional Office			
	West	Residential Low Density			
Existing Zoning:		PO-1 Professional Office			
Proposed Zoning:		N/A			
Surrounding Zoning:	North	RA-1 Residential Agricultural			
	South	PO-1 Professional Office			
	East	PO-1 Professional Office			
	West	R1-12000 Residential			
Land Use Plan Designation:		Professional Office			
Zoning within Land Use Plan Designation?		x	Yes		No

Background

Auble Office Condominium is a subdivision of parcel 14:017:0284 and proposes to create 3 condominium units. The subdivision units meet or exceed the area and dimensional requirements of the PO-1 Professional Office zone.

Consistency with the Land Use Plan

The plat and zoning comply with the Land Use Plan designation; therefore the proposed subdivision is consistent with the Land Use Plan designation.

Section 17.8.211 of the Development Code

The Planning Commission may act to recommend approval of a final plat upon a finding that:

a. The final plat conforms with the terms of the preliminary plan approval.

   The preliminary plan and final plat are processed concurrently and are consistent with one another.

b. The final plat complies with all City requirements and standards relating to Subdivisions.

   This criterion has been met.

c. The detailed engineering plans and materials comply with the City standards and policies.

   Engineering will address concerns, if any, at the time of the Planning Commission Meeting.

d. The estimates of cost of constructing the required improvements are realistic.

   Engineering will determine whether the cost estimates of constructing any required improvements are realistic.

e. The water rights conveyance documents have been provided.

   Any water rights conveyance shall be satisfied prior to plat recordation.

FINDINGS OF FACT/CONDITION OF APPROVAL

After reviewing the application for final plat approval, the following finding of fact and condition of approval are offered for consideration:

1. The final plat meets Section 17.8.101 (Intent) of Chapter 17.8 (Subdivisions).
2. The final plat meets the criteria as found in Section 17.8.211 of the Development Code.

POTENTIAL MOTIONS

PRELIMINARY PLAN

Mr. Chairman, I move that we approve the preliminary plan for the Auble Office Condominiums, located at 1134 East 300 North subject to any findings, conditions and modifications found in the engineering report.

FINAL PLAT

Mr. Chairman, I move that we recommend approval of the final plat for the Auble Office Condominiums, located at 1134 East 300 North with the findings listed in the staff report, and subject to any findings, conditions and modifications found in the engineering report.

DENIAL

PRELIMINARY PLAN

Mr. Chairman, I move that we deny the preliminary plan for the Auble Office Condominiums, located at 1134 East 300 North.

FINAL PLAT

N/A [If the preliminary plan is denied, there can be no recommendation on the final plat.]

TABLE

PRELIMINARY PLAN

Mr. Chairman, I move that we table action on the preliminary plan for the Auble Office Condominiums, located at 1134 East 300 North.

FINAL PLAT

Mr. Chairman, I move that we table action on the final plat for the Auble Office Condominiums, located at 1134 East 300 North.

AMERICAN FORK CITY ENGINEERING DIVISION
STAFF REPORT

Planning Commission Meeting Date: 11/17/2021

This report is a summary of the American Fork City Engineering Division plan review comments regarding the subject plan as submitted by the applicant for American Fork City Land Use Authority approval:

Project Name: Auble Office Condominiums

Project Address: 1134 East 300 North

Developer / Applicant's Name: Davies Design Build/Steve Davies

Type of Application:

- ☒ Subdivision Final Plat
- ☒ Subdivision Preliminary Plan
- ☐ Annexation
- ☐ Code Text Amendment
- ☐ General Plan Amendment
- ☐ Zone Change
- ☐ Commercial Site Plan
- ☐ Residential Accessory Structure Site Plan

Project Map:



Engineering Division Recommendation: The Engineering Division recommends APPROVAL of the proposed development with the following conditions:

STANDARD CONDITIONS OF APPROVAL

Standard Conditions of Approval:

APPLICANT is responsible and shall submit/post/obtain all necessary documentation and evidence to comply with these Standard Conditions of Approval prior to any platting, permitting, or any other form of authorization by the City including plat recording or other property conveyance to the City and prior to scheduling a pre-construction meeting. All recording shall take place at the Utah County Recorder's Office.

1. **Title Report:** Submit an updated Title Report not older than 30 days or other type of appropriate verification that shows all dedications to the City are free and clear of encumbrances, taxes, or other assessments.
2. **Property Taxes and Liens:** Submit evidence that all the property taxes, for the current and/or previous years, liens, and agricultural land use roll over fees have been paid in full.
3. **Water Rights:** Submit evidence that all the required water rights have been conveyed to American Fork City.
4. **Performance Guarantee:** Post a performance guarantee for all required public and essential common improvements.
5. **Easements and Agreements:** Submit/record a long-term Storm Water Pollution Prevention Maintenance Agreement signed and dated by the property owner and any required easement documentation.
6. **Land Disturbance Permit:** Obtain a Land Disturbance Permit.
7. **Compliance with the Engineering Division Plan Review Comments:** All plans and documents shall comply with all the Technical Review Committee comments and the City Engineer's final review.
8. **Commercial Structure:** Record an Owner Acknowledgment and Utility Liability Indemnification if the proposed building is a multi-unit commercial structure served by a single utility service.
9. **Sensitive Lands:** Record all applicable documents required for compliance with the City's Sensitive Lands Ordinance.
10. **Utility Notification Form:** Submit a Subdivision Utility Notification Form.
11. **Professional Verification:** Submit final stamped construction documentation by all appropriate professionals.
12. **Fees:** Payment of all development, inspection, recording, street light, and other project related fees.
13. **Mylar:** Submit a Mylar. All plats will receive final verification of all formats, notes, conveyances, and other items contained on the plat by City staff (recorder, legal, engineer, GIS, planning).

AUBLE OFFICE CONDOMINIUMS


LOCATED IN THE SOUTHWEST QUARTER OF SECTION 18,
TOWNSHIP 5 SOUTH, RANGE 2 EAST,
SALT LAKE BASE AND MERIDIAN
AMERICAN FORK CITY, UTAH COUNTY, UTAH

NORTH

GRAPHIC SCALE

20 0 10 20 40

(IN FEET)
1 inch = 20ft.



LEGEND & ABBREVIATIONS

SECTION CORNER OR QUARTER CORNER (FOUND)

BOUNDARY CORNER
(SET 5/8" x 24" REBAR AND CAPS OR PLAT NOTED)

OFFSET PINS TO BE SET IN TOP BACKS OF CURB AND 5/#8 x 24" REBAR AND CAPS TO BE SET AT ALL REAR LOT CORNERS MARKED "BENCHMARK ENG."

SOUTHWEST CORNER OF SECTION 18, TOWNSHIP 5 SOUTH, RANGE 2 EAST, SALT LAKE BASE AND MERIDIAN (FOUND BRASS CAP)

SECTION LINE

BOUNDARY LINE

ADJACENT PROPERTY

STREET CENTERLINE

P.U.E. - PUBLIC UTILITY EASEMENT

RIGHT OF WAY

FIRE HYDRANT

LAND USE TABLE

BUILDING AREA = 5,539 SQ FT

LIMITED COMMON AREA = 0

COMMON AREA = 34,782 SQ FT

TOTAL AREA = 40,321 SQ FT

1 - BUILDING
3 - UNITS

BASIS OF BEARINGS

THE BASIS OF BEARINGS IS BETWEEN THE WEST QUARTER CORNER AND THE SOUTHWEST QUARTER OF SECTION 18, TOWNSHIP 5 SOUTH, RANGE 2 EAST, SALT LAKE BASE AND MERIDIAN. WITH A BEARING OF SOUTH 00°25'18" EAST


FLOOD ZONE DESIGNATION

SUBJECT PROPERTY DELINEATED AS ZONE "X" BY F.E.M.A. FLOOD INSURANCE RATE MAP, COMMUNITY PANEL MAP NO. 49049C0169F, EFFECTIVE JUNE 19, 2020.

ZONE

ZONE PO-1

VICINITY MAP



WATER AND SEWER AUTHORITY APPROVAL

APPROVED THE ____ DAY OF _____ A.D. 2021. BY THE WATER AND SEWER AUTHORITY.

PUBLIC WORKS DEPARTMENT DIRECTOR

BENCHMARK CIVIL

BENCHMARK ENGINEERING & LAND SURVEYING
9138 SOUTH STATE STREET SUITE # 100
SANDY, UTAH 84070 (801) 542-7192
www.benchmarkcivil.com

SURVEYOR'S SEAL

PROFESSIONAL LAND SURVEYOR
11-10-21
7240531
BRIAN A. LINAM
STATE OF UTAH

NOTARY PUBLIC SEAL

CLERK - RECORDER SEAL

SURVEYOR'S CERTIFICATE

I, BRIAN A. LINAM DO HEREBY CERTIFY THAT I AM A PROFESSIONAL LAND SURVEYOR, AND THAT I HOLD A LICENSE IN ACCORDANCE WITH TITLE 58, CHAPTER 22, PROFESSIONAL ENGINEERS AND LAND SURVEYORS LICENSING ACT, UTAH CODE ANNOTATED, 1953 AS AMENDED CERTIFICATE NUMBER 7240531. I FURTHER CERTIFY THAT BY AUTHORITY OF THE OWNERS, I HAVE MADE A SURVEY OF THE TRACT OF LAND SHOWN ON THIS PLAT AND DESCRIBED BELOW, UPON WHICH HAS BEEN CONSTRUCTED, HEREAFTER KNOWN AS AUBLE OFFICE CONDOMINIUMS, A UTAH CONDOMINIUM PROJECT. IN ACCORDANCE WITH THE UTAH CONDOMINIUM OWNERSHIP ACT, I FURTHER CERTIFY THAT THE CONDOMINIUM PLAT FOR SAID PROJECT IS ACCURATE AND COMPLIES WITH THE PROVISION OF SECTION 57-11-13 (1) OF THE UTAH CONDOMINIUM OWNERSHIP ACT.

BOUNDARY DESCRIPTION

AN ENTIRE TRACT OF LAND, SITUATE IN THE NORTH HALF OF THE SOUTHWEST QUARTER OF SECTION 18, TOWNSHIP 5 SOUTH, RANGE 2 EAST, SALT LAKE BASE AND MERIDIAN, IN UTAH COUNTY, STATE OF UTAH, WHICH TRACT IS DESCRIBED MORE PARTICULARLY AS FOLLOWS:

BEGINNING AT A POINT BEING S 00°25'18" E 543.92 FEET ALONG THE SECTION LINE AND EAST 1472.23 AND SOUTH 21.26 SOUTH FROM THE WEST QUARTER CORNER OF SAID SECTION 18; AND RUNNING THENCE THENCE SOUTH 143.74 FEET; THENCE WEST 281.02 FEET TO A POINT ON THE EASTERLY RIGHT OF WAY OF SR-129 (NORTH COUNTY BOULEVARD); THENCE N 00°08'35" E 132.33 FEET ALONG SAID EASTERLY RIGHT OF WAY LINE; THENCE N 65°43'43" E 29.61 FEET TO A POINT ON THE SOUTHERLY RIGHT OF WAY LINE OF 300 NORTH STREET; THENCE SOUTH 89°49'42" EAST 253.70 FEET ALONG SAID SOUTHERLY RIGHT OF WAY LINE TO THE POINT OF BEGINNING.

THE ABOVE DESCRIBED ENTIRE TRACT OF LAND CONTAINS 40,321 SQUARE FEET OR 0.926 ACRES, MORE OR LESS.

3 UNITS

OWNER'S DEDICATION

KNOW ALL MEN BY THESE PRESENTS THAT THE UNDERSIGNED OWNER(S) OF SAID TRACT OF LAND DESCRIBED HEREON DO HEREBY CERTIFY THAT WE CONSENT TO THE RECORDATION OF THIS CONDOMINIUM PLAT IN ACCORDANCE WITH UTAH CODE ANNOTATED 57-M3, SUBDIVIDING THE LAND INTO CONDOMINIUM OWNERSHIP, AND CREATING UNITS, COMMON AREAS, LIMITED COMMON AREAS AND EASEMENTS ALL AS SET FORTH HEREIN TO HEREAFTER BE KNOWN AS

AUBLE OFFICE CONDOMINIUMS

UTILITY DEDICATION

BY EXECUTION OF THIS PLAT, THE OWNER(S) SHOWN BELOW DOES HEREBY GRANT AND CONVEY TO THE CITY AND OTHER PUBLIC UTILITY COMPANIES, A PERMANENT EASEMENT AND RIGHT OF WAY IN AND TO THOSE AREAS REFLECTED ON THE MAP AND DEFINED IN THE DECLARATION OF CONDOMINIUM APPLICABLE TO THIS PROJECT AS "COMMON AREA" (INCLUDING PRIVATE STREETS AND PRIVATE DRIVEWAYS) FOR CONSTRUCTION AND MAINTENANCE OF APPROVED PUBLIC UTILITIES AND APPURTENANCES TOGETHER WITH RIGHT OF ACCESS THERETO.

RESERVATION OF COMMON AREAS

BY EXECUTION OF THIS PLAT. THE OWNER(S) SHOWN BELOW DOES HEREBY RESERVE ALL AREAS SHOWN ON THIS PLAT OR DESCRIBED IN THE DECLARATION OF CONDOMINIUM AS "COMMON AREA" FOR THE COMMON ENJOYMENT OF ALL OWNERS AND SUCH OWNERS GUESTS AND INVITEES AS SPECIFICALLY DESCRIBED IN THE DECLARATION OF CONDOMINIUM APPLICABLE TO THE PROJECT.
IN WITNESS HEREOF, THE OWNER(S) HAVE HEREUNTO SET OUR HANDS THIS ___ DAY OF _____, A.D. 2021

BY: _____

ITS: _____

ACKNOWLEDGMENT

STATE OF UTAH
County of Salt Lake } S.S.

ON THIS ___DAY OF _____, IN THE YEAR 20___, BEFORE ME _____, A NOTARY PUBLIC, PERSONALLY APPEARED _____ THE MANAGING MEMBER OF AUBLE OFFICE BUILDING, LLC PROVED ON THE BASIS OF SATISFACTORY EVIDENCE TO BE THE PERSON(S) WHOSE NAME(S) IS/ARE SUBSCRIBED TO IN THE FOREGOING OWNER'S DEDICATION AND CONSENT REGARDING AUBLE OFFICE CONDOMINIUMS AND WAS SIGNED BY HIM/HER ON BEHALF OF SAID AUBLE OFFICE BUILDING, LLC AND ACKNOWLEDGED THAT HE/SHE/THEY EXECUTED THE SAME.

MY COMMISSION EXPIRES: _____ (DATE)

COMMISSION NUMBER: _____

PRINT NAME

(SIGNED) A NOTARY PUBLIC COMMISSIONED IN UTAH

ACCEPTANCE BY LEGISLATIVE BODY

THE CITY COUNCIL OF THE CITY OF AMERICAN FORK, COUNTY OF UTAH, APPROVES THIS DEDICATION PLAT, AND HEREBY ACCEPTS THE DEDICATION OF ALL EASEMENTS AND OTHER PARCELS OF LAND INTENDED FOR THE PUBLIC PURPOSE OF THE PERPETUAL USE OF SAID PUBLIC.
THIS _____ DAY OF _____, A.D. _____.

CITY MAYOR

CITY COUNCIL MEMBER

CITY COUNCIL MEMBER

CITY COUNCIL MEMBER

CITY COUNCIL MEMBER

CITY COUNCIL MEMBER

CITY ENGINEER

ATTEST: _____
CLERK-RECORDER (SEE SEAL BELOW)

PLANNING COMMISSION APPROVAL

APPROVED THIS _____ DAY OF _____ A.D. 20____, BY THE AMERICAN FORK CITY PLANNING COMMISSION.

PLANNER

PLANNING COMMISSION CHAIR


AUBLE OFFICE CONDOMINIUMS

LOCATED IN THE SOUTHWEST QUARTER OF SECTION 18,
TOWNSHIP 5 SOUTH, RANGE 2 EAST,
SALT LAKE BASE AND MERIDIAN
AMERICAN FORK CITY, UTAH COUNTY, UTAH


2011308CP.DWG

AUBLE OFFICE CONDOMINIUMS


LOCATED IN THE SOUTHWEST QUARTER OF SECTION 18,
TOWNSHIP 5 SOUTH, RANGE 2 EAST,
SALT LAKE BASE AND MERIDIAN
AMERICAN FORK CITY, UTAH COUNTY, UTAH



FIRST FLOOR



THIRD FLOOR



SECOND FLOOR

PRIVATELY OWNED UNITS

COMMON AREAS

LIMITED COMMON AREAS

BENCHMARK ENGINEERING & LAND SURVEYING
9138 SOUTH STATE STREET SUITE # 100
SANDY, UTAH 84070 (801) 542-7192
www.benchmarkcivil.com

PROFESSIONAL LAND SURVEYOR
11-10-21
7240531
BRIAN A. LIMAM
STATE OF UTAH


AUBLE OFFICE CONDOMINIUMS

LOCATED IN THE SOUTHWEST QUARTER OF SECTION 18,
TOWNSHIP 5 SOUTH, RANGE 2 EAST,
SALT LAKE BASE AND MERIDIAN
AMERICAN FORK, UTAH COUNTY, UTAH


2011308cp.dwg

AUBLE OFFICE CONDOMINIUMS


LOCATED IN THE SOUTHWEST QUARTER OF SECTION 18,
TOWNSHIP 5 SOUTH, RANGE 2 EAST,
SALT LAKE BASE AND MERIDIAN
AMERICAN FORK CITY, UTAH COUNTY, UTAH



FRONT AND REAR ELEVATIONS



LEFT SIDE



RIGHT SIDE

PRIVATELY OWNED UNITS

COMMON AREAS


LIMITED COMMON AREAS

BENCHMARK ENGINEERING & LAND SURVEYING
9138 SOUTH STATE STREET SUITE # 100
SANDY, UTAH 84070 (801) 542-7192
www.benchmarkcivil.com

11/10/2011
7240531
BRIAN A. LINAM
PROFESSIONAL LAND SURVEYOR
STATE OF UTAH

AUBLE OFFICE CONDOMINIUMS
LOCATED IN THE SOUTHWEST QUARTER OF SECTION 18,
TOWNSHIP 5 SOUTH, RANGE 2 EAST,
SALT LAKE BASE AND MERIDIAN
AMERICAN FORK, UTAH COUNTY, UTAH

2011308cp.dwg



SEWER NOTES:

1. ALL SEWER MAINS AND LATERALS MUST BE INSPECTED AND APPROVED BY THE CITY OF AMERICAN FORK PUBLIC WORKS DEPARTMENT BEFORE BACKFILLING IS ACCOMPLISHED.
2. SEWER LATERALS ARE TO BE INSTALLED AT A MINIMUM SLOPE OF 2%
3. NEW SERVICE LATERALS SHALL BE PVC PLASTIC PIPE CONFORMING TO ASTM D3034 SDR35
4. ALL LATERAL CONNECTIONS SHALL "INSERT-A-TEE" OR WYE AT TEN O'CLOCK OR TWO O'CLOCK POSITIONING TO CENTER OF MAIN LINE AND SHALL BE ENCASED IN CONCRETE AFTER INSPECTION IS MADE.
5. THERE SHALL BE A MINIMUM 3 FEET OF COVER OVER ALL SEWER LATERAL LINES AND 3.5 FEET MINIMUM COVER AT PROPERTY LINE.
6. THERE SHALL BE A MAXIMUM DISTANCE OF 5 FEET FROM THE FOUNDATION WALL TO THE FIRST EXTERIOR CLEANOUT WITH A MAXIMUM DISTANCE BETWEEN CLEANOUTS OF 75 FEET.
7. THERE SHALL A BE CLEANOUT AT ANY 90° BEND OR ANY COMBINATION OF BENDS IN EXCESS OF 90°.
8. CLEANOUT STANDPIPE CAN BE CAST IRON OR IRON OR PVC WITH CAST IRON CAP OR BRASS CAP.
9. ALL CLEANOUTS SHALL REMAIN VISIBLE AND ACCESSIBLE.
10. ALL SEWER CONSTRUCTION MUST CONFORM TO AF CITY STANDARD DRAWINGS.

WATER NOTES:

1. ALL WATER MAINS, TRANSMISSION AND DISTRIBUTION LINES, SHALL BE CONSTRUCTED USING DUCTILE IRON IN ACCORDANCE WITH AWWA C151 AND ANSI A-21.51
2. DUCTILE IRON PIPE SHALL BE CLASS 50 FOR SLIP-ON OR MECHANICAL JOINT PIPING (CLASS 51 FOR 6 INCH SIZE AND UNDER) AND CLASS 53 FOR FLANGED JOINT PIPING UNLESS OTHERWISE REQUIRED BY THE CITY ENGINEER.
3. ALL WATER CONSTRUCTION TO CONFORM TO AF CITY STANDARD DRAWINGS.
4. WATER LINE MIN. COVER IS 48" TO TOP OF PIPE.
5. WATER SERVICE MATERIAL TO BE TYPE K COPPER TUBING.

GENERAL UTILITY NOTES:

1. THERE ARE NO EXISTING LAND DRAINAGE SYSTEMS, WETLANDS, OR DRAINAGE AREAS TRIBUTARY TO THIS SITE.
2. NO UTILITY LINE EXTENSIONS REQUIRED FROM ADJACENT PROPERTY OWNERS.
3. ALL CONSTRUCTION SHALL CONFORM TO AMERICAN FORK CITY STANDARDS AND SPECIFICATIONS, LATEST EDITION.
4. ALL ROOF DRAINS WILL BE CONVEYED TO THE APPROPRIATE UNDERGROUND FACILITY WHERE POSSIBLE, NOT CONVEYED ACROSS PARKING OR SIDEWALK. ROOF DRAINS SHOULD DISCHARGE AT LEAST 10 FEET FROM FOUNDATIONS OR BACKFILL LIMITS, WHICHEVER IS GREATER. CONNECT ALL ROOF DRAINS TO STORM DRAIN PIPING SHOWN WHERE POSSIBLE.

POWER POLE RELOCATION NOTE:

IF POWER POLE RELOCATION IS REQUIRED, IT WILL BE COORDINATED WITH ROCKY MOUNTAIN POWER PRIOR TO CONSTRUCTION. ALIGNMENT OF POWER LINES WITH EXISTING POWER POLES WILL BE DETERMINED AT THAT TIME AS WELL.

NOTES TO CONTRACTOR

1. CONTRACTOR TO FIELD VERIFY ALL EXISTING CURB & GUTTER, STORM DRAIN, & SEWER ELEVATIONS OR INVERTS PRIOR TO CONSTRUCTION AND NOTIFY ENGINEER WHEN ELEVATIONS OR INVERTS DO NOT MATCH PLANS.
2. THE LOCATION OF EXISTING UNDERGROUND UTILITIES IS SHOWN IN APPROXIMATE LOCATIONS. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE AND ALL UNDERGROUND UTILITIES, WHETHER OR NOT SUCH FACILITIES ARE SHOWN ON THESE PLANS.

UTILITY LEGEND

- FIRE HYDRANT
- PRESSURE IRRIG.
- CULINARY WATER
- SEWER PIPE PVC SDR-35
- STORM DRAIN PIPE
- EDGE OF ASPHALT
- FENCE
- OVERHEAD POWER LINE
- GAS LINE

FIRE HYDANT NOTE

1. CONSTRUCTION TYPE = VB
2. TOTAL SQUARE FOOTAGE = 16,166 S.F.
3. REQUIRED FIRE FLOW = 3,500 GPM
4. 50% FLOW REDUCTION FOR FIRE SPRINKLERS PROVIDED = 1,750 GPM
5. HYDRANTS REQUIRED FOR 1,750 GPM = 1
6. THE EXISTING FIRE HYDRANT AT THE NORTHWEST CORNER SATISFIES THIS REQUIREMENT.

Know what's below. Call before you dig.

REGISTERED PROFESSIONAL ENGINEER — DAVID W. PETERSON — No. 270393 — STATE OF UTAH — 1/22/19

LAND SURVEYOR: J-U-B ENGINEERS, INC.

BENCH MARK

WEST QUARTER CORNER, SECTION 18, TOWNSHIP 5 SOUTH, RANGE 2 EAST, SALT LAKE BASE AND MERIDIAN UT. CO. GIS MON. NO. 879 ELEVATION = 4640.18

REVISIONS

Rev.	Date	Description
1	10/04/19	REVISED AS PER TECH REVIEW COMMENTS DATED 01/21/15
2	11/14/19	SHOWED ADDITIONAL WATER SERVICE CONNECTION TO BUILDING
3	10/08/21	SHOWED ADDITIONAL SEWER AND WATER SERVICES CONNECTION TO BUILDING
4	11/05/21	REVISED PER CITY COMMENTS

AUBLE OFFICE BUILDING LLC
2491 N 1200 E SUITE 201
LEHI UT 84043


EXCEL ENGINEERING
David W. Peterson, P.E. | License #270393
12 West 100 North Suite 201, American Fork, UT 84003
P: (801) 756-4504; dave@excelengll.com


AUBLE OFFICE BUILDING

AMERICAN FORK 1112 East 300 North UTAH

Drawn by:	Scale:
D.W.P.	1"=20'
Designed by: D.W.P.	Date: 01/22/19
Checked by: D.W.P.	C4

UTILITY PLAN





SEWER NOTES:

1. ALL SEWER MAINS AND LATERALS MUST BE INSPECTED AND APPROVED BY THE CITY OF AMERICAN FORK PUBLIC WORKS DEPARTMENT BEFORE BACKFILLING IS ACCOMPLISHED.
2. SEWER LATERALS ARE TO BE INSTALLED AT A MINIMUM SLOPE OF 2%
3. NEW SERVICE LATERALS SHALL BE PVC PLASTIC PIPE CONFORMING TO ASTM D3034 SDR35
4. ALL LATERAL CONNECTIONS SHALL "INSERT-A-TEE" OR WYE AT TEN O'CLOCK OR TWO O'CLOCK POSITIONING TO CENTER OF MAIN LINE AND SHALL BE ENCASED IN CONCRETE AFTER INSPECTION IS MADE.
5. THERE SHALL BE A MINIMUM 3 FEET OF COVER OVER ALL SEWER LATERAL LINES AND 3.5 FEET MINIMUM COVER AT PROPERTY LINE.
6. THERE SHALL BE A MAXIMUM DISTANCE OF 5 FEET FROM THE FOUNDATION WALL TO THE FIRST EXTERIOR CLEANOUT WITH A MAXIMUM DISTANCE BETWEEN CLEANOUTS OF 75 FEET.
7. THERE SHALL A BE CLEANOUT AT ANY 90° BEND OR ANY COMBINATION OF BENDS IN EXCESS OF 90°.
8. CLEANOUT STANDPIPE CAN BE CAST IRON OR IRON OR PVC WITH CAST IRON CAP OR BRASS CAP.
9. ALL CLEANOUTS SHALL REMAIN VISIBLE AND ACCESSIBLE.
10. ALL SEWER CONSTRUCTION MUST CONFORM TO AF CITY STANDARD DRAWINGS.

WATER NOTES:

1. ALL WATER MAINS, TRANSMISSION AND DISTRIBUTION LINES, SHALL BE CONSTRUCTED USING DUCTILE IRON IN ACCORDANCE WITH AWWA C151 AND ANSI A-21.51
2. DUCTILE IRON PIPE SHALL BE CLASS 50 FOR SUP-ON OR MECHANICAL JOINT PIPING (CLASS 51 FOR 6 INCH SIZE AND UNDER) AND CLASS 53 FOR FLANGED JOINT PIPING UNLESS OTHERWISE REQUIRED BY THE CITY ENGINEER.
3. ALL WATER CONSTRUCTION TO CONFORM TO AF CITY STANDARD DRAWINGS.
4. WATER LINE MIN. COVER IS 48" TO TOP OF PIPE.
5. WATER SERVICE MATERIAL TO BE TYPE K COPPER TUBING.

GENERAL UTILITY NOTES:

1. THERE ARE NO EXISTING LAND DRAINAGE SYSTEMS, WETLANDS, OR DRAINAGE AREAS TRIBUTARY TO THIS SITE.
2. NO UTILITY LINE EXTENSIONS REQUIRED FROM ADJACENT PROPERTY OWNERS.
3. ALL CONSTRUCTION SHALL CONFORM TO AMERICAN FORK CITY STANDARDS AND SPECIFICATIONS, LATEST EDITION.
4. ALL ROOF DRAINS WILL BE CONVEYED TO THE APPROPRIATE UNDERGROUND FACILITY WHERE POSSIBLE, NOT CONVEYED ACROSS PARKING OR SIDEWALK. ROOF DRAINS SHOULD DISCHARGE AT LEAST 10 FEET FROM FOUNDATIONS OR BACKFILL LIMITS, WHICHEVER IS GREATER. CONNECT ALL ROOF DRAINS TO STORM DRAIN PIPING SHOWN WHERE POSSIBLE.

POWER POLE RELOCATION NOTE:

IF POWER POLE RELOCATION IS REQUIRED, IT WILL BE COORDINATED WITH ROCKY MOUNTAIN POWER PRIOR TO CONSTRUCTION. ALIGNMENT OF POWER LINES WITH EXISTING POWER POLES WILL BE DETERMINED AT THAT TIME AS WELL.

NOTES TO CONTRACTOR

1. CONTRACTOR TO FIELD VERIFY ALL EXISTING CURB & GUTTER, STORM DRAIN, & SEWER ELEVATIONS OR INVERTS PRIOR TO CONSTRUCTION AND NOTIFY ENGINEER WHEN ELEVATIONS OR INVERTS DO NOT MATCH PLANS.
2. THE LOCATION OF EXISTING UNDERGROUND UTILITIES IS SHOWN IN APPROXIMATE LOCATIONS. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE AND ALL UNDERGROUND UTILITIES, WHETHER OR NOT SUCH FACILITIES ARE SHOWN ON THESE PLANS.

UTILITY LEGEND

- FIRE HYDRANT
- PRESSURE IRRIG
- CULINARY WATER
- SEWER PIPE PVC SDR-35
- STORM DRAIN PIPE
- EDGE OF ASPHALT
- FENCE
- OVERHEAD POWER LINE
- GAS LINE

FIRE HYDANT NOTE

1. CONSTRUCTION TYPE = VB
2. TOTAL SQUARE FOOTAGE = 16,166 S.F.
3. REQUIRED FIRE FLOW = 3,500 GPM
4. 50% FLOW REDUCTION FOR FIRE SPRINKLERS PROVIDED = 1,750 GPM
5. HYDRANTS REQUIRED FOR 1,750 GPM = 1
6. THE EXISTING FIRE HYDRANT AT THE NORTHWEST CORNER SATISFIES THIS REQUIREMENT.

20 10 0 20 40 60

Scale 1" = 20'

811 Know what's below. Call before you dig.

REGISTERED PROFESSIONAL ENGINEER — DAVID W. PETERSON — No. 270393 — 1/22/19 — STATE OF UTAH

LAND SURVEYOR: JUB — J-U-B ENGINEERS, INC.

BENCH MARK

WEST QUARTER CORNER, SECTION 16, TOWNSHIP 5 SOUTH, RANGE 2 EAST, SALT LAKE BASE AND MERIDIAN UT. CO. GS MON. NO. 879 ELEVATION = 4640.18

REVISIONS

Rev.	Date	Description
1	03/04/19	REVISED AS PER TECH REVIEW COMMENTS DATED 01/31/19
2	11/24/19	SHOWED ADDITIONAL WATER SERVICE CONNECTION TO BUILDING
3	10/05/21	SHOWED ADDITIONAL SEWER AND WATER SERVICES CONNECTION TO BUILDING
A	11/09/21	REVISED PER CITY COMMENTS

AUBLE OFFICE BUILDING LLC
2491 N 1200 E, SUITE 201
LEHI, UT 84043

EXCEL ENGINEERING
David W. Peterson, P.E., License #270393
12 West 100 North, Suite 201, American Fork, UT 84003
P. (801) 756-4981, Email: excelcivil.com

AUBLE OFFICE BUILDING

AMERICAN FORK 1112 East 300 North UTAH

Drawn by: D.W.P.
Designed by: D.W.P.
Checked by: D.W.P.

UTILITY PLAN

Scale: 1"=20'
Date: 01/22/19
C4

AMERICAN FORK CITY
PLANNING COMMISSION

MEETING DATE: 11/17/2021
STAFF: Ben Hunter

AGENDA TOPIC: Hearing, review and action on a preliminary plan and final plat for Stonecreek Plat G, located at approximately 350 West 900 South in the PR-3.0 Residential zone

BACKGROUND INFORMATION					
Location:		350 West 900 South			
Applicants:		Woodside Homes of Utah			
Existing Land Use:		Residential Low Density			
Proposed Land Use:		N/A			
Surrounding Land Use:	North	Residential Low Density			
	South	Residential Low Density			
	East	Residential Low Density			
	West	Residential Low Density			
Existing Zoning:		PR-3 Planned Residential			
Proposed Zoning:		N/A			
Surrounding Zoning:	North	PR-3 Planned Residential			
	South	PR-3 Planned Residential			
	East	PR-3 Planned Residential			
	West	PR-3 Planned Residential			
Land Use Plan Designation:		Planned Residential			
Zoning within Land Use Plan Designation?		x	Yes		No

Background

Stonecreek Plat G is a subdivision of parcels 13:065:0074 and 13:065:0075 and proposes to create 32 lots. The subdivision units meet or exceed the area and dimensional requirements of the PR-3 Planned Residential zone.

Consistency with the Land Use Plan

The plat and zoning comply with the Land Use Plan designation; therefore, the proposed subdivision is consistent with the Land Use Plan designation.

Section 17.8.211 of the Development Code

The Planning Commission may act to recommend approval of a final plat upon a finding that:

a. The final plat conforms with the terms of the preliminary plan approval.

   The preliminary plan and final plat are processed concurrently and are consistent with one another.

b. The final plat complies with all City requirements and standards relating to Subdivisions.

   This criterion has been met.

c. The detailed engineering plans and materials comply with the City standards and policies.

   Engineering will address concerns, if any, at the time of the Planning Commission Meeting.

d. The estimates of cost of constructing the required improvements are realistic.

   Engineering will determine whether the cost estimates of constructing any required improvements are realistic.

e. The water rights conveyance documents have been provided.

   Any water rights conveyance shall be satisfied prior to plat recordation.

FINDINGS OF FACT/CONDITION OF APPROVAL

After reviewing the application for final plat approval, the following finding of fact and condition of approval are offered for consideration:

1. The final plat meets Section 17.8.101 (Intent) of Chapter 17.8 (Subdivisions).
2. The final plat meets the criteria as found in Section 17.8.211 of the Development Code.

POTENTIAL MOTIONS

PRELIMINARY PLAN

Mr. Chairman, I move that we approve the preliminary plan for the Stonecreek Plat G, located at approximately 350 West 900 South subject to any findings, conditions and modifications found in the engineering report.

FINAL PLAT

Mr. Chairman, I move that we recommend approval of the final plat for the Stonecreek Plat G, located at approximately 350 West 900 South with the findings listed in the staff report, and subject to any findings, conditions and modifications found in the engineering report.

DENIAL

PRELIMINARY PLAN

Mr. Chairman, I move that we deny the preliminary plan for the Stonecreek Plat G, located at approximately 350 West 900 South.

FINAL PLAT

N/A [If the preliminary plan is denied, there can be no recommendation on the final plat.]

TABLE

PRELIMINARY PLAN

Mr. Chairman, I move that we table action on the preliminary plan for the Stonecreek Plat G, located at approximately 350 West 900 South.

FINAL PLAT

Mr. Chairman, I move that we table action on the final plat for the Stonecreek Plat G, located at approximately 350 West 900 South.

AMERICAN FORK CITY ENGINEERING DIVISION
STAFF REPORT

Planning Commission Meeting Date: 11/17/2021

This report is a summary of the American Fork City Engineering Division plan review comments regarding the subject plan as submitted by the applicant for American Fork City Land Use Authority approval:

Project Name: Stonecreek Plat G


Project Address: 350 West 900 South

Developer / Applicant's Name: Woodside Homes of Utah

Type of Application:

- ☒ Subdivision Final Plat
- ☒ Subdivision Preliminary Plan
- ☐ Annexation
- ☐ Code Text Amendment
- ☐ General Plan Amendment
- ☐ Zone Change
- ☐ Commercial Site Plan
- ☐ Residential Accessory Structure Site Plan

Project Map:



Engineering Division Recommendation: The Engineering Division recommends APPROVAL of the proposed development with the following conditions:

STANDARD CONDITIONS OF APPROVAL

Standard Conditions of Approval:


APPLICANT is responsible and shall submit/post/obtain all necessary documentation and evidence to comply with these Standard Conditions of Approval prior to any platting, permitting, or any other form of authorization by the City including plat recording or other property conveyance to the City and prior to scheduling a pre-construction meeting. All recording shall take place at the Utah County Recorder's Office.


1. **Title Report:** Submit an updated Title Report not older than 30 days or other type of appropriate verification that shows all dedications to the City are free and clear of encumbrances, taxes, or other assessments.
2. **Property Taxes and Liens:** Submit evidence that all the property taxes, for the current and/or previous years, liens, and agricultural land use roll over fees have been paid in full.
3. **Water Rights:** Submit evidence that all the required water rights have been conveyed to American Fork City.
4. **Performance Guarantee:** Post a performance guarantee for all required public and essential common improvements.
5. **Easements and Agreements:** Submit/record a long-term Storm Water Pollution Prevention Maintenance Agreement signed and dated by the property owner and any required easement documentation.
6. **Land Disturbance Permit:** Obtain a Land Disturbance Permit.
7. **Compliance with the Engineering Division Plan Review Comments:** All plans and documents shall comply with all the Technical Review Committee comments and the City Engineer's final review.
8. **Commercial Structure:** Record an Owner Acknowledgment and Utility Liability Indemnification if the proposed building is a multi-unit commercial structure served by a single utility service.
9. **Sensitive Lands:** Record all applicable documents required for compliance with the City's Sensitive Lands Ordinance.
10. **Utility Notification Form:** Submit a Subdivision Utility Notification Form.
11. **Professional Verification:** Submit final stamped construction documentation by all appropriate professionals.
12. **Fees:** Payment of all development, inspection, recording, street light, and other project related fees.
13. **Mylar:** Submit a Mylar. All plats will receive final verification of all formats, notes, conveyances, and other items contained on the plat by City staff (recorder, legal, engineer, GIS, planning).

STONECREEK PLAT 'G'

LOCATED IN THE NORTHWEST QUARTER OF
SECTION 26, TOWNSHIP 5 SOUTH, RANGE 1 EAST,
SALT LAKE BASE AND MERIDIAN
AMERICAN FORK CITY, UTAH COUNTY.

Curve Table					
Curve #	Length	Radius	Delta	Chord	Chord Bearing
C1	23.57	15.00	90°01'23"	21.22	N44°11'22"W
C2	23.56	15.00	89°58'37"	21.21	S45°48'38"W
C3	23.57	15.00	90°01'23"	21.22	N44°11'22"W
C4	23.62	15.00	90°12'29"	21.25	N44°16'56"W
C5	23.51	15.00	89°47'31"	21.17	S45°43'04"W
C6	23.62	15.00	90°12'29"	21.25	N44°16'56"W
C7	23.51	15.00	89°47'31"	21.17	S45°43'04"W
C8	23.56	15.00	89°58'37"	21.21	N45°48'38"E
C9	23.57	15.00	90°01'23"	21.22	S44°11'22"E
C10	23.56	15.00	89°58'37"	21.21	N45°48'38"E





VICINITY MAP

SCALE: 1" = 60'


LEGEND

- FOUND SECTION CORNER
- DEDICATED TO AMERICAN FORK CITY
- BOUNDARY
- SECTION LINE
- ROAD CENTER LINE
- EASEMENT LINE
- FIRE HYDRANT
- STREET LIGHT

FLOOD ZONE DESIGNATION: X
MAP NUMBER: 49049C0306F
EFFECTIVE DATE: JUNE 19, 2020

LAND USE:	
PLAT "G" =	6.87 ACRES
ZONING=	PR-3.0
TOTAL LOTS=	32 LOTS
DENSITY OVERALL =	3.0 LOTS/ACRE
OPEN SPACE =	0.20 ACRE

NOTE: THIS PLAT IS BASED ON THE PLANNED UNIT DEVELOPMENT-CONSERVATION SUBDIVISION PROJECT



TYPICAL CORNER LOT TYPICAL INTERIOR LOT

EASEMENT DETAIL
-NTS-

NOTES:
1. OFFSET NAILS TO BE PLACED IN THE CURB AND 5/8" BY 24" REBAR WITH SURVEY CAP TO BE PLACED AT ALL REAR LOT CORNERS PRIOR TO OCCUPANCY.
2. BUILDING PERMITS WILL NOT BE ISSUED FOR ANY HOME UNTIL ALL ASPHALT PAVING IS INSTALLED AND THE FIRE HYDRANTS ARE INSTALLED, APPROVED BY THE FIRE MARSHALL AND CHARGE WITH CULINARY WATER.
3. ALL PUBLIC STREETS TO BE DEDICATED TO AMERICAN FORK CITY.
4. LOWEST FLOOR SLAB ELEVATION MUST BE A MINIMUM OF 3 FEET ABOVE WATER LEVEL MEASURED DURING SPRING SEASON. NO BASEMENTS TO BE CONSTRUCTED WITHIN THIS PLAT.

DEVELOPER
WOODSIDE HOMES
460 WEST 50 NORTH
SUITE #200 SLC, UT 84101
PHONE (801) 372-2077

TRANE ENGINEERING, P.C.
CONSULTING ENGINEERS AND LAND SURVEYORS
27 EAST MAIN LEHI, UTAH 84043 (801) 768-4544

SURVEYOR'S CERTIFICATE

I, TRAVIS TRANE, DO HEREBY CERTIFY THAT I AM A PROFESSIONAL LAND SURVEYOR AND THAT I HOLD LICENSE NO. 5152741, IN ACCORDANCE WITH TITLE 58, CHAPTER 22 OF THE PROFESSIONAL ENGINEERS AND LAND SURVEYORS LICENSING ACT. I FURTHER CERTIFY THAT BY AUTHORITY OF THE OWNERS, A SURVEY WAS COMPLETED IN ACCORDANCE WITH SECTION 17-23-17, I FURTHER CERTIFY THAT I HAVE VERIFIED ALL MEASUREMENTS AND THAT MONUMENTS HAVE BEEN PLACED AS SHOWN ON THIS PLAT, I HEREBY STATE THAT THIS PLAT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE, INFORMATION, BELIEF AND IN MY PROFESSIONAL OPINION.

(SURVEYOR), P.L.S. DATE

BOUNDARY DESCRIPTION

Commencing at a point which is North 89°48'57" East 1163.09 feet along the section line and South 860.79 feet from the Northwest Corner of Section 26, Township 5 South, Range 1 East, Salt Lake Base and Meridian: thence South 89°23'10" East 541.60 feet; thence South 00°51'25" West 157.75 feet; thence South 00°51'24" West 320.68 feet; thence South 00°51'25" West 13.94 feet; thence North 89°10'41" West 113.00 feet; thence South 00°49'19" West 83.09 feet; thence South 85°52'36" West 62.23 feet; thence Northwesterly 23.57 feet along the arc of a 15.00 foot radius curve to the left, through a central angle of 90°01'23", the chord of which bears North 44°11'22" West 21.22 feet; thence North 89°12'04" West 173.00 feet; thence Southwesterly 23.56 feet along the arc of a 15.00 foot radius curve to the left, through a central angle of 89°58'37", the chord of which bears South 45°48'38" West 21.21 feet; thence North 89°12'44" West 62.00 feet; thence Northwesterly 23.57 feet along the arc of a 15.00 foot radius curve to the left, through a central angle of 90°01'23", the chord of which bears North 44°11'22" West 21.22 feet; thence North 89°12'04" West 85.99 feet; thence North 00°32'41" East 62.00 feet; thence North 00°49'19" East 502.00 feet to the point of beginning.

Parcel contains: 6.87 acres

Number of lots = 32

Basis of bearing: The line between the Northwest Corner and the North Quarter Corner of Section 26, Township 5 South, Range 1 East, Salt Lake Base and meridian which bears North 89°48'57" East.

OWNER'S DEDICATION

Known all men by these present that we, all of the undersigned owners of all of the property described in the surveyor's certificate herein and shown on this map, have caused the same to be subdivided into lots, blocks, streets and easements and do hereby dedicate the streets and other public areas as indicated hereon for perpetual use of the public.

IN WITNESS HEREOF WE HAVE HEREUNTO SET OUR HANDS THIS_____ DAY OF_____, 20___

ACKNOWLEDGEMENT

STATE OF UTAH)
: S.S.
COUNTY OF UTAH)

ON THE_____DAY OF_____, 20___ PERSONALLY APPEARED BEFORE ME THE SIGNERS OF THE FOREGOING DEDICATION WHO DULY ACKNOWLEDGE TO ME THAT THEY DID EXECUTE THE SAME.

NOTARY _____ NOTARY PUBLIC SIGNATURE

COMMISSION # _____

A NOTARY PUBLIC COMMISSIONED IN UTAH

MY COMMISSION EXPIRES _____

ACCEPTANCE BY LEGISLATIVE BODY

THE_____OF_____
COUNTY OF UTAH, APPROVES THIS SUBDIVISION AND HEREBY ACCEPTS THE DEDICATION OF ALL STREETS; EASEMENTS, AND OTHER PARCELS OF LAND INTENDED FOR PUBLIC PURPOSES FOR THE PERPETUAL USE OF THE PUBLIC THIS_____DAY OF _____, 20

MAYOR — CITY COUNCIL MEMBER

CITY COUNCIL MEMBER — CITY COUNCIL MEMBER

CITY COUNCIL MEMBER — CITY COUNCIL MEMBER

APPROVED: _____ CITY ENGINEER

ATTEST: _____ CLERK-RECORDER (See Seal Below)

PLANNING COMMISSION APPROVAL

APPROVED THIS_____DAY OF _____, A.D. 20___
BY THE AMERICAN FORK CITY PLANNING COMMISSION.

PLANNER — PLANNING COMMISSION CHAIRMAN

PLAT 'G'

STONECREEK

CONSERVATION PUD

AMERICAN FORK CITY, UTAH COUNTY, UTAH
SCALE: 1"= 60 FEET

SEWER/WATER AUTHORITY APPROVAL

APPROVED BY THE SEWER AUTHORITY
ON THIS DAY OF_____, A.D., 20_____

SEWER/WATER AUTHORITY

SURVEYOR SEAL	CLERK-RECORDED SEAL	RECORDING INFORMATION

AMERICAN FORK CITY
PLANNING COMMISSION

MEETING DATE: 11/17/2021
STAFF: Ben Hunter

AGENDA TOPIC: Hearing, review and action on the preliminary plan and final plat for 500 East Auto Mall Drive Business Center Plat B, located at 450 East Auto Mall Drive in the PI-1 Planned Industrial zone.

BACKGROUND INFORMATION					
Location:		450 East Auto Mall Drive			
Applicants:		Davies Design Build/Steve Davies			
Existing Land Use:		Planned Industrial			
Proposed Land Use:		N/A			
Surrounding Land Use:	North	Design Commercial and Design Industrial			
	South	Design Industrial			
	East	Design Commercial			
	West	Design Industrial			
Existing Zoning:		PI-1 Planned Industrial			
Proposed Zoning:		N/A			
Surrounding Zoning:	North	GC-2 Planned Commercial			
	South	GC-1 General Commercial			
	East	GC-2 Planned Commercial			
	West	Unincorporated			
Land Use Plan Designation:		Planned Industrial			
Zoning within Land Use Plan Designation?		x	Yes		No

Background

500 East Auto Mall Drive Business Center Plat B is a subdivision of parcel 13:061:0111 and proposes to construct 2 commercial buildings. One is 51,063 SQ.-FT office and warehouse building. And a 6,132 SQ.-FT Maverik convenience store. The subdivision units meet or exceed the area and dimensional requirements of the PI-1 Planned Industrial zone.

Consistency with the Land Use Plan

The plat and zoning comply with the Land Use Plan designation; therefore the proposed subdivision is consistent with the Land Use Plan designation.

Section 17.8.211 of the Development Code

The Planning Commission may act to recommend approval of a final plat upon a finding that:

a. The final plat conforms with the terms of the preliminary plan approval.

   The preliminary plan and final plat are processed concurrently and are consistent with one another.

b. The final plat complies with all City requirements and standards relating to Subdivisions.

   This criterion has been met.

c. The detailed engineering plans and materials comply with the City standards and policies.

   Engineering will address concerns, if any, at the time of the Planning Commission Meeting.

d. The estimates of cost of constructing the required improvements are realistic.

   Engineering will determine whether the cost estimates of constructing any required improvements are realistic.

e. The water rights conveyance documents have been provided.

   Any water rights conveyance shall be satisfied prior to plat recordation.

FINDINGS OF FACT/CONDITION OF APPROVAL

After reviewing the application for final plat approval, the following finding of fact and condition of approval are offered for consideration:

1. The final plat meets Section 17.8.101 (Intent) of Chapter 17.8 (Subdivisions).
2. The final plat meets the criteria as found in Section 17.8.211 of the Development Code.

500 East Auto Mall Drive Business Center Plat B, located at 450 East Auto Mall Drive

POTENTIAL MOTIONS

PRELIMINARY PLAN

Mr. Chairman, I move that we approve the preliminary plan for the 500 East Auto Mall Drive Business Center Plat B, located at 450 East Auto Mall Drive subject to any findings, conditions and modifications found in the engineering report.

FINAL PLAT

Mr. Chairman, I move that we recommend approval of the final plat for the 500 East Auto Mall Drive Business Center Plat B, located at 450 East Auto Mall Drive with the findings listed in the staff report, and subject to any findings, conditions and modifications found in the engineering report.

DENIAL

PRELIMINARY PLAN

Mr. Chairman, I move that we deny the preliminary plan for the 500 East Auto Mall Drive Business Center Plat B, located at 450 East Auto Mall Drive.

FINAL PLAT

N/A [If the preliminary plan is denied, there can be no recommendation on the final plat.]

TABLE

PRELIMINARY PLAN

Mr. Chairman, I move that we table action on the preliminary plan for the 500 East Auto Mall Drive Business Center Plat B, located at 450 East Auto Mall Drive.

FINAL PLAT

Mr. Chairman, I move that we table action on the final plat for the 500 East Auto Mall Drive Business Center Plat B, located at 450 East Auto Mall Drive.

AMERICAN FORK CITY ENGINEERING DIVISION
STAFF REPORT

Planning Commission Meeting Date: 11/17/2021

This report is a summary of the American Fork City Engineering Division plan review comments regarding the subject plan as submitted by the applicant for American Fork City Land Use Authority approval:

Project Name: 500 E Auto Mall Drive Business Center Plat B


Project Address: 450 East Auto Mall Drive

Developer / Applicant's Name: Davies Design Build/Steve Davies

Type of Application:

- ☒ Subdivision Final Plat
- ☒ Subdivision Preliminary Plan
- ☐ Annexation
- ☐ Code Text Amendment
- ☐ General Plan Amendment
- ☐ Zone Change
- ☐ Commercial Site Plan
- ☐ Residential Accessory Structure Site Plan

Project Map:



Engineering Division Recommendation: The Engineering Division recommends APPROVAL of the proposed development with the following conditions:

STANDARD CONDITIONS OF APPROVAL


Standard Conditions of Approval:

APPLICANT is responsible and shall submit/post/obtain all necessary documentation and evidence to comply with these Standard Conditions of Approval prior to any platting, permitting, or any other form of authorization by the City including plat recording or other property conveyance to the City and prior to scheduling a pre-construction meeting. All recording shall take place at the Utah County Recorder's Office.

1. **Title Report:** Submit an updated Title Report not older than 30 days or other type of appropriate verification that shows all dedications to the City are free and clear of encumbrances, taxes, or other assessments.
2. **Property Taxes and Liens:** Submit evidence that all the property taxes, for the current and/or previous years, liens, and agricultural land use roll over fees have been paid in full.
3. **Water Rights:** Submit evidence that all the required water rights have been conveyed to American Fork City.
4. **Performance Guarantee:** Post a performance guarantee for all required public and essential common improvements.
5. **Easements and Agreements:** Submit/record a long-term Storm Water Pollution Prevention Maintenance Agreement signed and dated by the property owner and any required easement documentation.
6. **Land Disturbance Permit:** Obtain a Land Disturbance Permit.
7. **Compliance with the Engineering Division Plan Review Comments:** All plans and documents shall comply with all the Technical Review Committee comments and the City Engineer's final review.
8. **Commercial Structure:** Record an Owner Acknowledgment and Utility Liability Indemnification if the proposed building is a multi-unit commercial structure served by a single utility service.
9. **Sensitive Lands:** Record all applicable documents required for compliance with the City's Sensitive Lands Ordinance.
10. **Utility Notification Form:** Submit a Subdivision Utility Notification Form.
11. **Professional Verification:** Submit final stamped construction documentation by all appropriate professionals.
12. **Fees:** Payment of all development, inspection, recording, street light, and other project related fees.
13. **Mylar:** Submit a Mylar. All plats will receive final verification of all formats, notes, conveyances, and other items contained on the plat by City staff (recorder, legal, engineer, GIS, planning).

AUTO MALL DRIVE BUSINESS CENTER PLAT B

LOCATED IN THE NORTHWEST QUARTER OF SECTION 25,
TOWNSHIP 5 SOUTH, RANGE 1 EAST,
SALT LAKE BASE AND MERIDIAN
AMERICAN FORK CITY, UTAH COUNTY, UTAH



LINE TABLE		
LINE #	BEARING	DISTANCE
L1	N 30°09'02" E	6.00'
L2	S 60°07'22" E	5.00'
L3	N 29°36'14" E	6.00'

CURVE TABLE					
CURVE #	LENGTH	RADIUS	DELTA	CHORD BEARING	CHORD DISTANCE
C1	4.94'	518.00'	0°32'48"	S 60°07'22" E	4.94'

LEGEND

- UTAH COUNTY SECTION CORNER
- BOUNDARY CORNER (SET ⅝ REBAR AND CAP OR NAIL AND WASHER STAMPED "BENCHMARK ENG.")
- SECTION LINE
- BOUNDARY LINE
- ADJACENT PROPERTY
- STREET CENTERLINE EXISTING
- EXISTING RIGHT OF WAY
- EASEMENT
- PUE — PUBLIC UTILITY EASEMENT
- POB — POINT OF BEGINNING

NOTES:
1. LOWEST FLOOR SLAB ELEVATION MUST BE A MINIMUM OF 3 FEET ABOVE WATER LEVEL MEASURED DURING SPRING SEASON, OR SUPPORTIVE GEOTECHNICAL INFORMATION INDICATING OTHERWISE.
2. OFF-SET NAIL AND WASHERS TO BE PLACED IN THE BACK OF CURB AND 5/8" BY 24" REBAR WITH NUMBERED SURVEY CAP TO BE PLACED AT ALL LOT CORNERS PRIOR TO OCCUPANCY.
3. BUILDING PERMITS WILL NOT BE ISSUED FOR ANY HOME UNTIL 1) ASPHALT PAVING IS INSTALLED AND 2) FIRE HYDRANTS ARE INSTALLED, APPROVED BY THE FIRE MARSHALL AND CHARGED WITH CULINARY WATER.
4. LAND USE - PROFESSIONAL OFFICE

NORTH

GRAPHIC SCALE

50 0 25 50 100

(IN FEET)
1 inch = 50ft.

SURVEYOR'S CERTIFICATE

I, BRIAN A. LINAM, DO HEREBY CERTIFY THAT I AM A PROFESSIONAL LAND SURVEYOR, AND THAT I HOLD A LICENSE IN ACCORDANCE WITH TITLE 58, CHAPTER 22, PROFESSIONAL ENGINEERS AND LAND SURVEYORS LICENSING ACT, UTAH CODE ANNOTATED, 1953 AS AMENDED CERTIFICATE NUMBER 7240531. I FURTHER CERTIFY THAT BY AUTHORITY OF THE OWNERS, I HAVE MADE A SURVEY OF THE TRACT OF LAND SHOWN ON THIS PLAT AND DESCRIBED BELOW, AND HAVE SUBDIVIDED SAID TRACT OF LAND INTO LOTS, HEREAFTER TO BE KNOWN AS AUTO MALL DRIVE BUSINESS CENTER PLAT B, AND THAT THE SAME HAS BEEN CORRECTLY SURVEYED AS SHOWN ON THIS PLAT.

BOUNDARY DESCRIPTION

A TRACT OF LAND SITUATED IN THE NORTHWEST QUARTER OF SECTION 30, TOWNSHIP 5 SOUTH, RANGE 1 EAST, SALT LAKE BASE AND MERIDIAN, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT NORTH 790.59 FEET AND EAST 867.93 FEET, ACCORDING TO UTAH COORDINATE BEARINGS, CENTRAL ZONE, FROM THE WEST QUARTER CORNER OF SECTION 25, TOWNSHIP 5 SOUTH, RANGE 1 EAST, SALT LAKE BASE AND MERIDIAN, AND RUNNING THENCE NORTH 88°21'00" EAST 236.09 FEET; THENCE NORTH 00°59'20" EAST 42.68 FEET; THENCE EAST 44.05 FEET TO A POINT ON THE SOUTHWESTERLY RIGHT OF WAY LINE OF AUTO MALL DRIVE; THENCE RUNNING ALONG SAID SOUTHWESTERLY RIGHT OF WAY LINE THE FOLLOWING FOUR (4) COURSES: 1) SOUTHEASTERLY 410.76 FEET ALONG THE ARC OF A 508.00 FOOT NON-TANGENT CURVE TO THE LEFT, CHORD BEARS SOUTH 60°43'04" EAST 399.66 FEET; 2) SOUTH 81°01'24" EAST 55.22 FEET; 3) SOUTH 89°15'02" EAST 148.83 FEET; 4) SOUTH 44°44'26" EAST 49.07 FEET TO A POINT ON THE WESTERLY RIGHT OF WAY LINE OF 500 EAST STREET; THENCE RUNNING ALONG SAID WESTERLY RIGHT OF WAY LINE THE FOLLOWING TWO (2) COURSES: 1) SOUTH 00°13'50" EAST 224.17 FEET; 2) SOUTH 00°15'03" WEST 79.10 FEET; THENCE NORTH 88°13'25" WEST 504.67 FEET TO A POINT ON THE EASTERLY RIGHT OF WAY LINE OF THE SOUTHERN PACIFIC RAILROAD; THENCE NORTH 37°10'59" WEST 601.28 FEET TO THE POINT OF BEGINNING.

CONTAINS 6.206 ACRES, MORE OR LESS
2 LOTS

OWNER'S DEDICATION

KNOWN ALL MEN BY THESE PRESENTS THAT I / WE, THE UNDERSIGNED OWNER(S) OF THE ABOVE DESCRIBED TRACT OF LAND, HAVING CAUSED SAME TO BE SUBDIVIDED, HEREAFTER KNOWN AS THE

AUTO MALL DRIVE BUSINESS CENTER PLAT B

DO HEREBY DEDICATE THE EASEMENTS AND OTHER PUBLIC AREAS AS INDICATED HEREON FOR THE PERPETUAL USE OF THE PUBLIC.
IN WITNESS WHEREOF I / WE HAVE HEREUNTO SET OUR HAND (S) THIS 24th DAY OF AUGUST A.D., 20 21.

BY: Steve Davis
ITS: MANAGER
500 EAST at AUTO MALL, LLC

ACKNOWLEDGMENT

STATE OF UTAH
County of Salt Lake } S.S.

ON THIS 24 DAY OF August, IN THE YEAR 2021, BEFORE ME Audrey Rock, A NOTARY PUBLIC, PERSONALLY APPEARED Steve Davies, THE MANAGING MEMBER OF AXLEY-WAY INVESTEMNTS, LLC PROVED ON THE BASIS OF SATISFACTORY EVIDENCE TO BE THE PERSON(S) WHOSE NAME(S) IS/ARE SUBSCRIBED TO IN THE FOREGOING OWNER'S DEDICATION AND CONSENT REGARDING AUTO MALL DRIVE BUSINESS CENTER PLAT B AND WAS SIGNED BY HIM/HER ON BEHALF OF SAID AXLEY-WAY INVESTEMNTS, LLC AND ACKNOWLEDGED THAT HE/SHE/THEY EXECUTED THE SAME.

MY COMMISSION EXPIRES: 04/29/2025 COMMISSION NUMBER: 717980

Audrey Rock
PRINT NAME

AUDREY D ROCK
Notary Public - State of Utah
Comm. No. 717980
My Commission Expires on
Apr 29, 2025

Audrey Rock
(SIGNED) A NOTARY PUBLIC COMMISSIONED IN UTAH

ACCEPTANCE BY LEGISLATIVE BODY

THE CITY COUNCIL OF THE CITY OF AMERICAN FORK, COUNTY OF UTAH, APPROVES THIS DEDICATION PLAT, AND HEREBY ACCEPTS THE DEDICATION OF ALL STREETS, EASEMENTS AND OTHER PARCELS OF LAND INTENDED FOR THE PUBLIC PURPOSE OF THE PERPETUAL USE OF SAID PUBLIC.
THIS _____ DAY OF _____, A.D. _____.


CITY MAYOR
CITY COUNCIL MEMBER
CITY COUNCIL MEMBER
CITY COUNCIL MEMBER
CITY COUNCIL MEMBER
CITY COUNCIL MEMBER
CITY ENGINEER
ATTEST: _____ CLERK-RECORDER (SEE SEAL BELOW)

PLANNING COMMISSION APPROVAL

APPROVED THIS _____ DAY OF _____ A.D. 20____, BY THE AMERICAN FORK CITY PLANNING COMMISSION.

PLANNER
John W. Wahlen PG
PLANNING COMMISSION CHAIR

VICINITY MAP



WEST QUARTER CORNER OF SECTION 25, TOWNSHIP 5 SOUTH, RANGE 1 EAST, SALT LAKE BASE AND MERIDIAN (FOUND BRASS CAP)

S 00°04'25" E 38.96' (MEASURED)
S 00°05'12" E 39.00' (RECORD)

WITNESS CORNER FOR THE WEST QUARTER CORNER OF SECTION 25, TOWNSHIP 5 SOUTH, RANGE 1 EAST, SALT LAKE BASE AND MERIDIAN (FOUND BRASS CAP)

DEVELOPER:
DAVIES DESIGN BUILD
JONATHAN JENSEN
240 N. 1200 E. #201
LEHI, UT 84043
801-583-6044

FLOOD ZONE DESIGNATION

SUBJECT PROPERTY HAS NO DATA DELINEATED BY F.E.M.A. FLOOD INSURANCE RATE MAP, COMMUNITY PANEL MAP NO. 49049C0306F, EFFECTIVE JUNE 19, 2020.

WATER AND SEWER AUTHORITY APPROVAL


APPROVED THE ____ DAY OF _____ A.D. 2021. BY THE WATER AND SEWER AUTHORITY.

PUBLIC WORKS DEPARTMENT DIRECTOR

BENCHMARK CIVIL

BENCHMARK ENGINEERING & LAND SURVEYING
9138 SOUTH STATE STREET SUITE # 100
SANDY, UTAH 84070 (801) 542-7192
www.benchmarkcivil.com

SURVEYOR'S SEAL



NOTARY PUBLIC SEAL

CLERK - RECORDER SEAL

AUTO MALL DRIVE BUSINESS CENTER PLAT B

LOCATED IN THE NORTHWEST QUARTER
OF SECTION 25, TOWNSHIP 5 SOUTH, RANGE 1 EAST,
SALT LAKE BASE AND MERIDIAN
AMERICAN FORK CITY, UTAH COUNTY, UTAH

SHEET 1 OF 1

AMERICAN FORK CITY
PLANNING COMMISSION

MEETING DATE: November 17, 2021
STAFF PRESENTATION: Ben Hunter

AGENDA TOPIC: Hearing, review and action on the preliminary plan, final plat and site plan for Deer Park Subdivision, located in the area of 9 West 1100 South, in the PI-1 Planned Industrial zone.

ACTION REQUESTED: Recommendation of approval to City Council.

BACKGROUND INFORMATION					
Location:		9 West 1100 South			
Applicants:		Deer Park LLC			
Existing Land Use:		Agriculture			
Proposed Land Use:		Commercial			
Surrounding Land Use:	North	Agriculture			
	South	Agriculture			
	East	Agriculture			
	West	Agriculture			
Existing Zoning:		PI-1 (Planned Industrial)			
Proposed Zoning:		N/A			
Surrounding Zoning:	North	Unincorporated			
	South	PF (Public Facilities)			
	East	RA-5 Residential Agricultural			
	West	Unincorporated			
Land Use Plan Designation:		Design Industrial			
Zoning within density range?		x	Yes		No

Background

In 2021 there was a zone change for these parcels to the current PI-1 Planned Industrial Zone. This area was annexed into the City under the Pulley Annexation in 2016. This site plan and subdivision plat is proposed to have an office-warehouse development. These 2 lots will consist of two office-warehouse buildings totaling 252,130 square feet on approximately 14.06 acres. The site is bound by 1100 South on the north, agricultural properties on the east and west and the future arterial to the south currently owned by UDOT. Access points will be provided off 1100 South. The Pedestrian and Bike Master Plan identifies a trail along the east property line adjacent to the existing slough. The necessary trail dedication or easement will be provided as condition of approval of the plat and site plan. Trail improvements will not be constructed at this time.

Parking and landscaping are provided per the City's requirements. Landscape plans have been provided in the submittal materials. Renderings of the structures are also provided in the submittal materials.

Consistency with the Land Use Plan:

The Land Use Plan designates this area as "Design Industrial". The site plan is consistent with the Land Use Plan Designation.

FINDING OF FACT

After reviewing the application for site plan approval, the following finding of fact is offered for consideration:

1. The proposed site plan meets the criteria as found in Section 17.7.701 (Planned Industrial Projects) of the Development Code.

POTENTIAL MOTIONS PRELIMINARY PLAN AND FINAL PLAT

APPROVAL

Mr. Chairman, I move that we recommend approval of the preliminary plan, final plat and commercial site plan for Deer Park Subdivision, with the findings listed in the staff report and subject to any findings, conditions and modifications listed in the Engineering report.

DENIAL

Mr. Chairman, I move that we recommend denial of the preliminary plan, final plat and commercial site plan for Deer Park Subdivision.

TABLE

Mr. Chairman, I move that we table action on preliminary plan, final plat and commercial site plan for Deer Park Subdivision.

AMERICAN FORK CITY ENGINEERING DIVISION
STAFF REPORT

Planning Commission Meeting Date: 11/17/2021

This report is a summary of the American Fork City Engineering Division plan review comments regarding the subject plan as submitted by the applicant for American Fork City Land Use Authority approval:

Project Name: Deer Park Subdivision

Project Address: 9 West 1100 South

Developer / Applicant's Name: Deer Park LLC

Type of Application:

- ☒ Subdivision Final Plat
- ☒ Subdivision Preliminary Plan
- ☐ Annexation
- ☐ Code Text Amendment
- ☐ General Plan Amendment
- ☐ Zone Change
- ☒ Commercial Site Plan
- ☐ Residential Accessory Structure Site Plan

Project Map:



Engineering Division Recommendation: The Engineering Division recommends APPROVAL of the proposed development with the following conditions:

STANDARD CONDITIONS OF APPROVAL

Standard Conditions of Approval:


APPLICANT is responsible and shall submit/post/obtain all necessary documentation and evidence to comply with these Standard Conditions of Approval prior to any platting, permitting, or any other form of authorization by the City including plat recording or other property conveyance to the City and prior to scheduling a pre-construction meeting. All recording shall take place at the Utah County Recorder's Office.

1. **Title Report:** Submit an updated Title Report not older than 30 days or other type of appropriate verification that shows all dedications to the City are free and clear of encumbrances, taxes, or other assessments.
2. **Property Taxes and Liens:** Submit evidence that all the property taxes, for the current and/or previous years, liens, and agricultural land use roll over fees have been paid in full.
3. **Water Rights:** Submit evidence that all the required water rights have been conveyed to American Fork City.
4. **Performance Guarantee:** Post a performance guarantee for all required public and essential common improvements.
5. **Easements and Agreements:** Submit/record a long-term Storm Water Pollution Prevention Maintenance Agreement signed and dated by the property owner and any required easement documentation.
6. **Land Disturbance Permit:** Obtain a Land Disturbance Permit.
7. **Compliance with the Engineering Division Plan Review Comments:** All plans and documents shall comply with all the Technical Review Committee comments and the City Engineer's final review.
8. **Commercial Structure:** Record an Owner Acknowledgment and Utility Liability Indemnification if the proposed building is a multi-unit commercial structure served by a single utility service.
9. **Sensitive Lands:** Record all applicable documents required for compliance with the City's Sensitive Lands Ordinance.
10. **Utility Notification Form:** Submit a Subdivision Utility Notification Form.
11. **Professional Verification:** Submit final stamped construction documentation by all appropriate professionals.
12. **Fees:** Payment of all development, inspection, recording, street light, and other project related fees.
13. **Mylar:** Submit a Mylar. All plats will receive final verification of all formats, notes, conveyances, and other items contained on the plat by City staff (recorder, legal, engineer, GIS, planning).

Conditions of Approval:

All TRC comments are fully addressed and 3rd party review of the geotechnical report is completed.



SIGNAGE
SIGNAGE
SIGNAGE
aeurbia
architects and engineers



NORTH


aeurbia
architects and engineers

6800 N INDUSTRIAL
AMERICAN FORK - BUILDING 1



1 X - 02 FRONT ELEVATION

1" = 20'-0"




2 X - 02 SIDE ELEVATION

1" = 20'-0"



3 X - 02 REAR ELEVATION

1" = 20'-0"



NORTH

aeurbia
architects and engineers


6800 N INDUSTRIAL

AMERICAN FORK - BUILDING 2




1 X - 02 FRONT ELEVATION

1" = 20'-0"



2 X - 02 SIDE ELEVATION

1" = 20'-0"



3 X - 02 REAR ELEVATION

1" = 20'-0"

aeurbia
architects and engineers

6800 N INDUSTRIAL

AMERICAN FORK - BUILDING 2

LANDSCAPE PLAN SPECIFICATIONS

PART 1 - GENERAL

1.1 SUMMARY

A. This section includes landscape procedures for the Project including all labor, materials, and installation necessary, but not limited to, the following:

1. Site Conditions
2. Guarantees
3. Maintenance
4. Soil Amendments
5. Fine Grading
6. Landscape Edging
7. Furnish and Installing Plant
8. Turf Planting
9. Weed Barrier

1.2 SITE CONDITIONS

A. Examination: Before submitting a Bid, each Contractor shall carefully examine the Contract Documents; shall visit the site of the Work; shall fully inform themselves as to all existing conditions and limitations; and shall include in the Bid the cost of all items required by the Contract Documents are at a variance with the applicable laws, building codes, rules, regulations, or contain obvious erroneous or uncoordinated information, the Contractor shall promptly notify the Project Representative and the necessary changes shall be accomplished by Addendum.

B. Protection: Contractor to conduct the Work in such a manner to protect all existing underground utilities or structures. Contractor to repair or replace any damaged utility or structure using identical materials to match existing at no expense to the Owner.

C. Irrigation System: Do not begin planting until the irrigation system is completely installed, is adjusted for full coverage and is completely operational.

1.3 PERMITS

A. Blue Stake/ Dig Line: When digging is required, "Blue Stake" or "Dig Line" the work site and identify the approximate location of all known underground utilities or structures.

1.4 PLANT DELIVERY, QUALITY, AND AVAILABILITY

A. Unauthorized substitutions will not be accepted. If proof is submitted that specific plants or plant sizes are unobtainable, written substitution requests will be considered for the nearest equivalent plant or size. All substitution requests must be made in writing and preferably before the bid due date.

1.5 FINAL INSPECTION

A. All plants will be inspected at the time of Final Inspection prior to receiving a Landscape Substantial Completion for conformance to specified planting procedures, and for general appearance and vitality. Any plant not approved by the Project Representative will be rejected and replaced immediately.

1.6 LANDSCAPE SUBSTANTIAL COMPLETION

A. A Substantial Completion Certificate will only be issued by the Project Representative for "landscape and irrigation" in their entirety. Substantial Completion will not be proportioned to be designated areas of a project.

1.7 MAINTENANCE

A. Plant Material: The Contractor is responsible to maintain all planted materials in a healthy and growing condition for 30 days after receiving a Landscape Substantial Completion at which time the Guarantee period commences. This maintenance is to include mowing, weeding, cultivating, fertilizing, monitoring water schedules, controlling insects and diseases, re-guying and staking, and all other operations of care necessary for the promotion of root growth and plant life so that all plants are in a condition satisfactory at the end of the guarantee period. The Contractor shall be held responsible for failure to monitor watering operations and shall replace any and all plant material that is lost due to improper application of water.

1.8 GUARANTEE

A. Guarantee: A guarantee period of one year shall begin from end of maintenance period and final acceptance for trees, shrubs, and ground covers. All plants shall grow and be healthy for the guarantee period and trees shall live and grow in acceptable upright position. Any plant not alive, in poor health, or in poor condition at the end of the guarantee period will be replaced immediately. Any plant will only need to be replaced once during the guarantee period. Contractor to provide documentation showing where each plant to be replaced is located. Any outside factors, such as vandalism or lack of maintenance on the part of the Owner, shall not be part of the guarantee

PART II - PRODUCTS

2.1 LANDSCAPE MATERIALS

A. Tree Staking: All trees shall be staked for one year warranty period. All trees not plumb shall be replaced. Staked trees shall use vinyl tree ties and tree stakes two (2) inch by two (2) by eight (8) foot common pine stakes used as shown on the details.

B. Tree Wrap: Tree wrap is not to be used.

C. Mulch/Rock: See Plans. All planter beds to receive a minimum 3" layer for trees, shrubs, and perennials and 1" for groundcovers.

D. Weed Barrier: DeWitt 5 oz. weed barrier fabric. Manufactured by DeWitt Company, dewitteompany.com or approved equal.

E. Tree, Shrub, and Grass Backfill Mixture; Backfill mixture to be 75% native soil and 25% topsoil, thoroughly mixed together prior to placement.

F. Topsoil: Required for turf areas, planter beds and Backfill Mixture. Acceptable topsoil shall meet the following standards:

a. PH: 5.5-7.5

b. EC (electrical conductivity): < 2.0 mmhos per centimeter

c. SAR (sodium absorption ration): < 3.0

d. % OM (percent organic matter): >1%

e. Texture (particle size per USDA soil classification): Sand <70%; Clay < 30%; Silt < 70%, Stone fragments (gravel or any soil particle greater than two (2) mm in size) < 5% by volume.

G. Turf Sod: All sod shall be 18 month old as specified on plans (or approved equal) that has been cut fresh the morning of installation. Only sod that has been grown on a commercial sod farm shall be used. Only use sod from a single source.

H. Landscape Curb Edging: six (6) inches by four (4) inches extruded concrete curb made up of the following materials:

a. Washed mortar sand free of organic material.

b. Portland Cement (see concrete spec. below for type)

c. Reinforced fiber - Specifically produced for compatibility with aggressive alkaline environment of Portland cement-based composites.

d. Only potable water for mixing.

I. Landscape Metal Edging: 5.5" steel edging with 18" dowels into the ground for stabilization.

PART III - EXECUTION

3.1 GRADING

A. Topsoil Preparation: Grade planting areas according to the grading plan. Eliminate uneven areas and low spots. Provide for proper grading and drainage.

B. Topsoil Placement: Slope surfaced away from building at two (2) percent slope with no pockets of standing water. Establish finish grades of one (1) inches for planters below grade of adjacent paved surfaced. Provide neat, smooth, and uniform finish grades. Remove surplus sub-soil and topsoil from the site.

C. Compaction: compaction under hard surface areas (asphalt paths and concrete surfaces) shall be ninety-five (95) percent. Compaction under planting areas shall be between eighty-five (85) and ninety (90) percent.

3.2 TURF GRADING

A. The surface on which the sod is to be laid shall be firm and free from footprints, depressions, or undulations of any kind. The surface shall be free of all materials larger than 1/2" in diameter.

B. The finish grade of the topsoil adjacent to all sidewalks, mow-strips, etc. prior to the laying of sod, shall be set such that the crown of the grass shall be at the same level as the adjacent concrete or hard surface. No exceptions.

3.3 PLANTING OPERATIONS

A. Review the exact loations of all trees and shrubs with the Project Representative for approval prior to the digging of any holes. Prepare all holes according to the details on the drawings.

B. Water plants immediately upon arrival at the site. Maintain in moist condition until planted.

C. Before planting, locate all underground utilities prior to digging. Do not place plants on or near utility lines.

D. The tree planting hole should be the same depth as the root ball, and two times the diameter of the root ball.

E. Trees must be placed on undisturbed soil at the bottom of the planting hole.

F. The tree hole depth shall be determined so that the tree may be set slightly high of finish grade, 1" to 2" above the base of the trunk flare, using the top of the root ball as a guide.

G. Plant immediately after removal of container for container plants.

H. Set tree on soil and remove all burlap, wire baskets, twine, wrappings, etc. before beginning and backfilling operations. Do not use planting stock if the ball is cracked or broken before or during planting operation.

I. Apply vitamin B-1 root stimulator at the rate of one (1) tablespoon per gallon.

J. Upon completion of backfilling operation, thoroughly water tree to completely settle the soil and fill any voids that may have occurred. Use a watering hose, not the area irrigation system. If additional prepared topsoil mixture needs to be added. It should be a courser mix as required to establish finish grade as indicated on the drawings.

K. The amount of pruning shall be limited to the minimum necessary to remove dead or injured twigs and branches. All cuts, scars, and bruises shall be properly treated according to the direction of the Project Representative. Proper pruning techniques shall be used. Do not leave stubs and do not cut the leader branch. Improper pruning shall be cause for rejection of the plant material.

L. Prepare a watering circle of 2' diameter around the trunk. For conifers, extend the watering well to the drip line of the tree canopy. Place mulch around the planted trees.

4. TURF - SOD LAYING

A. Top Soil Amendments: Prior to laying sod, commercial fertilizer shall be applied and incorporated into the upper four (4) inches of the topsoil at a rate of four pounds of nitrogen per one thousand (1,000) square feet. Adjust fertilization mixture and rate of application as needed to meet recommendations given by topsoil analysis. Include other amendments as required.

B. Fertilization: Three weeks after sod placement fertilize the turf at a rate of ½ pound of nitrogen per 1000 square feet. Use fertilizer specified above. Adjust fertilization mixture and rates to meet recommendations given by topsoil analysis.

C. Sod Availability and Condition: Sod is to be delivered to the site in good condition. It is to be inspected upon arrival and installed within 24 hours. Sod is to be moist and cool to ensure that decomposition has not begun and is to be free of pests, diseases, or blemishes. The Contractor shall satisfy himself as to the existing conditions prior to any construction. The Contractor shall be fully responsible for furnishing and laying all sod required on the plans. He shall furnish new sod as specified above and lay it so as too completely satisfy the intent and meaning of the plans and specification at no extra cost to the owner. In the case of any discrepancy in the amount of sod to be removed or amount to be used, it shall be the Contractor's responsibility to report such to the Project Representative prior to commencing the work.

D. Sod Laying: The surface upon which the new sod to be laid will be prepared as specified in the detail and be lightly watered before laying. Areas where sod is to be laid shall be cut trimmed, or shaped to receive full width sod (minimum twelve (12) inches). No partial strip or pieces will be accepted.

E. Sod shall be tamped lightly as each piece is set to ensure that good contact is made between edges and also the ground. If voids or holes are discovered, the sod piece(s) is (are) to be raised and topsoil is to be used to fill in the areas until level. Sod laid on any sloped areas shall be anchored with wooden dowels or other materials which are accepted by the grass sod industry.

F. Sod shall be rolled with a roller that is at least 50% full immediately after installation to ensure the full contact with soil is made.

G. Apply water directly after laying sod. Rainfall is not acceptable.

H. Watering of the sod shall be the complete responsibility of the Contractor by whatever means necessary to establish the sod in an acceptable manner to the end of the Maintenance period. If an irrigation system is in place on the site, but for whatever reason, water is not available in the system. It is the responsibility of the Contractor to water the sod by whatever means, until the sod is accepted by the Project Representative.

I. Protection of the newly laid sod shall be the complete responsibility of the Contractor. The Contractor shall provide acceptable visual barriers, to include barricades set appropriate distances with strings or tapes between barriers, as an indication of new work. The Contractor is to restore any damaged areas caused by others (including vehicular traffic), erosion, etc, until such time as the lawn is accepted by the Owner.

J. All sod that has not been laid within 24 hours shall be deemed unacceptable and will be removed from the site.

3.5 WEED BARRIER

A. For the health of the soil and the microorganisms, weed barrier is not recommended. If use is required or requested, do not place in annual or grass areas.

B. Cut weed barrier back to the edge of the plant rootball.

C. Overlap rows of fabric min. 6"

D. Stable fabric edges and overlaps to ground.

END OF SECTION

LANDSCAPE NOTES

INSTALLATION


1. LANDSCAPE CONTRACTOR SHALL HAVE ALL UTILITIES BLUE STAKED PRIOR TO DIGGING. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE WITH NO ADDITIONAL COST TO THE OWNER.
2. DURING THE BIDDING AND INSTALLATION PROCESS, THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR VERIFYING QUANTITIES OF ALL MATERIALS. IF DISCREPANCIES EXIST, THE PLAN SHALL DICTATE QUANTITIES TO BE USED.
3. ALL PLANT MATERIAL SHALL BE PLANTED ACCORDING TO INTERNATIONAL SOCIETY OF ARBORICULTURE (ISA) STANDARDS WITH CONSIDERATION TO INDIVIDUAL SOIL AND SITE CONDITIONS, AND NURSERY CARE AND INSTALLATION INSTRUCTIONS.
4. SELECTED PLANTS WILL BE ACCORDING TO THE PLANT LEGEND. IF SUBSTITUTIONS ARE NECESSARY, PROPOSED LANDSCAPE CHANGES MUST BE SUBMITTED TO THE LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO LAYING SOD.
5. SHOULD THE SITE REQUIRE ADDITIONAL TOPSOIL, REFER TO SOIL TEST WHEN MATCHING EXISTING SOIL. IF A MATCHING SOIL IS NOT LOCATABLE, A 6" DEPTH OF SANDY LOAM TOPSOIL (MIXED PRIOR TO SPREADING WITH 2-3" OF QUALITY COMPOST) CAN BE INCORPORATED INTO THE EXISTING SOIL USING THE FOLLOWING DIRECTIONS: SCARIFY TOP 6" OF EXISTING SUBSOIL AND INCORPORATE 3" OF NEW COMPOST ENRICHED TOPSOIL. SPREAD REMAINING TOPSOIL TO REACH FINISHED GRADE.
6. SOD FOR NEW LAWN AREAS SHALL BE A DROUGHT TOLERANT VARIETY. FINE LEVEL ALL AREAS PRIOR TO LAYING SOD.
7. EDGING, AS INDICATED ON PLAN, IS TO BE INSTALLED BETWEEN ALL LAWN AND PLANTER AREAS. ANY TREES LOCATED IN LAWN MUST HAVE A 4-6' TREE RING OF THE SAME EDGING.
8. IF REQUIRED BY CITY OR OWNER SPECIFIED, DeWit 5 OZ WEED BARRIER FABRIC TO BE INSTALLED IN ALL PLANTER AREAS EXCEPT UNDER ANNUAL PLANTING AREAS AS SHOWN ON PLAN. WEED BARRIER SHALL BE CUT BACK FROM EACH PLANT TO THE DIAMETER OF THE ROOTBALL.
9. ROCK MULCH (INORGANIC MULCH) TO BE APPLIED AT THE FOLLOWING DEPTHS: 3" IN ALL TREE, SHRUB, AND PERENNIAL PLANTER AREAS; ANNUAL PLANTING AREAS AS SHOWN ON PLAN TO RECEIVE 4" OF SOIL AID MATERIAL (ORGANIC MULCH). NO MULCH SHALL BE PLACED WITHIN 12" OF BASE OF TREE AND 6" WITHIN BASE OF SHRUBS AND PERENNIALS.
10. A NEW UNDERGROUND, AUTOMATIC IRRIGATION SYSTEM IS TO BE INSTALLED BY CONTRACTOR IN ALL LANDSCAPED AREAS. LAWN AREAS TO RECEIVE AT LEAST 100% HEAD TO HEAD COVERAGE AND PLANTER AREAS TO RECEIVE A FULL DRIP SYSTEM TO EACH TREE AND SHRUB. POINT SOURCE DRIP OR IN-LINE DRIP TUBING TO BE SECURED AT EDGE OF ROOTBALL, NOT AGAINST TRUNK. SEE IRRIGATION PLAN.
11. UPON REQUEST, A PLANT GUIDE IS AVAILABLE WITH OUR RECOMMENDATIONS REGARDING WEED BARRIER, PLANT CARE AND MAINTENANCE

INSTALLER RESPONSIBILITIES AND LIABILITIES

1. THESE PLANS ARE FOR BASIC DESIGN LAYOUT AND INFORMATION. LANDSCAPE CONTRACTOR IS REQUIRED TO USE TRADE KNOWLEDGE FOR IMPLEMENTATION. OWNER ASSUMES NO LIABILITIES FOR INADEQUATE ENGINEERING CALCULATIONS, MANUFACTURER PRODUCT DEFECTS, INSTALLATION OF ANY LANDSCAPING AND COMPONENTS, OR TIME EXECUTION.
2. LANDSCAPE CONTRACTOR IS RESPONSIBLE AND LIABLE FOR INSTALLATION OF ALL LANDSCAPING AND IRRIGATION SYSTEMS INCLUDING CODE REQUIREMENTS, TIME EXECUTIONS, INSTALLED PRODUCTS AND MATERIALS.

GRADING AND DRAINAGE REQUIREMENTS

1. AS PER CODE, ALL GRADING IS TO SLOPE AWAY FROM ANY STRUCTURE. SURFACE OF THE GROUND WITHIN 10' FEET OF THE FOUNDATION SHOULD DRAIN AWAY FROM THE STRUCTURE WITH A MINIMUM FALL OF 6"
2. AS PER CODE, FINISHED GRADE WILL NOT DRAIN ON NEIGHBORING PROPERTIES
3. A MINIMUM OF 6" OF FOUNDATION WILL BE LEFT EXPOSED AT ALL CONDITIONS
4. LANDSCAPE CONTRACTOR TO MAINTAIN OR IMPROVE FINAL GRADE AND PROPER DRAINAGE ESTABLISHED BY EXCAVATOR, INCLUDING BUT NOT LIMITED TO ANY MAINTENANCE, PRESERVATION, OR EXAGGERATION OF SLOPES, BERMS, AND SWALES.
5. LANDSCAPE CONTRACTOR IS RESPONSIBLE TO CORRECT ANY DAMAGED OR IMPROPER WATERFLOW OF ALL SWALES, BERMS, OR GRADE
6. DEVICES FOR CHANNELING ROOF RUN-OFF SHOULD BE INSTALLED FOR COLLECTION AND DISCHARGE OF RAINWATER AT A MINIMUM OF 10' FROM THE FOUNDATION, OR BEYOND THE LIMITS OF FOUNDATION WALL BACKFILL; WHICHEVER DISTANCE IS GREATER



SHEET INDEX

LP-101	LP-104
LP-102	LP-105
LP-103	LP-106

PLANT LEGEND

DECIDUOUS TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
Ax'p	Ax'p	38	Acer truncatum x platanoides `Warrenred` TM Pacific Sunset Maple	B & B	2"Cal	
Ag'a	Ag'a	8	Amelanchier x grandiflora `Autumn Brilliance` `Autumn Brilliance` Serviceberry	B & B	Multi-trunked	
Cb'f	Cb'f	22	Carpinus betulus `Franz Fontaine` Franz Fontaine Hornbeam	B & B	2"Cal	
Fs'o	Fs'o	17	Fagus sylvatica `Red Obelisk` Red Obelisk Europcan Beech	B & B	2"Cal	
Gt's	Gt's	35	Gleditsia triacanthos `Skycole` Skyline Honey Locust	B & B	2"Cal	
G'su	G'su	36	Gleditsia triacanthos inermis `Suncole` Sunburst Honey Locust	B & B	2"Cal	
Us'f	Us'f	6	Ulmus x `Frontier` Frontier Elm	B & B	2"Cal	

EVERGREEN TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
Js'b	Js'b	37	Juniperus Scopulorum `Blue Arrow` Blue Arrow Juniper	B & B		5'-6'

DECIDUOUS SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
Aa'o	Aa'o	62	Amelanchier alnifolia `Obelisk` TM Standing Ovation Serviceberry	5 gal
Am'h	Am'h	50	Aronia melanocarpa `UCONNAM166` TM Low Scape Hedger Chokeberry	5 gal
Br'l	Br'l	126	Berberis thunbergii `BailErin` TM Limoncello Barberry	5 gal
Br'm	Br'm	48	Berberis thunbergii `Maria` TM Sunjoy Gold Pillar Barberry	5 gal
Bl'pa	Bl'pa	46	Buddleja x `SMNBDL` Pugster Amethyst Dwarf Butterfly Bush	5 gal
Ph'f	Ph'f	7	Physocarpus opulifolius `UMNHarpell` Fireside TM Fireside Ninebark	5 gal
Pt'g	Pt'g	30	Potentilla fruticosa `Gold Drop` Gold Drop Potentilla	5 gal
Rt'a	Rt'a	46	Rhus trilobata `Autumn Amber` Autumn Amber Sumac	5 gal

EVERGREEN SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
Jc'd	Jc'd	57	Juniperus chinensis `Daub's Frosted` Daub's Frosted Juniper	5 gal

GRASSES	CODE	QTY	BOTANICAL / COMMON NAME	CONT
Hs's	Hs's	377	Helictotrichon sempervirens `Sapphire` Blue Oat Grass	1 gal
Pv's	Pv's	165	Panicum virgatum `Shenandoah` Shenandoah Switch Grass	1 gal

SITE MATERIALS LEGEND

SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
1-01	SODDED LAWN AREA LAWN AREAS SHALL BE SOD. NEW TURF AREAS TO BE SODDED WITH 18% "BLUESTAR KENTUCKY BLUEGRASS, 19% "MARQUIS" KENTUCKY BLUEGRASS, 17% "NEWPORT" KENTUCKY BLUEGRASS, 17% "TOUCHDOWN" KENTUCKY BLUEGRASS, 16% "APM PERENNIAL RYEGRASS, 13% "ACCENT PERENNIAL RYEGRASS OR APPROVED EQUAL AT A RATE OF 220 LBS. PER ACRE. FINE LEVEL ALL AREAS PRIOR TO LAYING SOD. ALL LAWN AREAS SHALL BE IRRIGATED WITH 100% COVERAGE BY POP-UP SPRAY HEADS AND GEAR-DRIVEN ROTORS. ALL DECIDUOUS AND CONIFER TREES PLANTED WITHIN SOD AREAS SHALL HAVE A FOUR FOOT(4') DIAMETER TREE RING COVERED WITH CHOCOLATE BROWN BARK MULCH, NO SHREDDED FINES. SUBMIT SAMPLES TO BE APPROVED BY LANDSCAPE ARCHITECT AND OWNER BEFORE INSTALLATION.	19,174 sf
1-03	OQUIRRH GRAVEL STONE MULCH OR APPROVED EQUAL PLANTING AREAS TO RECEIVE MIN. 6" DEPTH OF QUALITY TOPSOIL. IF TOPSOIL IS PRESENT ON SITE, PROVIDE SOIL TEST TO DETERMINE SOIL QUALITY FOR PROPOSED PLANTINGS. PROVIDE 3" DEPTH OF STONE MULCH TOP DRESSING.	61,490 sf

SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
1-07	BOULDERS - 2'-3'	35

ISSUE DATE: 11/11/2021
PROJECT NUMBER: UT21101

NO.	REVISION	DATE
1	CITY COMMENTS: ADDED PERIMETER TREES	11-11-2021
2		
3		
4		
5		
6		
7		

PLAN INFORMATION

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

0' 50' 100' 200' 400'
GRAPHIC SCALE: 1" = 100'

PROJECT INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture / Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP


LICENSED LANDSCAPE ARCHITECT
JESSE A. KNOWLTON
8150764-5301
11/10/2021
ELECTRONIC SEAL
STATE OF UTAH

DRAWING INFO
PM: JTA
DRAWN: ACP
CHECKED: JMA
PLOT DATE: 11/11/2021

LANDSCAPE PLAN COVER

PRELIMINARY PLANS NOT FOR CONSTRUCTION

LP-100



ISSUE DATE	PROJECT NUMBER
11/11/2021	UT21101

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

PLAN INFORMATION

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

0' 25' 50' 100' 200'
GRAPHIC SCALE: 1" = 50'

PROJECT INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture / Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
8128127-5301
11/11/2021
RENEWAL 3/31/2023
STATE OF UTAH


DRAWING INFO

PM:	JTA
DRAWN:	ACP
CHECKED:	JMA
PLOT DATE:	11/11/2021

LANDSCAPE PLAN OVERALL

PRELIMINARY PLANS NOT FOR CONSTRUCTION

LP-O



PLANT LEGEND

DECIDUOUS TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
Ax'p	Ax'p	38	Acer truncatum x platanoides `Warrenred` TM Pacific Sunset Maple	B & B	2"Cal	
Ag'a	Ag'a	8	Amelanchier x grandiflora `Autumn Brilliance` `Autumn Brilliance` Serviceberry	B & B	Multi-trunked	
Cb'f	Cb'f	22	Carpinus betulus `Franz Fontaine` Franz Fontaine Hornbeam	B & B	2"Cal	
Fs'o	Fs'o	17	Fagus sylvatica `Red Obelisk` Red Obelisk European Beech	B & B	2"Cal	
Gt's	Gt's	35	Gleditsia triacanthos `Skycole` Skyline Honey Locust	B & B	2"Cal	
G'su	G'su	36	Gleditsia triacanthos inermis `Suncole` Sunburst Honey Locust	B & B	2"Cal	
Ul'f	Ul'f	6	Ulmus x `Frontier` Frontier Elm	B & B	2"Cal	

EVERGREEN TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
	Js'b	37	Juniperus Scopulorum `Blue Arrow` Blue Arrow Juniper	B & B		5'-6'

DECIDUOUS SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Aa'o	62	Amelanchier alnifolia `Obelisk` TM Standing Ovation Serviceberry	5 gal
	Am'h	50	Aronia melanocarpa `UCONNAM166` TM Low Scape Hedger Chokeberry	5 gal
	Bt'l	126	Berberis thunbergii `BailErin` TM Limoncello Barberry	5 gal
	Bt'm	48	Berberis thunbergii `Maria` TM Sunjoy Gold Pillar Barberry	5 gal
	B'pa	46	Buddleja x `SMNBDL` Pugster Amethyst Dwarf Butterfly Bush	5 gal
	Pv'f	7	Physocarpus opulifolius `UMNHarpell` Fireside TM Fireside Ninebark	5 gal
	Pf'g	30	Potentilla fruticosa `Gold Drop` Gold Drop Potentilla	5 gal
	Rt'a	46	Rhus trilobata `Autumn Amber` Autumn Amber Sumac	5 gal

EVERGREEN SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Jc'd	57	Juniperus chinensis `Daub's Frosted` Daub's Frosted Juniper	5 gal

GRASSES	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Hs's	377	Helictotrichon sempervirens `Sapphire` Blue Oat Grass	1 gal
	Pv's	165	Panicum virgatum `Shenandoah` Shenandoah Switch Grass	1 gal

SITE MATERIALS LEGEND

SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
1-01	SODDED LAWN AREA LAWN AREAS SHALL BE SOD. NEW TURF AREAS TO BE SODDED WITH 18% "BLUESTAR KENTUCKY BLUEGRASS, 19% "MARQUIS" KENTUCKY BLUEGRASS, 17% "NEWPORT" KENTUCKY BLUEGRASS, 17% "TOUCHDOWN" KENTUCKY BLUEGRASS, 16% "APM PERENNIAL RYEGRASS, 13% "ACCENT PERENNIAL RYEGRASS OR APPROVED EQUAL AT A RATE OF 220 LBS. PER ACRE. FINE LEVEL ALL AREAS PRIOR TO LAYING SOD. ALL LAWN AREAS SHALL BE IRRIGATED WITH 100% COVERAGE BY POP-UP SPRAY HEADS AND GEAR-DRIVEN ROTORS. ALL DECIDUOUS AND CONIFER TREES PLANTED WITHIN SOD AREAS SHALL HAVE A FOUR FOOT(4') DIAMETER TREE RING COVERED WITH CHOCOLATE BROWN BARK MULCH, NO SHREDDED FINES. SUBMIT SAMPLES TO BE APPROVED BY LANDSCAPE ARCHITECT AND OWNER BEFORE INSTALLATION.	19,174 sf
1-03	OQUIRRH GRAVEL STONE MULCH OR APPROVED EQUAL. PLANTING AREAS TO RECEIVE MIN. 6" DEPTH OF QUALITY TOPSOIL. IF TOPSOIL IS PRESENT ON SITE, PROVIDE SOIL TEST TO DETERMINE SOIL QUALITY FOR PROPOSED PLANTINGS. PROVIDE 3" DEPTH OF STONE MULCH TOP DRESSING.	61,490 sf

SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
1-07	BOULDERS - 2'-3'	35

ISSUE DATE	PROJECT NUMBER
11/11/2021	UT21101

NO.	REVISION	DATE
1	CITY COMMENTS: ADDED PERIMETER TREES	11-11-2021
2		
3		
4		
5		
6		
7		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

0' 10' 20' 40' 80'
GRAPHIC SCALE: 1" = 20'

PLAN INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

PROJECT INFORMATION

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture / Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
813812-5301
11/11/2021
ELECTRONIC SEAL
STATE OF UTAH


DRAWING INFO

PM:	JTA
DRAWN:	ACP
CHECKED:	JMA
PLOT DATE:	11/11/2021

LANDSCAPE PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

LP-101



PLANT LEGEND

DECIDUOUS TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
AVG	Aa'p	38	Acer truncatum x platanoides `Warrenred` TM Pacific Sunset Maple	B & B	2"Cal	
Ag'a	Ag'a	8	Amelanchier x grandiflora `Autumn Brilliance` `Autumn Brilliance` Serviceberry	B & B	Multi-trunked	
Cb'f	Cb'f	22	Carpinus betulus `Franz Fontaine` Franz Fontaine Hornbeam	B & B	2"Cal	
Fs'o	Fs'o	17	Fagus sylvatica `Red Obelisk` Red Obelisk European Beech	B & B	2"Cal	
Gt's	Gt's	35	Gleditsia triacanthos `Skycole` Skyline Honey Locust	B & B	2"Cal	
G'su	G'su	36	Gleditsia triacanthos inermis `Suncole` Sunburst Honey Locust	B & B	2"Cal	
Ux'f	Ux'f	6	Ulmus x `Frontier` Frontier Elm	B & B	2"Cal	

EVERGREEN TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
	Js'b	37	Juniperus Scopulorum `Blue Arrow` Blue Arrow Juniper	B & B		5`-6`

DECIDUOUS SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Aa'o	62	Amelanchier alnifolia `Obelisk` TM Standing Ovation Serviceberry	5 gal
	Am'h	50	Aronia melanocarpa `UCONNAM166` TM Low Scape Hedger Chokeberry	5 gal
	Bt'l	126	Berberis thunbergii `BailErin` TM Limoncello Barberry	5 gal
	Bt'm	48	Berberis thunbergii `Maria` TM Sunjoy Gold Pillar Barberry	5 gal
	B'pa	46	Buddleja x `SMNBDL` Pugster Amethyst Dwarf Butterfly Bush	5 gal
	Pv'f	7	Physocarpus opulifolius `UMNHarpell` Fireside TM Fireside Ninebark	5 gal
	Pf'g	30	Potentilla fruticosa `Gold Drop` Gold Drop Potentilla	5 gal
	Rt'a	46	Rhus trilobata `Autumn Amber` Autumn Amber Sumac	5 gal

EVERGREEN SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Jc'd	57	Juniperus chinensis `Daub`s Frosted` Daub`s Frosted Juniper	5 gal

GRASSES	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Hs's	377	Helictotrichon sempervirens `Sapphire` Blue Oat Grass	1 gal
	Pv's	165	Panicum virgatum `Shenandoah` Shenandoah Switch Grass	1 gal

SITE MATERIALS LEGEND

	SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
	1-01	SODDED LAWN AREA LAWN AREAS SHALL BE SOD. NEW TURF AREAS TO BE SODDED WITH 18% "BLUESTAR KENTUCKY BLUEGRASS, 19% "MARQUIS" KENTUCKY BLUEGRASS, 17% "NEWPORT" KENTUCKY BLUEGRASS, 17% "TOUCHDOWN" KENTUCKY BLUEGRASS, 16% "APM PERENNIAL RYEGRASS, 13% "ACCENT PERENNIAL RYEGRASS OR APPROVED EQUAL AT A RATE OF 220 LBS. PER ACRE. FINE LEVEL ALL AREAS PRIOR TO LAYING SOD. ALL LAWN AREAS SHALL BE IRRIGATED WITH 100% COVERAGE BY POP-UP SPRAY HEADS AND GEAR-DRIVEN ROTORS. ALL DECIDUOUS AND CONIFER TREES PLANTED WITHIN SOD AREAS SHALL HAVE A FOUR FOOT(4`) DIAMETER TREE RING COVERED WITH CHOCOLATE BROWN BARK MULCH. NO SHREDDED FINES. SUBMIT SAMPLES TO BE APPROVED BY LANDSCAPE ARCHITECT AND OWNER BEFORE INSTALLATION.	19,174 sf
	1-03	OQUIRRH GRAVEL STONE MULCH OR APPROVED EQUAL PLANTING AREAS TO RECEIVE MIN. 6" DEPTH OF QUALITY TOPSOIL. IF TOPSOIL IS PRESENT ON SITE, PROVIDE SOIL TEST TO DETERMINE SOIL QUALITY FOR PROPOSED PLANTINGS. PROVIDE 3" DEPTH OF STONE MULCH TOP DRESSING.	61,490 sf

	SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
	1-07	BOULDERS - 2`-3`	35

ISSUE DATE: 11/11/2021 | PROJECT NUMBER: UT21101

NO.	REVISION	DATE
1	CITY COMMENTS- ADDED PERIMETER TREES	11/11/2021
2	XXXX	XX-XX-XX
3		
4		
5		
6		
7		
8		
9		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

0' 10' 20' 40' 80'
GRAPHIC SCALE: 1" = 20'

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT:
AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER:
PKJ DESIGN GROUP
Landscape Architecture / Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com


LICENSE STAMP: REGISTERED LANDSCAPE ARCHITECT JEREMY AINSWORTH 812812-5301 PROFESSIONAL 11/11/2021 ELECTRONIC SEAL STATE OF UTAH

DRAWING INFO
PM: JTA
DRAWN: ACP
CHECKED: JMA
PLOT DATE: 11/11/2021

LANDSCAPE PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

LP-102



PLANT LEGEND

DECIDUOUS TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
	Ax'p	38	Acer truncatum x platanoides `Warrenred` TM Pacific Sunset Maple	B & B	2"Cal	
	Ag'a	8	Amelanchier x grandiflora `Autumn Brilliance` `Autumn Brilliance` Serviceberry	B & B	Multi-trunked	
	Cb'f	22	Carpinus betulus `Franz Fontaine` Franz Fontaine Hornbeam	B & B	2"Cal	
	Fs'o	17	Fagus sylvatica `Red Obelisk` Red Obelisk European Beech	B & B	2"Cal	
	Gt's	35	Gleditsia triacanthos `Skycole` Skyline Honey Locust	B & B	2"Cal	
	G'su	36	Gleditsia triacanthos inermis `Suncole` Sunburst Honey Locust	B & B	2"Cal	
	Ux'f	6	Ulmus x `Frontier` Frontier Elm	B & B	2"Cal	

EVERGREEN TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
	Js'b	37	Juniperus Scopulorum `Blue Arrow` Blue Arrow Juniper	B & B		5`-6`

DECIDUOUS SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Aa'o	62	Amelanchier alnifolia `Obelisk` TM Standing Ovation Serviceberry	5 gal
	Am'h	50	Aronia melanocarpa `UCONNAM166` TM Low Scape Hedger Chokeberry	5 gal
	Bt'l	126	Berberis thunbergii `BailErin` TM Limoncello Barberry	5 gal
	Bt'm	48	Berberis thunbergii `Maria` TM Sunjoy Gold Pillar Barberry	5 gal
	B'pa	46	Buddleja x `SMNBDL` Pugster Amethyst Dwarf Butterfly Bush	5 gal
	Po'f	7	Physocarpus opulifolius `UMNHarpell` Fireside TM Fireside Ninebark	5 gal
	Pf'g	30	Potentilla fruticosa `Gold Drop` Gold Drop Potentilla	5 gal
	Rt'a	46	Rhus trilobata `Autumn Amber` Autumn Amber Sumac	5 gal

EVERGREEN SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Jc'd	57	Juniperus chinensis `Daub`s Frosted` Daub`s Frosted Juniper	5 gal

GRASSES	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Hs's	377	Helictotrichon sempervirens `Sapphire` Blue Oat Grass	1 gal
	Pv's	165	Panicum virgatum `Shenandoah` Shenandoah Switch Grass	1 gal

SITE MATERIALS LEGEND

	SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
	1-01	SODDED LAWN AREA LAWN AREAS SHALL BE SOD. NEW TURF AREAS TO BE SODDED WITH 18% "BLUESTAR KENTUCKY BLUEGRASS, 19% "MARQUIS" KENTUCKY BLUEGRASS, 17% "NEWPORT" KENTUCKY BLUEGRASS, 17% "TOUCHDOWN" KENTUCKY BLUEGRASS, 16% "APM PERENNIAL RYEGRASS, 13% "ACCENT PERENNIAL RYEGRASS OR APPROVED EQUAL AT A RATE OF 220 LBS. PER ACRE. FINE LEVEL ALL AREAS PRIOR TO LAYING SOD. ALL LAWN AREAS SHALL BE IRRIGATED WITH 100% COVERAGE BY POP-UP SPRAY HEADS AND GEAR-DRIVEN ROTORS. ALL DECIDUOUS AND CONIFER TREES PLANTED WITHIN SOD AREAS SHALL HAVE A FOUR FOOT(4`) DIAMETER TREE RING COVERED WITH CHOCOLATE BROWN BARK MULCH, NO SHREDDED FINES. SUBMIT SAMPLES TO BE APPROVED BY LANDSCAPE ARCHITECT AND OWNER BEFORE INSTALLATION.	19,174 sf
	1-03	OQUIRRH GRAVEL STONE MULCH OR APPROVED EQUAL PLANTING AREAS TO RECEIVE MIN. 6" DEPTH OF QUALITY TOPSOIL. IF TOPSOIL IS PRESENT ON SITE, PROVIDE SOIL TEST TO DETERMINE SOIL QUALITY FOR PROPOSED PLANTINGS. PROVIDE 3" DEPTH OF STONE MULCH TOP DRESSING.	61,490 sf

	SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
	1-07	BOULDERS - 2`-3`	35

ISSUE DATE: 11/11/2021

PROJECT NUMBER: UT21101

NO.	REVISION	DATE
1	CITY COMMENTS: ADDED PERIMETER TREES	11-11-2021
2	XXXX	XX-XX-XX
3		
4		
5		
6		
7		

PLAN INFORMATION

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

N

0' 10' 20' 40' 80'
GRAPHIC SCALE: 1" = 20'

PROJECT INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
8128121-5301
11/11/2021
ELECTRONIC SEAL
STATE OF UTAH


DRAWING INFO

PM: JTA
DRAWN: ACP
CHECKED: JMA
PLOT DATE: 11/11/2021

LANDSCAPE PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

LP-103



PLANT LEGEND

DECIDUOUS TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
AXP	Ax'p	38	Acer truncatum x platanoides `Warrenred` TM Pacific Sunset Maple	B & B	2"Cal	
Ag'a	Ag'a	8	Amelanchier x grandiflora `Autumn Brilliance` `Autumn Brilliance` Serviceberry	B & B	Multi-trunked	
Cb'f	Cb'f	22	Carpinus betulus `Franz Fontaine` Franz Fontaine Hornbeam	B & B	2"Cal	
Fs'o	Fs'o	17	Fagus sylvatica `Red Obelisk` Red Obelisk European Beech	B & B	2"Cal	
GLS	Gl's	35	Gleditsia triacanthos `Skycole` Skyline Honey Locust	B & B	2"Cal	
	G'su	36	Gleditsia triacanthos inermis `Suncole` Sunburst Honey Locust	B & B	2"Cal	
UVF	Us'f	6	Ulmus x `Frontier` Frontier Elm	B & B	2"Cal	

EVERGREEN TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
	Js'b	37	Juniperus Scopulorum `Blue Arrow` Blue Arrow Juniper	B & B		5'-6'

DECIDUOUS SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Aa'o	62	Amelanchier alnifolia `Obelisk` TM Standing Ovation Serviceberry	5 gal
	Am'h	50	Aronia melanocarpa `UCONNAM166` TM Low Scape Hedger Chokeberry	5 gal
	Bt'l	126	Berberis thunbergii `BailErin` TM Limoncello Barberry	5 gal
	Bt'm	48	Berberis thunbergii `Maria` TM Sunjoy Gold Pillar Barberry	5 gal
	B'pa	46	Buddleja x `SMNBDL` Pugster Amethyst Dwarf Butterfly Bush	5 gal
	Pv'f	7	Physocarpus opulifolius `UMNHarpell` Fireside TM Fireside Ninebark	5 gal
	Pf'g	30	Potentilla fruticosa `Gold Drop` Gold Drop Potentilla	5 gal
	Rt'a	46	Rhus trilobata `Autumn Amber` Autumn Amber Sumac	5 gal

EVERGREEN SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Jc'd	57	Juniperus chinensis `Daub's Frosted` Daub's Frosted Juniper	5 gal

GRASSES	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Hs's	377	Helictotrichon sempervirens `Sapphire` Blue Oat Grass	1 gal
	Pv's	165	Panicum virgatum `Shenandoah` Shenandoah Switch Grass	1 gal

SITE MATERIALS LEGEND

	SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
	L-01	SODDED LAWN AREA LAWN AREAS SHALL BE SOD. NEW TURF AREAS TO BE SODDED WITH 18% "BLUESTAR KENTUCKY BLUEGRASS, 19% "MARQUIS" KENTUCKY BLUEGRASS, 17% "NEWPORT" KENTUCKY BLUEGRASS, 17% "TOUCHDOWN" KENTUCKY BLUEGRASS, 16% "APM PERENNIAL RYEGRASS, 13% "ACCENT PERENNIAL RYEGRASS OR APPROVED EQUAL AT A RATE OF 220 LBS. PER ACRE. FINE LEVEL ALL AREAS PRIOR TO LAYING SOD. ALL LAWN AREAS SHALL BE IRRIGATED WITH 100% COVERAGE BY POP-UP SPRAY HEADS AND GEAR-DRIVEN ROTORS. ALL DECIDUOUS AND CONIFER TREES PLANTED WITHIN SOD AREAS SHALL HAVE A FOUR FOOT(4') DIAMETER TREE RING COVERED WITH CHOCOLATE BROWN BARK MULCH, NO SHREDDED FINES. SUBMIT SAMPLES TO BE APPROVED BY LANDSCAPE ARCHITECT AND OWNER BEFORE INSTALLATION.	19,174 sf
	L-03	OQUIRRH GRAVEL STONE MULCH OR APPROVED EQUAL PLANTING AREAS TO RECEIVE MIN. 6" DEPTH OF QUALITY TOPSOIL. IF TOPSOIL IS PRESENT ON SITE, PROVIDE SOIL TEST TO DETERMINE SOIL QUALITY FOR PROPOSED PLANTINGS. PROVIDE 3" DEPTH OF STONE MULCH TOP DRESSING.	61,490 sf

	SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
	L-07	BOULDERS - 2'-3'	35

ISSUE DATE	PROJECT NUMBER	PLAN INFORMATION
11/11/2021	UT21101	

NO.	REVISION	DATE
1	CITY COMMENTS: ADDED PERIMETER TREES	11-11-2021
2		
3		
4		
5		
6		
7		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

0' 10' 20' 40' 80'
GRAPHIC SCALE: 1" = 20'

PROJECT INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture Planning &Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
8172847-5301
11/11/2021
REGISTERED
STATE OF UTAH


DRAWING INFO

PM:	JTA
DRAWN:	ACP
CHECKED:	JMA
PLOT DATE:	11/11/2021

LANDSCAPE PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

LP-104



PLANT LEGEND

DECIDUOUS TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
AcQ	Aa'p	38	Acer truncatum x platanoides `Warrenred` TM Pacific Sunset Maple	B & B	2"Cal	
Ag'a	Ag'a	8	Amelanchier x grandiflora `Autumn Brilliance` `Autumn Brilliance` Serviceberry	B & B	Multi-trunked	
Cb'f	Cb'f	22	Carpinus betulus `Franz Fontaine` Franz Fontaine Hornbeam	B & B	2"Cal	
Fs'O	Fs'o	17	Fagus sylvatica `Red Obelisk` Red Obelisk European Beech	B & B	2"Cal	
Gt's	Gt's	35	Gleditsia triacanthos `Skycole` Skyline Honey Locust	B & B	2"Cal	
Gs'su	G'su	36	Gleditsia triacanthos inermis `Suncole` Sunburst Honey Locust	B & B	2"Cal	
Us'f	Us'f	6	Ulmus x `Frontier` Frontier Elm	B & B	2"Cal	

EVERGREEN TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
	Js'b	37	Juniperus Scopulorum `Blue Arrow` Blue Arrow Juniper	B & B		5`-6`

DECIDUOUS SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Aa'o	62	Amelanchier alnifolia `Obelisk` TM Standing Ovation Serviceberry	5 gal
	Am'h	50	Aronia melanocarpa `UCONNAM166` TM Low Scape Hedger Chokeberry	5 gal
	Br'l	126	Berberis thunbergii `BailErin` TM Limoncello Barberry	5 gal
	Br'm	48	Berberis thunbergii `Maria` TM Sunjoy Gold Pillar Barberry	5 gal
	B'pa	46	Buddleja x `SMNBDL` Pugster Amethyst Dwarf Butterfly Bush	5 gal
	Pv'f	7	Physocarpus opulifolius `UMNHarpell` Fireside TM Fireside Ninebark	5 gal
	Pf'g	30	Potentilla fruticosa `Gold Drop` Gold Drop Potentilla	5 gal
	Rt'a	46	Rhus trilobata `Autumn Amber` Autumn Amber Sumac	5 gal

EVERGREEN SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
Jc'd	Jc'd	57	Juniperus chinensis `Daub's Frosted` Daub's Frosted Juniper	5 gal

GRASSES	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Hs's	377	Helictotrichon sempervirens `Sapphire` Blue Oat Grass	1 gal
	Pv's	165	Panicum virgatum `Shenandoah` Shenandoah Switch Grass	1 gal

SITE MATERIALS LEGEND

SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
1-01	SODDED LAWN AREA LAWN AREAS SHALL BE SOD. NEW TURF AREAS TO BE SODDED WITH 18% "BLUESTAR KENTUCKY BLUEGRASS, 19% "MARQUIS" KENTUCKY BLUEGRASS, 17% "NEWPORT" KENTUCKY BLUEGRASS, 17% "TOUCHDOWN" KENTUCKY BLUEGRASS, 16% "APM PERENNIAL RYEGRASS, 13% "ACCENT" PERENNIAL RYEGRASS OR APPROVED EQUAL AT A RATE OF 220 LBS. PER ACRE. FINE LEVEL ALL AREAS PRIOR TO LAYING SOD. ALL LAWN AREAS SHALL BE IRRIGATED WITH 100% COVERAGE BY POP-UP SPRAY HEADS AND GEAR-DRIVEN ROTORS. ALL DECIDUOUS AND CONIFER TREES PLANTED WITHIN SOD AREAS SHALL HAVE A FOUR FOOT(4') DIAMETER TREE RING COVERED WITH CHOCOLATE BROWN BARK MULCH, NO SHREDDED FINES. SUBMIT SAMPLES TO BE APPROVED BY LANDSCAPE ARCHITECT AND OWNER BEFORE INSTALLATION.	19,174 sf
1-03	OQUIRRH GRAVEL STONE MULCH OR APPROVED EQUAL PLANTING AREAS TO RECEIVE MIN. 6" DEPTH OF QUALITY TOPSOIL. IF TOPSOIL IS PRESENT ON SITE, PROVIDE SOIL TEST TO DETERMINE SOIL QUALITY FOR PROPOSED PLANTINGS. PROVIDE 3" DEPTH OF STONE MULCH TOP DRESSING.	61,490 sf

SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
1-07	BOULDERS - 2`-3`	35

ISSUE DATE	PROJECT NUMBER
11/11/2021	UT21101

NO.	REVISION	DATE
1	CITY COMMENTS: ADDED PERIMETER TREES	11-11-2021
2		
3		
4		
5		
6		
7		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

0' 10' 20' 40' 80'
GRAPHIC SCALE: 1" = 20'

PLAN INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

PROJECT INFORMATION

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture / Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
8172812-5301
11/11/2021
REGISTERED
STATE OF UTAH


DRAWING INFO

PM:	JTA
DRAWN:	ACP
CHECKED:	JMA
PLOT DATE:	11/11/2021

LANDSCAPE PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

LP-105



PLANT LEGEND

DECIDUOUS TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
AcP	Aa'p	38	Acer truncatum x platanoides `Warrenred` TM Pacific Sunset Maple	B & B	2"Cal	
Ag'a	Ag'a	8	Amelanchier x grandiflora `Autumn Brilliance` `Autumn Brilliance` Serviceberry	B & B	Multi-trunked	
Cb'f	Cb'f	22	Carpinus betulus `Franz Fontaine` Franz Fontaine Hornbeam	B & B	2"Cal	
Fs'o	Fs'o	17	Fagus sylvatica `Red Obelisk` Red Obelisk European Beech	B & B	2"Cal	
Gl's	Gl's	35	Gleditsia triacanthos `Skycole` Skyline Honey Locust	B & B	2"Cal	
G'su	G'su	36	Gleditsia triacanthos inermis `Suncole` Sunburst Honey Locust	B & B	2"Cal	
UnF	Un'f	6	Ulmus x `Frontier` Frontier Elm	B & B	2"Cal	

EVERGREEN TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	SIZE
	Js'b	37	Juniperus Scopulorum `Blue Arrow` Blue Arrow Juniper	B & B		5'-6'

DECIDUOUS SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Aa'o	62	Amelanchier alnifolia `Obelisk` TM Standing Ovation Serviceberry	5 gal
	Am'h	50	Aronia melanocarpa `UCONNAM166` TM Low Scape Hedger Chokeberry	5 gal
	Br'l	126	Berberis thunbergii `BailErin` TM Limoncello Barberry	5 gal
	Br'm	48	Berberis thunbergii `Maria` TM Sunjoy Gold Pillar Barberry	5 gal
	B'pa	46	Buddleja x `SMNBDL` Pugster Amethyst Dwarf Butterfly Bush	5 gal
	Pv'f	7	Physocarpus opulifolius `UMNHarpell` Fireside TM Fireside Ninebark	5 gal
	Pf'g	30	Potentilla fruticosa `Gold Drop` Gold Drop Potentilla	5 gal
	Rt'a	46	Rhus trilobata `Autumn Amber` Autumn Amber Sumac	5 gal

EVERGREEN SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	CONT
Jc'd	Jc'd	57	Juniperus chinensis `Daub's Frosted` Daub's Frosted Juniper	5 gal

GRASSES	CODE	QTY	BOTANICAL / COMMON NAME	CONT
	Hs's	377	Helictotrichon sempervirens `Sapphire` Blue Oat Grass	1 gal
	Pv's	165	Panicum virgatum `Shenandoah` Shenandoah Switch Grass	1 gal

SITE MATERIALS LEGEND

SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
1-01	SODDED LAWN AREA LAWN AREAS SHALL BE SOD. NEW TURF AREAS TO BE SODDED WITH 18% "BLUESTAR KENTUCKY BLUEGRASS, 19% "MARQUIS" KENTUCKY BLUEGRASS, 17% "NEWPORT" KENTUCKY BLUEGRASS, 17% "TOUCHDOWN" KENTUCKY BLUEGRASS, 16% "APM PERENNIAL RYEGRASS, 13% "ACCENT PERENNIAL RYEGRASS OR APPROVED EQUAL AT A RATE OF 220 LBS. PER ACRE. FINE LEVEL ALL AREAS PRIOR TO LAYING SOD. ALL LAWN AREAS SHALL BE IRRIGATED WITH 100% COVERAGE BY POP-UP SPRAY HEADS AND GEAR-DRIVEN ROTORS. ALL DECIDUOUS AND CONIFER TREES PLANTED WITHIN SOD AREAS SHALL HAVE A FOUR FOOT(4') DIAMETER TREE RING COVERED WITH CHOCOLATE BROWN BARK MULCH, NO SHREDDED FINES. SUBMIT SAMPLES TO BE APPROVED BY LANDSCAPE ARCHITECT AND OWNER BEFORE INSTALLATION.	19,174 sf
1-03	OQUIRRH GRAVEL STONE MULCH OR APPROVED EQUAL PLANTING AREAS TO RECEIVE MIN. 6" DEPTH OF QUALITY TOPSOIL. IF TOPSOIL IS PRESENT ON SITE, PROVIDE SOIL TEST TO DETERMINE SOIL QUALITY FOR PROPOSED PLANTINGS. PROVIDE 3" DEPTH OF STONE MULCH TOP DRESSING.	61,490 sf

SYMBOL	1 LANDSCAPE DESCRIPTION	QTY
1-07	BOULDERS - 2'-3'	35

ISSUE DATE: 11/11/2021 | PROJECT NUMBER: UT21101

NO.	REVISION	DATE
1	CITY COMMENTS: ADDED PERIMETER TREES	11-11-2021
2		
3		
4		
5		
6		
7		

PLAN INFORMATION

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

0' 10' 20' 40' 80'
GRAPHIC SCALE: 1" = 20'

PROJECT INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture / Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
812812 - 5301
11/11/2021
ELECTRONIC SEAL
STATE OF UTAH


DRAWING INFO

PM: JTA
DRAWN: ACP
CHECKED: JMA
PLOT DATE: 11/11/2021


LANDSCAPE PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION


LP-106




A DECIDUOUS TREE PLANTING
NOT TO SCALE
PKJ DESIGN GROUP




B TREE ON SLOPE 5% (20:1) TO 50% (2:1)
NOT TO SCALE
PKJ DESIGN GROUP




C TREE W/ BERM (EXISTING SOIL MODIFIED)
NOT TO SCALE
PKJ DESIGN GROUP




D EVERGREEN TREE PLANTING
NOT TO SCALE
PKJ DESIGN GROUP




E SHRUB - MODIFIED SOIL
NOT TO SCALE
PKJ DESIGN GROUP




F PERENNIAL PLANTING
NOT TO SCALE
PKJ DESIGN GROUP




G METAL EDGING DETAIL
NOT TO SCALE
PKJ DESIGN GROUP



H PERENNIAL/GROUNDCOVER PLANTING
NOT TO SCALE
PKJ DESIGN GROUP



I SOD LAYING/MULCH DETAIL
NOT TO SCALE
PKJ DESIGN GROUP



J BOULDER AND DRY STREAM BED DETAIL
NOT TO SCALE
PKJ DESIGN GROUP

ISSUE DATE	PROJECT NUMBER
7/20/2021	UT21101

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

PLAN INFORMATION

PROJECT INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture / Planning &Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
STATE OF UTAH
7/20/2021

DRAWING INFO

PM:	JTA
DRAWN:	ACP
CHECKED:	JMA
PLOT DATE:	7/20/2021

LANDSCAPE DETAILS

PRELIMINARY PLANS NOT FOR CONSTRUCTION

LP-501

DEER PARK
AMERICAN FORK, UTAH

IRRIGATION PLAN SPECIFICATIONS

IRRIGATION SPECIFICATIONS

PART 1 - GENERAL

1.1 SUMMARY

Work to be done includes all labor, materials, equipment and services required to complete the Project irrigation system as indicated on the Construction Drawings, and as specified herein. Includes but is not limited to: Furnishing and installing underground and above ground sprinkler system complete with any accessories necessary for proper function and operation of the system. All plant material on the Project shall be irrigated. Remove and dispose of any existing sprinkler system components which are disturbed during the construction process and are not to be saved. Restoration of any altered or damaged existing landscape to original state and condition.

1.2 SYSTEM DESCRIPTION

A. Design of irrigation components: Locations of irrigation components on Construction Drawings may be approximate. Piping, sleeving and/or other components shown on Construction drawings may be shown schematically for graphic clarity and demonstration of component groupings and separations. All irrigation components shall be placed in landscaped areas, with the exception of popc and wire in sleeving under hardscapes. Actual routing of pipe, wire or other components may be altered due to site conditions not accounted for in the design process.

B. Construction requirements: Actual placement may vary as required to achieve a minimum of 100% coverage without overspray onto hardscape, buildings or other features.

C. Layout of Irrigation Components: During layout and staking, consult with Owner Approved Representative (hereafter referred to as OAR) to verify proper placement of irrigation components, and to provide Contractor recommendations for changes where revisions may be advisable. Small or minor adjustments to system layout are permissible to avoid existing field obstructions such as utility boxes or street light poles. Contractor shall place remote control valves in groups as practical to economize on quantity of manifold isolation valves. Quick coupler valves shall be placed with manifold groups and protected by manifold isolation valves. Quick coupler valves are shown on Construction Documents in approximate locations.

1.3 DEFINITIONS

A. Water Supply: Secondary water piping and components, furnished and installed by others to provide irrigation water to this Project, including but not limited to filter, saddles, nipples, spools, shut off valves, corporation stop valves, water meters, pressure regulation valves, and piping upstream of (or prior to) the Point of Connection.

B. Point of Connection: Location where the Contractor shall tie into the water supply. May require filter, saddle, nipples, spools, isolation valves or Stop and Waste valve for landscape irrigation needs and use.

C. Main Line Piping: Pressurized piping downstream of the Point of Connection to provide water to remote control valves and quick couplers. Normally under constant pressure.

D. Lateral Line Piping: Circuit piping downstream of remote control valves to provide water to sprinkler heads, drip systems or bubblers.

1.4 REFERENCES

A. The following standards will apply to the work of this Section:

a. ASTM-American Society for Testing and Materials

b. IA - The Irrigation Association: Main BMP Document, Landscape Irrigation Scheduling and Water Management Document.

1.5 SUBMITTALS

A. At least thirty (30) days prior to ordering of any materials, the Contractor shall provide manufacturer catalog cut sheet and current printed specifications for each element or component of the irrigation system. Submittals shall be in three ring binders or other similar bound form. Provide five copies of submittals to OAR for distribution. Place cover or index sheet indicating order in submittal document. No material shall be ordered, delivered or any work preceded in the field until the required submittals have need reviewed in its entirety and stamped approved. Delivered material shall match the approved samples.

B. Operation and Maintenance Manual:

a. At least thirty (30) days prior to final inspection, the Contractor shall provide Operation and Maintenance manual to OAR, containing:

i. Manufacturer catalog cut sheet and current printed specifications for each element or component of the irrigation system.

ii. Parts list for each operating element of the system

iii. Manufacturer printed literature on operation and maintenance of operating elements of the system.

iv. Section listing instructions for overall system operation and maintenance. Include directions for Spring Start-up and Winterization.

b. Project Record Copy

i. Maintain at project site one copy of all project documents clearly marked "Project Record Copy". Mark any deviation in material installation on Construction drawings. Maintain and update drawing at least weekly. Project Record Copy to be available to OAR on demand.

ii. Completed Project As-Built Drawings

1. Prior to final inspection, prepare and submit to OAR accurate as-built drawings
2. Show detail and dimension changes made during installation. Show significant details and dimensions that were not shown in original Contract Documents.
3. Field dimension locations of sleeving, points of connection, main line piping, wiring runs not contained in main line pipe trenches, valves and valve boxes, quick coupler valves.
4. Dimensions are to be taken from permanent constructed surfaces, features, or finished edges located at or above finished grade.
5. Controller Map: upon completion of system, place in each controller a color coded copy of the area that controller services: indicating zone number, type of plant material and location on project that zone services. Laminate map with heat shrink clear plastic.

1.6 QUALITY ASSURANCE

A. Acceptance: Do not install work in this section prior to acceptance by OAR.

B. Regulatory Requirements: All work and materials shall be according to any and all rules, regulations or codes, whether they are State or Local laws and ordinances. Contract documents, drawings or specifications may not be construed or interpreted to permit work or materials not conforming to the above codes.

C. Adequate Water Supply: Water supply to this Project exists, installed by others. Connections to these supply lines shall be by this Contractor. Verify that proper connection is available to supply line and is of adequate size. Verify that secondary connection components may be installed if necessary. Perform static pressure test prior to commencement of work. Notify OAR in writing of problems encountered prior to proceeding.

D. Workmanship and Materials:

a. It is the intent of this specification that all material herein specified and shown on the construction documents shall be of the highest quality available and meeting the requirements specified.

b. All work shall be performed in accordance with the best standards of practice relating to the trade.

E. Contractor Qualifications:

a. Contractor shall provide document or resume including at least the following items:

i. That Contractor has been installing sprinklers on commercial projects for five previous consecutive years.

ii. Contractor is licensed to perform Landscape and Irrigation construction in the State of this Project.

iii. Contractor is bondable for the work to be performed.

iv. References of five projects of similar size and scope completed within the last five years. Three of the projects listed shall be local.

v. Listing of suppliers where materials will be obtained for use on this Project.

vi. Project site Foreman or Supervisor has at least five consecutive years of commercial irrigation installation experience. This person shall be a current Certified Irrigation Contractor in good standing as set forth by the Irrigation Association. This person shall be on Project site at least 75% of each working day.

vii. Evidence that Contractor currently employs workers in sufficient quantities to complete Project within time limits that are established by the Contract.

viii. All General laborers or workers on the Project shall be previously trained and familiar with sprinkler installation and have a minimum of one-year experience. Those workers performing tasks related to PVC pipe shall have certificates designated below.

1.7 DELIVERY-STORAGE-HANDLING

A. During delivery, installation and storage of materials for Project, all materials shall be protected from contamination, damage, vandalism, and prolonged exposure to sunlight. All material stored at Project site shall be neatly organized in a compact arrangement and storage shall not disrupt Project Owner or other trades on Project site. All material to be installed shall be handled by Contractor with care to avoid breakage or damage. Damaged materials attributed to Contractor shall be replaced with new at Contractor's expense.

1.8 SEQUENCING

A. Perform site survey, research utility records, contact utility location services. The Contractor shall familiarize himself with all hazards and utilities prior to work commencement. Install sleeving prior to installation of concrete, paving or other permanent site elements. Irrigation system Point of Connection components, backflow prevention and pressure regulation devices shall be installed and operational prior to all downstream components. All main lines shall be thoroughly flushed of all debris prior to installation of any sprinkler heads.

1.9 WARRANTY

A. Contractor shall provide one year Warranty. Warranty shall cover all materials, workmanship and labor. Warranty shall include filling and or repairing depressions or replacing turf or other plantings due to settlement of irrigation trenches or irrigation system elements. Valve boxes, sprinklers or other components settled from original finish grade shall be restored to proper grade. Irrigation system shall have been adjusted to provide proper, adequate coverage of irrigated areas.

1.10 OWNER'S INSTRUCTION

A. After system is installed, inspected, and approved, instruct Owner's Representatives in complete operation and maintenance procedures. Coordinate instruction with references to previously submitted Operation and Maintenance Manual.

1.11 MAINTENANCE

A. Furnish the following items to Owner's Representative:

a. Two quick coupler keys with hose swivels.

b. One of each type or size of quick coupler valve and remote control valve. Five percent of total quantities used of each sprinkler and sprinkler nozzle.

B. Provide the following services:

a. Winterize entire irrigation system installed under this contract. Winterize by 'blow-out' method using compressed air. Compressor shall be capable of minimum of 175 CFM. This operation shall occur at the end of first growing season after need for plant irrigation but prior to freezing. Compressor shall be capable of evacuating system of all water pressure regulation devices. Compressor shall be regulated to not more than 60 PSI. Start up system the following spring after danger of freezing has passed. Contractor shall train Owner's Representative in proper start-up and winterization procedure.

PART 2 - PRODUCTS

2.1 GENERAL NOTES

A. Contractor shall provide materials to be used on this Project. Contractor shall not remove any material purchased for this Project from the Project Site, nor mix Project materials with other Contractor owned materials. Owner retains right to purchase and provide project material.

2.2 POINT OF CONNECTION

A. The Contractor shall connect onto existing irrigation or water main line as needed for Point(s) of Connection. Contractor shall install new main line as indicated.

2.3 CONNECTION ASSEMBLY

A. Secondary water shall be used on this Project. Install filter and RPZ as needed.

2.4 CONTROL SYSTEM

A. Power supply to the irrigation controller shall be provided for by this Contract.

B. Controller shall be as specified in the drawings. Controller shall be surge protected.

a. Installation of wall-mount/ground pedestal timer controllers: Irrigation contractor shall be responsible for this task. Power configuration for wall-mount/ground pedestal timer controllers shall be 120 VAC unless otherwise noted.

b. Locate Controller(s) in general location shown on Construction drawings. Coordinate power supply and breaker allocation with electrical contractor. Contractor shall be responsible for all power connections to Controllers, whether they are wall mount or pedestal mount. Contractor shall coordinate with electrical or other Project trades as needed to facilitate installation of power to controllers.

C. Wires connecting the remote control valves to the irrigation controller are single conductors, type PE. Wire construction shall incorporate a solid copper conductor and polyethylene (PE) insulation with a minimum thickness of 0.045 inches. The wires shall be UL listed for direct burial in irrigation systems and be rated at a minimum of 30 VAC. Paige Electric Co., LP specification number P7079D.

a. A minimum of 24" of additional wire shall be left at each valve, each splice box and at each controller.

b. Common wire shall be white in color, 12 gauge. Control wire shall be red in color, 14 gauge. Spare/extra wire (3 ft.) shall be looped within each valve box of the grouping it is to service.

D. RCV wire splicing connectors shall be 3M brand DBY or DBR. Wire splicing between controller and valves shall be avoided if at all possible. Any wire splices shall be contained within a valve box. Splices within a valve box that contains no control valves shall be stamped 'WIRE SPLICE' or 'WS' on box lid.

2.5 SLEEVING

A. Contractor shall be responsible to protect existing underground utilities and components. Sleeving minimum size shall be 2". Sleeving 2" through 4" in size shall be S/40 PVC solvent weld. Sleeving 6" and larger shall be CL 200 PVC gasketed. Sleeve diameter shall be at least two times the diameter of the pipe within the sleeve. Sleeves shall be extended 6" minimum beyond walk or edge of pavement. Wire or cable shall not be installed in the same sleeve as piping, but shall be installed in separate sleeves. Sleeve ends on sleeve sizes 4" and larger shall be capped with integral corresponding sized PVC slip cap, pressure fit, until used, to prevent contamination. Sleeves shall be installed at appropriate depths for main line pipe or lateral pipe.

2.6 MAIN LINE PIPE

A. All main line pipe 4" and larger shall be Class 200 gasketed bell end. All main line pipe 3" in size and smaller shall be Schedule 40 PVC solvent weld bell end.

a. Maximum flows allowed through main line pipe shall be:

3/4"	8 GPM
1"	12 GPM
1-1/2"	30 GPM
2"	53 GPM
2-1/2"	75 GPM
3"	110 GPM
4"	180 GPM

b. Main line pipe shall be buried with 24" cover

2.7 MAIN LINE FITTINGS

A. All main line fittings 3" and larger shall be gasketed ductile iron material. All ductile iron fittings having change of direction shall have proper concrete thrust block installed. All main line fittings smaller than 3" in size shall be Schedule 80 PVC.

2.8 ISOLATION VALVES

A. Isolation valves 3" and larger shall be Waterous brand model 2500 cast iron gate valve, resilient wedge, push on type, with 2" square operating nut. Place sleeve of 6" or larger pipe over top of valve vertically and then extend to grade. Place 10" round valve box over sleeve at grade.

B. Isolation valves 2-1/2" and smaller shall be Apollo brand 70 series brass ball valves, contained in a Carson Standard size valve box. Valves shall be installed with S/80 PVC TOE Nipples on both sides of the valve. Valve shall be placed so that the handle is vertical toward the top of the valve box in the 'off' position.

2.9 MANIFOLDS

A. Action Manifold fittings shall be used to create unions on both sides of each control valve, allowing the valve to be removed from the box without cutting piping. Valves shall be located in boxes with ample space surrounding them to allow access for maintenance and repair. Where practical, group remote control valves in close proximity, and protect each grouping with a manifold isolation valve as shown in details. Manifold Main Line (or Sub-Main Line) and all manifold components and isolation valves shall be at least as large as the largest diameter lateral served by the respective manifold.

2.10 REMOTE CONTROL VALVES

A. Remote control valves shall be as specified on the drawings. Remote control valves shall be located separately and individually in separate control boxes.

2.11 MANUAL CONTROL VALVES

A. Quick coupler valve shall be attached to the manifold sub-main line using a Lasco G175212 swing joint assembly with snap-lock outlet and brass stabilizer elbow. Quick coupler valve shall be placed within a Carson 10" round valve box. Top of quick coupler valve cover shall allow for complete installation of valve box lid, but also allow for insertion and operation of key. Base of quick coupler valve and top of quick coupler swing joint shall be encased in ¼" gravel. Contractor shall not place quick coupler valves further than 200 feet apart, to allow for spot watering or supplemental irrigation of new plant material. Quick coupler valve at POC shall not be eliminated or relocated.

2.12 LATERAL LINE PIPE

A. All lateral piping shall be Schedule 40 PVC, solvent weld, and bell end. Lateral pipe shall be buried with 12-18" of cover typically. Lateral pipe shall be ¾", 1", 1 ¼", 1 ½" or 2" in size as indicated on Construction Drawings.

2.13 LATERAL LINE FITTINGS

A. All lateral line fittings shall be S/40 PVC

2.14 Spray Sprinklers

A. Spray head sprinklers shall be as specified on the drawings. Nozzles shall be as specified on the drawings.

2.15 VALVE BOXES

A. Rainbird valve boxes shall be used on this project. Sizes are as directed in these Specifications, detail sheets or plan sheets. Valve boxes shall be centered over the control valve or element they cover. Valve box shall be sized large enough to allow ample room for services access, removal or replacement of valve or element. Valve box shall be set to flush to finish grade of topsoil or barked areas. Contractor shall provide extensions or stack additional valve boxes as necessary to bring valve box pit to proper grade.

2.16 IMPORT BACKFILL

A. All main line pipe, lateral line pipe and other irrigation elements shall be bedded and backfilled with clean soil, free of rocks 1" and larger. Contractor shall furnish and install additional backfill material as necessary due to rocky conditions. Trenches and other elements shall be compacted and/or water settled to eliminate settling. Debris from trenching operations un-usable for fill shall be removed from project and disposed of properly by Contractor.

2.17 OTHER PRODUCTS

A. Substitution of equivalent products is subject to the OAR's approval and must be designated as accepted in writing.

a. The Contractor shall provide materials to make the system complete and operational.

PART 3 - EXECUTION

3.1 PREPARATION

A. Contractor shall repair or replace work damaged by irrigation system installation. If damaged work is new, repair or replacement shall be performed by the original installer of that work. The existing landscape of this Project shall remain in place. Contractor shall protect and work around existing plant material. Coordination of trench and valve locations shall be laid out for the OAR prior to any excavation occurring. Plant material deemed damaged by the OAR shall be replaced with new plant material at Contractor's expense. Contractor shall not cut existing tree roots larger than 2" to install this Project. Route pipe, wire and irrigation elements around tree canopy drip line to minimize damage to tree roots. Contractor shall have no part of existing system used by other portions of site landscape without water for more than 24 hours at a time.

3.2 TRENCHING AND BACKFILLING

A. Pulling of pipe shall not be permitted on this project. Over excavate trenches both in width and depth. Ensure base of trench is rock or debris free to protect pipe and wire. Grade trench base to ensure flat, even support of piping. Backfill with clean soil or import material. Contractor shall backfill no less than 2" around entire pipe with clean, rock free fill. Main line piping and fittings shall not be backfilled until OAR has inspected and pipe has passed pressure testing. Perform balance of backfill operation to eliminate any settling.

3.3 SLEEVING

A. Sleeve all piping and wiring that pass under paving or hardscape features. Wiring shall be placed in separate sleeving from piping. Sleeves shall be positioned relative to structures or obstructions to allow for pipe or wire within to be removed if necessary.

3.4 GRADES AND DRAINAGE

A. Place irrigation pipe and other elements at uniform grades. Winterization shall be by evacuation with compressed air. Automatic drains shall not be installed on this Project. Manual drains shall only be installed at POC where designated on Construction Drawings.

3.5 PVC PIPE

A. Install pipe to allow for expansion and contraction as recommended by pipe manufacturer.

B. Install main line pipes with 18" of cover, lateral line pipes with 12" of cover.

C. Drawings show diagrammatic or conceptual location of piping - Contractor shall install piping to minimize change of direction, avoid placement under large trees or large shrubs, avoid placement under hardscape features.

D. Plastic pipe shall be cut squarely. Burrs shall be removed. Spigot ends of pipes 3" and larger shall be beveled.

E. Pipe shall not be glued unless ambient temperature is at least 50 degress F. Pipe shall not be glued in rainy conditions unless properly tented. All solvent weld joints shall be assembled using IPS 711 glue and P70 primer according to manufacturer's specification, no exceptions. All workers performing glue operations shall provide evidence of certification. Glued main line pipe shall eure a minimum of 24 hours prior to being energized. Lateral lines shall eure a minimum of 2 hours prior to being energized and shall not remain under constant pressure unless cured for 24 hours.

F. Appropriate thrust blocking shall be performed on fittings 3" and larger. All threaded joints shall be wrapped with Teflon tape or paste unless directed by product manufacturer or sealing by o-ring.

3.6 CONTROLLERS

A. All grounding for pedestal controllers shall be as directed by controller manufacturer and ASIC guidelines, not to exceed a resistance reading of 5 OHMs.

B. Locate controllers in protected, inconspicuous places, when possible. Coordinate location of pedestal controllers with Landscape Architect to minimize visibility.

C. Coordinate location of wall mount controllers with building or electrical Contractor to facilitate electrical service and future maintenance needs. Wall mount shall be securely fastened to surface. If exterior mounted, wall mount controllers shall have electrical service wire and field control wire in separate, appropriate sized weatherproof electrical conduit, PVC pipe shall not be used.

D. Wiring under hardscape surfaces shall be placed continuously in conduit. Contractor shall be responsible to coordinate sleeving needs for conduit or sweeps elbows from exterior to interior of building.

E. Pedestal controllers shall be placed upon VIT-Strong Box Quick Pad as per manufacturer's recommendations. Controllers shall be oriented such that Owner's Representative maintenance personnel may access easily and perform field system tests efficiently.

F. Place Standard valve box at base of controller or nearby to allow for three to five feet of slack field control wire to be placed at each controller. This Contractor shall provide conduit access if needed for Electrical Contractor. Electrical supply and installation, as well as hook-up to controller shall be by this Contractor.

3.7 VALVES

A. Isolation valves, remote control valves, and quick coupler valves shall be installed according to manufacturer recommendation and Contract Specifications and Details.

B. Valve boxes shall be set over valves so that all parts of the valve can be reached for service.

C. Valve box and lid shall be set to be flush with finished grade. Only one remote control valve may be installed in a Carson 1419124 box. Place a minimum of 4" of ¼" washed gravel beneath valve box for drainage. Bottom of remote control valve shall be a minimum of 2" above gravel.

3.8 SPRINKLER HEADS

A. No sprinkler shall be located closer than 6" to walls, fences, or buildings.

B. Heads adjacent to walks, curbs, or paths shall be located at grade and 2" away from hardscape.

C. Control valves shall be opened. Then fully flush lateral line pipe and swing joints prior to installation of sprinklers.

D. Spray heads shall be installed and flushed again prior to installation of nozzles.

E. Contractor shall be responsible for adjustment if necessary due to grade changes during landscape construction.

3.9 FIELD QUALITY CONTROL

A. Main line pipes shall not be backfilled or accepted until the system has been tested for 2 hours at 100 psi.

B. Main line pressure test shall include all pipe and components from the point of connection to the upstream side of remote control valves. Test shall include all manifold components under constant pressure. Piping may be tested in sections that can be isolated.

C. Contractor shall provide pressurized water pump to increase or boost pressure where existing static pressure is less than 100 psi.

D. Schedule testing with OAR 48 hours in advance for approval.

E. Leaks or defects shall promptly be repaired or rectified at the Contractors expense and retested until able to pass testing.

F. Grounding resistance at pedestal controller shall also be tested and shall not exceed 5 OHMs.

3.10 ADJUSTMENT

A. Sprinkler heads shall be adjusted to proper height when installed. Changes in grade or adjustment of head height after installation shall be considered a part of the original contract and at Contractor's expense.

B. Adjust all sprinkler heads for arc, radius, proper trim and distribution to cover all landscaped areas that are to be irrigated.

C. Adjust sprinklers so they do not water buildings, structures, or other hardscape features.

D. Adjust run times of station to meet needs of plant material the station services.

3.11 CLEANING

A. Contractor shall be responsible for cleanliness of jobsite. Work areas shall be swept cleanly and picked up daily.

B. Open trenches or hazards shall be protected with yellow caution tape.

C. Contractor is responsible for removal and disposal of offsite trash and debris generated as a result of this Project.

D. OAR shall perform periodic as well as a final cleanliness inspection.

E. Contractor shall leave Project in at least a 'broom clean' condition.

END OF SECTION

90 Day Establishment Period Irrigation Schedule (April, May, June)

	Type	Sun	Mon	Tues	Wed	Thurs	Fri	Sat	Operating Pressure
Turf	Turf	15 min	15 min	15 min	15 min	15 min	15 min	15 min	30 psi
Shrubs	Shrubs	25 min	0	25 min	0	25 min	0	25 min	40 psi

Note: Begin irrigation 4:00 am, only 1 cycle per day.


Regular Irrigation Schedule (see Seasonal Differential Chart)

	Type	Sun	Mon	Tues	Wed	Thurs	Fri	Sat	Operating Pressure
Turf	Turf	15 min	15 min		15 min		15 min		30 psi
Shrubs	Shrubs	45 min		45 min		45 min		45 min	40 psi

Note: Begin irrigation 4:00 am, only 1 cycle per day.

Seasonal Differential

	April	May	June	July	August	Sept.	October
Turf	10 min	10 min	15 min	15 min	15 min	10 min	10 min
Shrubs	30 min	30 min	45 min	45 min	45 min	30 min	30 min



2" MAINLINE ROUTING ,CONTROLLER AND P.O.C. LOCATION OVERVIEW

ISSUE DATE	PROJECT NUMBER
7/20/2021	UT21101

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

PLAN INFORMATION

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

N

0' 60' 120' 240' 480'

GRAPHIC SCALE: 1" = 120'

PROJECT INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture / Planning &Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
8728121-5301
07/06/2021
ELECTRONIC SEAL
STATE OF UTAH


DRAWING INFO

PM: JTA
DRAWN: ACP
CHECKED: JMA
PLOT DATE: 7/20/2021

IRRIGATION PLAN COVER

PRELIMINARY PLANS NOT FOR CONSTRUCTION

IR-100



ISSUE DATE	PROJECT NUMBER	PLAN INFORMATION
7/20/2021	UT21101	

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

N

0' 25' 50' 100' 200'
GRAPHIC SCALE: 1" = 50'

PROJECT INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture / Planning &Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

UTAH LICENSED LANDSCAPE ARCHITECT
JEREMY TA ANDWORTH
812812-5301
07/26/2021
ELECTRONIC SEAL
STATE OF UTAH


DRAWING INFO

PM:	JTA
DRAWN:	ACP
CHECKED:	JMA
PLOT DATE:	7/20/2021

IRRIGATION PLAN OVERALL

PRELIMINARY PLANS NOT FOR CONSTRUCTION

IR-O



IRRIGATION LEGEND

SYMBOL	MANUFACTURER-MODEL NUMBER
	RAINBIRD RD04-S-PRS POP UP SPRAY 5 SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 8 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 10 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 12 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 SST @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 EST @ 30 PSI
	RAINBIRD 5000 SERIES MPR NOZZLES @ 55 PSI
	RAINBIRD 8005 SERIES Q#8-6.6 GPM, H#14-12.6 GPM, F#26-24.3 GPM NOZZLES @ 55 PSI
S	POINT OF CONNECTION (SECONDARY WATER) SEE PLAN FOR SIZE
A	CONTROLLER:RAINBIRD ESP-LXIVM WITH LIMR REMOTE KIT, PLACE IN FIRE RISER ROOM, CONTRACTOR TO ADJUST LOCATION WITH OWNER PRIOR TO CONSTRUCTION.
R	RAINBIRD WR2-RC WIRELESS RAIN SHUT OFF DEVICE
	ISOLATION BALL VALVE - LINE SIZED INSTALL PER MANUFACTURER'S SPEC.
	2" T SUPER AMIAD PLASTIC FILTER - INSTALL PER MANUFACTURE'S. RECOMMENDATIONS (130 MICRON)
M	MASTER VALVE
F	FLOW SENSOR
Q	QUICK COUPLER: RAINBIRD 44LRC INSTALL PER MANUFACTURER'S SPEC.
DEC / L	VALVE DECODER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC. LIGHTNING ARRESTER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC.
	REMOTE CONTROL VALVE: RAINBIRD IVMSOL AUTOMATIC CONTROL VALVE (SIZE AS NOTED ON PLAN- USE JUMBO BOX-PURPLE LID) PLACE YELLOW TAGS ON ALL VALVES AND LABEL.
	DRIP CONTROL ZONE KIT: RAINBIRD XCZ-(PER PLAN)-PRBR-COM MED FLOW (SIZE AS NOTED ON PLAN)
	MAINLINE: SCHEDULE 40 PVC WITH SCHEDULE 80 FITTINGS, 2" DIAMETER 24" MIN. COVER
	LATERAL LINE: SCHEDULE 40 PVC WITH SCH. 40 FITTINGS. SEE PIPE SIZING CHART
*	DRIP CONNECTION. PROVIDE DRIP IRRIGATION TO ALL TREES, SHRUBS,AND PERENNIALS IN PLANTER AREAS
	DRIP LINE: RAINBIRD XFSP-09-18-100 OR EQUIVALENT
	CLASS 200 SLEEVE PER PLAN
NO SYMBOL	WIRE CHASE, SIZE TO BE TWICE THE DIAMETER OF THE WIRE BUNDLE WITHIN. 1.1/4" DIAMETER MINIMUM 14 GAUGE SOLID COPPER SINGLE STRAND CONTROL WIRE. INSTALL PER MANUFACTURER'S SPEC. PROVIDE 2 WIRE LOOP SYSTEM. ONLY WIRE FROM POC TO CONTROLLER IS DEPICTED ON PLANS. CONTRACTOR TO INSTALL WIRE IN CONDUIT FROM POC TO ALL VALVES. THE WIRE TO VALVES IS NOT SHOWN ON PLAN

DRIP ZONE

TYPE	PART NUMBER	EMITTER FLOW		
XFS DRIPLINE	XFSP-09-18	.9 GPH		
TOTAL DRIP ZONE FLOW		20 GPM	*EACH ZONE NOT TO EXCEED 20 GPM	
NUMBER OF FLUSH POINTS		2	DRIP ZONE TO APPLY 1/4" OF WATER	23
*ONLY WATER PLANT SPECIFICALLY - DO NOT WATER ROCK AREA WITH NO PLANTS				
*NUMBERS MAY CHANGE DUE TO SIZE OF DRIP ZONE PER PLAN				

IRRIGATION NOTES

1. BEFORE WORK IS TO COMMENCE, BLUE STAKES/DIG LINE IS TO BE CALLED AND NOTIFIED. IF ANY DAMAGE TO UTILITIES HAPPEN DURING CONSTRUCTION, THE CONTRACTOR SHALL REPAIR IT AT THEIR EXPENSE WITH NO ADDITIONAL COST TO THE OWNER.
2. CONTRACTOR SHALL APPLY AND PAY FOR ALL NECESSARY PERMITS IN ACCORDANCE WITH CITY AND/OR COUNTY CODES AND COMPLY WITH SPECIFICATIONS AND DRAWINGS.
3. INVESTIGATE TO MAKE SURE THAT THE IRRIGATION SYSTEM IS, IN FACT, BEING CONNECTED TO A SECONDARY SYSTEM. IF IT IS NOT CONNECTED TO SECONDARY, CONTACT THE OWNER AND LANDSCAPE ARCHITECT TO COORDINATE A CULINARY SYSTEM AND REQUIRED COMPONENTS. A FUNCTIONING AMIAD FILTER IS TO BE USED AT THE POINT OF CONNECTION.
4. VERIFY THAT THE POINT OF CONNECTION IS IN THE CORRECT LOCATION BEFORE INSTALLATION. ALL CONNECTIONS ON THIS PROJECT ARE TO SECONDARY WATER AND SHOULD BE NOTED AS SUCH; THEREFORE, ALL PARTS MUST MEET WATER STANDARDS THAT PERTAIN TO SECONDARY WATER.USE PURPLE VALVE BOXES FOR SECONDARY WATER SYSTEMS.
5. ON OCCASION AND FOR GRAPHIC PURPOSES ONLY, THE IRRIGATION SYSTEM MIGHT BE SHOWN IN HARDSCAPE AREAS. THIS IRRIGATION IS TO BE PLACED IN LANDSCAPED AREAS ON THE PROPERTY SITE.
6. CONTRACTOR SHALL USE ONLY COMMERCIAL GRADE IRRIGATION PRODUCTS. THIS INCLUDES PIPE TO BE SCHEDULE 40 PVC OR BETTER. NO POLY PIPE IS TO BE USED. FITTINGS UP TO 1-1/2" MUST BE SCHEDULE 40 OR BETTER. FITTINGS LARGER THAN 1-1/2" SHALL BE SCHEDULE 80 OR BETTER. CONTRACTOR IS RESPONSIBLE FOR ENSURING ACCURATE COUNTS AND QUANTITIES OF ALL IRRIGATION MATERIALS FOR BIDDING AND INSTALLATION.
7. MAIN LINES SHALL BE A MINIMUM OF 24" DEEP AND LATERAL LINES A MINIMUM OF 12" DEEP. NO ROCK GREATER THAN 1/2" DIAMETER SHALL BE ALLOWED IN TRENCHES. TRENCHING BACKFILL MATERIAL SHALL BE COMPACTED TO PROPER FINISHED GRADE.
8. NO IRRIGATION MAIN LINE MAY BE LOCATED WITHIN 5 FEET OF ANY STRUCTURE.
9. TO AVOID PIPE DAMAGE, ADJUST LOCATION OF PIPE TO NOT BE DIRECTLY UNDER PLANT MATERIALS. VALVE BOXES ARE PREFERRED TO BE IN PLANTER BEDS INSTEAD OF THE LAWN.
10. PLAN INDICATES 100% OR BETTER HEAD TO HEAD COVERAGE. SHOULD CONTRACTOR FIND DISCREPANCIES DUE TO NECESSARY FIELD ADJUSTMENTS, CONTACT LANDSCAPE ARCHITECT FOR IRRIGATION CORRECTION.
11. DRIP IRRIGATION TO BE INSTALLED PER DETAILS. CONTRACTOR SHALL MAKE NECESSARY ADJUSTMENTS. TUBING SHOULD REST TOWARD OUTER EDGE OF ROOTBALL AND NOT AGAINST TRUNK OF PLANT.
12. A QUICK COUPLER SHALL BE INSTALLED AT POINT OF CONNECTION TO ALLOW BLOW OUT OF SYSTEM BY AIR COMPRESSOR AT END OF EACH SEASON.
13. INSTALL SLEEVES FOR ALL PIPES AND WIRE CONDUIT THAT ARE PLACED UNDER PAVEMENT AND SIDEWALKS. SLEEVES SHALL BE 2 SIZES LARGER THAN PIPE BEING PLACED INTERNALLY. WIRE CONDUIT SHALL BE INSTALLED IN CLASS 200 PIPE. AT ANY DIRECTIONAL CHANGE THAT OCCURS, A JUNCTION BOX IS TO PLACED.
14. CONDUITS CAN NOT BE SHARED BY WATER AND ELECTRICAL LINES. ALL WIRE TO BE PUT IN PVC CONDUIT. ALL WIRE CONNECTIONS TO BE PLACED IN A VALVE BOX. ALL WIRE CONNECTIONS TO USE WATERPROOF WIRE CONNECTORS WITH AT LEAST 3' OF EXTRA WIRE. PROVIDE PLENTY OF EXTRA WIRE AT EVERY DIRECTIONAL CHANGE. INSULATED 14 GAUGE COPPER TO BE USED FOR ALL CONTROL WIRES AND INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
15. CONTRACTOR TO INSTALL LIGHTNING ARRESTOR AND GROUNDING RODS ON SITE PER MANUFACTURER'S RECOMMENDATIONS, SEE DETAILS.
16. CONTRACTOR TO SEPARATE SYSTEM (CONTROLLER, VALVES, AND DIFFERENT COLORED WIRE) FROM CITY MAINTAINED PROPERTY AND HOA/OWNER MAINTAINED PROPERTY.
17. DUCT TAPE ALL SLEEVES TO PREVENT SOIL OR OTHER DEBRIS ENTERING PIPE. IDENTIFY ALL SLEEVES BY WOOD OR PVC STAKES AND SPRAY PAINT WITH MARKING PAINT. REMOVE STAKES ONCE IRRIGATION SYSTEM IS COMPLETE.
18. TO PREVENT EROSION AND LOW POINT DRAINAGE CONTRACTOR SHALL INSTALL CHECK VALVES
19. LOCATE SPRAY HEADS NO CLOSER THAN 6" FROM WALLS, FENCES OR BUILDINGS AND 2" AWAY FROM WALKS, PATHS OR CURBS.
20. PRESSURE TEST MAINLINE FOR LEAKS PRIOR TO BACKFILLING. CONTACT LANDSCAPE ARCHITECT/OWNER AT THIS TIME FOR COMPLIANCE.
21. CONTRACTOR TO CONSULT WITH OWNER ON EXACT LOCATION OF CONTROLLER. CONTRACTOR TO COORDINATE WITH ELECTRICAL CONTRACTOR AND OWNER FOR THE POWER SUPPLY. INSTALL ALL PER MANUFACTURER'S SPECIFICATIONS. CONTRACTOR SHALL INSTALL A RAIN SENSOR WITH THE CONTROLLER UNLESS OTHERWISE DIRECTED BY OWNER OR LANDSCAPE ARCHITECT.
22. LATERAL LINES SHALL BE NO SMALLER THAN 3/4". LANDSCAPE CONTRACTOR TO ENSURE THE FOLLOWING PIPE SIZES DO NOT EXCEED THE SUGGESTED GPM LISTED BELOW:

3/4"	8 GPM
1"	12 GPM
1-1/2"	30 GPM
2"	53 GPM
2-1/2"	75 GPM
3"	110 GPM
4"	180 GPM

VALVE ID TAG

A1 — CONTROLLER NUMBER, VALVE NUMBER
1.0 | 18 — VALVE SIZE; GALLONS PER MINUTE
55 — PSI AT LAST HEAD IN ZONE

NOTE:
1. VALVE ID TAGS ARE LOCATED NEAR VALVES IN THE ORDER THE VALVES APPEAR ON THE DRAWING

ISSUE DATE	PROJECT NUMBER	PLAN INFORMATION
7/20/2021	UT21101	

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

N

0' 10' 20' 40' 80'
GRAPHIC SCALE: 1" = 20'

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

PROJECT INFORMATION

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

LANDSCAPE ARCHITECT / PLANNER

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

PKJ DESIGN GROUP
Landscape Architecture Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
813917-5301
07/20/2021
ELECTRONIC SEAL
STATE OF UTAH


DRAWING INFO

PM:	JTA
DRAWN:	ACP
CHECKED:	JMA
PLOT DATE:	7/20/2021

IRRIGATION PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

IR-101



IRRIGATION LEGEND

SYMBOL	MANUFACTURER-MODEL NUMBER
	RAINBIRD RD04-S-PRS POP UP SPRAY 5 SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 8 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 10 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 12 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 SST @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 EST @ 30 PSI
	RAINBIRD 5000 SERIES MPR NOZZLES @ 55 PSI
	RAINBIRD 8005 SERIES Q#8-6.6 GPM, H#14-12.6 GPM, F#26-24.3 GPM NOZZLES @ 55 PSI
S	POINT OF CONNECTION (SECONDARY WATER) SEE PLAN FOR SIZE
A	CONTROLLER:RAINBIRD ESP-LXIVM WITH LIMR REMOTE KIT, PLACE IN FIRE RISER ROOM, CONTRACTOR TO ADJUST LOCATION WITH OWNER PRIOR TO CONSTRUCTION.
R	RAINBIRD WR2-RC WIRELESS RAIN SHUT OFF DEVICE
	ISOLATION BALL VALVE - LINE SIZED INSTALL PER MANUFACTURER'S SPEC.
	2" T SUPER AMIAD PLASTIC FILTER - INSTALL PER MANUFACTURE'S. RECOMMENDATIONS (130 MICRON)
M	MASTER VALVE
F	FLOW SENSOR
Q	QUICK COUPLER: RAINBIRD 44LRC INSTALL PER MANUFACTURER'S SPEC.
DEC	VALVE DECODER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC. LIGHTNING ARRESTER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC.
L	
	REMOTE CONTROL VALVE: RAINBIRD IVMSOL AUTOMATIC CONTROL VALVE (SIZE AS NOTED ON PLAN- USE JUMBO BOX-PURPLE LID) PLACE YELLOW TAGS ON ALL VALVES AND LABEL.
	DRIP CONTROL ZONE KIT: RAINBIRD XCZ-(PER PLAN)-PRBR-COM MED FLOW (SIZE AS NOTED ON PLAN)
	MAINLINE: SCHEDULE 40 PVC WITH SCHEDULE 80 FITTINGS, 2" DIAMETER 24" MIN. COVER
	LATERAL LINE: SCHEDULE 40 PVC WITH SCH. 40 FITTINGS. SEE PIPE SIZING CHART
	DRIP CONNECTION. PROVIDE DRIP IRRIGATION TO ALL TREES, SHRUBS,AND PERENNIALS IN PLANTER AREAS
	DRIP LINE: RAINBIRD XFSP-09-18-100 OR EQUIVALENT
	CLASS 200 SLEEVE PER PLAN
NO SYMBOL	WIRE CHASE, SIZE TO BE TWICE THE DIAMETER OF THE WIRE BUNDLE WITHIN. 1.1/4" DIAMETER MINIMUM 14 GAUGE SOLID COPPER SINGLE STRAND CONTROL WIRE. INSTALL PER MANUFACTURER'S SPEC. PROVIDE 2 WIRE LOOP SYSTEM. ONLY WIRE FROM POC TO CONTROLLER IS DEPICTED ON PLANS. CONTRACTOR TO INSTALL WIRE IN CONDUIT FROM POC TO ALL VALVES. THE WIRE TO VALVES IS NOT SHOWN ON PLAN

DRIP ZONE


TYPE	PART NUMBER	EMITTER FLOW		
XFS DRIPLINE	XFSP-09-18	.9 GPH		
TOTAL DRIP ZONE FLOW		20 GPM	*EACH ZONE NOT TO EXCEED 20 GPM	
NUMBER OF FLUSH POINTS		2	DRIP ZONE TO APPLY 1/4" OF WATER	23
*ONLY WATER PLANT SPECIFICALLY. DO NOT WATER ROCK AREA WITH NO PLANTS				
*NUMBERS MAY CHANGE DUE TO SIZE OF DRIP ZONE PER PLAN				

IRRIGATION NOTES

1. BEFORE WORK IS TO COMMENCE, BLUE STAKES/DIG LINE IS TO BE CALLED AND NOTIFIED. IF ANY DAMAGE TO UTILITIES HAPPEN DURING CONSTRUCTION, THE CONTRACTOR SHALL REPAIR IT AT THEIR EXPENSE WITH NO ADDITIONAL COST TO THE OWNER.
2. CONTRACTOR SHALL APPLY AND PAY FOR ALL NECESSARY PERMITS IN ACCORDANCE WITH CITY AND/OR COUNTY CODES AND COMPLY WITH SPECIFICATIONS AND DRAWINGS.
3. INVESTIGATE TO MAKE SURE THAT THE IRRIGATION SYSTEM IS, IN FACT, BEING CONNECTED TO A SECONDARY SYSTEM. IF IT IS NOT CONNECTED TO SECONDARY, CONTACT THE OWNER AND LANDSCAPE ARCHITECT TO COORDINATE A CULINARY SYSTEM AND REQUIRED COMPONENTS. A FUNCTIONING AMIAD FILTER IS TO BE USED AT THE POINT OF CONNECTION.
4. VERIFY THAT THE POINT OF CONNECTION IS IN THE CORRECT LOCATION BEFORE INSTALLATION. ALL CONNECTIONS ON THIS PROJECT ARE TO SECONDARY WATER AND SHOULD BE NOTED AS SUCH; THEREFORE, ALL PARTS MUST MEET WATER STANDARDS THAT PERTAIN TO SECONDARY WATER.USE PURPLE VALVE BOXES FOR SECONDARY WATER SYSTEMS.
5. ON OCCASION AND FOR GRAPHIC PURPOSES ONLY, THE IRRIGATION SYSTEM MIGHT BE SHOWN IN HARDSCAPE AREAS. THIS IRRIGATION IS TO BE PLACED IN LANDSCAPED AREAS ON THE PROPERTY SITE.
6. CONTRACTOR SHALL USE ONLY COMMERCIAL GRADE IRRIGATION PRODUCTS. THIS INCLUDES PIPE TO BE SCHEDULE 40 PVC OR BETTER. NO POLY PIPE IS TO BE USED. FITTINGS UP TO 1-1/2" MUST BE SCHEDULE 40 OR BETTER. FITTINGS LARGER THAN 1-1/2" SHALL BE SCHEDULE 80 OR BETTER. CONTRACTOR IS RESPONSIBLE FOR ENSURING ACCURATE COUNTS AND QUANTITIES OF ALL IRRIGATION MATERIALS FOR BIDDING AND INSTALLATION.
7. MAIN LINES SHALL BE A MINIMUM OF 24" DEEP AND LATERAL LINES A MINIMUM OF 12" DEEP. NO ROCK GREATER THAN 1/2" DIAMETER SHALL BE ALLOWED IN TRENCHES. TRENCHING BACKFILL MATERIAL SHALL BE COMPACTED TO PROPER FINISHED GRADE.
8. NO IRRIGATION MAIN LINE MAY BE LOCATED WITHIN 5 FEET OF ANY STRUCTURE.
9. TO AVOID PIPE DAMAGE, ADJUST LOCATION OF PIPE TO NOT BE DIRECTLY UNDER PLANT MATERIALS. VALVE BOXES ARE PREFERRED TO BE IN PLANTER BEDS INSTEAD OF THE LAWN.
10. PLAN INDICATES 100% OR BETTER HEAD TO HEAD COVERAGE. SHOULD CONTRACTOR FIND DISCREPANCIES DUE TO NECESSARY FIELD ADJUSTMENTS, CONTACT LANDSCAPE ARCHITECT FOR IRRIGATION CORRECTION.
11. DRIP IRRIGATION TO BE INSTALLED PER DETAILS. CONTRACTOR SHALL MAKE NECESSARY ADJUSTMENTS. TUBING SHOULD REST TOWARD OUTER EDGE OF ROOTBALL AND NOT AGAINST TRUNK OF PLANT.
12. A QUICK COUPLER SHALL BE INSTALLED AT POINT OF CONNECTION TO ALLOW BLOW OUT OF SYSTEM BY AIR COMPRESSOR AT END OF EACH SEASON.
13. INSTALL SLEEVES FOR ALL PIPES AND WIRE CONDUIT THAT ARE PLACED UNDER PAVEMENT AND SIDEWALKS. SLEEVES SHALL BE 2 SIZES LARGER THAN PIPE BEING PLACED INTERNALLY. WIRE CONDUIT SHALL BE INSTALLED IN CLASS 200 PIPE. AT ANY DIRECTIONAL CHANGE THAT OCCURS, A JUNCTION BOX IS TO PLACED.
14. CONDUITS CAN NOT BE SHARED BY WATER AND ELECTRICAL LINES. ALL WIRE TO BE PUT IN PVC CONDUIT. ALL WIRE CONNECTIONS TO BE PLACED IN A VALVE BOX. ALL WIRE CONNECTIONS TO USE WATERPROOF WIRE CONNECTORS WITH AT LEAST 3' OF EXTRA WIRE. PROVIDE PLENTY OF EXTRA WIRE AT EVERY DIRECTIONAL CHANGE. INSULATED 14 GAUGE COPPER TO BE USED FOR ALL CONTROL WIRES AND INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
15. CONTRACTOR TO INSTALL LIGHTNING ARRESTOR AND GROUNDING RODS ON SITE PER MANUFACTURER'S RECOMMENDATIONS, SEE DETAILS.
16. CONTRACTOR TO SEPARATE SYSTEM (CONTROLLER, VALVES, AND DIFFERENT COLORED WIRE) FROM CITY MAINTAINED PROPERTY AND HOA/OWNER MAINTAINED PROPERTY.
17. DUCT TAPE ALL SLEEVES TO PREVENT SOIL OR OTHER DEBRIS ENTERING PIPE. IDENTIFY ALL SLEEVES BY WOOD OR PVC STAKES AND SPRAY PAINT WITH MARKING PAINT. REMOVE STAKES ONCE IRRIGATION SYSTEM IS COMPLETE.
18. TO PREVENT EROSION AND LOW POINT DRAINAGE CONTRACTOR SHALL INSTALL CHECK VALVES
19. LOCATE SPRAY HEADS NO CLOSER THAN 6" FROM WALLS, FENCES OR BUILDINGS AND 2" AWAY FROM WALKS, PATHS OR CURBS.
20. PRESSURE TEST MAINLINE FOR LEAKS PRIOR TO BACKFILLING. CONTACT LANDSCAPE ARCHITECT/OWNER AT THIS TIME FOR COMPLIANCE.
21. CONTRACTOR TO CONSULT WITH OWNER ON EXACT LOCATION OF CONTROLLER. CONTRACTOR TO COORDINATE WITH ELECTRICAL CONTRACTOR AND OWNER FOR THE POWER SUPPLY. INSTALL ALL PER MANUFACTURER'S SPECIFICATIONS. CONTRACTOR SHALL INSTALL A RAIN SENSOR WITH THE CONTROLLER UNLESS OTHERWISE DIRECTED BY OWNER OR LANDSCAPE ARCHITECT.
22. LATERAL LINES SHALL BE NO SMALLER THAN 3/4". LANDSCAPE CONTRACTOR TO ENSURE THE FOLLOWING PIPE SIZES DO NOT EXCEED THE SUGGESTED GPM LISTED BELOW:

3/4"	8 GPM
1"	12 GPM
1-1/2"	30 GPM
2"	53 GPM
2-1/2"	75 GPM
3"	110 GPM
4"	180 GPM

VALVE ID TAG



NOTE:
1. VALVE ID TAGS ARE LOCATED NEAR VALVES IN THE ORDER THE VALVES APPEAR ON THE DRAWING

ISSUE DATE	PROJECT NUMBER	PLAN INFORMATION	PROJECT INFORMATION	DEVELOPER / PROPERTY OWNER / CLIENT	LANDSCAPE ARCHITECT / PLANNER	LICENSE STAMP	DRAWING INFO
7/20/2021	UT21101		DEER PARK 6800 NORTH AMERICAN FORK, UTAH	AE URBIA 909 W. SOUTH JORDAN PARKWAY SOUTH JORDAN, UT 84095 801-575-6455 CIR CIVIL ENGINEERING 3032 SOUTH 1030 WEST, SUITE 202 SALT LAKE CITY, UT 84119 801-949-6296	PKJ DESIGN GROUP Landscape Architecture / Planning & Visualization 3450 N. TRIUMPH BLVD. SUITE 102 LEHI, UTAH 84043 (801) 960-2698 www.pkjdesigngroup.com	LICENSED LANDSCAPE ARCHITECT KEVIN AINSWORTH 812812 - 5301 07/26/2021 ELECTRONIC SEAL STATE OF UTAH	PM: JTA DRAWN: ACP CHECKED: JMA PLOT DATE: 7/20/2021

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org


N

0' 10' 20' 40' 80'
GRAPHIC SCALE: 1" = 20'

IRRIGATION PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

IR-102



IRRIGATION LEGEND

SYMBOL	MANUFACTURER-MODEL NUMBER
	RAINBIRD RD04-S-PRS POP UP SPRAY 5 SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 8 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 10 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 12 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 SST @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 EST @ 30 PSI
	RAINBIRD 5000 SERIES MPR NOZZLES @ 55 PSI
	RAINBIRD 8005 SERIES Q#8-6.6 GPM, H#14-12.6 GPM, F#26-24.3 GPM NOZZLES @ 55 PSI
S	POINT OF CONNECTION (SECONDARY WATER) SEE PLAN FOR SIZE
A	CONTROLLER:RAINBIRD ESP-LXIVM WITH LIMR REMOTE KIT, PLACE IN FIRE RISER ROOM, CONTRACTOR TO ADJUST LOCATION WITH OWNER PRIOR TO CONSTRUCTION.
R	RAINBIRD WR2-RC WIRELESS RAIN SHUT OFF DEVICE
	ISOLATION BALL VALVE - LINE SIZED INSTALL PER MANUFACTURER'S SPEC.
	2" T SUPER AMIAD PLASTIC FILTER - INSTALL PER MANUFACTURE'S. RECOMMENDATIONS (130 MICRON)
M	MASTER VALVE
F	FLOW SENSOR
Q	QUICK COUPLER: RAINBIRD 44LRC INSTALL PER MANUFACTURER'S SPEC.
DEC / L	VALVE DECODER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC. LIGHTNING ARRESTER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC.
	REMOTE CONTROL VALVE: RAINBIRD IVMSOL AUTOMATIC CONTROL VALVE (SIZE AS NOTED ON PLAN- USE JUMBO BOX-PURPLE LID) PLACE YELLOW TAGS ON ALL VALVES AND LABEL.
	DRIP CONTROL ZONE KIT: RAINBIRD XCZ-(PER PLAN)-PRBR-COM MED FLOW (SIZE AS NOTED ON PLAN)
	MAINLINE: SCHEDULE 40 PVC WITH SCHEDULE 80 FITTINGS, 2" DIAMETER 24" MIN. COVER
	LATERAL LINE: SCHEDULE 40 PVC WITH SCH. 40 FITTINGS. SEE PIPE SIZING CHART
	DRIP CONNECTION. PROVIDE DRIP IRRIGATION TO ALL TREES, SHRUBS,AND PERENNIALS IN PLANTER AREAS
	DRIP LINE: RAINBIRD XFSP-09-18-100 OR EQUIVALENT
	CLASS 200 SLEEVE PER PLAN
NO SYMBOL	WIRE CHASE, SIZE TO BE TWICE THE DIAMETER OF THE WIRE BUNDLE WITHIN. 1.1/4" DIAMETER MINIMUM 14 GAUGE SOLID COPPER SINGLE STRAND CONTROL WIRE. INSTALL PER MANUFACTURER'S SPEC. PROVIDE 2 WIRE LOOP SYSTEM. ONLY WIRE FROM POC TO CONTROLLER IS DEPICTED ON PLANS. CONTRACTOR TO INSTALL WIRE IN CONDUIT FROM POC TO ALL VALVES. THE WIRE TO VALVES IS NOT SHOWN ON PLAN

DRIP ZONE


TYPE	PART NUMBER	EMITTER FLOW		
XFS DRIPLINE	XFSP-09-18	.9 GPH		
TOTAL DRIP ZONE FLOW		20 GPM	*EACH ZONE NOT TO EXCEED 20 GPM	
NUMBER OF FLUSH POINTS		2	DRIP ZONE TO APPLY 1/4" OF WATER	23
*ONLY WATER PLANT SPECIFICALLY- DO NOT WATER ROCK AREA WITH NO PLANTS				
*NUMBERS MAY CHANGE DUE TO SIZE OF DRIP ZONE PER PLAN				

IRRIGATION NOTES

1. BEFORE WORK IS TO COMMENCE, BLUE STAKES/DIG LINE IS TO BE CALLED AND NOTIFIED. IF ANY DAMAGE TO UTILITIES HAPPEN DURING CONSTRUCTION, THE CONTRACTOR SHALL REPAIR IT AT THEIR EXPENSE WITH NO ADDITIONAL COST TO THE OWNER.
2. CONTRACTOR SHALL APPLY AND PAY FOR ALL NECESSARY PERMITS IN ACCORDANCE WITH CITY AND/OR COUNTY CODES AND COMPLY WITH SPECIFICATIONS AND DRAWINGS.
3. INVESTIGATE TO MAKE SURE THAT THE IRRIGATION SYSTEM IS, IN FACT, BEING CONNECTED TO A SECONDARY SYSTEM. IF IT IS NOT CONNECTED TO SECONDARY, CONTACT THE OWNER AND LANDSCAPE ARCHITECT TO COORDINATE A CULINARY SYSTEM AND REQUIRED COMPONENTS. A FUNCTIONING AMIAD FILTER IS TO BE USED AT THE POINT OF CONNECTION.
4. VERIFY THAT THE POINT OF CONNECTION IS IN THE CORRECT LOCATION BEFORE INSTALLATION. ALL CONNECTIONS ON THIS PROJECT ARE TO SECONDARY WATER AND SHOULD BE NOTED AS SUCH; THEREFORE, ALL PARTS MUST MEET WATER STANDARDS THAT PERTAIN TO SECONDARY WATER.USE PURPLE VALVE BOXES FOR SECONDARY WATER SYSTEMS.
5. ON OCCASION AND FOR GRAPHIC PURPOSES ONLY, THE IRRIGATION SYSTEM MIGHT BE SHOWN IN HARDSCAPE AREAS. THIS IRRIGATION IS TO BE PLACED IN LANDSCAPED AREAS ON THE PROPERTY SITE.
6. CONTRACTOR SHALL USE ONLY COMMERCIAL GRADE IRRIGATION PRODUCTS. THIS INCLUDES PIPE TO BE SCHEDULE 40 PVC OR BETTER. NO POLY PIPE IS TO BE USED. FITTINGS UP TO 1-1/2" MUST BE SCHEDULE 40 OR BETTER. FITTINGS LARGER THAN 1-1/2" SHALL BE SCHEDULE 80 OR BETTER. CONTRACTOR IS RESPONSIBLE FOR ENSURING ACCURATE COUNTS AND QUANTITIES OF ALL IRRIGATION MATERIALS FOR BIDDING AND INSTALLATION.
7. MAIN LINES SHALL BE A MINIMUM OF 24" DEEP AND LATERAL LINES A MINIMUM OF 12" DEEP. NO ROCK GREATER THAN 1/2" DIAMETER SHALL BE ALLOWED IN TRENCHES. TRENCHING BACKFILL MATERIAL SHALL BE COMPACTED TO PROPER FINISHED GRADE.
8. NO IRRIGATION MAIN LINE MAY BE LOCATED WITHIN 5 FEET OF ANY STRUCTURE.
9. TO AVOID PIPE DAMAGE, ADJUST LOCATION OF PIPE TO NOT BE DIRECTLY UNDER PLANT MATERIALS. VALVE BOXES ARE PREFERRED TO BE IN PLANTER BEDS INSTEAD OF THE LAWN.
10. PLAN INDICATES 100% OR BETTER HEAD TO HEAD COVERAGE. SHOULD CONTRACTOR FIND DISCREPANCIES DUE TO NECESSARY FIELD ADJUSTMENTS, CONTACT LANDSCAPE ARCHITECT FOR IRRIGATION CORRECTION.
11. DRIP IRRIGATION TO BE INSTALLED PER DETAILS. CONTRACTOR SHALL MAKE NECESSARY ADJUSTMENTS. TUBING SHOULD REST TOWARD OUTER EDGE OF ROOTBALL AND NOT AGAINST TRUNK OF PLANT.
12. A QUICK COUPLER SHALL BE INSTALLED AT POINT OF CONNECTION TO ALLOW BLOW OUT OF SYSTEM BY AIR COMPRESSOR AT END OF EACH SEASON.
13. INSTALL SLEEVES FOR ALL PIPES AND WIRE CONDUIT THAT ARE PLACED UNDER PAVEMENT AND SIDEWALKS. SLEEVES SHALL BE 2 SIZES LARGER THAN PIPE BEING PLACED INTERNALLY. WIRE CONDUIT SHALL BE INSTALLED IN CLASS 200 PIPE. AT ANY DIRECTIONAL CHANGE THAT OCCURS, A JUNCTION BOX IS TO PLACED.
14. CONDUITS CAN NOT BE SHARED BY WATER AND ELECTRICAL LINES. ALL WIRE TO BE PUT IN PVC CONDUIT. ALL WIRE CONNECTIONS TO BE PLACED IN A VALVE BOX. ALL WIRE CONNECTIONS TO USE WATERPROOF WIRE CONNECTORS WITH AT LEAST 3' OF EXTRA WIRE. PROVIDE PLENTY OF EXTRA WIRE AT EVERY DIRECTIONAL CHANGE. INSULATED 14 GAUGE COPPER TO BE USED FOR ALL CONTROL WIRES AND INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
15. CONTRACTOR TO INSTALL LIGHTNING ARRESTOR AND GROUNDING RODS ON SITE PER MANUFACTURER'S RECOMMENDATIONS, SEE DETAILS.
16. CONTRACTOR TO SEPARATE SYSTEM (CONTROLLER, VALVES, AND DIFFERENT COLORED WIRE) FROM CITY MAINTAINED PROPERTY AND HOA/OWNER MAINTAINED PROPERTY.
17. DUCT TAPE ALL SLEEVES TO PREVENT SOIL OR OTHER DEBRIS ENTERING PIPE. IDENTIFY ALL SLEEVES BY WOOD OR PVC STAKES AND SPRAY PAINT WITH MARKING PAINT. REMOVE STAKES ONCE IRRIGATION SYSTEM IS COMPLETE.
18. TO PREVENT EROSION AND LOW POINT DRAINAGE CONTRACTOR SHALL INSTALL CHECK VALVES
19. LOCATE SPRAY HEADS NO CLOSER THAN 6" FROM WALLS, FENCES OR BUILDINGS AND 2" AWAY FROM WALKS, PATHS OR CURBS.
20. PRESSURE TEST MAINLINE FOR LEAKS PRIOR TO BACKFILLING. CONTACT LANDSCAPE ARCHITECT/OWNER AT THIS TIME FOR COMPLIANCE.
21. CONTRACTOR TO CONSULT WITH OWNER ON EXACT LOCATION OF CONTROLLER. CONTRACTOR TO COORDINATE WITH ELECTRICAL CONTRACTOR AND OWNER FOR THE POWER SUPPLY. INSTALL ALL PER MANUFACTURER'S SPECIFICATIONS. CONTRACTOR SHALL INSTALL A RAIN SENSOR WITH THE CONTROLLER UNLESS OTHERWISE DIRECTED BY OWNER OR LANDSCAPE ARCHITECT.
22. LATERAL LINES SHALL BE NO SMALLER THAN 3/4". LANDSCAPE CONTRACTOR TO ENSURE THE FOLLOWING PIPE SIZES DO NOT EXCEED THE SUGGESTED GPM LISTED BELOW:

3/4"	8 GPM
1"	12 GPM
1-1/2"	30 GPM
2"	53 GPM
2-1/2"	75 GPM
3"	110 GPM
4"	180 GPM

VALVE ID TAG



NOTE:
1. VALVE ID TAGS ARE LOCATED NEAR VALVES IN THE ORDER THE VALVES APPEAR ON THE DRAWING

ISSUE DATE	PROJECT NUMBER
7/20/2021	UT21101

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

N

0' 10' 20' 40' 80'
GRAPHIC SCALE: 1" = 20'

PROJECT INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture / Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
STATE OF UTAH
5132127-5301
REGISTERED
07/06/2021
ELECTRONIC SEAL


DRAWING INFO

PM: JTA
DRAWN: ACP
CHECKED: JMA
PLOT DATE: 7/20/2021

IRRIGATION PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

IR-103



IRRIGATION LEGEND

SYMBOL	MANUFACTURER-MODEL NUMBER
	RAINBIRD RD04-S-PRS POP UP SPRAY 5 SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 8 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 10 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 12 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 SST @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 EST @ 30 PSI
	RAINBIRD 5000 SERIES MPR NOZZLES @ 55 PSI
	RAINBIRD 8005 SERIES Q#8-6.6 GPM, H#14-12.6 GPM, F#26-24.3 GPM NOZZLES @ 55 PSI
S	POINT OF CONNECTION (SECONDARY WATER) SEE PLAN FOR SIZE
A	CONTROLLER:RAINBIRD ESP-LXIVM WITH LIMR REMOTE KIT, PLACE IN FIRE RISER ROOM, CONTRACTOR TO ADJUST LOCATION WITH OWNER PRIOR TO CONSTRUCTION.
R	RAINBIRD WR2-RC WIRELESS RAIN SHUT OFF DEVICE
	ISOLATION BALL VALVE - LINE SIZED INSTALL PER MANUFACTURER'S SPEC.
	2" T SUPER AMIAD PLASTIC FILTER - INSTALL PER MANUFACTURE'S. RECOMMENDATIONS (130 MICRON)
M	MASTER VALVE
F	FLOW SENSOR
Q	QUICK COUPLER: RAINBIRD 44LRC INSTALL PER MANUFACTURER'S SPEC.
DEC / L	VALVE DECODER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC. LIGHTNING ARRESTER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC.
	REMOTE CONTROL VALVE: RAINBIRD IVMSOL AUTOMATIC CONTROL VALVE (SIZE AS NOTED ON PLAN- USE JUMBO BOX-PURPLE LID) PLACE YELLOW TAGS ON ALL VALVES AND LABEL.
	DRIP CONTROL ZONE KIT: RAINBIRD XCZ-(PER PLAN)-PRBR-COM MED FLOW (SIZE AS NOTED ON PLAN)
	MAINLINE: SCHEDULE 40 PVC WITH SCHEDULE 80 FITTINGS, 2" DIAMETER 24" MIN. COVER
	LATERAL LINE: SCHEDULE 40 PVC WITH SCH. 40 FITTINGS. SEE PIPE SIZING CHART
	DRIP CONNECTION. PROVIDE DRIP IRRIGATION TO ALL TREES, SHRUBS,AND PERENNIALS IN PLANTER AREAS
	DRIP LINE: RAINBIRD XFSP-09-18-100 OR EQUIVALENT
	CLASS 200 SLEEVE PER PLAN
NO SYMBOL	WIRE CHASE, SIZE TO BE TWICE THE DIAMETER OF THE WIRE BUNDLE WITHIN. 1.1/4" DIAMETER MINIMUM
	14 GAUGE SOLID COPPER SINGLE STRAND CONTROL WIRE: INSTALL PER MANUFACTURER'S SPEC. PROVIDE 2 WIRE LOOP SYSTEM. ONLY WIRE FROM POC TO CONTROLLER IS DEPICTED ON PLANS. CONTRACTOR TO INSTALL WIRE IN CONDUIT FROM POC TO ALL VALVES. THE WIRE TO VALVES IS NOT SHOWN ON PLAN

DRIP ZONE

TYPE	PART NUMBER	EMITTER FLOW		
XFS DRIPLINE	XFSP-09-18	.9 GPH		
TOTAL DRIP ZONE FLOW		20 GPM	*EACH ZONE NOT TO EXCEED 20 GPM	
NUMBER OF FLUSH POINTS		2	DRIP ZONE TO APPLY 1/4" OF WATER	23
*ONLY WATER PLANT SPECIFICALLY. DO NOT WATER ROCK AREA WITH NO PLANTS				
*NUMBERS MAY CHANGE DUE TO SIZE OF DRIP ZONE PER PLAN				

IRRIGATION NOTES

1. BEFORE WORK IS TO COMMENCE, BLUE STAKES/DIG LINE IS TO BE CALLED AND NOTIFIED. IF ANY DAMAGE TO UTILITIES HAPPEN DURING CONSTRUCTION, THE CONTRACTOR SHALL REPAIR IT AT THEIR EXPENSE WITH NO ADDITIONAL COST TO THE OWNER.
2. CONTRACTOR SHALL APPLY AND PAY FOR ALL NECESSARY PERMITS IN ACCORDANCE WITH CITY AND/OR COUNTY CODES AND COMPLY WITH SPECIFICATIONS AND DRAWINGS.
3. INVESTIGATE TO MAKE SURE THAT THE IRRIGATION SYSTEM IS, IN FACT, BEING CONNECTED TO A SECONDARY SYSTEM. IF IT IS NOT CONNECTED TO SECONDARY, CONTACT THE OWNER AND LANDSCAPE ARCHITECT TO COORDINATE A CULINARY SYSTEM AND REQUIRED COMPONENTS. A FUNCTIONING AMIAD FILTER IS TO BE USED AT THE POINT OF CONNECTION.
4. VERIFY THAT THE POINT OF CONNECTION IS IN THE CORRECT LOCATION BEFORE INSTALLATION. ALL CONNECTIONS ON THIS PROJECT ARE TO SECONDARY WATER AND SHOULD BE NOTED AS SUCH; THEREFORE, ALL PARTS MUST MEET WATER STANDARDS THAT PERTAIN TO SECONDARY WATER.USE PURPLE VALVE BOXES FOR SECONDARY WATER SYSTEMS.
5. ON OCCASION AND FOR GRAPHIC PURPOSES ONLY, THE IRRIGATION SYSTEM MIGHT BE SHOWN IN HARDSCAPE AREAS. THIS IRRIGATION IS TO BE PLACED IN LANDSCAPED AREAS ON THE PROPERTY SITE.
6. CONTRACTOR SHALL USE ONLY COMMERCIAL GRADE IRRIGATION PRODUCTS. THIS INCLUDES PIPE TO BE SCHEDULE 40 PVC OR BETTER. NO POLY PIPE IS TO BE USED. FITTINGS UP TO 1-1/2" MUST BE SCHEDULE 40 OR BETTER. FITTINGS LARGER THAN 1-1/2" SHALL BE SCHEDULE 80 OR BETTER. CONTRACTOR IS RESPONSIBLE FOR ENSURING ACCURATE COUNTS AND QUANTITIES OF ALL IRRIGATION MATERIALS FOR BIDDING AND INSTALLATION.
7. MAIN LINES SHALL BE A MINIMUM OF 24" DEEP AND LATERAL LINES A MINIMUM OF 12" DEEP. NO ROCK GREATER THAN 1/2" DIAMETER SHALL BE ALLOWED IN TRENCHES. TRENCHING BACKFILL MATERIAL SHALL BE COMPACTED TO PROPER FINISHED GRADE.
8. NO IRRIGATION MAIN LINE MAY BE LOCATED WITHIN 5 FEET OF ANY STRUCTURE.
9. TO AVOID PIPE DAMAGE, ADJUST LOCATION OF PIPE TO NOT BE DIRECTLY UNDER PLANT MATERIALS. VALVE BOXES ARE PREFERRED TO BE IN PLANTER BEDS INSTEAD OF THE LAWN.
10. PLAN INDICATES 100% OR BETTER HEAD TO HEAD COVERAGE. SHOULD CONTRACTOR FIND DISCREPANCIES DUE TO NECESSARY FIELD ADJUSTMENTS, CONTACT LANDSCAPE ARCHITECT FOR IRRIGATION CORRECTION.
11. DRIP IRRIGATION TO BE INSTALLED PER DETAILS. CONTRACTOR SHALL MAKE NECESSARY ADJUSTMENTS. TUBING SHOULD REST TOWARD OUTER EDGE OF ROOTBALL AND NOT AGAINST TRUNK OF PLANT.
12. A QUICK COUPLER SHALL BE INSTALLED AT POINT OF CONNECTION TO ALLOW BLOW OUT OF SYSTEM BY AIR COMPRESSOR AT END OF EACH SEASON.
13. INSTALL SLEEVES FOR ALL PIPES AND WIRE CONDUIT THAT ARE PLACED UNDER PAVEMENT AND SIDEWALKS. SLEEVES SHALL BE 2 SIZES LARGER THAN PIPE BEING PLACED INTERNALLY. WIRE CONDUIT SHALL BE INSTALLED IN CLASS 200 PIPE. AT ANY DIRECTIONAL CHANGE THAT OCCURS, A JUNCTION BOX IS TO PLACED.
14. CONDUITS CAN NOT BE SHARED BY WATER AND ELECTRICAL LINES. ALL WIRE TO BE PUT IN PVC CONDUIT. ALL WIRE CONNECTIONS TO BE PLACED IN A VALVE BOX. ALL WIRE CONNECTIONS TO USE WATERPROOF WIRE CONNECTORS WITH AT LEAST 3' OF EXTRA WIRE. PROVIDE PLENTY OF EXTRA WIRE AT EVERY DIRECTIONAL CHANGE. INSULATED 14 GAUGE COPPER TO BE USED FOR ALL CONTROL WIRES AND INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
15. CONTRACTOR TO INSTALL LIGHTNING ARRESTOR AND GROUNDING RODS ON SITE PER MANUFACTURER'S RECOMMENDATIONS, SEE DETAILS.
16. CONTRACTOR TO SEPARATE SYSTEM (CONTROLLER, VALVES, AND DIFFERENT COLORED WIRE) FROM CITY MAINTAINED PROPERTY AND HOA/OWNER MAINTAINED PROPERTY.
17. DUCT TAPE ALL SLEEVES TO PREVENT SOIL OR OTHER DEBRIS ENTERING PIPE. IDENTIFY ALL SLEEVES BY WOOD OR PVC STAKES AND SPRAY PAINT WITH MARKING PAINT. REMOVE STAKES ONCE IRRIGATION SYSTEM IS COMPLETE.
18. TO PREVENT EROSION AND LOW POINT DRAINAGE CONTRACTOR SHALL INSTALL CHECK VALVES
19. LOCATE SPRAY HEADS NO CLOSER THAN 6" FROM WALLS, FENCES OR BUILDINGS AND 2" AWAY FROM WALKS, PATHS OR CURBS.
20. PRESSURE TEST MAINLINE FOR LEAKS PRIOR TO BACKFILLING. CONTACT LANDSCAPE ARCHITECT/OWNER AT THIS TIME FOR COMPLIANCE.
21. CONTRACTOR TO CONSULT WITH OWNER ON EXACT LOCATION OF CONTROLLER. CONTRACTOR TO COORDINATE WITH ELECTRICAL CONTRACTOR AND OWNER FOR THE POWER SUPPLY. INSTALL ALL PER MANUFACTURER'S SPECIFICATIONS. CONTRACTOR SHALL INSTALL A RAIN SENSOR WITH THE CONTROLLER UNLESS OTHERWISE DIRECTED BY OWNER OR LANDSCAPE ARCHITECT.
22. LATERAL LINES SHALL BE NO SMALLER THAN 3/4". LANDSCAPE CONTRACTOR TO ENSURE THE FOLLOWING PIPE SIZES DO NOT EXCEED THE SUGGESTED GPM LISTED BELOW:

3/4"	8 GPM
1"	12 GPM
1-1/2"	30 GPM
2"	53 GPM
2-1/2"	75 GPM
3"	110 GPM
4"	180 GPM

VALVE ID TAG

A1 — CONTROLLER NUMBER, VALVE NUMBER
VALVE SIZE — 1.0 | 18 — GALLONS PER MINUTE
PSI AT LAST HEAD IN ZONE — 55

NOTE:
1. VALVE ID TAGS ARE LOCATED NEAR VALVES IN THE ORDER THE VALVES APPEAR ON THE DRAWING

ISSUE DATE | PROJECT NUMBER | PLAN INFORMATION | PROJECT INFORMATION | DEVELOPER / PROPERTY OWNER / CLIENT | LANDSCAPE ARCHITECT / PLANNER | LICENSE STAMP | DRAWING INFO

7/20/2021 UT21101

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

N

0' 10' 20' 40' 80'
GRAPHIC SCALE: 1" = 20'

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

PKJ DESIGN GROUP
Landscape Architecture / Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com


LICENSED LANDSCAPE ARCHITECT — JEREMY AINSWORTH — 8128121-5301 — EXPIRATION 07/26/2021 — ELECTRONIC SEAL — STATE OF UTAH

DRAWING INFO
PM: JTA
DRAWN: ACP
CHECKED: JMA
PLOT DATE: 7/20/2021

IRRIGATION PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

IR-104



IRRIGATION LEGEND

SYMBOL	MANUFACTURER-MODEL NUMBER
	RAINBIRD RD04-S-PRS POP UP SPRAY 5 SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 8 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 10 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 12 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 SST @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 EST @ 30 PSI
	RAINBIRD 5000 SERIES MPR NOZZLES @ 55 PSI
	RAINBIRD 8005 SERIES Q#8-6.6 GPM, H#14-12.6 GPM, F#26-24.3 GPM NOZZLES @ 55 PSI
S	POINT OF CONNECTION (SECONDARY WATER) SEE PLAN FOR SIZE
A	CONTROLLER:RAINBIRD ESP-LXIVM WITH LIMR REMOTE KIT, PLACE IN FIRE RISER ROOM, CONTRACTOR TO ADJUST LOCATION WITH OWNER PRIOR TO CONSTRUCTION.
R	RAINBIRD WR2-RC WIRELESS RAIN SHUT OFF DEVICE
	ISOLATION BALL VALVE - LINE SIZED INSTALL PER MANUFACTURER'S SPEC.
	2" T SUPER AMIAD PLASTIC FILTER - INSTALL PER MANUFACTURE'S. RECOMMENDATIONS (130 MICRON)
M	MASTER VALVE
F	FLOW SENSOR
Q	QUICK COUPLER: RAINBIRD 44LRC INSTALL PER MANUFACTURER'S SPEC.
DEC	VALVE DECODER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC. LIGHTNING ARRESTER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC.
L	
	REMOTE CONTROL VALVE: RAINBIRD IVMSOL AUTOMATIC CONTROL VALVE (SIZE AS NOTED ON PLAN- USE JUMBO BOX-PURPLE LID) PLACE YELLOW TAGS ON ALL VALVES AND LABEL.
	DRIP CONTROL ZONE KIT: RAINBIRD XCZ-(PER PLAN)-PRBR-COM MED FLOW (SIZE AS NOTED ON PLAN)
	MAINLINE: SCHEDULE 40 PVC WITH SCHEDULE 80 FITTINGS, 2" DIAMETER 24" MIN. COVER
	LATERAL LINE: SCHEDULE 40 PVC WITH SCH. 40 FITTINGS. SEE PIPE SIZING CHART
	DRIP CONNECTION. PROVIDE DRIP IRRIGATION TO ALL TREES, SHRUBS,AND PERENNIALS IN PLANTER AREAS
	DRIP LINE: RAINBIRD XFSP-09-18-100 OR EQUIVALENT
	CLASS 200 SLEEVE PER PLAN
NO SYMBOL	WIRE CHASE, SIZE TO BE TWICE THE DIAMETER OF THE WIRE BUNDLE WITHIN. 1.1/4" DIAMETER MINIMUM

14 GAUGE SOLID COPPER SINGLE STRAND CONTROL WIRE. INSTALL PER MANUFACTURER'S SPEC. PROVIDE 2 WIRE LOOP SYSTEM. ONLY WIRE FROM POC TO CONTROLLER IS DEPICTED ON PLANS. CONTRACTOR TO INSTALL WIRE IN CONDUIT FROM POC TO ALL VALVES. THE WIRE TO VALVES IS NOT SHOWN ON PLAN

DRIP ZONE


TYPE	PART NUMBER	EMITTER FLOW		
XFS DRIPLINE	XFSP-09-18	.9 GPH		
TOTAL DRIP ZONE FLOW		20 GPM	*EACH ZONE NOT TO EXCEED 20 GPM	
NUMBER OF FLUSH POINTS		2	DRIP ZONE TO APPLY 1/4" OF WATER	23
*ONLY WATER PLANT SPECIFICALLY. DO NOT WATER ROCK AREA WITH NO PLANTS				
*NUMBERS MAY CHANGE DUE TO SIZE OF DRIP ZONE PER PLAN				

IRRIGATION NOTES

1. BEFORE WORK IS TO COMMENCE, BLUE STAKES/DIG LINE IS TO BE CALLED AND NOTIFIED. IF ANY DAMAGE TO UTILITIES HAPPEN DURING CONSTRUCTION, THE CONTRACTOR SHALL REPAIR IT AT THEIR EXPENSE WITH NO ADDITIONAL COST TO THE OWNER.
2. CONTRACTOR SHALL APPLY AND PAY FOR ALL NECESSARY PERMITS IN ACCORDANCE WITH CITY AND/OR COUNTY CODES AND COMPLY WITH SPECIFICATIONS AND DRAWINGS.
3. INVESTIGATE TO MAKE SURE THAT THE IRRIGATION SYSTEM IS, IN FACT, BEING CONNECTED TO A SECONDARY SYSTEM. IF IT IS NOT CONNECTED TO SECONDARY, CONTACT THE OWNER AND LANDSCAPE ARCHITECT TO COORDINATE A CULINARY SYSTEM AND REQUIRED COMPONENTS. A FUNCTIONING AMIAD FILTER IS TO BE USED AT THE POINT OF CONNECTION.
4. VERIFY THAT THE POINT OF CONNECTION IS IN THE CORRECT LOCATION BEFORE INSTALLATION. ALL CONNECTIONS ON THIS PROJECT ARE TO SECONDARY WATER AND SHOULD BE NOTED AS SUCH; THEREFORE, ALL PARTS MUST MEET WATER STANDARDS THAT PERTAIN TO SECONDARY WATER.USE PURPLE VALVE BOXES FOR SECONDARY WATER SYSTEMS.
5. ON OCCASION AND FOR GRAPHIC PURPOSES ONLY, THE IRRIGATION SYSTEM MIGHT BE SHOWN IN HARDSCAPE AREAS. THIS IRRIGATION IS TO BE PLACED IN LANDSCAPED AREAS ON THE PROPERTY SITE.
6. CONTRACTOR SHALL USE ONLY COMMERCIAL GRADE IRRIGATION PRODUCTS. THIS INCLUDES PIPE TO BE SCHEDULE 40 PVC OR BETTER. NO POLY PIPE IS TO BE USED. FITTINGS UP TO 1-1/2" MUST BE SCHEDULE 40 OR BETTER. FITTINGS LARGER THAN 1-1/2" SHALL BE SCHEDULE 80 OR BETTER. CONTRACTOR IS RESPONSIBLE FOR ENSURING ACCURATE COUNTS AND QUANTITIES OF ALL IRRIGATION MATERIALS FOR BIDDING AND INSTALLATION.
7. MAIN LINES SHALL BE A MINIMUM OF 24" DEEP AND LATERAL LINES A MINIMUM OF 12" DEEP. NO ROCK GREATER THAN 1/2" DIAMETER SHALL BE ALLOWED IN TRENCHES. TRENCHING BACKFILL MATERIAL SHALL BE COMPACTED TO PROPER FINISHED GRADE.
8. NO IRRIGATION MAIN LINE MAY BE LOCATED WITHIN 5 FEET OF ANY STRUCTURE.
9. TO AVOID PIPE DAMAGE, ADJUST LOCATION OF PIPE TO NOT BE DIRECTLY UNDER PLANT MATERIALS. VALVE BOXES ARE PREFERRED TO BE IN PLANTER BEDS INSTEAD OF THE LAWN.
10. PLAN INDICATES 100% OR BETTER HEAD TO HEAD COVERAGE. SHOULD CONTRACTOR FIND DISCREPANCIES DUE TO NECESSARY FIELD ADJUSTMENTS, CONTACT LANDSCAPE ARCHITECT FOR IRRIGATION CORRECTION.
11. DRIP IRRIGATION TO BE INSTALLED PER DETAILS. CONTRACTOR SHALL MAKE NECESSARY ADJUSTMENTS. TUBING SHOULD REST TOWARD OUTER EDGE OF ROOTBALL AND NOT AGAINST TRUNK OF PLANT.
12. A QUICK COUPLER SHALL BE INSTALLED AT POINT OF CONNECTION TO ALLOW BLOW OUT OF SYSTEM BY AIR COMPRESSOR AT END OF EACH SEASON.
13. INSTALL SLEEVES FOR ALL PIPES AND WIRE CONDUIT THAT ARE PLACED UNDER PAVEMENT AND SIDEWALKS. SLEEVES SHALL BE 2 SIZES LARGER THAN PIPE BEING PLACED INTERNALLY. WIRE CONDUIT SHALL BE INSTALLED IN CLASS 200 PIPE. AT ANY DIRECTIONAL CHANGE THAT OCCURS, A JUNCTION BOX IS TO PLACED.
14. CONDUITS CAN NOT BE SHARED BY WATER AND ELECTRICAL LINES. ALL WIRE TO BE PUT IN PVC CONDUIT. ALL WIRE CONNECTIONS TO BE PLACED IN A VALVE BOX. ALL WIRE CONNECTIONS TO USE WATERPROOF WIRE CONNECTORS WITH AT LEAST 3' OF EXTRA WIRE. PROVIDE PLENTY OF EXTRA WIRE AT EVERY DIRECTIONAL CHANGE. INSULATED 14 GAUGE COPPER TO BE USED FOR ALL CONTROL WIRES AND INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
15. CONTRACTOR TO INSTALL LIGHTNING ARRESTOR AND GROUNDING RODS ON SITE PER MANUFACTURER'S RECOMMENDATIONS, SEE DETAILS.
16. CONTRACTOR TO SEPARATE SYSTEM (CONTROLLER, VALVES, AND DIFFERENT COLORED WIRE) FROM CITY MAINTAINED PROPERTY AND HOA/OWNER MAINTAINED PROPERTY.
17. DUCT TAPE ALL SLEEVES TO PREVENT SOIL OR OTHER DEBRIS ENTERING PIPE. IDENTIFY ALL SLEEVES BY WOOD OR PVC STAKES AND SPRAY PAINT WITH MARKING PAINT. REMOVE STAKES ONCE IRRIGATION SYSTEM IS COMPLETE.
18. TO PREVENT EROSION AND LOW POINT DRAINAGE CONTRACTOR SHALL INSTALL CHECK VALVES
19. LOCATE SPRAY HEADS NO CLOSER THAN 6" FROM WALLS, FENCES OR BUILDINGS AND 2" AWAY FROM WALKS, PATHS OR CURBS.
20. PRESSURE TEST MAINLINE FOR LEAKS PRIOR TO BACKFILLING. CONTACT LANDSCAPE ARCHITECT/OWNER AT THIS TIME FOR COMPLIANCE.
21. CONTRACTOR TO CONSULT WITH OWNER ON EXACT LOCATION OF CONTROLLER. CONTRACTOR TO COORDINATE WITH ELECTRICAL CONTRACTOR AND OWNER FOR THE POWER SUPPLY. INSTALL ALL PER MANUFACTURER'S SPECIFICATIONS. CONTRACTOR SHALL INSTALL A RAIN SENSOR WITH THE CONTROLLER UNLESS OTHERWISE DIRECTED BY OWNER OR LANDSCAPE ARCHITECT.
22. LATERAL LINES SHALL BE NO SMALLER THAN 3/4". LANDSCAPE CONTRACTOR TO ENSURE THE FOLLOWING PIPE SIZES DO NOT EXCEED THE SUGGESTED GPM LISTED BELOW:

3/4"	8 GPM
1"	12 GPM
1-1/2"	30 GPM
2"	53 GPM
2-1/2"	75 GPM
3"	110 GPM
4"	180 GPM

VALVE ID TAG



NOTE:
1. VALVE ID TAGS ARE LOCATED NEAR VALVES IN THE ORDER THE VALVES APPEAR ON THE DRAWING

ISSUE DATE	PROJECT NUMBER
7/20/2021	UT21101

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

N

0' 10' 20' 40' 80'
GRAPHIC SCALE: 1" = 20'

PLAN INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

PROJECT INFORMATION

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
812812-5301
07/20/2021
ELECTRONIC SEAL
STATE OF UTAH


DRAWING INFO

PM:	JTA
DRAWN:	ACP
CHECKED:	JMA
PLOT DATE:	7/20/2021

IRRIGATION PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

IR-105



IRRIGATION LEGEND

SYMBOL	MANUFACTURER-MODEL NUMBER
	RAINBIRD RD04-S-PRS POP UP SPRAY 5 SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 8 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 10 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 12 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 U-SERIES @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 SST @ 30 PSI
	RAINBIRD RD04-S-PRS POP UP SPRAY 15 EST @ 30 PSI
	RAINBIRD 5000 SERIES MPR NOZZLES @ 55 PSI
	RAINBIRD 8005 SERIES Q#8-6.6 GPM, H#14-12.6 GPM, F#26-24.3 GPM NOZZLES @ 55 PSI
S	POINT OF CONNECTION (SECONDARY WATER) SEE PLAN FOR SIZE
A	CONTROLLER:RAINBIRD ESP-LXIVM WITH LIMR REMOTE KIT, PLACE IN FIRE RISER ROOM, CONTRACTOR TO ADJUST LOCATION WITH OWNER PRIOR TO CONSTRUCTION.
R	RAINBIRD WR2-RC WIRELESS RAIN SHUT OFF DEVICE
	ISOLATION BALL VALVE - LINE SIZED INSTALL PER MANUFACTURER'S SPEC.
	2" T SUPER AMIAD PLASTIC FILTER - INSTALL PER MANUFACTURE'S. RECOMMENDATIONS (130 MICRON)
M	MASTER VALVE
F	FLOW SENSOR
Q	QUICK COUPLER: RAINBIRD 44LRC INSTALL PER MANUFACTURER'S SPEC.
DEC	VALVE DECODER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC. LIGHTNING ARRESTER (AT ALL VALVE GROUPINGS) INSTALL PER MANUFACTURER'S SPEC.
L	
	REMOTE CONTROL VALVE: RAINBIRD IVMSOL AUTOMATIC CONTROL VALVE (SIZE AS NOTED ON PLAN- USE JUMBO BOX-PURPLE LID) PLACE YELLOW TAGS ON ALL VALVES AND LABEL.
	DRIP CONTROL ZONE KIT: RAINBIRD XCZ-(PER PLAN)-PRBR-COM MED FLOW (SIZE AS NOTED ON PLAN)
	MAINLINE: SCHEDULE 40 PVC WITH SCHEDULE 80 FITTINGS, 2" DIAMETER 24" MIN. COVER
	LATERAL LINE: SCHEDULE 40 PVC WITH SCH. 40 FITTINGS. SEE PIPE SIZING CHART
	DRIP CONNECTION. PROVIDE DRIP IRRIGATION TO ALL TREES, SHRUBS,AND PERENNIALS IN PLANTER AREAS
	DRIP LINE: RAINBIRD XFSP-09-18-100 OR EQUIVALENT
	CLASS 200 SLEEVE PER PLAN
NO SYMBOL	WIRE CHASE, SIZE TO BE TWICE THE DIAMETER OF THE WIRE BUNDLE WITHIN. 1.1/4" DIAMETER MINIMUM 14 GAUGE SOLID COPPER SINGLE STRAND CONTROL WIRE. INSTALL PER MANUFACTURER'S SPEC. PROVIDE 2 WIRE LOOP SYSTEM. ONLY WIRE FROM POC TO CONTROLLER IS DEPICTED ON PLANS. CONTRACTOR TO INSTALL WIRE IN CONDUIT FROM POC TO ALL VALVES. THE WIRE TO VALVES IS NOT SHOWN ON PLAN

DRIP ZONE


TYPE	PART NUMBER	EMITTER FLOW		
XFS DRIPLINE	XFSP-09-18	.9 GPH		
TOTAL DRIP ZONE FLOW		20 GPM	*EACH ZONE NOT TO EXCEED 20 GPM	
NUMBER OF FLUSH POINTS		2	DRIP ZONE TO APPLY 1/4" OF WATER	23
*ONLY WATER PLANT SPECIFICALLY. DO NOT WATER ROCK AREA WITH NO PLANTS				
*NUMBERS MAY CHANGE DUE TO SIZE OF DRIP ZONE PER PLAN				

IRRIGATION NOTES

1. BEFORE WORK IS TO COMMENCE, BLUE STAKES/DIG LINE IS TO BE CALLED AND NOTIFIED. IF ANY DAMAGE TO UTILITIES HAPPEN DURING CONSTRUCTION, THE CONTRACTOR SHALL REPAIR IT AT THEIR EXPENSE WITH NO ADDITIONAL COST TO THE OWNER.
2. CONTRACTOR SHALL APPLY AND PAY FOR ALL NECESSARY PERMITS IN ACCORDANCE WITH CITY AND/OR COUNTY CODES AND COMPLY WITH SPECIFICATIONS AND DRAWINGS.
3. INVESTIGATE TO MAKE SURE THAT THE IRRIGATION SYSTEM IS, IN FACT, BEING CONNECTED TO A SECONDARY SYSTEM. IF IT IS NOT CONNECTED TO SECONDARY, CONTACT THE OWNER AND LANDSCAPE ARCHITECT TO COORDINATE A CULINARY SYSTEM AND REQUIRED COMPONENTS. A FUNCTIONING AMIAD FILTER IS TO BE USED AT THE POINT OF CONNECTION.
4. VERIFY THAT THE POINT OF CONNECTION IS IN THE CORRECT LOCATION BEFORE INSTALLATION. ALL CONNECTIONS ON THIS PROJECT ARE TO SECONDARY WATER AND SHOULD BE NOTED AS SUCH; THEREFORE, ALL PARTS MUST MEET WATER STANDARDS THAT PERTAIN TO SECONDARY WATER.USE PURPLE VALVE BOXES FOR SECONDARY WATER SYSTEMS.
5. ON OCCASION AND FOR GRAPHIC PURPOSES ONLY, THE IRRIGATION SYSTEM MIGHT BE SHOWN IN HARDSCAPE AREAS. THIS IRRIGATION IS TO BE PLACED IN LANDSCAPED AREAS ON THE PROPERTY SITE.
6. CONTRACTOR SHALL USE ONLY COMMERCIAL GRADE IRRIGATION PRODUCTS. THIS INCLUDES PIPE TO BE SCHEDULE 40 PVC OR BETTER. NO POLY PIPE IS TO BE USED. FITTINGS UP TO 1-1/2" MUST BE SCHEDULE 40 OR BETTER. FITTINGS LARGER THAN 1-1/2" SHALL BE SCHEDULE 80 OR BETTER. CONTRACTOR IS RESPONSIBLE FOR ENSURING ACCURATE COUNTS AND QUANTITIES OF ALL IRRIGATION MATERIALS FOR BIDDING AND INSTALLATION.
7. MAIN LINES SHALL BE A MINIMUM OF 24" DEEP AND LATERAL LINES A MINIMUM OF 12" DEEP. NO ROCK GREATER THAN 1/2" DIAMETER SHALL BE ALLOWED IN TRENCHES. TRENCHING BACKFILL MATERIAL SHALL BE COMPACTED TO PROPER FINISHED GRADE.
8. NO IRRIGATION MAIN LINE MAY BE LOCATED WITHIN 5 FEET OF ANY STRUCTURE.
9. TO AVOID PIPE DAMAGE, ADJUST LOCATION OF PIPE TO NOT BE DIRECTLY UNDER PLANT MATERIALS. VALVE BOXES ARE PREFERRED TO BE IN PLANTER BEDS INSTEAD OF THE LAWN.
10. PLAN INDICATES 100% OR BETTER HEAD TO HEAD COVERAGE. SHOULD CONTRACTOR FIND DISCREPANCIES DUE TO NECESSARY FIELD ADJUSTMENTS, CONTACT LANDSCAPE ARCHITECT FOR IRRIGATION CORRECTION.
11. DRIP IRRIGATION TO BE INSTALLED PER DETAILS. CONTRACTOR SHALL MAKE NECESSARY ADJUSTMENTS. TUBING SHOULD REST TOWARD OUTER EDGE OF ROOTBALL AND NOT AGAINST TRUNK OF PLANT.
12. A QUICK COUPLER SHALL BE INSTALLED AT POINT OF CONNECTION TO ALLOW BLOW OUT OF SYSTEM BY AIR COMPRESSOR AT END OF EACH SEASON.
13. INSTALL SLEEVES FOR ALL PIPES AND WIRE CONDUIT THAT ARE PLACED UNDER PAVEMENT AND SIDEWALKS. SLEEVES SHALL BE 2 SIZES LARGER THAN PIPE BEING PLACED INTERNALLY. WIRE CONDUIT SHALL BE INSTALLED IN CLASS 200 PIPE. AT ANY DIRECTIONAL CHANGE THAT OCCURS, A JUNCTION BOX IS TO PLACED.
14. CONDUITS CAN NOT BE SHARED BY WATER AND ELECTRICAL LINES. ALL WIRE TO BE PUT IN PVC CONDUIT. ALL WIRE CONNECTIONS TO BE PLACED IN A VALVE BOX. ALL WIRE CONNECTIONS TO USE WATERPROOF WIRE CONNECTORS WITH AT LEAST 3' OF EXTRA WIRE. PROVIDE PLENTY OF EXTRA WIRE AT EVERY DIRECTIONAL CHANGE. INSULATED 14 GAUGE COPPER TO BE USED FOR ALL CONTROL WIRES AND INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
15. CONTRACTOR TO INSTALL LIGHTNING ARRESTOR AND GROUNDING RODS ON SITE PER MANUFACTURER'S RECOMMENDATIONS, SEE DETAILS.
16. CONTRACTOR TO SEPARATE SYSTEM (CONTROLLER, VALVES, AND DIFFERENT COLORED WIRE) FROM CITY MAINTAINED PROPERTY AND HOA/OWNER MAINTAINED PROPERTY.
17. DUCT TAPE ALL SLEEVES TO PREVENT SOIL OR OTHER DEBRIS ENTERING PIPE. IDENTIFY ALL SLEEVES BY WOOD OR PVC STAKES AND SPRAY PAINT WITH MARKING PAINT. REMOVE STAKES ONCE IRRIGATION SYSTEM IS COMPLETE.
18. TO PREVENT EROSION AND LOW POINT DRAINAGE CONTRACTOR SHALL INSTALL CHECK VALVES
19. LOCATE SPRAY HEADS NO CLOSER THAN 6" FROM WALLS, FENCES OR BUILDINGS AND 2" AWAY FROM WALKS, PATHS OR CURBS.
20. PRESSURE TEST MAINLINE FOR LEAKS PRIOR TO BACKFILLING. CONTACT LANDSCAPE ARCHITECT/OWNER AT THIS TIME FOR COMPLIANCE.
21. CONTRACTOR TO CONSULT WITH OWNER ON EXACT LOCATION OF CONTROLLER. CONTRACTOR TO COORDINATE WITH ELECTRICAL CONTRACTOR AND OWNER FOR THE POWER SUPPLY. INSTALL ALL PER MANUFACTURER'S SPECIFICATIONS. CONTRACTOR SHALL INSTALL A RAIN SENSOR WITH THE CONTROLLER UNLESS OTHERWISE DIRECTED BY OWNER OR LANDSCAPE ARCHITECT.
22. LATERAL LINES SHALL BE NO SMALLER THAN 3/4". LANDSCAPE CONTRACTOR TO ENSURE THE FOLLOWING PIPE SIZES DO NOT EXCEED THE SUGGESTED GPM LISTED BELOW:

3/4"	8 GPM
1"	12 GPM
1-1/2"	30 GPM
2"	53 GPM
2-1/2"	75 GPM
3"	110 GPM
4"	180 GPM

VALVE ID TAG



NOTE:
1. VALVE ID TAGS ARE LOCATED NEAR VALVES IN THE ORDER THE VALVES APPEAR ON THE DRAWING

ISSUE DATE	PROJECT NUMBER	PLAN INFORMATION	PROJECT INFORMATION	DEVELOPER / PROPERTY OWNER / CLIENT	LANDSCAPE ARCHITECT / PLANNER	LICENSE STAMP	DRAWING INFO
7/20/2021	UT21101	811 BLUE STAKES OF UTAH UTILITY NOTIFICATION CENTER, INC 1-800-662-4111 www.bluestakes.org	DEER PARK 6800 NORTH AMERICAN FORK, UTAH	AE URBIA 909 W. SOUTH JORDAN PARKWAY SOUTH JORDAN, UT 84095 801-575-6455	PKJ DESIGN GROUP Landscape Architecture Planning & Visualization 3450 N. TRIUMPH BLVD. SUITE 102 LEHI, UTAH 84043 (801) 960-2698 www.pkjdesigngroup.com	LICENSED LANDSCAPE ARCHITECT JEREMY AINSWORTH 8128727-5301 07/20/2021 ELECTRONIC SEAL STATE OF UTAH	PM: JTA DRAWN: ACP CHECKED: JMA PLOT DATE: 7/20/2021

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

N

0' 10' 20' 40' 80'


GRAPHIC SCALE: 1" = 20'

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

IRRIGATION PLAN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

IR-106




1. TWO-WIRE CONTROLLER: RAIN BIRD ESP-LXIVM/PRO IN LXMM METAL CABINET WITH OUTSIDE WALL MOUNT. INSTALL CONTROLLER AND CABINET ON WALL PER MANUFACTURER'S RECOMMENDATIONS.
2. JUNCTION BOX
3. 1-INCH CONDUIT AND FITTINGS FOR POWER SUPPLY WIRE
4. 2-INCH CONDUIT AND FITTINGS FOR TWO-WIRE CABLE
5. MAXICABLE TWO-WIRE PATH TO FIELD DEVICES, USE A DIFFERENT CABLE JACKET COLOR FOR EACH PATH.
6. 1-INCH CONDUIT AND FITTINGS FOR GROUND WIRE. ONLY FOR OUTDOOR INSTALLATIONS.

NOTES:
1. ESP-LXIVM CONTROLLER IS AVAILABLE IN TWO MODELS. THE LXIVM WITH 60 STATIONS AND THE LMIVM-PRO WITH 240 STATIONS. REFER TO THE CHART BELOW FOR DIFFERENCES BETWEEN THE TWO MODELS.
2. USE STEEL CONDUIT FOR ABOVE GRADE AND SCH 40 PVC CONDUIT FOR BELOW GRADE CONDITIONS.
3. PROVIDE PROPER GROUNDING COMPONENTS TO ACHIEVE GROUND RESISTANCE OF 10 OHMS OR LESS. IF CONTROLLER IS MOUNTED INDOORS, USE POWER SUPPLY GROUND.


KEY SPECIFICATIONS

MODEL / FEATURE	MAX PROGRAMS	STATIONS	MAX SIMUL.STATIONS	MASTER VALVES	FLOW SENSORS	WEATHER SENSORS
LX-IVM	10	60	8	5	5	4
LX-IVM PRO	40	240	16	10	10	8

A ESP-LXIVM/PRO TWO-WIRE CONTROLLER IN METAL CABINET
NOT TO SCALE




B 2" PLASTIC FILTER DETAIL
NOT TO SCALE




NOTES:
1. INSTALL GATE VALVE PER MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
2. VALVE BOX SHALL BE WRAPPED WITH MINIMUM 3 MIL. THICK PLASTIC AND SECURE IT TO VALVE BOX USING DUCT TAPE OR ELECTRICAL TAPE.
3. VALVE BOX SHALL BE LOCATED IN PLANTING AREA.

C GATE VALVE AND ANCHOR DETAIL
NOT TO SCALE




D TYPICAL SLEEVING DETAIL
NOT TO SCALE




NOTES:
1. SEE IRRIGATION LEGEND FOR MAINLINE AND LATERAL LINE PIPE SIZE AND TYPE.
2. DIRECT BURIAL CONTROL WIRES SHALL BE INSTALLED IN SCH. 40 PVC ELECTRICAL CONDUIT IF REQUIRED.
3. 2-WIRE IRRIGATION WIRE SHALL BE INSTALLED IN SCH. 40 PVC ELECTRICAL CONDUIT.
4. DETECTABLE LOCATOR TAPE SHALL BE LOCATED SIX INCHES (6") ABOVE THE ENTIRE MAINLINE RUN.

E IRRIGATION TRENCHING DETAIL
NOT TO SCALE




NOTES:
1. ALL THREADED CONNECTIONS SHALL BE INSTALLED USING TEFLON TAPE.
2. VALVE BOX SHALL BE WRAPPED WITH A MINIMUM 3 MIL THICK PLASTIC AND SECURED TO THE VALVE BOX USING DUCT TAPE OR ELECTRICAL TAPE.
3. ALL QUICK COUPLERS SHALL BE INSTALLED A MINIMUM OF 18" OFF OF THE MAINLINE.
4. VALVE BOXES SHALL BE LOCATED IN PLANTING AREAS.

G QUICK COUPLER DETAIL
NOT TO SCALE



NOTES:
1. ALL FITTINGS TO BE SCH. 80 PVC
2. PROVIDE OWNER WITH KEY


H STOP AND WASTE VALVE ASSEMBLY DETAIL
NOT TO SCALE



NOTES:
1. ALL FITTINGS TO BE SCH. 80 PVC
2. PROVIDE OWNER WITH KEY

F MANUAL DRAIN DETAIL
NOT TO SCALE

1. NORMALLY OPEN MASTER VALVE(S)
2. 36-INCH LENGTH OF COILED WIRE TO SATELLITE CONTROLLER SPARE STATION
3. 3-INCH MINIMUM DEPTH OF 3/4-INCH WASHED GRAVEL
4. BRICK (1 OF 4)
5. VALVE BOX WITH COVER - 12-INCH SIZE
6. FINISH GRADE
7. RAIN BIRD FS SERIES 350 FLOW SENSOR(S)
8. 36-INCH LENGTH OF COILED PE-CABLE TO FLOW SENSING EQUIPMENT AT CCU/SATELLIT CONTROLLER ASSEMBLY
9. DOUBLE-STRAP SADDLE
10. SEE MAXICOM DETAIL 611 FOR SPLICE. SEE FLOW SENSOR DETAIL FOR WIRING DIAGRAM.
11. CONCENTRIC REDUCER



I MASTER VALVE AND FLOW SENSOR DETAIL
NOT TO SCALE

ISSUE DATE: 7/20/2021
PROJECT NUMBER: UT21101

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT:
AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER:
PKJ DESIGN GROUP
Landscape Architecture / Planning & Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com


LICENSE STAMP: LICENSED LANDSCAPE ARCHITECT — JEREMY AINSWORTH — 8129124-5301 — 07/20/2021 — STATE OF UTAH

DRAWING INFO
PM: JTA
DRAWN: ACP
CHECKED: JMA
PLOT DATE: 7/20/2021

IRRIGATION DETAILS

PRELIMINARY PLANS NOT FOR CONSTRUCTION


IR-501



J 2-WIRE CONNECTION DETAIL

PKJ DESIGN GROUP

NOT TO SCALE




NOTES:
1. ALL GROUNDING REQUIREMENTS FOR CONTROLLERS SHALL CONFORM TO LOCAL ELECTRIC CODES.
2. GROUNDING ROD SHALL NOT BE LOCATED IN THE SAME TRENCH AS THE IRRIGATION MAINLINES OR LATERAL LINES.
3. VALVE BOX SHALL BE WRAPPED WITH A MINIMUM 3 MIL THICK PLASTIC AND SECURED TO THE VALVE BOX USING DUCT TAPE OR ELECTRICAL TAPE.
4. INSTALL GROUNDING ROD PER THE CONTROLLER MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.

K GROUNDING ROD DETAIL

PKJ DESIGN GROUP

NOT TO SCALE



1. 30-INCH LENGTH OF 2-WIRE CABLE
2. WATERPROOF CONNECTION RAIN BIRD WC20 (TWO REQUIRED)
3. ID TAG: RAIN BIRD VID SERIES
4. REMOTE CONTROL VALVE: RAIN BIRD PEB/PESB/PESB-R WITH IVM
5. VALVE BOX WITH COVER: RAIN BIRD VB-STD
6. FINISH GRADE/TOP OF MULCH
7. PVC SCH 80 NIPPLE (CLOSE)
8. PVC SCH 40 ELL
9. PVC SCH 80 NIPPLE (LENGTH AS REQUIRED)
10. BRICK (1 OF 4)
11. PVC MAINLINE PIPE SCH 80 NIPPLE (2-INCH LENGTH, HIDDEN) AND SCH 40 ELL
12. PVC SCH 40 TEE OR ELL
13. PVC SCH 40 MALE ADAPTER
14. PVC LATERAL PIPE
15. 3-INCH MINIMUM DEPTH OF 3/4-INCH WASHED GRAVEL

M ELECTRIC REMOTE-CONTROL VALVE PEB OR PESB SERIES WITH IVM

PKJ DESIGN GROUP


NOT TO SCALE

NOTES:
1. ALL THREADED CONNECTION POINTS BETWEEN SCH. 40 PVC AND SCH. 80 PVC FITTING SHALL BE INSTALLED USING TEFLON TAPE.
2. CONTRACTOR SHALL COMPACT SOIL AROUND ROTOR AND RISER PRIOR TO PLANTING, PLUGGING, SEEDING, OR LAYING OF SOD.

N ROTOR SPRAYHEAD DETAIL

PKJ DESIGN GROUP

NOT TO SCALE




1. FINISH GRADE/TOP OF MULCH
2. VALVE BOX WITH COVER: RAIN BIRD VB-6RND
3. PVC SCH 40 TEE
4. PVC LATERAL PIPE
5. FILTERED DRAIN VALVE: RAIN BIRD 16A-FDV-075
6. BRICK (1 OF 2)
7. 6-INCH MINIMUM DEPTH OF 3/4" WASHED GRAVEL

L LATERAL LINE DRAIN VALVE DETAIL

PKJ DESIGN GROUP

NOT TO SCALE



NOTE:
1. 6" POP UPS SHALL BE USED IN TURF AREAS.
2. CONTRACTOR SHALL SETTLE SOIL AROUND THE POP UP AFTER INSTALLATION.
3. ALL POP UP SPRAY HEADS SHALL HAVE CHECK VALVES.
4. ALL SCH. 40 PVC TO SCH. 80 PVC CONNECTIONS SHALL BE MADE USING TEFLON TAPE.

O POP UP-SPRAY HEAD DETAIL

PKJ DESIGN GROUP

NOT TO SCALE

ISSUE DATE: 7/20/2021 | PROJECT NUMBER: UT21101

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

PLAN INFORMATION

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

PROJECT INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture / Planning &Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY AINSWORTH
812812-5301
07/26/2021
ELECTRONIC SEAL
STATE OF UTAH


DRAWING INFO

PM: JTA
DRAWN: ACP
CHECKED: JMA
PLOT DATE: 7/20/2021

IRRIGATION DETAILS

PRELIMINARY PLANS NOT FOR CONSTRUCTION

IR-502




1. FINISH GRADE/TOP OF MULCH
2. VALVE BOX WITH COVER: RAIN BIRD VB-STD
3. 30-INCH LINEAR LENGTH OF WIRE, COILED
4. WATERPROOF CONNECTION: RAIN BIRD DB SERIES
5. 1-INCH BALL VALVE (INCLUDED IN XCZ-PRB-100-COM KIT)
6. ID TAG
7. REMOTE CONTROL VALVE: RAIN BIRD PESB (INCLUCED IN XCZ-PRB-100-COM KIT)
8. PRESSURE REGULATING QUICK CHECK BASKET FILTER: RAIN BIRD PRB-QKCHK-100 (INCLUDED IN XCZ-PRB-100-COM KIT)
9. PVC SCH 40 FEMALE ADAPTOR
10. LATERAL PIPE
11. PVC SCH 80 NIPPLE (LENGTH AS REQUIRED)
12. PVC SCH 40 ELL
13. PVC SCH 80 NIPPLE (2-INCH LENGTH, HIDDEN) AND PVC SCH 40 ELL
14. PVC SCH 40 TEE OR ELL
15. MAINLINE PIPE
16. 3-INCH MINIMUM DEPTH OF 3/4-INCH WASHED GRAVEL
17. PVC SCH 80 NIPPLE, CLOSE (INCLUDED IN XCZ-PRB-100-COM KIT)

P DRIP CONTROL ZONE KIT DETAIL

NOT TO SCALE

PKJ DESIGN GROUP




1. MULCH
2. FLUSH CAP FOR EASY FIT COMPRESSION FITTINGS: POTABLE:RAIN BIRD MDCFCAP
3. EASY FIT COUPLING: RAIN BIRD MDCFCOUP
4. SUBTERRANEAN EMITTER BOX: RAIN BIRD SEB 7XB
5. ½" POLYETHYLENE TUBING: RAIN BIRD XF BLANK TUBING
6. FINISH GRADE
7. PVC EXHAUST HEADER
8. PVC SCH 40 TEE OR EL
9. BARB X MALE FITTING: RAIN BIRD XFF-MA FITTING (TYPICAL)
10. ON-SURFACE DRIPLINE: RAIN BIRD XF SERIES DRIPLINE POTABLE: XFCV DRIPLINE
11. 3-INCH MINIMUM DEPTH OF 3/4 " WASHED GRAVEL
12. BRICK (1 OF 2)

NOTE:
1. ALLOW A MINIMUM OF 6-INCHES OF DRIPLINE TUBING IN VALVE BOX IN ORDER TO DIRECT FLUSHED WATER OUTSIDE VALVE BOX.

Q ON-SURFACE DRIPLINE FLUSH POINT DETAIL

NOT TO SCALE

PKJ DESIGN GROUP




1. FINISH GRADE
2. SUBTERRANEAN EMITTER BOX: RAIN BIRD SEB 7XB
3. ½" AIR RELIEF VALVE: RAIN BIRD ARV050 TO BE INSTALLED AT HIGH POINTS IN DRIP ZONE
4. PVC SCH 40 FEMALE ADAPTER
5. PVC SCH 80 RISER
6. BRICK (1 OF 2)
7. PVC HEADER PIPE
8. PVC SCH 40 TEE
9. 3" MINIMUM DEPTH OF 3/4" WASHED GRAVEL

R AIR RELIEF VALVE DETAIL

NOT TO SCALE

PKJ DESIGN GROUP



1. RAIN BIRD CONTROL ZONE KIT (SIZED TO ACCOMIDATE LATERAL FLOW DEMAND)
2. PVC DRIP MANIFOLD PIPE
3. PVC SCH 40 TEE OR EL (TYPICAL)
4. ¼" POLYETHYLENE TUBING: RAIN BIRD XF SERIES BLANK TUBING (TYPICAL)
5. BARB X BARB INSERT TEE: RAIN BIRD XFF-TEE (TYPICAL)
6. PROJECTED CANOPY LINE OF TREE OR SHRUB (TYPICAL)
7. ON-SURFACE DRIPLINE: RAIN BIRD XF SERIES DRIPLINE POTABLE: XFCV SERIES PLACE AS SHOWN (LENGTH AS REQUIRED, TYPICAL)
8. ROOT BALL (TYPICAL)
9. BARB X BARB INSERT CROSS: RAIN BIRD XFD-CROSS (TYPICAL)
10. DRIPLINE FLUSH POINT (SEE RAIN BIRD DETAIL: "XFCV DRIPLINE FLUSH POINT WITH BALL VALVE")
11. SPACING PER SPECIFICATION
12. TIE DOWN STAKE: RAIN BIRD TDS-050 WITH BEND (QUANTITY AS REQUIRED, SEE NOTES 2-3 BELOW)

NOTES:
1. INSTALL MULTIPLE RINGS AS REQUIRED TO PROVIDE IRRIGATION COVERAGE FROM ROOT BALL TO PROJECTED TREE CANOPY. REFER TO RAIN BIRD DESIGN GUIDELINES AND SPECIFICATIONS FOR RECOMMENDED SPACING BETWEEN RINGS.
2. PLACE TIE DOWN STAKES EVERY THREE FEET IN SAND, FOUR FEET IN LOAM, AND FIVE FEET IN CLAY.
3. AT FITTINGS WHERE THERE IS A CHANGE OF DIRECTION SUCH AS TEES OR ELBOWS, USE TIE-DOWN STAKES ON EACH LEG OF THE CHANGE OF DIRECTION.

S ON-SURFACE DRIPLINE TREE/SHRUB DETAIL

NOT TO SCALE

PKJ DESIGN GROUP

ISSUE DATE 7/20/2021

PROJECT NUMBER UT21101

NO.	REVISION	DATE
1	XXXX	XX-XX-XX
2		
3		
4		
5		
6		
7		

PLAN INFORMATION

811 BLUE STAKES OF UTAH
UTILITY NOTIFICATION CENTER, INC
1-800-662-4111
www.bluestakes.org

PROJECT INFORMATION

DEER PARK
6800 NORTH
AMERICAN FORK, UTAH

DEVELOPER / PROPERTY OWNER / CLIENT

AE URBIA
909 W. SOUTH JORDAN PARKWAY
SOUTH JORDAN, UT 84095
801-575-6455

CIR CIVIL ENGINEERING
3032 SOUTH 1030 WEST, SUITE 202
SALT LAKE CITY, UT 84119
801-949-6296

LANDSCAPE ARCHITECT / PLANNER

PKJ DESIGN GROUP
Landscape Architecture / Planning &Visualization
3450 N. TRIUMPH BLVD. SUITE 102
LEHI, UTAH 84043 (801) 960-2698
www.pkjdesigngroup.com

LICENSE STAMP

LICENSED LANDSCAPE ARCHITECT
JEREMY ANDREW AINSWORTH
8128121-5301
07/06/2021
ELECTRONIC SEAL
STATE OF UTAH

DRAWING INFO

PM: JTA
DRAWN: ACP
CHECKED: JMA
PLOT DATE: 7/20/2021


IRRIGATION DETAILS


PRELIMINARY PLANS NOT FOR CONSTRUCTION

IR-503

DEER PARK SUBDIVISION

LOCATED IN THE SOUTHEAST QUARTER OF SECTION 26, TOWNSHIP 5 SOUTH, RANGE 1 EAST, SALT LAKE BASE AND MERIDIAN AMERICAN FORK CITY, UTAH COUNTY, UTAH





PLAT NOTES:

1. Lowest Floor Slab must be a minimum of 3 feet above water level measured during Spring Season.

2. Off-set pins to be placed in the back of the curb and 5/8" by 24" rebar with numbered survey cap to be placed at all lots rear corners prior to occupancy.

3. Building permits will not be issued for any home until 1) asphalt paving is installed and 2) fire hydrants are installed, approved by the Fire Marshall and charged with culinary water.

LEGEND

- Boundary Line
- Adjacent Parcel Line
- Section Line
- Easement Line
- Parcel Line
- Existing Asphalt Road Centerline
- Set Rebar and Cap stamped CIR Engineering
- Proposed Fire Hydrant

OWNER:

Deer Park, LLC
6755 North 5750 West
American Fork, UT 84003

DEVELOPER:

Harbor View Development, LLC
6755 North 5750 West
American Fork, UT 84003

PRELIMINARY

SHEET 1 / 1

PREPARED BY:
CIR | CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 - 801-949-6296

BASIS OF BEARING:

The Basis of Bearings was established as S. 89°00'19" E (NAD83 Utah Central Zone) between the Reference Corner to the South Quarter Corner and the Reference Corner to the Southeast Corner of Section 26, Township 5 South, Range 1 East, Salt Lake Base & Meridian.

LAND USE AND ZONING DESIGNATION

Subject property includes the following zoning classifications:
- Planned industrial (PI-1)
- Industrial (i-1)
- Marina (m-1)

Subject property includes the following land use zones:
- Design industrial
- Residential very low density
- Shoreline protection

FLOOD ZONE DESIGNATION

The subject property falls within Flood Zone X (Other Flood Areas) as delineated by F.E.M.A. Flood Insurance Rate Map, Community Panel No. 49049C0306F, which bears and Effective Date of June 19, 2020.

WATER & SEWER AUTHORITY APPROVAL

Approved this _____ day of _____ A.D. 20____ by the Water & Sewer Authority

_____
Public Works Department Director

SURVEYOR CERTIFICATE

I, GARY CHRISTENSEN, do hereby certify that I am a Professional Land Surveyor in the State of Utah and that I hold License No. 5152617 in accordance with Title 58, Chapter 22, of the Professional Engineers and Land Surveyors Act; I further certify that by authority of the owners I have made a survey of the property described on this plat in accordance with 17-23-17 and have verified all measurements, and have subdivided said property into lots and streets, together with easements, hereafter to be known as ***DEER PARK SUBDIVISION*** and that the same has been correctly surveyed and monumented on the ground as shown on this plat.

Signed this ___day of _____, 20___

BOUNDARY DESCRIPTION

A parcel of land being all or part of those three (3) entire tracts of land described in that 1) Special Warranty Deed recorded May 19, 2015 as Entry No. 42947:2015; 2) Special Warranty Deed recorded May 19, 2015 as Entry No. 42948:2015 and; 3) Warranty Deed recorded January 6, 2016 as Entry No. 1068:2016 in the Office of the Utah County Recorder. Said entire tract of land is located in the Southeast Quarter of Section 26, Township 5 South, Range 1 East, Salt Lake Base and Meridian and described as follows:

Beginning at the southwesterly corner of said entire tract described in that Special Warranty Deed recorded as Entry No. 42947:2015, which is 631.44 feet S. 89°00'19" E. along a monument line and 1968.32 feet North from a Reference Monument to the South Quarter Corner of said Section 26; thence N. 00°28'09" E. (Record = N 0 DEG 28'0" E) 698.34 feet along the westerly boundary line of said entire tract and extension thereof; thence S. 89°12'49" E. 738.73 feet to an existing fence; thence S. 00°24'46" W. (Record = N 0 DEG 27'17" E) 873.04 feet along said existing fence; thence along said entire tracts described in said Special Warranty Deed recorded as Entry No. 42947:2015 and 42948:2015 the following two (2) courses: 1) N. 89°59'51" W. (Record = W) 344.31 feet; 2) N. 64°51'27" W. (Record = N 64 DEG 51'36" W) 435.00 feet to the **Point of Beginning**.

The above-described entire tract contains 612,519 sq. ft. in area or 14.061 acres, more or less. Two (2) Lots.

OWNERS DEDICATION

Know all men by these present that we, the undersigned are owners of all of the property described in the Surveyor's Certificate herein and shown on this map, have caused the same to be subdivided into lots, blocks, streets, and easements and do hereby dedicate the streets and other public areas as indicated hereon for perpetual use of the public.

In witness whereof, We have hereunto set our hands this _____ day of _____, A.D. 2021.

Deer Park, LLC

By: _____

Print Name: _____

By: _____

NOTARY ACKNOWLEDGMENT

State of Utah)
:ss
County of Utah)

On the _____ day of _____, in the year A.D. 20_____, personally appeared before me, the signers of the foregoing dedication who duly acknowledge to me that they did execute the same.

Commission Number _____
My Commission Expires _____

Signature: _____
Print: _____
Name: _____

A Notary Public Commissioned in Utah

ACCEPTANCE BY LEGISLATIVE BODY

The _____ of _____ County of Utah, approves this subdivision and hereby accepts the dedication of all the streets, easements, and other parcels of land intended for public purposes for the perpetual use of the public this _____ day of _____, A.D. 20___

_____ Mayor

_____ City Council Member

_____ City Council Member

_____ City Council Member

_____ City Council Member

_____ City Council Member

_____ City Engineer

ATTEST: _____ Clerk - Recorder (See Seal below)

PLANNING COMMISSION APPROVAL

Approved this _____day of _____ A.D. 20____ by the American Fork Planning Commission

_____ Planner

_____ Planning Commission Chairman

DEER PARK SUBDIVISION

LOCATED IN THE SOUTHEAST QUARTER OF SECTION 26, TOWNSHIP 5 SOUTH, RANGE 1 EAST, SALT LAKE BASE AND MERIDIAN AMERICAN FORK CITY, UTAH COUNTY, UTAH

SURVEYOR'S SEAL	NOTARY PUBLIC SEAL	COUNTY RECORDER SEAL
GARY CHRISTENSEN 5152617 07/15/2021 STATE OF UTAH PROFESSIONAL LAND SURVEYOR PRELIMINARY		

Deer Park

25 EAST 1100 SOUTH
AMERICAN FORK, UTAH 84003


JULY 26, 2021
OCTOBER 18, 2021

LEGEND

PROPERTY LINE		EXISTING FIRE HYDRANT	
EASEMENT LINE		PROPOSED FIRE HYDRANT	
4240.0 PROPOSED GRADE CONTOURS		EXISTING STREET LIGHT	
4240.0 EXISTING GRADE CONTOURS		PROPOSED STREET LIGHT	
EXISTING CURB		PROPOSED PARKING LOT LIGHT	
PROPOSED CURB AND GUTTER			
PROPOSED CURB WALL		EXISTING WATER METER	
REVERSE PAN CURB & GUTTER		EXISTING WATER VALVE	
SS EXISTING SEWER		EXISTING GATE VALVE	
SS PROPOSED SEWER		EXISTING OVERHEAD POWER POLE	
W EXISTING WATER	TBC	TOP BACK CONCRETE	
W PROPOSED WATER	FF	FINISHED FLOOR	
F EXISTING FIRE LINE	HW	HIGH WATER	
F PROPOSED FIRE LINE	TOG	TOP OF GRATE	
SD EXSITING STORM DRAIN	TOL	TOP OF LID	
SD PROPOSED STORM DRAIN	IE	INVERT ELEVATION	
RD PROPOSED ROOF DRAIN	EX	EXISTING	
G EXISTING GAS	NG	NATURAL GROUND	
G PROPOSED GAS	TA	TOP OF ASPHALT	
OHP EXISTING OVERHEAD POWER	TC	TOP OF CONCRETE	
UGP EXISTING UNDERGROUND POWER	EC	EDGE OF CONCRETE	
UGP PROPOSED UNDERGROUND POWER	EA	EDGE OF ASPHALT	
T EXISTING TELEPHONE LINE	TOW	TOP OF WALL	
T PROPOSED TELEPHONE LINE	TG	TOP OF GRAVEL	
FO EXISTING FIBER OPTIC LINE	TL	TOP OF LANDSCAPING	
FO PROPOSED FIBER OPTIC LINE	TS	TOP OF SIDEWALK	
	PROP	PROPOSED	
PROPOSED CONCRETE	39.0	TBC CALLOUT UNLESS OTHERWISE DESIGNATED	
PROPOSED ASPHALT			
PROPOSED LANDSCAPING			

PROJECT CONTACT INFORMATION:

AF CITY CULINARY WATER	JAY BREMS	(801) 763 3060
AF PRESSURIZED IRRIGATION	JAY BREMS	(801) 763 3060
AF SANITARY SEWER	ASHTON HARDY	(801) 763 3060
AF STORM DRAIN SEWER	ASHTON HARDY	(801) 763 3060
AF FIRE MARSHALL	MAT SACCO	(801) 763 3040
AF CITY INSPECTOR	DEE HOWARD	(801) 763 3060
AF FIBER	KYLE PETERSEN	(801) 400 2933
AF FLOOD IRRIGATION COMPANY	ERNIE JOHN	(801) 471 6576
TIMPANOGOS SSD	DAVID BARLOW	(801) 756 5231
ROCKY MOUNTAIN POWER	TERIA WALKER	(801) 756 1310
COMCAST	ELYSIA VALDEZ	(801) 401 3017
CENTURY LINK	RYAN ALLRED	(385) 223 0084
DOMINION ENERGY	TRENT JOHNSON	(801) 853 6548



VICINITY MAP
NOT TO SCALE

SHEET INDEX

CV	COVER SHEET
GN	GENERAL NOTES
C1.0	SITE PLAN
C2.0	GRADING PLAN
C2.1	DRAINAGE PLAN
C3.0	UTILITY PLAN
C3.1	UTILITY PLAN
C4.0	1100 SOUTH – ROAD PLAN & PROFILE
C4.1	1100 SOUTH – UTILITY PLAN & PROFILE
C4.2	1100 SOUTH – UTILITY PLAN & PROFILE
C4.3	1100 SOUTH – STRIPING PLAN
C5.0	DETAIL SHEET
C5.1	AMERICAN FORK DETAIL SHEET
C5.2	AMERICAN FORK DETAIL SHEET
C6.0	EROSION CONTROL PLAN (SWPPP)
C7.0	EROSION CONTROL DETAIL SHEET

PROJECT CONSTRUCTION NOTES:

1. CONTRACTOR TO NOTIFY BLUE STAKES PRIOR TO CONSTRUCTION, 1-800-662-4111.
2. CONTRACTOR TO VERIFY LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.
3. SEE SOILS REPORT FOR PAVEMENT SECTION DETAILS, INSTALLATION SPECIFICATIONS AND ALL SITE EARTHWORK REQUIREMENTS.
4. IF SOFT SOILS ARE ENCOUNTERED DURING CONSTRUCTION ACTIVITIES, CONTRACTOR TO FOLLOW THE RECOMMENDATIONS OF THE GEOTECHNICAL REPORT TO MITIGATE.
5. ALL CONSTRUCTION SHALL CONFORM TO CITY STANDARDS AND SPECIFICATIONS. IF A CONFLICT BETWEEN THESE PLANS AND THE CITY STANDARDS AND SPECIFICATIONS OCCURS, THE CITY STANDARDS AND SPECIFICATIONS SHALL GOVERN.
6. ALL HANDICAP PARKING STALLS TO BE INSTALLED PER ADA STANDARDS. SLOPE ON ANY ADA STALL IS TO BE LESS THAN 2% IN ALL DIRECTIONS.
7. CONTRACTOR TO VERIFY PRIOR TO ANY CONSTRUCTION THAT THE BUILDING AND BUILDING LOCATION SHOWN ON CIVIL DRAWINGS MATCHES THE ARCHITECTURAL PLANS.
8. CONTRACTOR TO VERIFY, WITH ARCHITECT, THAT F.F. ELEVATION SHOWN ON CIVIL PLANS EQUALS THE ARCHITECTS 100.0' ELEVATION.
9. CONTRACTOR TO REPLACE IN KIND ANY AREAS THAT ARE DAMAGED DURING CONSTRUCTION.
10. INSTALL ALL SIDEWALKS PER CITY STANDARDS OR APWA PLAN NO. 231, 235, AND 236 WHERE APPLICABLE.
11. INSTALL ALL CONCRETE PAVEMENT JOINTS PER CITY STANDARDS OR APWA PLAN NO. 261.
12. ALL SEWER, WATER AND STORM DRAIN PIPES SHALL BE BACKFILLED WITH SELECT GRANULAR FILL PER AMERICAN FORK CITY STANDARDS AND SPECIFICATIONS. SEE AMERICAN FORK CITY STANDARD PLAN NO. 15.22
13. ALL CATCH BASINS AND MANHOLES TO BE INSTALLED PER CITY STANDARDS.
14. ALL STORM DRAIN PIPING TO BE CUT OFF FLUSH WITH INSIDE WALL OF DRAINAGE BOX. INSIDE WALL TO BE GROUTED SMOOTH WITH A NON-SHRINK GROUT.
15. FOR STORM DRAIN INLET BOXES AND MANHOLES THE I.E. IN AND I.E. OUT ELEVATIONS ARE THE SAME UNLESS OTHERWISE CALLED OUT ON THE PLANS
16. ALL WATER LINES TO HAVE A MINIMUM 4' OF COVER WITH A MINIMUM VERTICAL CLEARANCE OF 1' OF COVER BETWEEN OTHER UTILITY LINES (1.5' VERTICAL SEPARATION WITH SEWER).
17. THRUST BLOCKS TO BE INSTALLED PER AMERICAN FORK CITY PLAN NO 15.21
18. CONTRACTOR SHALL COORDINATE CONSTRUCTION AND INSTALLATION OF ELECTRICAL, TELEPHONE, NATURAL GAS AND CABLE TV SERVICES WITH THE RESPECTIVE UTILITY COMPANY.
19. THE EXISTENCE AND LOCATION OF ALL UNDERGROUND UTILITY PIPES, LINES OR STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED AND SHOWN FROM SURVEYED INFORMATION AND EXISTING UTILITY LOCATIONS PROVIDED BY OTHERS. THERE IS NO GUARANTEE THAT ALL EXISTING UTILITY INFORMATION IS SHOWN ON THESE PLANS. CONTRACTOR IS RESPONSIBLE FOR CONTACTING BLUE STAKES AND FIELD VERIFYING THE LOCATION AND ELEVATION OF ALL EXISTING UTILITY PIPES, LINES AND STRUCTURES, PRIOR TO CONSTRUCTION.
20. ANY OFF SITE DAMAGE TO EXISTING ASPHALT, CURB & GUTTER, LANDSCAPING AND ALL UTILITIES TO BE REPLACED IN KIND.
21. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING ALL SITE DEMOLITION REQUIRED TO COMPLETE THIS PROJECT.

General Notes:

CONTRACTOR SHALL COORDINATE CONSTRUCTION AND INSTALLATION OF ELECTRICAL, TELEPHONE, NATURAL GAS AND CABLE TV SERVICES WITH THE RESPECTIVE UTILITY COMPANY.

ALL CONSTRUCTION SHALL CONFORM TO CITY STANDARDS AND SPECIFICATIONS. IF A CONFLICT BETWEEN THESE PLANS AND THE CITY STANDARDS AND SPECIFICATIONS OCCURS, THE CITY STANDARDS AND SPECIFICATIONS SHALL GOVERN.

THE EXISTENCE AND LOCATION OF ALL UNDERGROUND UTILITY PIPES, LINES OR STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED AND SHOWN FROM SURVEYED INFORMATION AND EXISTING UTILITY LOCATIONS PROVIDED BY OTHERS. THERE IS NO GUARANTEE THAT ALL EXISTING UTILITY INFORMATION IS SHOWN ON THESE PLANS. CONTRACTOR IS RESPONSIBLE FOR CONTACTING BLUE STAKES AND FIELD VERIFYING THE LOCATION AND ELEVATION OF ALL EXISTING UTILITY PIPES, LINES AND STRUCTURES, PRIOR TO CONSTRUCTION.

FEMA NOTE:
THIS PROJECT LIES IN A FEMA DESIGNATED FLOOD ZONE X WHICH IS DEFINED AS AREAS OF 0.2% ANNUAL CHANCE FLOOD; AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.
PER MAP NO. 49049C0307F EFFECTIVE DATE: JULY 19, 2020 PANEL 307 OF 1450.

DEMOLITION NOTE:
CONTRACTOR TO VISIT SITE AND DETERMINE ALL NECESSARY DEMOLITION REQUIRED TO INSTALL PROPOSED IMPROVEMENTS AND TO FIELD VERIFY ALL NECESSARY DEMOLITION HAS BEEN COMPLETED PRIOR TO CONSTRUCTION.

Benchmark Info

The Benchmark for the project is the South Quarter Corner of Section 26, T.5.S. R.1.E., SLB&M
Elevation= 4503.89'
Datum is NAVD 88 derived from UTAH TURNGPS System

CIVIL ENGINEER:

CIR | CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 – PH: 801-949-6296

ARCHITECT:

AE URBIA
2875 SOUTH DECKER LAKE DRIVE, SUITE 275
SALT LAKE CITY, UTAH 84119
CONTACT PERSON: ANDREW BOLLSCHWEILER
PH: (801) 746-0456

NO.	REVISIONS	BY	DATE
1.	CITY COMMENTS	RGW	10/18/21

DESIGNER: RGW PROJECT ENGINEER: SDT

CIR | CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 – 801-949-6296

DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH
COVER SHEET

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

CALL BEFORE YOU DIG! IT'S THE LAW! BLUE STAKES 1-800-662-4111

SHEET NO.	CV
PROJECT ID	A1140-01
DATE:	07/26/21
FILE NAME:	PRJ-AFH
SCALE:	1"=40'

GENERAL NOTES

1. City of American Fork, A.P.W.A, Utah Chapter and Utah Department of Transportation Construction and Material Specifications, current editions, and any supplements thereto (hereafter referred to as Standard Specifications), shall govern all construction items unless otherwise noted. If a conflict between specifications is found, the more strict specification will apply as decided by the City Engineer. Item Numbers listed refer to City of American Fork Item Numbers unless otherwise noted.
2. The City Engineer will not be responsible for means, methods, procedures, techniques, or sequences of construction that are not specified herein. The City Engineer will not be responsible for safety on the work site, or for failure by the Contractor to perform work according to contract documents.
3. The Developer or Contractor shall be responsible to obtain all necessary permits including but not limited to Road Cut Permits and Notices of Intent (NOI), Building Permits, etc.
4. The Contractor shall notify the City of American Fork, Public Works Department in writing at least 7 working days prior to beginning construction and request a pre–construction meeting. Bond for public improvements and inspection fees must be paid in full prior to requesting a pre–construction meeting.
5. The Contractor shall be solely responsible for complying with all federal, state and local safety requirements including the Occupational Safety and Health Act of 1970. The Contractor shall exercise precaution always for the protection of persons (including employees) and property. It shall also be the sole responsibility of the Contractor to initiate, maintain and supervise all safety requirements, precautions and programs in connection with the work, including the requirements for confined spaces per 29 CFR 1910.146.
6. Following completion of construction of the site improvements and before requesting occupancy, a proof survey shall be provided to the City of American Fork, Public Works Department, that documents "as _ built" elevations, dimensions, slopes and alignments of all elements of this project. The proof survey shall be prepared, signed and submitted by the Professional Engineer who sealed the constructions drawings.
7. The Contractor shall restrict construction activity to public right_of_way and areas defined as permanent and/or temporary construction easements, unless otherwise authorized by the City Engineer.
8. The Contractor shall carefully preserve benchmarks, property corners, reference points, stakes and other survey reference monuments or markers. In cases of willful or careless destruction, the Contractor shall be responsible for restorations. Resetting of markers shall be performed by a License Utah Professional Surveyor as approved by the City Engineer.
9. Non_rubber tired vehicles shall not be moved on or across public streets or highways without the written permission of the City Engineer.
10. The Contractor shall restore all disturbed areas to equal or better condition than existed before construction. Drainage ditches or watercourses that are disturbed by construction shall be restored to the grades and cross_sections that existed before construction.
11. Tracking or spilling mud, dirt or debris upon streets, residential or commercial drives, sidewalks or bike paths is prohibited. Any such occurrence shall be cleaned up immediately by the Contractor at no cost to the City. If the Contractor fails to remove said mud, dirt, debris, or spillage, the City reserves the right to remove these materials and clean affected areas, the cost of which shall be the responsibility of the Contractor.
12. Disposal of excess excavation within Special Flood Hazard Areas (100–year floodplain) must be approved by the City Engineer.
13. All signs, landscaping, structures or other appurtenances within right–of–way disturbed or damaged during construction shall be replaced or repaired to the satisfaction of the City Engineer. The cost of this work shall be the responsibility of the Contractor.
14. All field tile broken or encountered during excavation shall be replaced or repaired and connected to the public storm sewer system as directed by the City Engineer. The cost of this work shall be the responsibility of the Contractor.
15. All precast concrete products shall be inspected at the location of manufacture. Approved precast concrete products will be stamped or have such identification noting that inspection has been conducted by the City of American Fork. Precast concrete products without proof of inspection shall not be approved for installation.
16. All trenches within public right–of–way shall be backfilled according to the approved construction drawings or securely plated during nonworking hours.
17. Trenches outside these areas shall be backfilled or shall be protected by approved temporary fencing or barricades during nonworking hours. Clean up shall follow closely behind the trenching operation.
18. All trees within the construction area not specifically designated for removal shall be preserved, whether shown or not shown on the approved construction drawings. Trees to be preserved shall be protected with high visibility fencing placed a minimum 15 feet from the tree trunk. Trees 6 – inches or greater at DBH (Diameter Breast Height) must be protected with fencing placed at the critical root zone or 15 feet, whichever is greater.
19. Trees not indicated on the approved construction drawings for removal may not be removed without prior approval of the Division of Engineering.
20. Permits to construct in the right–of–way of existing streets must be obtained from the City of American Fork, Public Works Department before commencing construction.
21. The Contractor shall be responsible for the condition of trenches within the right–of–way and public easements for a period of one year from the final acceptance of the work, and shall make any necessary repairs at no cost to the City.
22. Pavements shall be cut in neat, straight lines the full depth of the existing pavement, or as required by the City Engineer.
23. The replacement of driveways, handicapped ramps, sidewalks, bike paths, parking lot pavement, etc. shall be provided according to the approved construction drawings and the City of American Fork standard construction drawings.
24. Any modification to the work shown on drawings must have prior written approval by the City Engineer.
25. Traffic control and other regulatory signs shall comply with the Utah Department of Transportation Traffic Control guidelines and MUTCD Manual, current edition
26. Public street signs shall meet all City of American Fork specifications with lettering colored in white displayed over a green background.
27. Private street signs shall meet all City of American Fork specifications with lettering colored in white displayed over a blue background

UTILITIES

1. The following utilities are known to be located within the limits of this project:

COMPANY		CONTACT	PHONE
QWEST	– TELEPHONE	Darren Keller	(801) 356 6975
PACIFIC CORP	– POWER	Dennis Patten	(801) 756 1344
COMCAST	– CABLE	Sheryl Pearson	(801) 401 3023
QUESTAR GAS	– GAS	Steve Adams	(801) 324 3383
AMERICAN FORK CITY	– WATER	Jay Brems	(801) 404 6129
AMERICAN FORK CITY	– SEWER	Aaron Brems	(801) 404 6126
AMERICAN FORK CITY	– STORM	Aaron Brems	(801) 404 6126
AMERICAN FORK CITY	– SWPPP	Harlan Nielson	(801) 404 6361
AMERICAN FORK CITY	– P.I.	Jay Brems	(801) 404 6129

2. The Contractor shall give notice of intent to construct to Blue Stake (telephone number 800_662–4111) at least 2 working days before start of construction.
3. The identity and locations of existing underground utilities in the construction area have been shown on the approved construction drawings as accurately as provided by the owner of the underground utility. The City of American Fork and the City Engineer assumes no responsibility for the accuracy or depths of underground facilities shown on the approved construction drawings. If damage is caused, the Contractor shall be responsible for repair of the same and for any resulting contingent damage.
4. Location, support, protection and restoration of all existing utilities and appurtenances, whether shown or not shown on the approved construction drawings, shall be the responsibility of the Contractor.
5. When unknown or incorrectly located underground utilities are encountered during construction, the Contractor shall immediately notify the owner and the City Engineer.

TRAFFIC CONTROL

1. Traffic control shall be furnished, erected, maintained, and removed by the Contractor according to Utah Department Of Transportation, Traffic Control guidelines or Manual of Uniform Traffic Control Devices, current edition.
2. All traffic lanes of public roadways shall be fully open to traffic from 7:00 AM to 9:00 AM and from 4:00 PM to 6:00 PM unless authorized differently by the City Engineer.
3. At all other hours the Contractor shall maintain minimum one _ lane two _ way traffic. Traffic circulation must be supervised by a Certified Flagger.
4. Steady _ burning, Type "C" lights shall be required on all barricades, drums, and similar traffic control devices in use at night.
5. Access from public roadways to all adjoining properties for existing residents or businesses shall be maintained throughout the duration of the project for mail, public water and sanitary sewer service, and emergency vehicles.
6. The Contractor shall provide a traffic control plan detailing the proposed maintenance of traffic procedures. The traffic control plan must incorporate any traffic control details contained herein.
7. The traffic control plan proposed by the Contractor must be approved by the City Engineer prior to construction.
8. Traffic Control requiring road closures and/ or detouring must be approved by the City Council.

EROSION AND SEDIMENT CONTROL

1. The Contractor or Developer is responsible for submitting a Notice of Intent (NOI) to be reviewed and approved by the Utah DWQ.
2. The NOI must be submitted to DWQ 45 days prior to the start of construction and may entitle coverage under the Utah DWQ General Permit for Storm Water Discharges associated with construction activity. A project location map must be submitted with the NOI.
3. A sediment and erosion control plan must be submitted to the City Engineer for approval if a sediment and erosion control plan has not already been included with the approved construction drawings. This plan must be made available at the project site at all times.
4. A UPDES Storm water Discharge Permit may be required. The Contractor shall be considered the Permittee.
5. The Contractor shall provide sediment control at all points where storm water runoff leaves the site, including waterways, overland sheet flow, and storm sewers.
6. Accepted methods of providing erosion/sediment control include but are not limited to: sediment basins, silt filter fence, aggregate check dams, and temporary ground cover. Hay or straw bales are not permitted.
7. The Contractor shall provide adequate drainage of the work area at all times consistent with erosion control practices.
8. Disturbed areas that will remain un–worked for 30 days or more shall be seeded or protected within seven calendar days of the disturbance.
9. Other sediment controls that are installed shall be maintained until vegetative growth has been established. The Contractor shall be responsible for the removal of all temporary sediment devices at the conclusion of construction but not before growth of permanent ground cover.

WATER LINE

1. All water line materials shall be provided and installed according to current specifications of the City of American Fork, Water Department.
2. All public water pipe with a diameter 3 inches to 8 inches shall be Ductile Iron, Class 53. Public water pipe 12 inches in diameter or larger shall be Ductile Iron, Class 54.
3. Only fire hydrants conforming to City of American Fork standards will be approved for use.
4. Public water lines shall be disinfected by the City of American Fork, Water Department. Requests for water line chlorination shall be made through the City of American Fork, Water Department. The cost for chlorination shall be paid for by the Contractor.
5. All water lines shall be disinfected according to City of American Fork Standard specifications. Special attention is directed to applicable sections of American Water Works Association specification C_651, particularly for flushing (Section 5) and for chlorinating valves and fire hydrants (Section 7).
6. Pressure testing shall be performed in accordance with the City of American Fork, Construction and Material Specifications. When water lines are ready for disinfection, the Contractor shall submit two (2) sets of "as–built" plans, and a letter stating that the water lines have been pressure tested and need to be disinfected, to the City of American Fork, Water Department.
7. The Contractor shall be responsible for all costs associated with the disinfection of all water lines construction per this plan. Pressure testing shall be performed in accordance with the City of American Fork, Construction and Material Specifications.
8. The Contractor shall paint all fire hydrants according to City of American Fork standards. The cost of painting fire hydrants shall be included in the contract unit price for fire hydrants.
9. No water taps or service connections (e.g., to curb stops or meter pits) may be issued until adjacent public water lines serving the construction site have been disinfected by the City of American Fork, Water Department and have been accepted by the Public Works Department.
10. The Contractor shall notify the City of American Fork, Water Department at (801) 763 3060 at least 24 hours before tapping into existing water lines.
11. All water main stationing shall be based on street centerline stationing.
12. All bends, joint deflections and fittings shall be backed with concrete per City of American Fork standards.
13. The Contractor shall give written notice to all affected property owners at least 1 working day but not more than 3 working days prior to any temporary interruption of water service. Interruption of water service shall be minimized and must be approved by the City Engineer.
14. All water lines shall be placed at a minimum depth of 4 feet measured from top of finished grade to top of water line. Water lines shall be set deeper at all points where necessary to clear existing or proposed utility lines or other underground restrictions by a minimum of 18 inches.

SANITARY SEWER

1. Sanitary sewage collection systems shall be constructed in accordance with the rules, regulations, standards and specifications of the City of American Fork, Public Works Department and the Utah Department of Health Code and Regulations.
2. The minimum requirements for sanitary sewer pipe with diameters 15 inches and smaller shall be reinforced concrete pipe ASTM C76 Class 3, or PVC sewer pipe ASTM D3034, SDR 35.
3. Pipe for 6–inch diameter house service lines shall be PVC pipe ASTM D3034, SDR 35. PVC pipe shall not be used at depths greater than 28 feet. Pipe materials and related structures shall be shop tested in accordance with City of American Fork Construction Inspection Division quality control requirements.
4. All manhole lids shall be provided with continuous self_sealing gaskets.
5. The approved construction drawings shall show where bolt_down lids are required.
6. Sanitary sewer manholes shall be precast concrete or as approved by the City Engineer and conform to the City of American Fork sanitary manhole standard drawing. Manhole lids shall include the word SEWER.
7. All PVC sewer pipes shall be deflection tested no less than 60 days after completion of backfilling operations.
7. At the determination of the City Engineer, the Contractor may be required to perform a TV inspection of the sanitary sewer system prior to final acceptance by the City. This work shall be completed by the Contractor at his expense.
8. Visible leaks or other defects observed or discovered during TV inspection shall be repaired to the satisfaction of the Engineer.
9. Roof drains, foundation drains, field tile or other clean water connections to the sanitary sewer system are strictly prohibited according to the American Fork Code of Ordinances.
10. All water lines shall be located at least 10 feet horizontally and 18 inches vertically, from sanitary sewers and storm sewers, to the greatest extent practicable.
11. Where sanitary sewers cross water mains or other sewers or other utilities, trench backfill shall be placed between the pipes crossing and shall be compacted granular material according to the city Standard Specifications. In the event that a water line must cross within 18 inches of a sanitary sewer, the sanitary sewer shall be concrete encased or consist of ductile iron pipe material.
12. Existing sanitary sewer flows shall be maintained at all times. Costs for pumping and bypassing shall be included in the Contractor's unit price bid for the related items.
13. The Contractor shall furnish all material, equipment, and labor to make connections to existing manholes.
14. All sewer lines shall be placed at a minimum depth of 4 feet measured from top of finished grade to top of sewer line.

STORM SEWER

1. All storm water detention and retention areas and major flood routing swales shall be constructed to finish grade and hydro _ seeded and hydro _ mulched according to the City of American Fork Standard Specifications.
2. Where private storm sewers connect to public storm sewers, the last run of private storm sewer connecting to the public storm sewer shall be Reinforced Concrete Pipe conforming to ASTM Designation C76, Wall B, Class IV for pipe diameters 12 inches to 15 inches, Class III for 18 inches to 24 inch pipes, and 27 inches and larger pipe shall be Class II, unless otherwise shown on the approved construction drawings.
3. Granular backfill shall be compacted granular material according to American Fork City Standard Specifications.
4. All public storm sewers shall be Reinforced Concrete Pipe conforming to ASTM Designation C76, Wall B, Class IV for pipe diameters 12 inches to 15 inches, Class III for 18 inches to 24 inch pipes, and 27 inches and larger pipe shall be Class II, unless otherwise shown on the approved construction drawings.
5. Headwalls and end walls shall be required at all storm sewer inlets or outlets to and from storm water management facilities. Natural stone and/or brick approved by the City Engineer shall be provided on all visible headwalls and/or end walls surfaces.
6. Storm inlets or catch basins shall be channelized and have bicycle safe grates. Manhole lids shall include the word STORM.
7. Storm sewer outlets greater than 18 inches in diameter accessible from storm water management facilities or watercourses shall be provided with safety grates, as approved by the City Engineer.

STRIPING AND SIGNING

1. All striping must be done following Utah Department of Transportation guidelines and MUTCD Manual recommendations, current edition.
2. All signing must be done following MUTCD Manual recommendations, current edition.
3. Only sand–blasting is allowed for removal of existing striping.
4. Contractor is responsible for removal of conflicting existing striping.
5. Materials used for striping must comply with the Utah Department of Transportation standard specifications.

MAIL DELIVERY

1. The Contractor shall be responsible to ensure that US Mail delivery within the project limits is not disrupted by construction operations.
2. This responsibility is limited to relocation of mailboxes to a temporary location that will allow the completion of the work and shall also include the restoration of mailboxes to their original location or approved new location.
3. Any relocation of mailbox services must be first coordinated with the US Postal Service and the homeowner.
4. Before relocating any mailboxes, the Contractor shall contact the U.S. Postal Service and relocate mailboxes according to the requirements of the Postal Service.

USE OF FIRE HYDRANTS

1. The Contractor shall make proper arrangements with the American Fork City, Water Department for the use of fire hydrants when used for work performed under this project's approval.

NO.	REVISIONS	BY	DATE
1.	CITY COMMENTS		RGW 10/18/21

DESIGNER: SDT PROJECT ENGINEER: SDT

CIVIL ENGINEERING + SURVEYING
CIR
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 – 801–949–6296

DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH


GENERAL NOTES

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

CALL BEFORE YOU DIG!
BLUE STAKES 1 800 662 4111

SHEET NO.	
GN	
PROJECT ID	DATE:
A1140–01	07/26/21
FILE NAME: PRJ–AFH	SCALE:

C:\



Benchmark Info

The Benchmark for the project is the South Quarter Corner of Section 26, T.5.S. R.1.E., SLB&M
Elevation= 4503.89'
Datum is NAVD 88 derived from UTAH TURNGPS System

SHEET LEGEND

ADA ROUTE

Scale in Feet
0 40 80 120
SEE COVER SHEET FOR PROJECT LEGEND

LOT 1 AREAS:

	SQ. FT. / ACRES
LOT 1	289,814 SQ. FT. / 6.65 ACRES
BUILDING FOOTPRINT	115,733 SQ. FT. / 2.66 ACRES
ASPHALT	99,284 SQ. FT. / 2.28 ACRES
LANDSCAPING	31,885 SQ. FT. / 0.73 ACRES
CONCRETE	42,912 SQ. FT. / 0.99 ACRES

NOTE:
1. ALL AREA CALCULATIONS ARE APPROXIMATE AND CAN CHANGE DUE TO CONSTRUCTION TOLERANCES.

LOT PARKING REQUIREMENTS:

	SQ. FT.	CITY REQM'T
OFFICE	20,000 SQ. FT.	80 (4/1000)
WAREHOUSE	94,913 SQ. FT.	95 (1/1000)
TOTAL REQUIRED:		175
TOTAL PROVIDED:		197
ACCESSIBLE SPACES		6 (6 REQ'D 151 TO 200)
BICYCLE SPACES		8

NOTES:
1. ALL AREA CALCULATIONS ARE APPROXIMATE AND CAN CHANGE DUE TO CONSTRUCTION TOLERANCES.

LOT 2 AREAS:

	SQ. FT. / ACRES
LOT 2	322,705 SQ. FT. / 7.41 ACRES
BUILDING FOOTPRINT	136,397 SQ. FT. / 3.13 ACRES
ASPHALT	101,304 SQ. FT. / 2.33 ACRES
LANDSCAPING	35,803 SQ. FT. / 0.82 ACRES
CONCRETE	49,201 SQ. FT. / 1.13 ACRES

NOTE:
1. ALL AREA CALCULATIONS ARE APPROXIMATE AND CAN CHANGE DUE TO CONSTRUCTION TOLERANCES.

LOT 2 PARKING REQUIREMENTS:

	SQ. FT.	CITY REQM'T
OFFICE	20,000 SQ. FT.	80 (4/1000)
WAREHOUSE	94,913 SQ. FT.	95 (1/1000)
TOTAL REQUIRED:		175
TOTAL PROVIDED:		217
ACCESSIBLE SPACES		7 (7 REQ'D 201 TO 300)
BICYCLE SPACES		8

NOTES:
1. ALL AREA CALCULATIONS ARE APPROXIMATE AND CAN CHANGE DUE TO CONSTRUCTION TOLERANCES.

SITE PLAN NOTES:

1. PROPOSED 24" CURB & GUTTER. SEE DETAIL 1/C5.0.
2. PROPOSED 24" REV PAN CURB & GUTTER. SEE DETAIL 3/C5.0.
3. CONTRACTOR TO PROVIDE A SMOOTH TRANSITION BETWEEN PROPOSED CURB & GUTTER AND REV PAN CURB & GUTTER.
4. PROPOSED 4' ROLL GUTTER. SEE DETAIL 2/C5.0.
5. ALL HANDICAP STALLS SHALL HAVE SLOPES OF LESS THAN 2% IN ALL DIRECTIONS. SEE DETAIL 11/C5.0.
6. ADA RAMPS ARE TO BE INSTALLED PER CITY AND ADA STANDARDS AND SPECIFICATIONS. SEE DETAILS 4/C5.0 & 14/C5.0.
7. PROPOSED TRASH ENCLOSURE PER AMERICAN FORK CITY STANDARD DETAIL 17.5.121.B SEE SHEET C5.2 FOR DETAIL.
8. PROPOSED "U" STYLE BICYCLE RACKS. SEE DETAIL 5/C5.0.
9. INSTALL RADIUS DRIVE APPROACH PER APWA STANDARD PLAN 255. SEE DETAIL SHEET C5.2. SIDEWALK ACROSS DRIVE APPROACHES TO BE 6" (TYP.)
10. EXISTING OVERHEAD POWER TO BE RELOCATED. CONTRACTOR TO COORDINATE WITH ROCKY MOUNTAIN POWER.
11. PROPOSED STAIR SECTION. SEE ARCHITECTURAL DRAWINGS FOR DETAILS.
12. PROPOSED ADA SIGN. SEE DETAIL 12/C5.0.
13. DOCK WALL, SEE STRUCTURAL PLANS FOR DETAILS
14. INSTALL DETECTABLE WARNING SURFACE PER APWA STANDARD PLAN NO. 238.
15. PROPOSED SIDEWALK PER APWA STANDARD PLAN NO. 231. SEE DETAIL ON SHEET C5.0.
16. INSTALL STOP SIGN PER MUTCD STANDARD R1-1.
17. INSTALL CONCRETE THROUGH GUTTER. SEE DETAIL 13/C5.0.
18. INSTALL PAINTED PEDESTRIAN CROSSWALK HATCHING.
19. EXISTING FENCE, TO REMAIN.
20. INSTALL PAINTED STOP LINE ACCORDING TO MUTCD STANDARDS.
21. EXISTING WELL HEAD.
22. EXISTING FENCE, TO BE REMOVED.

STOP

CALL BEFORE YOU DIG! IT'S THE LAW! BLUE STAKES 1 800 662 4111

NO.	REVISIONS	BY	DATE
1	CITY COMMENTS		RGW 10/18/21

DESIGNER: RGW PROJECT ENGINEER: SDT

CIR CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 – 801-949-6296

DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH

SITE PLAN

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

SHEET NO.
C1.0

PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE: 1"=40'

PROPOSED BUILDING 1
AREA = 115,733 SQ. FT.
F.F.E.=4518.30

PROPOSED BUILDING 2
AREA = 136,397 SQ. FT.
F.F.E.=4518.30


Benchmark Info

The Benchmark for the project is the South Quarter Corner of Section 26, T.5.S. R.1.E., SLB&M
Elevation= 4503.89'
Datum is NAVD 88 derived from UTAH TURNGPS System

SHEET LEGEND

- PROPOSED LIGHT ASPHALT 128,431 SF
- PROPOSED HEAVY ASPHALT 72,157 SF
- PROPOSED CONCRETE

0 40 80 120
Scale in Feet
SEE COVER SHEET FOR PROJECT LEGEND




PAVEMENT SECTIONS ARE PER THE MAY 14, 2021 GEOTECHNICAL STUDY BY GSH (JOB NO 2354-003-21). CONTRACTOR TO INSTALL ALL PAVEMENT PER THE GEOTECH REPORT.

OVER SUITABLE NATURAL SOILS, PROPERLY PREPARED EXISTING FILLS, AND/OR STRUCTURAL SITE GRADING FILL EXTENDING TO SUITABLE NATURAL SOILS.

LIGHT ASPHALT PAVEMENT

N.T.S.




PAVEMENT SECTIONS ARE PER THE MAY 14, 2021 GEOTECHNICAL STUDY BY GSH (JOB NO 2354-003-21). CONTRACTOR TO INSTALL ALL PAVEMENT PER THE GEOTECH REPORT.

OVER PROPERLY PREPARED NON-ENGINEERED FILLS, SUITABLE NATURAL SOILS AND/OR STRUCTURAL SITE GRADING FILL EXTENDING TO SUITABLE NATURAL SOILS.

HEAVY ASPHALT PAVEMENT

N.T.S.



PAVEMENT SECTIONS ARE PER THE MAY 14, 2021 GEOTECHNICAL STUDY BY GSH (JOB NO 2354-003-21). CONTRACTOR TO INSTALL ALL PAVEMENT PER THE GEOTECH REPORT.

OVER SUITABLE NATURAL SOILS, AND/OR STRUCTURAL SITE GRADING FILL EXTENDING TO SUITABLE NATURAL SOILS. (RIGID PAVEMENTS MUST NOT BE ESTABLISHED OVER NON-ENGINEERED FILLS.

HEAVY CONCRETE PAVEMENT

N.T.S.

NO	REVISIONS	BY	DATE
1	CITY COMMENTS	RGW	10/18/21

DESIGNER: RGW PROJECT ENGINEER: SDT

CIR CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 - 801-949-6296

DEER PARK

25 EAST 1100 SOUTH, AMERICAN FORK, UTAH

GRADING PLAN

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

CALL BEFORE YOU DIG! IT'S THE LAW
BLUE STAKES 1 800 662 4111

SHEET NO.
C2.0

PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE: 1"=40'

Benchmark Info

The Benchmark for the project is the South Quarter Corner of Section 26, T.5.S. R.1.E., SLB&M
Elevation= 4503.89'
Datum is NAVD 88 derived from UTAH TURNGPS System


0 40 80 120
Scale in Feet
SEE COVER SHEET FOR PROJECT LEGEND

SHEET LEGEND

DETENTION AREA
H.W.E.=4515.60

DRAINAGE PLAN NOTES:

1. INSTALL ZURN Z886 TRENCH DRAIN WITH DGE H-20 LOAD RATED GRATES. TOG=4514.30. SEE DETAIL 8/C5.0
2. CONNECT ROOF DRAINS DIRECTLY TO STORM DRAIN BOX.
3. END ROOF DRAIN 5' FROM BUILDING. SEE MECHANICAL PLAN FOR CONTINUATION TO BUILDING.
4. INSTALL 3' DEEP BY 2' WIDE GRAVEL TRENCH TO INTERCEPT AND PREVENT STORM WATER FROM FLOWING OFF SITE. GRAVEL TRENCH TO BE WRAPPED WITCH MIRAFI DRAINAGE FABRIC TO WITHIN 6" OF FINISH GRADE. GRAVEL TO HAVE A MINIMUM POROSITY OF 0.40.



1 OUTLET STRUCTURE
N.T.S.

NO	REVISIONS	BY	DATE
1	CITY COMMENTS	RGW	10/18/21

DESIGNER: RGW PROJECT ENGINEER: SDT

CIR CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 - 801-949-6296

DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH


DRAINAGE PLAN

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH


CALL BEFORE YOU DIG! BLUE STAKES 1 800 662 4111

SHEET NO.
C2.1

PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE: 1"=40'



MATCHLINE – SEE SHEET 3.1



KEY MAP
NOT TO SCALE

0 40 80 120
Scale in Feet
SEE COVER SHEET FOR PROJECT LEGEND

1. CONNECT TO PROPOSED SANITARY SEWER MANHOLE AND INSTALL 6" PVC SDR-35 LATERAL PER AMERICAN FORK STANDARDS. I.E.=4508.63.
2. INSTALL 105' 8" PVC SEWER PIPE, S=0.4% END PIPE 5' FROM BUILDING AND SEE MECHANICAL PLANS FOR CONTINUATION INTO BUILDING. I.E.=4509.10.
3. CONNECT TO PROPOSED SANITARY SEWER MANHOLE AND INSTALL 6" PVC SDR-35 LATERAL PER AMERICAN FORK STANDARDS. I.E.=4509.31.
4. INSTALL 111' 8" PVC SEWER PIPE, S=0.4% END PIPE 5' FROM BUILDING AND SEE MECHANICAL PLANS FOR CONTINUATION INTO BUILDING. I.E.=4509.80.
5. CONNECT TO PROPOSED 12" WATER MAIN AND INSTALL 8" PVC C-900 FIRE LINE AND 8" GATE VALVE W/ THRUST BLOCK. ALL WORK TO BE PER AMERICAN FORK STANDARDS.
6. INSTALL 8" PVC C-900 FIRE LINE.
7. INSTALL 8" TEE AND TWO 8" GATE VALVES W/ THRUST BLOCKS.
8. INSTALL 8"X6" & 6" GATE VALVE W/ THRUST BLOCK.
9. INSTALL FIRE HYDRANT PER AMERICAN FORK STD. 15.6. SEE DETAIL ON SHEET C5.1.
10. INSTALL 8" 45° BEND W/ THRUST BLOCK.
11. INSTALL 8" PVC C-900 FIRE LINE. END PIPE 5' FROM BUILDING AND SEE FIRE SPRINKLER PLANS FOR CONTINUATION INTO FIRE RISER ROOM.
12. INSTALL WALL MOUNTED FIRE DEPARTMENT CONNECTION (FDC).
13. INSTALL KNOX BOX 1650 OR 3200 SERIES KEY BOX FOR FIRE DEPARTMENT ACCESS.
14. PROPOSED CONCRETE PAD FOR TRANSFORMER.
15. PROPOSED CONCRETE PAD FOR ELECTRICAL SWITCH GEAR.
16. CONNECT TO PROPOSED 12" WATER MAIN AND INSTALL 2" POLY PIPE WATER LATERAL PER AMERICAN FORK STANDARD PLAN NO. 15.3 AND 15.5. SEE DETAIL SHEET C5.1 & C5.2.
17. INSTALL 2" WATER MERTER PER AMERICAN FORK CITY STANDARD PLAN NO 15.5. SEE DETAIL ON SHEET C5.1.
18. INSTALL 2" CULINARY WATER PIPE. END 5' FROM BUILDING AND SEE MECHANICAL PLANS FOR CONTINUATION TO BUILDING.
19. CONNECT TO PROPOSED 12" PRESSURIZED IRRIGATION MAIN AND INSTALL 2" POLY PIPE LATERAL PER AMERICAN FORK STD. PLAN NO. 15.5B AND NO-RISE SECONDARY METER COPPERSETTER W/27" FRAME & COVER (MANHOLE TYPE) PER 15.5E. SEE DETAIL SHEET C5.1 AND LANDSCAPE PLANS FOR CONTINUATION.
20. EXISTING OVERHEAD POWER.
21. EXISTING UNDERGROUND COMMUNICATIONS LINE.
22. EXISTING WATER MAIN.
23. INSTALL 8" 22.5° BEND W/ THRUST BLOCKS.
24. INSTALL 8" TEE & 8" GATE VALVE (CLOSED) W/ THRUST BLOCKS.
25. INSTALL 8" PVC C-900 FIRE LINE STUB. MARK AND CAP END FOR FUTURE CONNECTION.
26. INSTALL 8" CROSS W/ THRUST BLOCKS.
27. I.E. (8" W)=4211.33, TOP(8" SS)=4209.57, SEPARATION=1.76'
28. I.E. (18"SD)=4212.00, TOP (8" W)=4211.00, SEPARATION=1.00'
29. I.E. (10"SD)=4214.13, TOP (8" SS)=4210.15, SEPARATION=3.08'
30. I.E. (8" W)=4211.78, TOP(8" SS)=4210.28, SEPARATION=1.5'
31. I.E.(10" SD)=4213.37, TOP (8" W)=4212.37, SEPARATION=1.0'
32. I.E.(18" SD)=4212.04, TOP(8" SS)=4209.50, SEPARATION=2.54'
33. INSTALL FIRE HYDRANT PER AMERICAN FORK STD. 15.6. SEE DETAIL ON SHEET C5.0. INSTALL THREE PIPE BOLLARDS AROUND FIRE HYDRANT PER DETAIL 10/C5.0.
34. INSTALL 8" & 8" GATE VALVE W/ THRUST BLOCK.
35. I.E. (15" SD)=4212.77, TOP(8" W)=4211.30, SEPARATION=1.30'
36. I.E. (10" SD)=4211.23, TOP(8" W)=4210.00, SEPARATION=1.23'
37. I.E. (10" SD)=4211.22, TOP(8" W)=4210.00, SEPARATION=1.22'
38. I.E. (18" SD)=4211.03, TOP(8" W)=4210.00, SEPARATION=1.03'
39. I.E. (10" SD)=4211.47, TOP(8" W)=4210.00, SEPARATION=1.47'
40. I.E. (10" SD)=4211.47, TOP(8" W)=4210.00, SEPARATION=1.47'
41. I.E. (10" SD)=4211.59, TOP(8" W)=4210.00, SEPARATION=1.59'
42. I.E. (10" SD)=4211.76, TOP(8" W)=4210.00, SEPARATION=1.76'
43. I.E. (10" SD)=4211.52, TOP(8" W)=4210.00, SEPARATION=1.52'
44. I.E. (15" SD)=4212.98, TOP(8" W)=4211.96, SEPARATION=1.02'
45. I.E. (8" W)=4211.29, TOP(12" SS)=4209.03, SEPARATION=2.26'

Benchmark Info

The Benchmark for the project is the South Quarter Corner of Section 26, T.5.S. R.1.E., SLB&M
Elevation= 4503.89'
Datum is NAVD 88 derived from UTAH TURNGPS System

CALL BEFORE YOU DIG! BLUE STAKES 1 800 662 4111

NO.	REVISIONS	BY	DATE
1	CITY COMMENTS		
		RGW	10/18/21

DESIGNER: RGW PROJECT ENGINEER: SDT


CIR CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 – 801-949-6296

DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH

UTILTIY PLAN

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

SHEET NO.	
C3.0	
PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE: 1"=40'




Benchmark Info

The Benchmark for the project is the South Quarter Corner of Section 26, T.5.S. R.1.E., SLB&M
Elevation= 4503.89'
Datum is NAVD 88 derived from UTAH TURNGPS System

0 40 80 120

Scale in Feet
SEE COVER SHEET FOR PROJECT LEGEND



KEY MAP
NOT TO SCALE

1. INSTALL 8" PVC C-900 FIRE LINE.
2. INSTALL 8" 90° BEND W/ THRUST BLOCK.
3. CONNECT PROPOSED 8" WATER MAIN (HOP TAP) TO EXISTING 12" WATER MAIN AND INSTALL 8" GATE VALVE W/ THRUST BLOCKS. ALL WORK TO BE DONE PER AMERICAN FORK STANDARDS. .
4. SAW CUT EXISTING ASPHALT TO INSTALL LATERAL WORK TO BE DONE PER APWA PLAN NO 255 (ASPHALT CONCRETE "T" PATCH).
5. EXISTING OVERHEAD POWER.

NO.	REVISIONS	BY	DATE
1	CITY COMMENTS		
		RGW	10/18/21

DESIGNER: RGW PROJECT ENGINEER: SDT

CIR CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 - 801-949-6296

DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH


UTILTIY PLAN

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

CALL BEFORE YOU DIG! IT'S THE LAW BLUE STAKES 1 800 662 4111

SHEET NO.
C3.1

PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE: 1"=40'




KEY MAP
NOT TO SCALE


Benchmark Info


The Benchmark for the project is the South Quarter Corner of Section 26, T.5.S. R.1.E., SLB&M
Elevation= 4503.89'
Datum is NAVD 88 derived from UTAH TURNGPS System

CALL BEFORE YOU DIG! BLUE STAKES 1 800 662 4111



Scale in Feet
SEE COVER SHEET FOR PROJECT LEGEND






1100 SOUTH STREET CROSS SECTION (LOOKING EAST)



*PAVEMENT SECTION PER SECTION 13 OF THE AMERICAN FORK CITY STANDARD.

1100 SOUTH STREET
TYPICAL PAVEMENT SECTION
N.T.S.



DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH

1100 SOUTH – ROAD PLAN & PROFILE
STA 1+00 – 9+75

NO.	REVISIONS	BY	DATE
1.	CITY COMMENTS		
		RGW	10/18/21

DESIGNER: RGW
PROJECT ENGINEER: SDT

CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 – 801-949-6296

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH


SHEET NO.
C4.0

PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE: 1"=30'


SITE PLAN NOTES:

1. EXISTING LUMEN COMMUNICATION LINE. CONTRACTOR TO POTHOLE TO CHECK DEPTH OF COMMUNICATION LINE TO CONFIRM NO CONFLICTS WITH LATERALS PRIOR TO CONSTRUCTION.
2. INSTALL STREETLIGHT PER AMERICAN FORK STANDARDS.
3. INSTALL CONCRETE JERSEY BARRIER.

CALL BEFORE YOU DIG! 811 OR 1-800-662-4111 BLUE STAKES




KEY MAP
NOT TO SCALE




SEE COVER SHEET FOR PROJECT LEGEND

Benchmark Info

The Benchmark for the project is the South Quarter Corner of Section 26, T.5.S. R.1.E., SLB&M
Elevation= 4503.89'
Datum is NAVD 88 derived from UTAH TURNGPS System



MATCHLINE 8+56 – SEE SHEET C4.2



DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH
1100 SOUTH – UTILITY PLAN & PROFILE
STA 1+00 – 8+56

NO.	REVISIONS	BY	DATE
1	CITY COMMENTS	RGW	10/18/21

DESIGNER: RGW PROJECT ENGINEER: SDT

CIR CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 – 801-949-6296

LICENSED PROFESSIONAL ENGINEER SCOTT D. THORSEN No. 354291 STATE OF UTAH


SHEET NO. C4.1

PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE: 1"=30'


UTILITY PLAN NOTES:

1. SAW CUT EXISTING ASPHALT TO INSTALL UTILITIES. REPAIR IN KIND PER APWA PLAN NO. 255 (ASPHALT CONCRETE "T" PATCH)
2. EXISTING LUMEN COMMUNICATIONS LINE. CONTRACTOR TO POTHOLE TO CONFIRM NO CONFLICTS PRIOR TO CONSTRUCTIONS.
3. I.E.(15"SD)=4212.41
   I.E.(1"IRR)=4213.96

CALL BEFORE YOU DIG! 811 OR 1-800-662-4111 BLUE STAKES



KEY MAP
NOT TO SCALE





Scale in Feet
SEE COVER SHEET FOR PROJECT LEGEND

Benchmark Info

The Benchmark for the project is the South Quarter Corner of Section 26, T.5.S. R.1.E., SLB&M
Elevation= 4503.89'
Datum is NAVD 88 derived from UTAH TURNGPS System

MATCHLINE STA 9+75 – SEE SHEET C4.1





1	CITY COMMENTS			RGW	10/18/21
NO.	REVISIONS		BY	DATE	

DESIGNER: RGW
PROJECT ENGINEER: SDT

CIR CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 – 801-949-6296

DEER PARK

25 EAST 1100 SOUTH, AMERICAN FORK, UTAH


1100 SOUTH – UTILITY PLAN & PROFILE

STA 9+75 – 17+57

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

SHEET NO.
C4.2

PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE: 1"=30'




KEY MAP
NOT TO SCALE

Benchmark Info

The Benchmark for the project is the South Quarter Corner of Section 26, T.5.S. R.1.E., SLB&M
Elevation= 4503.89'
Datum is NAVD 88 derived from UTAH TURNGPS System


CALL BEFORE YOU DIG! BLUE STAKES 1 800 662 4111




Scale in Feet
SEE COVER SHEET FOR PROJECT LEGEND

SITE PLAN NOTES:

1. INSTALL 4" SINGLE SOLID WHITE LINE.
2. INSTALL 4" DOUBLE SOLID YELLOW LINE.
3. INSTALL 4" SINGLE DOTTED WHITE LINE.





1100 SOUTH STREET CROSS SECTION (LOOKING EAST)

NO.	REVISIONS	BY	DATE
1.	CITY COMMENTS		
		RGW	10/18/21

DESIGNER: RGW PROJECT ENGINEER: SDT

CIR CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 - 801-949-6296


DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH

1100 SOUTH - STRIPING PLAN
STA 1+00 - 9+75

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH


SHEET NO.
C4.3

PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE: 1"=30'




NOTE:
CURB AND GUTTER TO BE INSTALLED PER APWA STANDARDS PLAN NO. 205

1 | 24" CURB & GUTTER
N.T.S.




NOTE:
1. PER APWA PLAN NO. 211
2. ASPHALT PAVEMENT SECTION TO BE INSTALLED AT 0.03' HIGHER THAT THE TOP EDGE OF THE CONCRETE ROLL GUTTER, BOTH SIDES.

2 | 4'-0" ROLL GUTTER
N.T.S.




NOTE:
CURB AND GUTTER TO BE INSTALLED PER APWA STANDARDS PLAN NO. 205

3 | 24" REVERSE PAN CURB & GUTTER
N.T.S.




SEE APWA PLAN NO 235 FOR STANDARDS AND SPECIFICATIONS


4 | ADA RAMP
N.T.S.




5 | INVERTED "U" BIKE RACK
N.T.S.



6 | STANDARD STORM DRAIN CURB INLET BOX
N.T.S.




7 | STANDARD STORM DRAIN INLET BOX
N.T.S.




NOTE: + Actual Channel length is 81 1/4 [2064] to allow for overlap.


8 | ZURN Z886 TRENCH DRAIN SYSTEM
N.T.S.




9 | ORIFICE PLATE
N.T.S.




10 | BOLLARD PROTECTION AT HYDRANTS
N.T.S.



11 | ACCESSIBLE PARKING STALL
N.T.S.




12 | HANDICAPPED PARKING SIGN
N.T.S.



STREET TYPE	T
RESIDENTIAL (WITH PARK STRIP)	4"
RESIDENTIAL (NO PARK STRIP)	6"
OTHER	
REPLACING EXISTING SIDEWALK	MATCH EXISTING (4" MIN.)

SEE DRIVEWAY APPROACH PLANS FOR SIDEWALK THICKNESS AT DRIVEWAYS

SECTION A–A





SECTION B–B

SIDEWALK JOINT DETAIL

Sidewalk
Plan **231**
March 2009
57

13 | CONCRETE THROUGH GUTTER
N.T.S.





SEE APWA PLAN NO 235 FOR STANDARDS AND SPECIFICATIONS

14 | ADA RAMP
N.T.S.

NO.	REVISIONS	BY	DATE
1	CITY COMMENTS		
	ROW		10/18/21

DESIGNER: SDT PROJECT ENGINEER: SDT

CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 – 801-949-6296

DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH

DETAIL SHEET


LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

CALL BEFORE YOU DIG! IT'S THE LAW BLUE STAKES 1 800 662 4111

SHEET NO.
C5.0


PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE:

C1




VALVE BOX DETAIL

DRAWN: JRP REVISED: DATE: JULY 2002 SCALE: VARIES	Northern ENGINEERING LAND PLANNING CONSTRUCTION MANAGEMENT 1040 E. 800 N. OREM, UTAH 84057 (801) 802-8992	AMERICAN FORK CITY	STANDARD DETAIL FOR: VALVE BOX DETAIL	DRAWING NO. 15.4



SPACING TABLE	
SIZE	SPACING
3/4"	7 1/2"
1"	10 3/4"
1 1/2"	13"
2"	17"


DRAWN: JRP REVISED: DATE: MAY 2002 SCALE: VARIES	Northern ENGINEERING LAND PLANNING CONSTRUCTION MANAGEMENT 1040 E. 800 N. OREM, UTAH 84057 (801) 802-8992	AMERICAN FORK CITY	STANDARD DETAIL FOR: CULINARY WATER SERVICE CONNECTION	DRAWING NO. 15.5



NOTES:
1. HYDRANTS THAT ARE TO BE RELOCATED AS CALLED FOR ON THE PLAN VIEW SHALL BE REINSTALLED IN ACCORDANCE WITH THIS DETAIL.
2. ALL GATE VALVES SHALL BE LOCATED AT THE HYDRANT AS SHOWN ON THIS DETAIL.
3. WHERE EXISTING FITTINGS ARE NOT COMPATIBLE WITH NEW MAIN CONSTRUCTION, SUITABLE ADAPTORS OR NEW FITTINGS SHALL BE USED UPON APPROVAL BY THE AMERICAN FORK CITY ENGINEER.
4. ALL ANCHORS AND BLOCKING TO BEAR AGAINST UNDISTURBED SOIL.
5. IF LENGTH EXCEEDS 1 LENGTH OF PIPE, INCREASE DIAMETER TO 8 INCH MINIMUM.


FIRE HYDRANT DETAIL
-NTS-

DRAWN: JRP REVISED: DATE: MAY 2002 SCALE: VARIES	Northern ENGINEERING LAND PLANNING CONSTRUCTION MANAGEMENT 1040 E. 800 N. OREM, UTAH 84057 (801) 802-8992	AMERICAN FORK CITY	STANDARD DETAIL FOR: FIRE HYDRANT	DRAWING NO. 15.6



NOTE: ALL SEWER MANHOLES AND CLEANOUTS SHALL BE ACCESSIBLE BY MAINTENANCE PUMPER TRUCK.


DRAWN: JRP REVISED: DATE: MAY 2002 SCALE: VARIES	Northern ENGINEERING LAND PLANNING CONSTRUCTION MANAGEMENT 1040 E. 800 N. OREM, UTAH 84057 (801) 802-8992	AMERICAN FORK CITY	STANDARD DETAIL FOR: SEWER CLEANOUT SEWER PIPE INSTALLATION	DRAWING NO. 15.15



NOTE:
1) WHERE TRENCH PASSES THROUGH EXISTING PAVEMENT, THE PAVEMENT SHALL BE CUT ALONG A NEAT VERTICAL LINE A MINIMUM OF 12" FROM THE EDGE OF THE OPENING.

TYPICAL TRENCH DETAIL
-NTS-

DRAWN: JRP REVISED: DATE: MAY 2002 SCALE: VARIES	Northern ENGINEERING LAND PLANNING CONSTRUCTION MANAGEMENT 1040 E. 800 N. OREM, UTAH 84057 (801) 802-8992	AMERICAN FORK CITY	STANDARD DETAIL FOR: TYPICAL TRENCH DETAIL	DRAWING NO. 15.22




SEWER LATERAL DETAIL
-NTS-

SEWER SERVICE LATERAL SADDLE
-NTS-

NOTE:
1) LATERAL SHALL NOT ENTER MANHOLE, UNLESS OTHERWISE APPROVED BY CITY ENGINEER.
2) FOR CONCRETE PIPE ADD CONCRETE COLLAR AROUND INSERT-A-TEE.
3) ALSO SEE DRAWING NO. 15.19

DRAWN: JRP REVISED: DATE: JULY 2002 SCALE: VARIES	Northern ENGINEERING LAND PLANNING CONSTRUCTION MANAGEMENT 1040 E. 800 N. OREM, UTAH 84057 (801) 802-8992	AMERICAN FORK CITY	STANDARD DETAIL FOR: SANITARY SEWER LATERAL AND CLEAN OUT	DRAWING NO. 15.23




NOTES:
1. ALL THRUST BLOCK BEARING FACES SHALL BE POURED AGAINST UNDISTURBED SOIL OR APPROVED COMPACTED BACKFILL.
2. CONCRETE SHALL BE CLASS C.
3. CALCULATED ON 150 PSI. STATIC PRESSURE & ALLOWABLE BEARING PRESSURE OF 1500 LB. PER SQ. FT.
4. ALL THRUST BLOCK SIDES SHALL BE FORMED. (CITY INSPECTOR MAY REQUIRE WOOD FORMS.)

THRUST BLOCK BEARING AREA IN SQ. FEET								
PIPE SIZE (IN.)	CONDITION							
	I	II	III	IV	V	VI	VII	VIII
4	1.5	1.8	1	0.5	1.3	1.3	1.3	1.3
8	5	7.1	3.8	2	5	5	5	5
10	7.8	11.1	6	3	7.8	7.8	7.8	7.8
14	15.4	21.7	11.8	6	15.4	15.4	15.4	15.4

WATER LINE THRUST BLOCK DETAILS

DRAWN: JRP REVISED: DATE: MAY 2002 SCALE: VARIES	Northern ENGINEERING LAND PLANNING CONSTRUCTION MANAGEMENT 1040 E. 800 N. OREM, UTAH 84057 (801) 802-8992	AMERICAN FORK CITY	STANDARD DETAIL FOR: WATERLINE THRUST BLOCKING	DRAWING NO. 15.21



NOTES:
1. HYDRANTS THAT ARE TO BE RELOCATED AS CALLED FOR ON THE PLAN VIEW SHALL BE REINSTALLED IN ACCORDANCE WITH THIS DETAIL.
2. ALL GATE VALVES SHALL BE LOCATED AT THE HYDRANT AS SHOWN ON THIS DETAIL.
3. WHERE EXISTING FITTINGS ARE NOT COMPATIBLE WITH NEW MAIN CONSTRUCTION, SUITABLE ADAPTORS OR NEW FITTINGS SHALL BE USED UPON APPROVAL BY THE AMERICAN FORK CITY ENGINEER.
4. ALL ANCHORS AND BLOCKING TO BEAR AGAINST UNDISTURBED SOIL.
5. IF LENGTH EXCEEDS 1 LENGTH OF PIPE, INCREASE DIAMETER TO 8 INCH MINIMUM.

FIRE HYDRANT DETAIL
-NTS-

DRAWN: JRP REVISED: DATE: MAY 2002 SCALE: VARIES	Northern ENGINEERING LAND PLANNING CONSTRUCTION MANAGEMENT 1040 E. 800 N. OREM, UTAH 84057 (801) 802-8992	AMERICAN FORK CITY	STANDARD DETAIL FOR: FIRE HYDRANT	DRAWING NO. 15.6

NO.	BY	DATE
1	CITY COMMENTS	RGW 10/18/21

REVISIONS

DESIGNER: SDT PROJECT ENGINEER: SDT

CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 - 801-949-6296

DEER PARK

25 EAST 1100 SOUTH, AMERICAN FORK, UTAH

AMERICAN FORK CITY DETAIL SHEET


LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

CALL BEFORE YOU DIG! 811 OR 1-800-662-4111 BLUE STAKES 1-800-662-4111

SHEET NO.
C5.1

PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE:

CITY STANDARD - DUMPSTER/ TRASH ENCLOSURE STANDARD 17.5.121.B




NOTES:
1. LANDSCAPE SHALL INCLUDE COMBINATION OF TREES AND SHRUBBERY TO CREATE A LANDSCAPE SCREEN FOR THE ENCLOSURE
2. ENCLOSURE SHALL BE 6' TALL MIN.
3. ENCLOSURE EXTERIOR FINISH SHALL MATCH THE EXTERIOR OF THE BUILDING FOR WHICH IT SUPPORTS.
3. LANDSCAPE DIMENSIONS SHOWN ARE MINIMUMS.
4. ENCLOSURE DIMENSIONS MAY VARY DEPENDING UPON INTENDED USE, AS SUCH, CITY ENGINEER/CITY PLANNER SHALL HAVE THE ABILITY TO REVIEW AND RECOMMEND APPROPRIATE SIZE OF A GIVEN ENCLOSURE FOR A SPECIFIC USE.
5. A VARIANCE FROM THE REQUIREMENT OF AN ENCLOSURE CAN BE GRANTED BY THE LAND USE AUTHORITY FOR A GIVEN ZONE IF IT CAN BE DEMONSTRATED THAT THE USE FOR THE SITE DOES NOT REQUIRE MORE THAN A TRADITIONAL CURB SIDE PICK UP CONTAINER. CURB SIDE CONTAINER MUST BE AVAILABLE IN THAT AREA TO QUALIFY FOR THIS EXCEPTION.


T:\LD-PROJECT-AT-CITY-STANDARDS\DUMPSTER.DWG
DATE: NOV. 16, 2010

AMERICAN FORK — 1853 —

NOTES:
1. COORDINATE W/ AMERICAN FORK CITY ON LOCATION OF IRR. BOX.
2. ALL COMPRESSION FITTINGS SHALL INCLUDE A MUELLER 2"CTS PE LINER PART NO. 506141



2" DRAIN TO DAYLIGHT



NOTES:
1. PROPOSED DRAIN LINE CAN TIE INTO CATCH BASIN BOX (SHOWN) OR SUMP MANHOLE (NOT SHOWN), OR BOX CULVERT (NOT SHOWN)
2. ALL COMPRESSION FITTINGS SHALL INCLUDE A MUELLER 2"CTS PE LINER PART NO. 506141

2" DRAIN TO CATCH BASIN/SUMP/BOX CULVERT


DRAWN:		STANDARD DETAIL FOR	DRAWING NO.
REVISED:	11/2010	SECONDARY WATER DETAILS	15.31
DATE:			
SCALE:			

HORROCKS ENGINEERS — ONE WEST MAIN P.O. BOX 377 AMERICAN FORK (801) 763-5100

AMERICAN FORK CITY

SINGLE 1 1/2" SERVICE

WHEN THE PRIVATE SPRINKLING SYSTEM IS CONNECTED TO THE SERVICE, THE LOT OWNER'S IRRIGATION CONTROL BOX IS INSTALLED, WITH A SHUT OFF VALVE (PVC TWIST VALVE OR BALL VALVE) AND FILTER (OPTIONAL).



IRRIGATION CONNECTION NOTES:

1 1/2" or 2" SINGLE SERVICE CONNECTION TO MAIN.

GENERAL:

ALL FITTINGS SHALL BE COMPATIBLE WITH SERVICE SIZE.


SERVICE LINE INSTALLATION AT AN EXISTING CURB GUTTER & SIDEWALK WITH A PLANTER STRIP SHALL HAVE THE UTILITY BOX LOCATED 1'-0" BEHIND THE SIDEWALK.

SERVICE LINE INSTALLATION AT EXISTING OR NEW MONOLITHIC CURB, GUTTER & SIDEWALK SHALL HAVE THE UTILITY BOX LOCATED 1'-0" BEHIND THE SIDEWALK.

SERVICE LINE INSTALLATION AT A LOCATION WITH NO CURB, GUTTER & SIDEWALK SHALL HAVE THE UTILITY BOX LOCATED 1'-0" BEHIND THE FUTURE SIDEWALK.

SINGLE 2" SERVICE


WHEN THE PRIVATE SPRINKLING SYSTEM IS CONNECTED TO THE SERVICE, THE LOT OWNER'S IRRIGATION CONTROL BOX IS INSTALLED, WITH A SHUT OFF VALVE (PVC TWIST VALVE OR BALL VALVE) AND FILTER (OPTIONAL).



DRAWN:		STANDARD DETAIL FOR	DRAWING NO.
REVISED:	11/2010	LARGE SERVICE CONNECTION FOR SECONDARY WATER	15.5B
DATE:			
SCALE:			


HORROCKS ENGINEERS — ONE WEST MAIN P.O. BOX 377 AMERICAN FORK (801) 763-5100

AMERICAN FORK CITY




STREET TYPE	LENGTH (Y)	(T)	(R)
RESIDENTIAL	6"	6"	5 FT.
OTHER	24"	8"	5 to 25 FT.

OBLIQUE



STREET TYPE	BREAK OVER ANGLE (MAXIMUM) (A)	(B)	(C)
RESIDENTIAL	16%	12%	16%
OTHER	6%	8%	10%

SECTION A-A - APPROACH REQUIRING SERVICE TRUCK ACCESS




STREET TYPE	BREAK OVER ANGLE (MAXIMUM) (D)	(E)	(F)
RESIDENTIAL	16%	12%	16%
OTHER	6%	8%	10%

SECTION A-A - TYPICAL DRIVEWAY APPROACH


APWA Utah Chapter

Open driveway approach

Plan 225 December 2009




SECTION




NOTES:
VAULT TO BE PLACED ONE FOOT FRONT OF WALK WITHIN AN EIGHT FOOT PARK STRIP OR WITHIN 10' FRONT PUE.

NO.	*	ITEM	DESCRIPTION
A		27" FRAME AND COVER	APWA PLAN 502. CAST IRON LID WITH "IRRIGATION" AND RECESSED ORION HOLE. PART NUMBER 12.25PBLKWAMHO OR APPROVED EQUIVALENT.
B		CONCRETE BOX	APWA PLAN 505. 3' MINIMUM FLOOR TO ROOF.
C		CORE/KNOCKOUT THROUGH VAULT WALL	PIPES PASSING THROUGH CONCRETE VAULT SHALL BE PROTECTED AGAINST EXTERNAL CORROSION BY SHEATHING OR WRAPPING OR ANY OTHER MEANS THAT WILL WITHSTAND ANY REACTION FROM LIME AND ACID FROM CONCRETE, CINDER OR OTHER CORROSIVE MATERIAL. SHEATHING OR WRAPPING SHALL ALLOW FOR MOVEMENT INCLUDING EXPANSION AND CONTRACTION OF PIPING (IPC 305.1). REMAINING HOLE SHALL BE SEALED.

DRAWN:	MVU	AMERICAN FORK CITY PUBLIC WORKS 275 EAST 200 NORTH (801) 763-9030	STANDARD DETAIL FOR 1-1/2" OR 2" PI METER PLACEMENT	DRAWING NO. 15.5E
REVISED:				
DATE:	AUG 2019			
SCALE:	VARIES			



SECTION




SECTION A-A

ALTERNATE

TURBO METER INSTALLATION FOR ALL SYSTEMS USED EXCLUSIVELY FOR IRRIGATION OR FIRE PROTECTION.

LEGEND			
NO.	*	ITEM	DESCRIPTION
A		27" FRAME AND COVER	APWA PLAN 502
B		CONCRETE BOX	APWA PLAN 505
C		STAINLESS STEEL METER BOLT WITH NUT	5/8" x 2 3/4" 304 SS
D		1 1/2" CUSTOM SETTER WITH LOCKING BYPASS	
E		2" CUSTOM SETTER WITH LOCKING BYPASS	
F		CORE/KNOCKOUT THROUGH VAULT WALL	PIPES PASSING THROUGH CONCRETE VAULT SHALL BE PROTECTED AGAINST EXTERNAL CORROSION BY SHEATHING OR WRAPPING OR ANY OTHER MEANS THAT WILL WITHSTAND ANY REACTION FROM LIME AND ACID FROM CONCRETE. CINDER OR OTHER CORROSIVE MATERIAL. SHEATHING OR WRAPPING SHALL ALLOW FOR MOVEMENT INCLUDING EXPANSION AND CONTRACTION OF PIPING (IPC 305.1). REMAINING HOLE SHALL BE SEALED.


DRAWN:	ABW	AMERICAN FORK CITY PUBLIC WORKS 275 EAST 200 NORTH (801) 763-9030	STANDARD DETAIL FOR 1-1/2" OR 2" METER PLACEMENT	DRAWING NO. 15.5C
REVISED:				
DATE:	FEB 2019			
SCALE:	VARIES			



DRAWN:	JRP	STANDARD DETAIL FOR	DRAWING NO.
REVISED:		TYPICAL WATERMAN TAPS	15.3
DATE:	JULY 2002		
SCALE:	VARIES		

Northern — ENGINEERING AND PLANNING CONSULTANTS, INC. 1040 E. 800 N. OREM, UTAH 84057 (801) 802-8992

AMERICAN FORK CITY



LINE MANHOLE DETAIL
–NTS–

SECTION A–A
–NTS–

DRAWN:	JRP	STANDARD DETAIL FOR	DRAWING NO.
REVISED:		SANITARY SEWER LINE MANHOLE DETAIL	15.12
DATE:	JULY 2002		
SCALE:	VARIES		

Northern — ENGINEERING AND PLANNING CONSULTANTS, INC. 1040 E. 800 N. OREM, UTAH 84057 (801) 802-8992

AMERICAN FORK CITY

CIVIL ENGINEERING + SURVEYING
CIR
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 – 801-949-6296

NO.	REVISIONS	BY	DATE
1.	CITY COMMENTS	RGW	10/18/21

DESIGNER: SDT PROJECT ENGINEER: SDT

DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH

AMERICAN FORK CITY DETAIL SHEET

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

CALL BEFORE YOU DIG! 811 OR 1-800-662-4111 BLUE STAKES 1-800-662-4111

SHEET NO. C5.2

PROJECT ID	DATE:
A1140-01	07/26/21
FILE NAME: PRJ-AFH	SCALE:

PROPOSED BUILDING 1
AREA = 115,733 SQ. FT.
F.F.E.=4518.30

PROPOSED BUILDING 2
AREA = 136,397 SQ. FT.
F.F.E.=4518.30

LEGEND

SILT FENCE

WHEEL WASH AREA

BMP AREA

0 40 80 120

Scale in Feet

BMP CALLOUTS

(1) PLACE A SILT FENCE AROUND THE PERIMETER OF THE INLET, ONCE PAVEMENT AND/OR CURB HAS BEEN INSTALLED PLACE GRAVEL BAGS AROUND THE INLET. GRAVEL BAGS TO BE USED ON PAVED OR CONCRETE SURFACES AND SILT FENCE TO BE USED ON UNIMPROVED SURFACES.
NOTE: IN HIGH TRAFFIC AREAS CONTRACTOR TO USE INSERT FILTER FABRIC. IF INLET HAS CURB OPENING, THE FILTER FABRIC IS TO BE EXTENDED UP TO COVER THE CURB OPENING AND GRAVEL BAGS PLACED IN GUTTER AT EACH SIDE OF OPENING TO KEEP FILTER FABRIC SNUG AGAINST CURB WALL.

(2) INSTALL TYPICAL SILT FENCE, SILT FENCE TO BE INSTALLED PERPENDICULAR TO STORM WATER FLOW. INSTALLATION TO BE DONE SO AS TO PREVENT SEDIMENT FROM LEAVING THE SITE.
NOTE: CONTRACTOR TO USE VEGETATIVE BUFFER AND OR CUT BACK INSTEAD OF SILT FENCE WHERE POSSIBLE.

(3) CONTRACTOR TO INSTALL A MIMIMUM OF 6" DEEP GRAVEL (3" TO 6") OF SUFFICIENT SIZE (MINIMUM OF 50' IN LENGTH AND 20' WIDE) AS TO PROVIDE A WHEEL WASH AREA TO PREVENT THE TRACKING OF MUD OFFISTE. THE LOCATION OF WHEEL WASH MAY VARY FROM LOCATION SHOWN ON PLANS SO AS TO PROVIDE THE BEST PROTECTION AGAINST TRACKING MUD OFFSITE. CONTRACTOR TO MAINTAIN AND CLEAN WHEEL WASH AREA AS NEEDED TO PREVENT THE TRACKING OF MUD OFFSITE.

(4) CONTRACTOR TO INSTALL CONCRETE WASHOUT AREA. THE LOCATION MAY VARY FROM LOCATION SHOWN ON PLANS.

DURING CONSTRUCTION

1. ALL EROSION CONTROL BEST MANAGEMENT PRACTICES SHALL BE INSPECTED AND MAINTAINED REGULARLY (MINIMUM ONCE A WEEK) AND AFTER EVERY STORM EVENT
2. CONTRACTOR TO KEEP LAND DISTURBANCE TO MINIMUM TO CONTROL RUNOFF FROM THE SITE
3. LIMIT LAND CLEARING AND RESTORE ALL GRADING AS SOON AS POSSIBLE
4. STAGED SEEDING TO RE-VEGETATE CUT AND FILL SLOPES AS THE WORK IS IN PROGRESS
5. AT ALL TIMES DURING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING AND CONTROLLING EROSION DUE TO WIND AND OTHER EROSION
6. MAINTENANCE OF STREET: STREETS TO BE KEPT CLEAN AND FREE FROM DEBRIS
7. CONTRACTOR SHALL PROVIDE DUST CONTROL MEASURES AT ALL TIMES DURING CONSTRUCTION.
8. CONTRACTOR TO HAVE WATER TRUCK AVAILABLE AS WATER SOURCE FOR WHEEL WASH AREA, OR ALTERNATE WATER SOURCE MAY BE USED IF APPROVED BY CITY.
9. IF GROUND WATER IS ENCOUNTERED DURING THE CONSTRUCTION ACTIVITIES AND REQUIRES PUMPING OFF THE PROJECT, THE CONTRACTOR IS TO FILTER THE WATER THROUGH THE USE OF SAND BAGS AND/OR GEO FABRIC. THIS IS TO BE DONE PRIOR TO IT BEING INTRODUCED INTO THE PUBLIC STORM DRAIN SYSTEM.
10. A COPY OF THE STORM WATER POLLUTION PREVENTION PLAN SHALL BE KEPT ON THE SITE DURING ALL CONSTRUCTION ACTIVITY

POST CONSTRUCTION

1. EROSION CONTROL STRUCTURES MAY BE REMOVED ONCE FINAL LANDSCAPING IS IN PLACE
2. EROSION CONTROL STRUCTURES BELOW SEEDED AREAS MUST REMAIN IN PLACE UNTIL THE ENTIRE AREA HAS BEEN ESTABLISHED
3. EROSION CONTROL IN PROPOSED PAVEMENT AREAS SHALL REMAIN IN PLACE UNTIL PAVEMENT IS COMPLETE
4. THE FOLLOWING PRECAUTIONS SHALL BE PERFORMED:
A) PERIODIC INSPECTION OF CATCH BASIN SEDIMENT TRAPS AND CLEANING WHEN THE BASIN IS MORE THAN 1/4 FULL. INSPECTION SHALL BE DONE AFTER EVERY MAJOR RAINFALL AND EVERY 6 MONTHS AS A MINIMUM. DISPOSAL OF ANY GREASE OR OIL MUST BE DONE IN ACCORDANCE WITH CURRENT ENVIRONMENTAL REGULATIONS
B) LITTER, DEBRIS AND CHEMICALS MUST BE PICKED UP AND KEPT IN A CONTAINED LOCATION TO PREVENT POLLUTION OF STORM WATER DISCHARGE
C) PARKING AREAS SHALL BE KEPT FREE FROM AUTOMOBILE FLUIDS THAT COULD WASH INTO THE STORM DRAIN SYSTEM

NO.	REVISIONS	BY	DATE
1	CITY COMMENTS		RGW 10/18/21

DESIGNER: SDT PROJECT ENGINEER: SDT

CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 - 801-943-6296

DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH


EROSION CONTROL PLAN (SWPPP)

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

CALL BEFORE YOU DIG! 811 or 1-800-662-4111 BLUE STAKES 1-800-662-4111

SHEET NO.	
C6.0	
PROJECT ID: A1140-01	DATE: 07/26/21
FILE NAME: PRJ-AFH	SCALE: 1"=40'

BMP: Inlet Protection - Silt Fence or Straw Bale — IPS



Description:
Sediment barrier erected around storm drain inlet.

Application:
Construct at storm drainage inlets located downgradient of areas to be disturbed by construction (for inlets in paved areas see other information sheets for inlet protection)

Installation/Application Criteria:
- Provide upgradient sediment controls, such as silt fence during construction of inlet.
- When construction of inlet is complete, erect straw bale barrier or silt fence surrounding perimeter of inlet. Follow instructions and guidelines on individual BMP information sheets for straw bale barrier and silt fence construction.

Limitations:
- Recommended maximum contributing drainage area of one acre.
- Limited to inlets located in open unpaved areas.
- Requires shallow slopes adjacent to inlet.

Maintenance:
- Inspect inlet protection following storm event and at a minimum of once monthly.
- Remove accumulated sediment when it reaches 4-inches in depth.
- Repair or realign barrier/fence as needed.
- Look for bypassing or undercutting and recompact soil around barrier/fence as required.

Objectives
- ☐ Housekeeping Practices
- ☐ Contain Waste
- ☐ Minimize Disturbed Areas
- ☐ Stabilize Disturbed Areas
- ☐ Protect Slopes/Channels
- ☒ Control Site Perimeter
- ☒ Control Internal Erosion

ADAPTED FROM SALT LAKE COUNTY BMP FACTSHEET


Targeted Pollutants
- ▪ Sediment
- ▫ Nutrients
- ▫ Toxic Materials
- ▫ Oil & Grease
- ▪ Floatable Materials
- ▫ Other Waste

- ■ High Impact
- ☒ Medium Impact
- ☐ Low or Unknown Impact

Implementation Requirements
- ▪ Capital Costs
- ▫ O&M Costs
- ▪ Maintenance
- ▫ Training

■ High ☒ Medium ☐ Low

BMP: Inlet Protection - Gravel — IPG



Description:
Placement of gravel filter over inlet to storm drain to filter storm water runoff.

Application:
Construct at inlets in paved or unpaved areas where upgradient area is to be disturbed by construction activities.

Installation/Application Criteria:
- Place wire mesh (with ½ inch openings) over the inlet grate extending one foot past the grate in all directions.
- Place filter fabric over the mesh. Filter fabric should be selected based on soil type.
- Place graded gravel, to a minimum depth of 12-inches, over the filter fabric and extending 18-inches past the grate in all directions.

Limitations:
- Recommended for maximum drainage area of one acre.
- Excess flows may bypass the inlet requiring down gradient controls.
- Ponding will occur at inlet.

Maintenance:
- Inspect inlet protection after every large storm event and at a minimum of once monthly.
- Remove sediment accumulated when it reaches 4-inches in depth.
- Replace filter fabric and clean or replace gravel if clogging is apparent.

Objectives
- ☐ Housekeeping Practices
- ☐ Contain Waste
- ☐ Minimize Disturbed Areas
- ☐ Stabilize Disturbed Areas
- ☐ Protect Slopes/Channels
- ☒ Control Site Perimeter
- ☒ Control Internal Erosion

ADAPTED FROM SALT LAKE COUNTY BMP FACTSHEET


Targeted Pollutants
- ▪ Sediment
- ▫ Nutrients
- ▫ Toxic Materials
- ▫ Oil & Grease
- ▪ Floatable Materials
- ▫ Other Waste

- ■ High Impact
- ☒ Medium Impact
- ☐ Low or Unknown Impact

Implementation Requirements
- ▪ Capital Costs
- ▫ O&M Costs
- ▪ Maintenance
- ▫ Training

■ High ☒ Medium ☐ Low

BMP: Inlet Protection - Excavated — IPE



Description:
An area excavated around a storm drain inlet to impound water below the inlet.

Application:
Construct at storm drainage inlets located downgradient of areas to be disturbed by construction (for inlets in paved areas see other information sheets for inlet protection)

Installation/Application Criteria:
- Provide upgradient sediment controls, such as silt fence during construction of inlet.
- When construction of inlet is complete, excavate adjacent area 1 to 2 feet lower than the grate elevation. Size of excavated area should be based on soil type and contributing acreage.

Limitations:
- Recommended maximum contributing drainage area of one acre.
- Limited to inlets located in open unpaved areas.
- Requires flat area adjacent to inlet.

Maintenance:
- Inspect inlet protection following storm event and at a minimum of once monthly.
- Remove accumulated sediment when it reaches one half of the excavated sump below the grate.
- Repair side slopes as required.

Objectives
- ☐ Housekeeping Practices
- ☐ Contain Waste
- ☐ Minimize Disturbed Areas
- ☐ Stabilize Disturbed Areas
- ☐ Protect Slopes/Channels
- ☒ Control Site Perimeter
- ☒ Control Internal Erosion

ADAPTED FROM SALT LAKE COUNTY BMP FACTSHEET


Targeted Pollutants
- ▪ Sediment
- ▫ Nutrients
- ☒ Toxic Materials
- ☐ Oil & Grease
- ▪ Floatable Materials
- ☐ Other Waste

- ■ High Impact
- ☒ Medium Impact
- ☐ Low or Unknown Impact

Implementation Requirements
- ☐ Capital Costs
- ☐ O&M Costs
- ☒ Maintenance
- ☐ Training

■ High ☒ Medium ☐ Low

BMP: Catch Basin Cleaning — CBC



Description:
Maintain catch basin and stormwater inlets on a regular basis to remove pollutants, reduce high pollutant concentrations during the first flush of storms, prevent clogging of the downstream conveyance system, and restore the catch basins' sediment trapping capacity. A catch basin is distinguished from a stormwater inlet by having at its base a sediment sump designed to catch and retain sediments below the overflow point. This information sheet focuses on the cleaning of accumulated sediments from catch basins.

Approach:
Regular maintenance of catch basins and inlets is necessary to ensure their proper functioning. Clogged catch basins are not only useless but may act as a source of sediments and pollutants. In general, the key to effective catch basins are:
- At least annual inspections.
- Prioritize maintenance to clean catch basins and inlets in areas with the highest pollutant loading.
- Clean catch basins in high pollutant load areas just before the wet season to remove sediments and debris accumulated during the summer.
- Keep accurate logs of the number of catch basins cleaned.
- Record the amount of waste collected.

Limitations:
There are no major limitations to this best management practice.

Maintenance:
Regular maintenance of public and private catch basins and inlets is necessary to ensure their proper functioning. Clogged catch basins are not only useless but may act as a source of sediments and pollutants. In general, the keys to effective catch basins are:
- Annual/monthly inspection of public and private facilities to ensure structural integrity, a clean sump, and a stenciling of catch basins and inlets.
- Keep logs of the number of catch basins cleaned.
- Record the amount of waste collected.

Program Elements
- ☐ New Development
- ☐ Residential
- ☐ Commercial Activities
- ☐ Industrial Activities
- ☒ Municipal Facilities
- ☒ Illegal Discharges

ADAPTED FROM SALT LAKE COUNTY BMP FACTSHEET


Targeted Pollutants
- ■ Sediment
- ☒ Nutrients
- ■ Heavy Metals
- ☐ Toxic Materials
- ☒ Oxygen Demanding Substances
- ☒ Oil & Grease
- ■ Floatable Materials
- ☐ Bacteria & Viruses

- ■ High Impact
- ☒ Medium Impact
- ☐ Low or Unknown Impact

Implementation Requirements
- ☒ Capital Costs
- ■ O&M Costs
- ☐ Regulatory
- ☒ Training
- ■ Staffing
- ☒ Administrative

■ High ☒ Medium ☐ Low

BMP: Inlet Protection - Silt Fence or Straw Bale — IPS



Description:
Sediment barrier erected around storm drain inlet.

Application:
Construct at storm drainage inlets located downgradient of areas to be disturbed by construction (for inlets in paved areas see other information sheets for inlet protection)

Installation/Application Criteria:
- Provide upgradient sediment controls, such as silt fence during construction of inlet.
- When construction of inlet is complete, erect straw bale barrier or silt fence surrounding perimeter of inlet. Follow instructions and guidelines on individual BMP information sheets for straw bale barrier and silt fence construction.

Limitations:
- Recommended maximum contributing drainage area of one acre.
- Limited to inlets located in open unpaved areas.
- Requires shallow slopes adjacent to inlet.

Maintenance:
- Inspect inlet protection following storm event and at a minimum of once monthly.
- Remove accumulated sediment when it reaches 4-inches in depth.
- Repair or realign barrier/fence as needed.
- Look for bypassing or undercutting and recompact soil around barrier/fence as required.

Objectives
- ☐ Housekeeping Practices
- ☐ Contain Waste
- ☐ Minimize Disturbed Areas
- ☐ Stabilize Disturbed Areas
- ☐ Protect Slopes/Channels
- ☒ Control Site Perimeter
- ☒ Control Internal Erosion

ADAPTED FROM SALT LAKE COUNTY BMP FACTSHEET


Targeted Pollutants
- ▪ Sediment
- ▫ Nutrients
- ▫ Toxic Materials
- ▫ Oil & Grease
- ▪ Floatable Materials
- ▫ Other Waste

- ■ High Impact
- ☒ Medium Impact
- ☐ Low or Unknown Impact

Implementation Requirements
- ▪ Capital Costs
- ▫ O&M Costs
- ▪ Maintenance
- ▫ Training

■ High ☒ Medium ☐ Low

BMP: Silt Fence — SF



Description:
A temporary sediment barrier consisting of entrenched filter fabric stretched across and secured to supporting posts.

Application:
- Perimeter control: place barrier at downgradient limits of disturbance
- Sediment barrier: place barrier at toe of slope or soil stockpile
- Protection of existing waterways: place barrier near top of stream bank
- Inlet protection: place fence surrounding catchbasins

Installation/Application Criteria:
- Place posts 6 feet apart on center along contour (or use preassembled unit) and drive 2 feet minimum into ground. Excavate an anchor trench immediately upgradient of posts.
- Secure wire mesh (14 gage min. With 6 inch openings) to upslope side of posts. Attach with heavy duty 1 inch long wire staples, tie wires or hog rings.
- Cut fabric to required width, unroll along length of barrier and drape over barrier. Secure fabric to mesh with twine, staples, or similar, with trailing edge extending into anchor trench.
- Backfill trench over filter fabric to anchor.

Limitations:
- Recommended maximum drainage area of 0.5 acre per 100 feet of fence
- Recommended maximum upgradient slope length of 150 feet
- Recommended maximum uphill grade of 2:1 (50%)
- Recommended maximum flow rate of 0.5 cfs
- Ponding should not be allowed behind fence

Maintenance:
- Inspect immediately after any rainfall and at least daily during prolonged rainfall.
- Look for runoff bypassing ends of barriers or undercutting barriers.
- Repair or replace damaged areas of the barrier and remove accumulated sediment.
- Reanchor fence as necessary to prevent shortcutting.
- Remove accumulated sediment when it reaches ½ the height of the fence.

Objectives
- ☐ Housekeeping Practices
- ☐ Contain Waste
- ☐ Minimize Disturbed Areas
- ☐ Stabilize Disturbed Areas
- ☒ Protect Slopes/Channels
- ☒ Control Site Perimeter
- ☒ Control Internal Erosion

ADAPTED FROM SALT LAKE COUNTY BMP FACTSHEET

Targeted Pollutants
- ▪ Sediment
- ▫ Nutrients
- ☐ Toxic Materials
- ☐ Oil & Grease
- ☐ Floatable Materials
- ☐ Other Waste

- ■ High Impact
- ☒ Medium Impact
- ☐ Low or Unknown Impact

Implementation Requirements
- ▪ Capital Costs
- ▪ O&M Costs
- ▪ Maintenance
- ▫ Training

■ High ☒ Medium ☐ Low

NO	REVISIONS	BY	DATE
1	CITY COMMENTS	RGW	10/18/21

DESIGNER: SDT PROJECT ENGINEER: SDT

CIVIL ENGINEERING + SURVEYING
3032 SOUTH 1030 WEST, SUITE 202
SLC, Utah 84119 – 801-949-6296

DEER PARK
25 EAST 1100 SOUTH, AMERICAN FORK, UTAH

EROSION CONTROL DETAIL SHEET

LICENSED PROFESSIONAL ENGINEER
SCOTT D. THORSEN
No. 354291
STATE OF UTAH

CALL BEFORE YOU DIG! 811 IT'S THE LAW BLUE STAKES 1 800 662 4111

SHEET NO.
C7.0

PROJECT ID	DATE:
A1140–01	07/26/21
FILE NAME: PRJ–AFH	SCALE:

C:\

AMERICAN FORK CITY
PLANNING COMMISSION MINUTES
NOVEMBER 3, 2021

The American Fork City Planning Commission met in a regular session on November 3, 2021, at the American Fork City Hall, 31 North Church Street, commencing at 7:00 pm.

Present: Chairman Woffinden
Jenny Peay
Harold Dudley
Chris Christiansen
Christine Anderson
Rod Brocious

Absent: Bruce Frandsen

Staff Present: Scott Sensanbaugher, Public Works Director
Ben Hunter, Engineer
George Schade, Communications
Lisa Halversen, Administrative Assistant

Others Present:

Chairman Woffinden led the "Pledge of Allegiance."

1. Hearing, review and action on an ordinance repealing chapter 17.10.400 of the American Fork City Municipal Code and adopting 17.19 related to pioneering agreements for public facilities

Mr. Hunter explained to commissioners what a pioneering agreement is. When improvements need to go along an undeveloped parcel during the course of development, the city may enter into an agreement with the first, or "pioneer," developer that an adjoining property owner will share the cost of the improvements upon developing their portion of the property with the shared improvements. He stated that this Code Text Amendment has been written to clarify the City's intent to permit pioneering/connector's agreements for all public facilities, including water and sewer lines, roads, and related infrastructure. The amendment is consistent with the existing policies and practices of the City and allows for a more explicit and consistent application of Pioneering/Connector's Agreements.

The Engineering Division recommends approval of the proposed ordinance repealing Chapter 17.10.400 related to connector's agreements for water and sewer and adopting 17.19 related to Pioneering/Connector's Agreements for public facilities and providing for the adoption and enforcement of the amendment.

Chairman Woffinden said that he considered this to be a housekeeping issue.

Mr. Brocious asked if such agreements have a ten-year expiration, Mr. Hunter affirmed. The expiration period varies from city to city. If adjacent properties do not develop during the ten years, the original developer would bear the cost.

Mr. Brocious felt that there should not necessarily be a time limit on the reimbursement agreement as the adjacent property always benefits from the improvements.

Ms. Anderson thought that a ten-year period might be too short, it is possible that someone may delay development until the time expires to avoid having to reimburse the original developer.

Mr. Hunter stated that there should be an established timeline for the agreements, they should not go in perpetuity. This establishes parameters, and is a known risk taken by the developer. In many instances the original developer would be putting the improvements in anyway.

Ms. Anderson asked about the particulars of these types of agreements, Mr. Hunter stated that they are based on the amount of frontage the property has.

Mr. Sensanbaugher asked commissioners to approve the ten-year time frame, he believes that this recognizes that the life of improvements is not forever.

Ms. Anderson asked for an estimate of the lifetime of different improvements, and she pointed out that in ten years the improvements would still have some value to the next developer.

Mr. Sensanbaugher agreed that there would be some value left, but not full value. They would have depreciated. He thinks that a water line may last for thirty years, but asphalt may only be ten, depending on conditions.

Mr. Brocious added that in his experience, infrastructure is usually planned in thirty-year increments.

Public Hearing Opened

No comments received.

Public Hearing Closed

Ms. Anderson moved to recommend approval of the ordinance repealing Chapter 17.10.400 related to connector's agreements for water and sewer and adopting 17.19

related to Pioneering/Connector's Agreements for public facilities and providing for the adoption and enforcement of the amendment.

Mr. Dudley seconded the motion. Voting was as follows:

Chairman Woffinden	**Aye**
Rod Brocious	**Aye**
Jenny Peay	**Aye**
Harold Dudley	**Aye**
Christine Anderson	**Aye**
Chris Christiansen	**Aye**

The motion passed.

2. Other Business

Chairman Woffinden told commissioners that the city is still trying to hire people for the planning department.

3. Site Plan Committee Report

Mr. Hunter indicated that there may be a discussion of a code amendment regarding parking on the next agenda, and a zone change.

4. Review and action on the minutes of the October 20, 2021 Planning Commission Regular Session

Mr. Dudley moved to recommend approval of the minutes of the October 20, 2021 Planning Commission Regular Session.

Ms. Peay seconded the motion. Voting was as follows:

Chairman Woffinden	**Aye**
Rod Brocious	**Aye**
Jenny Peay	**Aye**
Harold Dudley	**Aye**
Chris Christiansen	**Abstain**
Christine Anderson	**Aye**

The motion passed.

5. Adjournment

Ms. Anderson motioned to adjourn.

Mr. Christiansen seconded the motion. All voted in favor.

Meeting adjourned at 7:30 pm.

Lisa Halversen
Administrative Assistant