

Teddy Lewis  
teddy@blakeelectric.com  
Drew Fielding  
drew@blakeelectric.com  
Larry Blake  
larry@blakeelectric.com

**Blake Electric Co. -**

50 West 100 North  
Richfield, UT 84701  
Phone: 435-896-5468  
Fax: 435-896-6188

Electrical Contracting  
Commercial & Residential  
New Construction & Remodel

September 21, 2022

To whom it may concern,

Blake Electric is pleased to submit a bid of \$5,500 for the rewire of electrical at the Turkey shed. This bid includes

- Remove existing electrical equipment
- Install 100 amp service on power pole
- Update service mast to 2" IMC w/standoffs, new feeder cables & weather hood
- Replaced underground conduit and conductors w/ 1" PVC from pole to building. ( I don't believe that the conduit running to the building is still ok. It is EMT and shouldn't be reused. If you have questions about this please call me 435-979-1171)
- Install new 100 amp 20 space electrical panel with breakers for the lights and door circuit
- Install 5 keyless receptacles w/150 watt equivalent LED lamps
- Provide light switch by load center, or wherever you choose for light control.
- Install two 20amp GFCI receptacle outlets. One on the north side of each overhead door
- Cable being installed will be #12 MC cable

This bid is good for 45 days, if cost go up so will our bid

Thank you for the opportunity of bidding this project. We look forward to working for you.

Teddy Lewis – Owner Blake Electric Co.

Blake Electric now offers whole home audio, surround systems and backup generators

---

## Fwd: Richfield City Turkey Barn Electrical install

1 message

---

**Keith Mogan** <keith@richfieldcity.com>  
To: Michele Jolley <michele@richfieldcity.com>

Wed, Sep 21, 2022 at 12:06 PM

----- Forwarded message -----

From: **Kevin Moore (via Google Docs)** <kevscto@gmail.com>  
Date: Fri, Sep 9, 2022 at 14:57  
Subject: Richfield City Turkey Barn Electrical install  
To: <keith@richfieldcity.com>

## Kevin Moore attached a document



Kevin Moore (kevscto@gmail.com) has attached the following document:

Hi Keith

Please find attached a proposed estimate for the electrical work at the Turkey Barn.

If you have any questions please let me know.

Thank You

Kevin Moore 435-979-7071

Derrick Moore 435-979-7076

 Richfield City Turkey Barn Electrical install

*Snapshot of the item below:*



KEVIN MOORE ELECTRIC 435.527.3866

77 West 100 North  
P.O. Box 265  
Elsinore, Utah 84724  
435-527-3866

Richfield City

75 East Center Street

Richfield, Utah 84701

**Update the Electrical Service Entrance for the Turkey Barn located West of the City. Removal of Existing Service Entrance Equipment and then install a new 100 Amp 240 Volt 1 Phase Service**

**\$2,506.00**

- Remove Electrical Equipment from existing power pole.
- Reuse existing Power Pole
- Install 100 Amp Service Entrance on power pole
- Update to 2 inch service mast, place service equipment on Stand Offs as per Rocky Mountain Power requirements.
- Utilize existing buried conduit, removed existing conductors and install new # 10 THHN Stranded conductors for 30 amp 240 volt feed to Barn.

**Install new Loadcenter inside of Turkey Barn.**

**\$3,310.00**

- There will be a disconnecting means as a Main inside the Barn in Loadcenter
- Install 5 Ceiling mounted keyless lamp holders each fitted with a 36 Watt LED lamp rated for 150 Watt Equivalent light output with a color of 5000 K.
- Installation of a Light Switch located near the Loadcenter to control the ceiling lights.
- Installation of 2 - 20 AMP GFI receptacle outlets one on the North Side of each overhead door.
- Cable being installed is #12 MC (Metal Clad) cable for protection of conductors.
- Strapped in accordance with the NEC