

February 23, 2023

ADDENDUM NO. 1 (DOCUMENT 00 91 13)
2023 Street Maintenance Project

Attached are copies of Addendum no. 1.

In case of any conflicts between the drawings, specifications, and the attached Addendum, the Addendum shall govern.

Addendum 1 extends the bid date to March 9, 2023.

This Addendum is hereby attached to and made part of the Contract Documents and each Bidder shall acknowledge receipt of this Addendum in this Bid.

The Addendum consists of 5 pages.

Sincerely,



Eric Casperson, PE
City Engineer

Attachments

cc: Susan Nance
Casey Hunsaker

DOCUMENT 00 91 13
ADDENDUM No. 1

PART 1 GENERAL

1.1 DOCUMENT INCLUDES

A. New Bid Schedule

1.2 CONSTRUCTION CONTRACT

A. 2023 Street Maintenance Project

PART 2 CHANGES

2.1 CHANGES TO PRIOR ADDENDA

A. None

2.2 CHANGES TO BIDDING REQUIREMENTS

A. None

2.3 CHANGES TO AGREEMENT AND OTHER CONTRACT FORMS

A. Replace Entire Bid Schedule

2.4 CHANGES TO CONDITIONS OF THE CONTRACT

A. Changes the Bid Date to March 9, 2023, 2:00 pm

2.5 CHANGES TO SPECIFICATIONS

A. None

2.6 CHANGE TO DRAWINGS

A. None

END OF ADDENDUM NO. 1

**BID SCHEDULE
NORTH OGDEN CITY
CORPORATION
2023 STREET MAINTENANCE PROJECT**

BASE BID - Schedule No. 1 2023 Street Maintenance Project – General Requirements				
Bid Item	Bid Item Description	Quantity And Unit	Unit Price	Total Amount
1	Traffic Control	1 Lump Sum	N/A	\$
2	SWPPP and NOI	1 Lump Sum	N/A	\$
3	Mobilization	1 Lump Sum	N/A	\$

Subtotal Schedule No. 1 = \$ _____

BASE BID - Schedule No. 2 2023 Street Maintenance Project – Fruitland Drive – 2600 N to 2100 N				
Bid Item	Bid Item Description	Quantity And Unit	Unit Price	Total Amount
4	Mill Roadway Surface – 10' each side of centerline – 2" Thick	8,400 Square Yards	\$	\$
5	Asphalt Pavement, 2" Thick, PG58-28 DM ½" 50 Blow	8,400 Square Yards	\$	\$
6	Chip and Seal with CSS-1 Fog Seal	14,700 Square Yards	\$	\$
7	Adjust Manhole	24 Each	\$	\$
8	Adjust Water Valve Box	16 Each	\$	\$

Subtotal Schedule No. 2..... = \$ _____

BASE BID - Schedule No. 3
2023 Street Maintenance Project – Barker Subdivision - 725 E (2600 N to End), 2450 N (725 E to 800 E), 2550 N (725 E to Fruitland Dr.), 800 E (2550 N to End), 750 E Cul-de-sac (2450 N to End)

Bid Item	Bid Item Description	Quantity And Unit	Unit Price	Total Amount
9	Mill Roadway Surface - 7' Wide from Lip of Gutter	5,700 Square Yards	\$	\$
10	Asphalt Pavement, 3" Thick, PG58-28 DM ½" 50 Blow – Asphalt Patching	60 Square Yards	\$	\$
11	Furnish & Install Untreated Base Course – Asphalt Patch Areas	60 Square Yards	\$	\$
12	Adjust Manhole	26 Each	\$	\$
13	Adjust Water Valve Box	17 Each	\$	\$
14	Asphalt Pavement, 2" Thick, PG58-28 DM ½" 50 Blow	18,400 Square Yards	\$	\$
15	Adjust Survey Monument Box	7 Each	\$	\$
16	Chip and Seal with CSS-1 Fog Seal	18,400 Square Yards	\$	\$

Subtotal Schedule No. 3..... = \$ _____

BASE BID - Schedule No. 4 2023 Street Maintenance Project - 850 E (1725 N to 1900 N), 800 East (1725 N to 1850 N), 1800 N Cul-de-sac (800 E to End)				
Bid Item	Bid Item Description	Quantity And Unit	Unit Price	Total Amount
9	Mill Roadway Surface - 7' Wide from Lip of Gutter	4,250 Square Yards	\$	\$
10	Asphalt Pavement, 3" Thick, PG58-28 DM ½" 50 Blow – Asphalt Patching	40 Square Yards	\$	\$
11	Furnish & Install Untreated Base Course – Asphalt Patch Areas	40 Square Yards	\$	\$
12	Adjust Manhole	29 Each	\$	\$
13	Adjust Water Valve Box	17 Each	\$	\$
14	Asphalt Pavement, 2" Thick, PG58-28 DM ½" 50 Blow	10,800 Square Yards	\$	\$
15	Adjust Survey Monument Box	7 Each	\$	\$
16	Chip and Seal with CSS-1 Fog Seal	10,800 Square Yards	\$	\$

Subtotal Schedule No. 4..... = \$_____

A. Base Bid

Schedule No. 1.....=\$_____

Schedule No. 2.....=\$_____

Schedule No. 3.....=\$_____

Schedule No. 4.....=\$_____

Total Base Bid = \$_____

It is understood that the quantities stated are approximate only and are for the purpose of comparing bids and fixing the amount of bonds, and the payments will only be made on the basis of the above unit prices in the actual quantities, as determined by the Owner's Engineer in the completed work.